

GOVERNMENT OF INDIA  
ARCHÆOLOGICAL SURVEY OF INDIA

CENTRAL  
ARCHÆOLOGICAL  
LIBRARY .

ACCESSION NO. 23470


CALL No. 491.4409/cha

D.G.A. 79

1875  
11. 11. 1875

1875





549

THE  
ORIGIN AND DEVELOPMENT OF  
THE BENGALI LANGUAGE

Part 2  
3738

BY  
SUNITI KUMAR CHATTERJI

M.A. (Calcutta), D.Lit. (London)

Khaira Professor of Indian Linguistics and Phonetics and Lecturer in  
English and Comparative Philology in the University of Calcutta

With a Foreword by  
SIR GEORGE ABRAHAM GRIERSON, K.C.I.E.

23470

In Two Parts

Part II : Morphology, Bengali Index

491.4409  
Cha



CALCUTTA UNIVERSITY PRESS

1926



52  
25  
144C  
21

PRINTED BY BHUPENDRALAL BANERJEE

AT THE UNIVERSITY PRESS, SENATE HOUSE, CALCUTTA.

Reg. No. 36B, August, 1926—500

CENTRAL ARCHAEOLOGICAL  
LIBRARY, NEW DELHI.

Acc. No. 23470.  
Date. 6. 4. 56.  
Call No. 491. 4409/Cha

## MORPHOLOGY





350 10 25  
E. H. H. H. H. H.  
H. H. H. H. H. H.

WILLIAM H. H. H.

## MORPHOLOGY

### CHAPTER I: FORMATIVE AFFIXES

394. Hoernle's discussion of the NIA. suffixes in his 'Gaudian Grammar' remains the most thorough study of the scope and origin of these, although some of his derivations are more or less speculative. The Bengali formative affixes have been discussed in some detail by Rai Bahadur Yōgesh Chandra Vidyānidhi in his Bengali grammar (published by the VSPd., pp. 147-191), but the arrangement is capable of improvement, and some of the etymologies can be questioned. There is no doubt as to the source of most NIA. affixes, but there are a few which have not been satisfactorily explained.

The OIA. affixes, primary or secondary, became disguised, or simply dropped off in NIA., through either assimilation or phonetic decay. But a number of OIA. affixes have been preserved, and occur in NIA. as living forms, although in their present shape they are widely removed from their OIA. originals (*e.g.*, «-pan» < «-tvana-»; «-ab, -ib, -iv» < «-tavya-»; «-ī» < «-ika, -ikā»; etc.). The NIA. speeches preserve only the relics of some OIA. affixes, which as a result of phonetic decay now form integral and indivisible parts of the words, and have, so far as the speech-feeling of the NIA. speaker is concerned, no separate existence, and are not recognisable or analysable any more as an affix. Thus, for example, the OIA. primary affixes «-ā, -ā, -as», in noun and adjective formations, are no longer living ones in Bengali, as they are lost in all inherited words; but the affix «-ana», to form verbal nouns, continues to be in full force as অন, ওন «-ānā, -ōnā»; and in words like কাম, কাম «cāmā, kāmā», the -ম «-mā» is only partially representative of the original OIA. affix «-man»; but it is no longer possible to analyse the Bengali words as being made up of a root *plus* an affix, and neither can -ম



< -mṣ > be distinguished from the -ম < mṣ > in words like জাম < jāmṣ > (jambu) and আম < āmṣ > (āmra). The words in Bengali have become to all intents and purposes root-words, or primitive words, the sense of their being composed forms being long lost, from the beginning of MIA. So in words like রাতি < rāti > (rātri), পাতি < pāti > (paṅkti), সোতা < sōtā > (MIA. sōnta-, OIA. srōtas), কাজ < kājṣ > (kārya), the OIA. affixes < -tri, -ti, -tas, -ya > are present, but they are no longer alive. These relics or fragments of dead forms are not necessary to consider, unless the subject of study were the history of the OIA. suffixes down to NIA. through MIA.

Below are given in a rough alphabetical order all the living affixes, primary as well as secondary, which are found in Bengali, Old, Middle and New, with indications of their origin.

#### [A] SUFFIXES

##### [I] TADBHAVA SUFFIXES

(1) অ < -ā, ṣ > : masculine, feminine and neuter noun affix.

395. Representing the primary affixes of OIA., masculine < -āḥ >, feminine < -ā >, neuter < -am >, also < -as >, with or without < guṇa > of the root-vowel, this affix may be said to have existed in Old Bengali and Early Middle Bengali, but was lost from Late Middle Bengali times with the loss or assimilation of the final vowel: *e.g.*, চার < cāra > (cāra), সান < sāna > (saṁjñā), মন < maṇa > (manas), সাঙ্কম < sāṅkama > (saṅkrama) *bridge*; but cf. Late MB. দে < dē > (dēha), মন < mānṣ > (manas), বাত < bātṣ > (vārtā), বোল < bōlṣ > *speech* (MIA. \*bōlla), চাল < cālṣ > *way, style* (cāla), etc.

(2) অ < -ā >, also written ও < -ō >.

396. This is the pleonastic suffix, found in a number of nouns and adjectives—*e.g.*, ভাল, ভালো < bhālā, bhālō > *good*; কাল, কালো < kālā, kālō > *black*; ধল < dhālā > *white*; etc. It comes from the pleonastic or pejorative < -kā > of OIA., added to nouns in < -ā > = < -ā-kā > > MIA. < -āā- > > < āwā >: see *ante*, pp. 302, 346, 347, 348. The affix is thus of secondary origin. The employment of the pleonastic < -ka >, giving, with the



preceding «-a» of the word, the MIA. forms «-aga, \*-aga, -aṃ/ya», is quite a note-worthy thing from the Second MIA. stage; and in Skt. as written in that period, as well as in later times, this vernacular habit is fully reflected: in the Skt. of inscriptions, this is very much in evidence. (Cf. Damodarpur Copper Plates of the Gupta Period, Ep. Ind., XV, pp. 130, 138.) The combination of «-āā» > «āwā» seems to have begun to be altered to an «ā» (long [a:]) sound in the OB. period; and it was accomplished by the 14th century. (See pp. 260, 302, 346.) In MB., it is frequently found in personal names, where it is commonly written as ও «-ō»: e.g., শিবো «Śibō» (OB. \*Śibawa = ts. Śiva + ka), রুদো «Rudō» (\*Rūdawa < Rudra + ka), বিভো «Bibhō» (\*Bibhawa < \*Vibha = Vibhu + ka), সিধো «Sidhō» (\*Sidhawa < Siddha [= Siddhēśvara] + ka), etc. These common contractions of personal names in MB. are thus on the basis of a form in «-ā-», shortened from the full names (e.g., জনো «Jānō» < «Janārdana», পিথো «Pithō» < «Pṛthvidhara», etc.), with the pleonastic «-kā» added. Forms like the above are very common in MB. genealogical works (kula-grantha, kulajī = kulāpañjikā): which shows that they were much in use.

There is another affix, also (occasionally) written অ «-ā», indicating the sense of *about to do something*: e.g., কাঁদ-কাঁদ «kāḍā-kāḍā», beside কাঁদো-কাঁদো «kāḍō-kāḍō» *ready to burst into tears*. This is a primary affix forming verbal adjectives and is derived from ও «-ō» < উ «-u», which see, *infra*.

(3) Affixes derived from the OIA. Active Present Participle «-ānt-»:  
অন্ত «-āntā»; অং > অতা, অতী (অতি) «-ātā > -ātā, -āti (-āti)», অত  
«-ātā». (Cf. also আইত, ইত «-āit, -it-», and আস্ত «-āntā».)

397. অন্ত «-āntā»: this is a stereotyped form, which occurs only in a few adjectives used attributively: e.g., জীবন্ত «jīāntā» > জ্যাস্ত «jyāntā» [jīāntō] *living* (jīvant-); চলন্ত «cālāntā» *moving* (calant-); বাড়ন্ত «bārāntā» *prospering* < বাঢ়ন্ত «bāṛhāntā» (√vr̥dh > \*vardhant-); ঘুমন্ত «ghumāntā» *sleeping* (ঘুম√ghum); ভাসন্ত *floating* (ভাস√bhās float); etc. It occurs in a feminine form অস্তী «-āntī» = «-ant- + -ikā» used with sentient feminine nouns: নাচুস্তী < নাচন্তী «nācuntī < nācāntī» (nr̥tyant- + -ikā); দেখুস্তি < দেখন্তি «dēkhuntī < dēkhāntī» *seeing, seer* (MIA. dōkhhantī), etc. অন্ত «-āntā»



is not the regular development in Bengali of the OIA. affix «-ant-», but it became established in some forms, which were set apart in MB., because of their adjectival force, from the regular MB. and NB. change which made ইত «-it» out of MIA. «-anta, -enta» < OIA. «-ant-» (see p. 335).

অন্ত «-ātā», found commonly in its extended form অতি «-āt-ā», feminine অতী, অতি «-āt-I, -āt-i». This affix seems to be borrowed from the Bihārī dialects, and Hindōstānī: «-anta»-at». The feminine force is lost to Bengali. Examples: ফেরত ডাক «phērātā ḍākā» *return post*, also ফিরতী ডাক «phirātī ḍākā» (ফির √phir); চলতী ভাষা «cālātī bhāṣā» *current speech, colloquial* (√cal), cf. Hindī «caltī cakki» *the moving wheel* (quern-stone = the world); বহত জল «bāhāt jālā» *running water* (বহ √bāh < √vah flow); উঠতি বয়স «uṭhātī bāyāsā» *growing age, youth* (উঠ √uṭh < ut+sthā); সব-জান্তা «sāb-jāntā» *all-knowing*; বিলাত-ফেরত, or ফেরতা «bilāt-phērātā, -phērātā» *returned from Europe*; দেখতা «dēkhātā» *seeing*, as in the idiom আমার দেখতা «āmār dēkhātā» (for আমি দেখতা «ami dēkhātā»?) *with me looking on*; বড়তি পড়তি «jhārātī parātī» *things that are scattered and fallen, remainder*; etc.

Another form of this affix is অত «-ātā», which seems to be a blend of অন্ত «-āt» + অন্ত «-antā»: e.g., জানত «jānātā», পারত «pārātā», করত «kārātā», etc. Forms with this affix, however, are rather rare, and they have a special employ. জানত «jānātā» is used as an absolutive with the subject in the genitive, e.g., আমার জানত «āmār jānātā» *me knowing, with my knowledge* (cf. আমার দেখতা «āmār dēkhātā» above); and it is frequently confused with the *ts.* passive part. adjective in ত «-tā», and used as an adjective: e.g., আমার জানত লোক «āmār jānātā lōkā» *a man known to me* beside আমার জানিত লোক «āmār jānitā lōkā» (where «jānitā» = জান √jān + *ts.* affix «-ita»). পারত «pārātā», also «pārātā» is commonly used in the phrase পারত-পক্ষে «pārāt(ā)-pākṣē» *on condition of being able*, which is frequently altered to a Skt. পারগ-পক্ষে «pārāgā-pākṣē». করত «kārātā» *doing*, is used as a conjunctive participle = *having done*, and sometimes a Sanskrit colour is given to this form by adding a «visarga», which helps to preserve the final «-ā» in the word: করত: [kārōṭa] *having done, after doing*.

In onomatopoeitic formations in অৎ < -āt > like পটাত < pātāt > *with a cracking noise*, ঝপাত < jhāpāt > *with a dashing or splashing sound*, কপাত, গপাত < kāpāt, gāpāt > *with a gulp*, ছলাত < chālāt > *with a splash*, which are used with the conjunctive করিয়া, করে < kārīyā, kōrē >, we have also possibly this < -anta > affix of MIA. and OIA.

(4) অতী, তী ( অতি, তি ) < -āti, -ṭī (-āti, -ṭī) >.

398. This forms abstract nouns of action or manner: e.g., পড়তি < pāṛṭi > *fall*; উঠতি < uṭṭṭi > *rise*; চুকতি < cukṭi > *settlement, fixing up*; বাড়তি < bārṭi < bārḥṭi > *rise, increase*; বাঢ়তি < ghāṭṭi > *decrease*; by analogy, the hybrid কমতি < kām-ti > *decrease*, from Persian, < kam >; খাঁকতি < khākṭi > *greed* (cf. onomatopoeitic খাঁখাঁ < khākhā > *the sense of emptiness and hunger*); গুনতি < guṇṭi > *counting*; ভরতি < bhārṭi > *filling-up*, etc.

Hoernle explains this affix (‘Gaudian Grammar,’ § 325) as being a Sanskrit (or OIA.) < \*-āptikā >, from the causative affix < -āp- > + < -ti > + pleonastic < -kā >: e.g., বিনতি < bināti > (vijñāptikā = vijñāptikā > viññattia), বাড়তি < bārṭi > (\*vardhāptikā > \*vaṛḍhattia); etc. But this derivation is rather problematical. Cases like ডাকাইত < dākā(i)ṭ > *robber* (ডাক < √dāk > *shout*: cf. under আইত < -āit > *below*), ডাকা(ই)তী < dākā(i)ṭī > *robbery*, ঢাঙ্গা(ই)ত > ঢাঙ্গা(ই)তী < dhāṅ(g)ā(i)ṭ > dhāṅgā(i)ṭī > *rowdy* > *rowdiness* (dhāṅga), etc., with the ত্তি (ই) < -ī (-i) > affix of abstraction (for which see *infra*), show that in examples like উঠতি < uṭṭṭi >, ভরতি < bhārṭi > etc. above, we have an extension of the অৎ < -āt > affix (< present participle < -anta >) by addition of the abstract ত্তি, ই < -ī, -i >: উঠতি < uṭṭṭi > = < uṭṭhā(n)t(ā) + -ī > *the state of rising = a rise*.

The change of < -anta > to < -āt- >, and not to < -it- >, would show that this affix is not native to Bengali, but borrowed, with cognate loan-words, from its western neighbours.

It seems also that in the formation of this affix, there was the influence of the Skt. nominal affix < -ti > as well, through the presence of a large number *ts.* as well as *sts.* forms in < -ti >, like < yukti (jugati), bhakti (bhakati), mati, gati, prañati > etc. In post MB. times,



the Perso-Arabic loan-words in «-at», with the Indian or Persian «-ī» added, re-inforced this affix: e.g., «wakālat» > ওকালতী «ōkālāt-ī» a pleader's profession; and by analogy, it was extended to other foreign words, e.g., জজ «jāj» = English *judge* > জজিয়ত, জজিয়তী «jājīyāt, jājīyāt-ī» the work of a judge.

(5) অন (ওন, এন) «-ānṣ (ōnṣ, ēnṣ).

399. This is a living suffix in Bengali, forming abstract verbal nouns, some of which have acquired a concrete sense. It is the OIA. «-ana». Examples: কঁদন «kādānṣ» (krandana); কুঁদন «kūdānṣ» (kūrdana); খাঁদন, খাঁওন «khāānṣ, khāōnṣ» (khādana); গায়ন, গায়োন «gāyānṣ, -yēnṣ» singer (gāyana: \*gāthayana? cf. Khaskurā «gāhinē» singer < «gāhiniyā»); ঘুরন «ghurānṣ» turning round and round (ঘুর √ghur < ghūr-); চাহন, চাহোন «cāhānṣ, cāōnṣ» gaze, look (চাহ √cāh); ছাড়ন «chārānṣ» leaving (ছাড় √chār); ছাঁদন «chādānṣ» binding (chandana); জ্বলন «jwālānṣ» [jṛṣṭoln] (jvalana); বাঁড়ন «bhārānṣ» dusting, a duster, বোঁটন «bhōtānṣ» crest, top-knot (see p. 479); ঝুলন «jhuḷānṣ» swing (see p. 479); ঢাকন «ḍhākānṣ» covering > a cover (ঢাক √ḍhāk); থাকন «thākānṣ» staying (থাক √thāk); দেখন «dēkhānṣ» sight; ধরণ «dhārānṣ» manner («ṇ» through Skt. influence) (dharana); নাচন «nācānṣ» dance (নাচ √nāc); পড়ন «pārānṣ» fall (paḍana < \*paṭana < patana); পায়ন, পায়োন «pāānṣ, pāōnṣ» (prāpana); পাড়ন «pārānṣ» (pātana); পোড়ন «pōrānṣ» burning (পুড় √puṛ < √puṭ); কোড়ন «phōrānṣ» spices, chatter (√sphuṭ); বাঁধন «bādānṣ» (bandhana); বাজন «bājānṣ» music (বাজ √bāj < vādya); বার্ডন «bārānṣ» broom (vardhana); বেঁধন, বিঁধন «bēdhānṣ, bīdhānṣ» piercing (viddha < √vyadh); মারণ «mārānṣ» (maraṇa); শুনন «śunānṣ» hearing (শুন √śun < śṛ-ṇō-ti); হঅন, হওন «hā(w)ānṣ, hāōnṣ» being (\*ahana = as-ana + bhav-ana); etc., etc.

This affix is now becoming a little archaic in the Standard Colloquial, which prefers the other verbal noun in অ «-ā»: but it is a very living form in the East Bengali dialects.

The affix «-ānṣ» has two extensions:

(5a) অনা > না < -ānā > -ānā : this is simply অন < -ānā > extended with the অি < -ā > affix. The < -ā > in this affix drops when inter-consonantal; when after a vowel, it becomes < e > or < o > and forms a diphthong. The original force of this < -ā > was to denote simply a coarser or bigger aspect of the action, or to indicate a connected object, but this has been to a considerable amount modified, so that অনা, না < -ānā, -ānā > in many cases is not different from অন < -ānā >. Examples: কান্না < kānā < kādānā, kādānā > (see p. 360), beside কান < kādānā > (kran-dana-); কুটনা < kuṭānā > *slicing* > *sliced vegetables* (কুটে √kuṭ); কাটনা < kāṭānā > *spindle* (কাটে √kāṭ *spin*); খেলনা < khēlānā > *playing* > *toy* beside খেলন < khēlānā > *playing* (খেল √khēl); গহনা, গয়না < gāhānā, gāyānā > *jewels* (grahaṇa-); গাথনা > গাওনা < \*gāhānā > gāonā > *singing* (গাহ √gāh < √gāthaya-); ছাঁকনা < chākānā > *strainer* (ছাঁক √chāk); ঝরনা < jhārānā > *water-fall* (ঝর √jhar: see p. 478); ঢাকনা < ḍhākānā > *largish lid* (ঢাক √ḍhāk); দোলনা < dōlānā > *swing* (দুল √dul); দেনা < dēnā > *giving* > *debt*, beside দেন < dēnā > *giving* (দে √dē *give* = √dā); so লেনা < lēnā > beside লেন < lēnā > *taking* (লে √lē *take* < √lah = labh + √ni); পাওনা < pāonā > *receiving*, dues (prāpaṇa-); পিটনা < piṭānā > *mallet to beat with* (পিটে √piṭ); বাজনা < bājānā > *musical instrument*, see বাজন < bājānā > above; বাটনা < bāṭānā > *paste of pounded spices* (বাটে √bāṭ *pound, mash*); মাগনা, মাদনা < māgānā, māḍānā > *asking* > *gratis* (mārgaṇa-); রান্না < rānā < rādānā > *cooking* (randhana-); শুখনা < śukhānā > *dry, dry-land* (শুখ √sukh < śuṣka); etc. There are some formations from nouns as well: ছানা < chānā > *youngling (of animals)* (beside ছা < chā >, = < śāba >); পাখনা < pākānā > *wings* (beside পাখ pākā < pakṣa).

(5b) অনী > নী, উনী (নি, উনি) < -ānī > -ānī, -unī (-ānī, -unī) >. Originally feminine in form (-ānā + i), indicating a diminutive or petty aspect of the action or object. All grammatical connexion with the feminine form is now lost, except where the word indicates a woman. The change to < -unī > is by Vowel Harmony (see p. 398). কাঁদনী < kādunī < kādānī > *weeping, petty fit of weeping, supplication*; SKK. নাচুনী < nācunī < nācānī > *dance*; ছেনী < chēnī > < \*chēanī > *a cutting instrument* (chēdana, chēdanikā); ছাউনী < chāunī < chāānī > *awning, camp* (chādanikā);



ছাঁকনী < chāṅkṇi > *small strainer* (ছাঁক √chāṅk); MB. পোড়নী < pōṛāni > *burning* (পুড় √pur); কুরনী > কুরনৌ < kurāni > kurāni > *scraper* (কুর √kur scrape); মউনৌ < māuni > < \*mā(h)āni > *churning stick* (\*mathanikā); etc., etc. The word রাঁধুনী < rāḍhuni < rāḍhāni > *cook* is now both masculine and feminine, but originally it seems to have been only feminine (< randhanikā >: or a masc. = < \*randhanikā > ?); when it means a kind of flavouring spice, it is the feminine form undoubtedly. So MB. বেচনী < bēcāni > *a seller* (বেচ √bēc).

Causative forms of this affix, in আন < -āṇ >, আন, আনা < āṇā, -āṇā > আনৌ, উনৌ < -āni, -uni > also occur: see *infra*.

In the word দাঁতন < dātāṇ > *twig used as tooth-brush* we do not have the < -āṇ > affix (unlike in formations from nouns পাখনা < pākhṇā >, বাজনা < bājṇā >, etc.): the Maithili < datamani >, Bhojpuriyā < datuan >, and Hindōstāni < datwan, dataun, datūn > show that the word is a compound of < danta > + < vana > (?).

(6) অ < -ā > (i): Definitive, Pejorative, Connective, Agentive, Pleonastic.

400. This affix is a very characteristic one of Bengali. It indicates definiteness (this definitive force is now considerably weakened); it implies coarseness or biggishness in the object; it means reference or connection; it forms agentive adjectives; and frequently it is also pleonastic. In all its various forces, the < -ā > affix of Bengali can be compared with the pleonastic affixes giving rise to the strong, long and redundant forms of the Bihārī dialects (see p. 96). The source of Bengali < -ā >, as an OIA. < \*-āka >, has been indicated at pp. 302, 348-349. Cf. Sanskritised forms like < Nāgāka, Dhamāka, Viśāka, Bhaluāka, Pappāka (beside Pappā), Rudāka, Chitarāka >, all representing vernacular names in < -ā >, in the Siyadoni Inscription (10th century: Lalitpur District, U.P.; Kielhorn, Ep. Ind., I, pp. 162 ff.) Where no special force of the < -ā > is present, as in a noun like ঘোড়া < ghōṛā > (beside ঘোড়- < ghōṛḍ > in compounds), that is, where it is merely a pleonastic extension, it is not unlikely that the < -ā > represents only the termination of an oblique case (see p. 349). Examples: OB. (Caryā 41) হাষ্টা (hasta-); (Caryā 49)

পউষা « pāūā = paṣūā » (\*paduma-, padma-); (Caryā 8) মাগা « māgā » (mārga-); (Caryā 2) পিটা « piṭā » *pail*; (Caryā 3, 20) পসারা « pasārā », নিসারা « nisārā » (prasāra-, nihsāra-); (Caryā 4) বীরা « bīrā » (vīra-); (Caryā 6) হরিণা « hariṇā » (hariṇa-); MB. নেহা « nēhā » (snēha-); MB., NB. নেতা « nētā » *rag* (nētra > nētā = *fine stuff*); কাঁসা « kāsā » (kāṁsya-); ŚKK. কনয়া « kanāyā » (kanaka-); পাতা « pātā » (patra-); কুয়া, কুয়া « kūā » (kūpa-); গোরা « gōrā » (gāura-); উঁচা « ūcā » (ucca-); চোরা « cōrā » (cāura-); বাঘা « bāghā » (vyāghrā) *big tiger > tiger-like, ferocious, strong* (e.g., বাঘা a common name for a dog, বাঘা তেঁতুল « bāghā tētul » *kind of tamarind with strong acid taste*); খাঁড়া « khārā » *sacrosanct sword* (khaṇḍa-); বকরা « bākārā » *goat* (barkara-); কুকড়া > কুকড়া, কুকড়া « kūkūrā > kūkārā, kūkārō » (kukkūṭa-); রামা « Rāmā » contemptuous for « Rāmā »; চাঁদা « cāḍā » *big round moon*, beside চাঁদ « cāḍā » *moon* (candra-); cf. চাঁদা মাছ « cāḍ-ā mācchā » *a kind of roundish fish, pomfret*; থালা « thālā » *plate* beside থাল « thālā » (sthāla-); ধূঁয়া, ধূঁয়া « dhūā » (dhūma-); রাঙ্গা, রাঙ্গা « rāṅ(g)-ā » *red in colour* (rangga-); তেলা « tēl-ā » *oily* (tāila-); লোনা « lōnā » *salty* (lavāna-); হাতা « hātā » *handle* (hasta-); তাওয়া « tāwā » *pot for heating or dry cooking* (tāpa-); বামনা « bāmānā » *a low Brāhman* (brāhmaṇa-); sts. পশ্চিমা « paścimā » *western* (paścima-); দক্ষিণা, by Vowel Harmony দ'খনে (see pp. 400-401) « dākkhinā » > [dokhne] *southern* (dakṣiṇa- > dākkhinā-); একা « ēkā » [æka], একলা « ēkalā » *alone* (ēka-, \*ēkāka; ēka-la-); মুহা « muh-ā » *with a face* (mukha-); ভদ্রা « bhāyā » *belonging to a buffalo* (bhāiṣā < mahiṣa + -ā); খেঁয়া « khēyā » *ferry* (kṣēpa-); etc.

In compounds with active meaning: ছেলে-ধরা « chēlē-dhār-ā » *child-stealing = kidnapper*; চাল-ধোয়া « cālā-dhōā » *rice-washing*; কাপড়-কাটা « kāpāṛḍ-kāc-ā » *cloth-washing*; কলম-কাটা ছুরী « kālāmḍ-kāṭ-ā churī » *pen-(cutting)-knife*; ভাত-রাঁধা হাঁড়ী « bhātḍ-rāḍh-ā hāṛī » *pot that boils rice*, etc.

This affix is added to both *tatsama* and foreign words: রোগা « rōg-ā » *sick, sickly, lean and thin* (rōga-); সফেদা « sāphēd-ā » *rice-powder* (Pers. safēd *white*);

Other affixes of Bengali, like « -āṭa, -uṭa, -ī(i) -ū(-u), -āla, -āra » etc., are extended by addition of this « -ā »: for which see below.



## (7) অ &lt; -ā &gt; (ii) : Passive Participle and Verbal Noun Affix.

401. This suffix is derived from the OIA. affix < -ta, -ita > > MIA. < -a, -ia > plus the preceding pleonastic affix অ < -ā >. The following examples illustrate the line of development : < yāta > jūa + -ā > OB. \*jāā, NB. যাওয়া \*jāwā > gone > a going ; < kṛta > \*karita (a non-Māgadhī formation : cf. p. 375) > karia + ā > OB. kariā > করা kārā > done > doing, as in New Bengali. So রাখা < rākhā > kept > keeping (rakṣita + ā) ; খাওয়া, খাওয়া < khāwā > (khādita + ā), etc. We have the loss of the < -i- > already in OB. : e.g., Caryā 20 < saṅghārā > struck ; but it is the < -i- > forms, with or without the pleonastic < -ā >, that are common in the Caryās (when without < -ā >, the final < -a > is found to have assimilated with the preceding < i >, as follows : < -ita > -ia > -ī, -i >) : e.g., in Caryā 19 < uchaliā > (ucchalita + ā), < calīā > (calita + ā) ; Caryā 13 < muniā > (=jñāta-) ; Caryā 17 < suñīā > (=śruta-), < miliā > (milita + ā), gunīā (=gaṇita + ā) ; beside < pahāri > (prahārita), < ahāri > (āhārita-), etc. ; and cases are found with the Western Apabhraṇśa modification of the < -itaḥ > to < -in > (< -itaḥ > -idō > -iō > -in > : cf. p. 115 *supra*). The affix seems to have come into prominence only after the Early MB. period : in the ŚKK. it is non-existent. The < -i- > as in < -iā > of OB. probably first became < -ā- > and then was dropped, following the forms in simple < -ā > like < yāta + -ā > যাওয়া jāwā >, < \*dita + ā > দেওয়া dēwā > etc. ; and possibly also through an attempt to distinguish this passive participle affix from the conjunctive participle in < -i(-ī), -iā > (e.g. রাখী, রাখি, রাখিয়া < rākhī, rākhi, rākhiā > having kept, with or without < -ā > < MIA. < rakkhiā > < OIA. < -rakṣ-ya >). The OB. forms of the passive participle in < -iā > show that < -ita + -ā > is the source of this passive participle affix of MB. and NB. In Panjābī, in the Old Western Hindī dialects and in Modern Hindōstānī we find a parallel development with loss of < -i- > : e.g., < calita-, calitaka > > MIA. (Śaurasenī) < cali(d)a-, cali(d)aa- >, nominative < cali(d)ō, cali(d)aō > > Śaur. Apabhraṇśa < caliu, caliaū >, whence Brajbhākhā < calyu, calyau >, Early Hindī or Hindōstānī < calyā > (beside Panjābī < caliā, cālā >), but Modern Hindōstānī < calā >, Bundēlī and Kanaujī < calō >. Ōriyā has this affix also : e.g., < jāṇ-ā > known, < kār-ā > done, < dēkh-ā > seen, etc.

It has been attempted to connect this «-ā» affix in its nominal employ with the verbal noun affix ইব, ইবা «-ibā, -ibā» < «itavya + ā» ; but that is hardly tenable.

In OB. and MB., there was a feminine form of this affix, with the ঙ্গ «-ī» (< -ikā) ; e.g., ŚKK. (p. 381) জড়ী «jārī» > *jewelled* qualifying চুড়ী «cuṛī» > *bracelet* (jaḍita + -ikā).

(8) আই «-āi» (i) : Verbal and Abstract Nouns.

402. This is a Late MIA. formation, being a feminine verbal noun from the causative stem of the root : an OIA. «-āp-ikā» (as in Skt. «jñ-āp-ikā» > *information*, which would be the basis of a possible NIA. «\*jñānāi») would give «-āviā, āviā, -āwī, āi» > আই āi. The causative in «-āpa» > -āva» became established in MIA., and on the model of the nouns in «-āpana-» > -āvaṇa-» (see *infra*, § xxx, under অন «-ānā»), formation of abstract and verbal nouns in «-ikā» from the «-āpa-» > -āva-» base would be a matter of course. Examples : যাচাই «jācāi» > *enquiry* (যাচ √yāc : OIA. \*yācāpikā) ; বাছাই «bācāi» > *selection* (বাছ √bāch) ; লড়াই «lārāi» > *fight* (লড় √lār) ; খোদাই «khōdāi», also খোঁদাই «khōdāi» > *engraving* (খোদ, খোঁদ √khōd, khōd) ; দোলাই «dōlāi» > *a hood or shawl fastened round the neck and covering the ears and head, and hanging on the back* (দুল, দোল «√dul, dōl» : possibly influenced by «dukūlikā» > ছলী «dūlī» [see p. 352], also meaning the same thing) ; ঝালাই «jhālāi» > *soldering* (ঝাল √jhāl) ; বাধাই «bādhāi» > *binding (of a book)* (বাধ √bādh) ; ঢালাই «ḍhālāi» > *founding (in metal)* (ঢাল √dhāl pour) ; etc.

This affix is not found with all roots, and is but restricted in use. Abstract nouns from noun and adjective bases are also formed, the nouns and adjectives being treated like denominative verbs : e.g., চোরাই «cōrāi» > *stolen property* (<cōra) ; ব্রাহ্মণাই «bāmṇāi» > *the way of a Brāhman, the pride of a Brāhman* (<bāmāṇḍ < brāhmaṇa) ; MB. রাজাই «rājāi» > *kingship, reign* (rājā) ; মিঠাই «mithāi» > *sweetness* > *sweetmeat* (< mithā < miṣṭa-) ; পালটাই «pālṭāi» > *exchange, returning* (pālāṭṭ = paryasta) ; ভালাই «bhālāi» > *well-being* (< bhālā = bhadra-) ; সঁচাই «sācāi» > *honesty* (sācā = satya-) ; বড়াই «bārāi» > *pride, boasting* (বড় bārā great) ;



খোলতাই • khōlātāi • *dazzle, beauty* (< khōlā *open, clear*, \*khōlāt- *opening*); পোষ্টাই • pōštāi • *nourishing* (sts. < puṣṭi); and even with foreign words, e.g., সাফাই • sāphāi • *clear* (Pers. < sāf • *pure*), MB. সাজাই • sājāi • *punishment* (Pers. saẓā).

There are a few borrowings from Hindōstānī also, showing this affix : e.g., চড়াই • cārāi • *ascent*; উতরাই • utrāi • *descent*; সেলাই • sēlāi • *sewing*; ধোলাই • dhōlāi • *washing, washing charges*; and ঢোলাই • cōlāi • *distilling, preparing liquor* (< √cū = < cyav • : may be native Bengali).

In one or two words, through dialectal influence (see *supra*, p. 407), < -āi • occurs as ই • -i • in the Standard Colloquial : e.g., বানী • bānī • for বানাই • bānāi • *making, charges for making jewellery* (probably from Hindōstānī • banāi •). It would be seen that there is semantic alteration in this affix, making its force that of *cost or wages* for the *work* indicated by it.

Hoernle's derivation of this suffix from the OIA. affix < -tā • plus pleonastic < -ka • (< -tikā • in the feminine) is not convincing (see 'Gaudian Grammar,' § 223).

(9) আই • -āi • (ii) : Diminutive.

403. Affectionate diminutives like কানাই • Kānāi • (< Kāna, Kaṇha, Kṛṣṇa), বলাই • Bālāi • (< Bala-rāma), সোমাই • Sōmāi • (Sōma-), দনাই • Dānāi • (Janārdana; Danuja- ?), রামাই • Rāmāi • (Rāma), জগাই • Jāgāi • (Jagat-), মাদাই • Mādhāi • (Mādhava), ছিরাই • Chirāi • (Śṛipati), etc., which are very common in MB. and fairly frequent in NB., are formed with this affix. It is of pleonastic origin, coming from an OB. < -āi • from Late MIA. < -āia, -āiā • = OIK. < -ākika, -akika (i.e. -āka, -āka + -ika) • : < Kānāi • < \*Kān(h)āi • < \*Kanhāia, \*Kanhāia • < \*Kṛṣṇākika, \*Kṛṣṇākika •. This affix is found in various forms in Hindōstānī and in Eastern Hindī and Bihārī. (Cf. Hoernle, *op. cit.*, pp. 100-101.) The suffixes ইয়া • -iā •, উয়া • -uā • (as well as ই, ই • -ī, -i • and উ, উ • -ū, -u •) are connected : see *infra*.

It is likely that in Bengali the আই • -āi • affix as an affectionate diminutive was influenced by the MB. word আই • āi • *long life* < āyus •.

(10) আইত, আত < -āitā, -ātā >, with extensions.

404. Causative and denominative present participle base: OIA. < -āp-ant-, -āy-ant > > MIA. < -āvant-, -āant- > > OB. < -āy/wanta > > MB. আইত < -āitā >: ডাকাইত, ডাকাত < ḍākāitā, ḍākātā > *robber* < *shouter* (ডাক √ḍāk *yell*); MB. বাইতি < bāiti > *player on a musical instrument* (vādayant- + -ika). This is a rare affix in Bengali. There are a few instances of this affix with nouns: সাঙ্গাং, সাঙাং < sāṅ(g)ātā > ([jāṅat, jəṅat]; for [æ], see p. 322) *companion, bosom friend* (sanga); সেবাইত < sēbāitā > *temple-priest* (sēvā); পোয়াতী, পোয়াতী, পোহাতী < pō(h)āti > *pregnant woman, a recent mother* (< pōta >: for intrusive < h >, see p. 341: this form has the feminine affix দে < -ī > < -ikā). Cf. Oriyā খণ্ডাইত < khāṇḍāitā > *a military caste* (in Orissa and S. W. Bengal) (khāṇḍa *sword*); Hindōstānī < ḍhalait > *shield-bearer* (ḍhāl), etc.

Abstract nouns are formed from this affix by adding দে, ই < -ī, -i > (see p. 655, *supra*): ডাকা(ই)তী < ḍākā(i)tī > *robbery*; MB. ঢাঙ্গাতী < ḍhāṅ(g)āti > *rowdiness* (ḍhanga).

(11) \*আউ > আও < \*-āū > āo >: Verbal Noun Affix.

405. This affix is now confined to a limited number of words; and in those cases where it is found, it seems there is reinforcement from similar Hindōstānī forms. It is connected with আই < -āi > (i) above. The source is apparently a verbal noun from the causative base: < -āpa >, with an extension < \*-āp-uk-ā (-āpa + -u-ka + -ā) >, corresponding to < \*-āpikā > the source of আই < -āi >. The affix, as < -āw, -āō, -āū > is a common one in Hindōstānī. Hoernle traces it (*op. cit.*, §227) to OIA. < -tva >: < -tva > > -tta > > -a >, a derivation which is inadmissible. Examples: চড়াও < cārāo > *aggression, attacking* (চড় √cār >: also used as an adjective, through influence of a form like উধাও < udhāo > *running out of one's sight* = < uddhāvuka >: cf. also ওয়া < ōā > in next paragraph); ঢালাও < ḍhālāo > *abundance, 'galore'* (ঢাল √ḍhāl *pour*); পাকড়াও < pākḍārāo > *arrest, seizure* (পাকড়া √pākḍār > *to seize*); দাবড়াও < ghābḍārāo > *fright* (দাবড়া √ghābḍār > *to be checked, to fear*); ছাড়াও < chārāo > *separation, release*;



ফালাও « phālāo » *spreading, abundance*, from Hind. « phailāw »; বনাও in বনি-বনাও, beside বনি-বনা « bāni-bānāo, -bānā » *amity, harmony*, cf. Hind. « banāw » *preparation, concord*.

(11a) আউআ, (আওআ) > ওয়া « -āuā > -ōā »: Adjectival as well as Abstract.

406. This affix is an extension of the preceding one with the adjectival or pleonastic আ « -ā » (see *ante*, § 400) = e.g., ঘরোয়া « ghārōā » *homely, domestic* [ghārōa] = « ghārāo, \*ghārāu + -ā » (this word shows extension of the affix to a noun); জড়োয়া « jāṛōā » *jewelled, adorned with precious stones* = « jāṛāo, \*jāṛāu + -ā »; বাচোয়া « bācōā » *safety, safe state* = « bācāo, \*bācāu + -ā »; চড়োয়া « cārōā » *aggressive* = « cārāo, \*cārāu + -ā ».

(12) আট, আটী (আটি), « -ātṭ, -āṭī, (-aṭi) ».

407. This is not so much an affix as an independent word, phonetically decayed, and forming part of a disguised compound. It is from কাঠ, কাঠি « kāṭṭh, kāṭhi » = « kāsṭha, \*kāsṭhikā », *wood, beam, stick*. গাবরাট « gābṛāṭ » *lintel* (garbhāgūrakāsṭha); পাকাটি « pākāṭi », see p. 492; MB. ধরাট « dhārāṭṭ » *a nautical term = special deck in a boat*; OB. চাষাটি « cāmāṭhi » *whip* as in Sarvānanda, is explained by that scholar as meaning « carma-yaṣṭi », but it may be equally from « carma + kāsṭhikā », which is also found in Sanskrit.

(13) আন, আন (আনো) « -ānṭ, -ānā (-ānō) » (i).

408. The affix, forming verbal nouns from causative and denominative bases, is from OB. « -āṇa, -āṇawa, -āwāṇa, āwāṇawa » (OIA. « -āp-ana, -āp-ana-ka »). The forms without the final « -a » in New Bengali have in most cases obtained a concrete or definite sense. Examples: আচান « ācānā » *washing mouth after meals* (\*ācamāpana = ācamana); জানান, জানান « jānānṭ, jūnānā » *making to know, information, intimation* (\*jāṇāpana = jñāpana-); চালান « cālānṭ » *invoice, send-up*, চালান « cālānā » *sending forward* (\*cālāpana = cālana); মানান « mānānṭ » *harmony, agreement, beauty* (\*mānāpana < mānaya-); উজান « ujānṭ » *flow-tide, up-stream* (\*udyāpana-); উড়(া)ন « urānṭ, urānṭ » উড়ান, উড়ন « urānā, urānā » *causing to fly away, extravagance*,

wasteful expenditure (\*udḍāpana-); † ছোড়ান্ < chōrānḥ > *separating, freeing, disclosing > a key* (ছোড় √chōr = ছাড় √chār); শোনান্ < śōnānḥ > *causing to hear* (MIA. \*sunāvaṇa = śrāvaṇa); গড়ান্ < gārānḥ > *slope*, গড়ান্ < gārānḥ > *a rolling, to roll* (MIA. \*gaḍḍ); etc. There are old and recent formations from nouns also: জুতান্, জুতানো < jutānḥ, jutānō >, also in Calcutta জুতানো, জুতুনো < jutōnō, jutunō > *shoe-beating* (জুতা < jutā > *shoe*); sts. যোগান্ < jōgānḥ > *aiding with materials*, যোগান্ < jōgānḥ > *act of supplying* (yōga); লাথানো < lāthānō > *kicking* (< লাথ lāthḥ, লাথি lāthi *kick*); হাতানো < hātānō > *obtaining, filching* (হাত < hātḥ > *hand*); পেঁচানো < pēcānō > *twisting, moving to and fro* (পেঁচ < pēc > *twist* from the Persian); কমান্ < kāmānḥ > *lessening* (Pers. < kam > *less*); জমান্ < jāmānḥ > *gathering* (Pers. jam<sup>e</sup>); etc.

The affix has a feminine form, from OIA. < -āpana + -ikā > = OB., eMB. < -āwāṇī, -ānī >, which gives in NB.

(13a) আনো (আনি) < -ānī (-ānī) >, উনো (উনি) < -unī (unī) >.

This affix possesses only a vague diminutive force. OB. < \*-āwāṇī > would normally be contracted to MB. and NB. < -ānī > (see p. 349), and this < -ānī > by Vowel Harmony becomes < -āni > and < -uni > (p. 398). But in the transformation of the affix from < \*-āwāṇī > to < -āni, -uni >, it seems that there was some influence of the glide < -w- > in bringing about the < -ā-, -u- >; dialectally at least, the < w > was pronounced in MB.: the word ভয়ানো < bhāyānī > *frightful* (\*bhāyāwāṇīa = \*bhāyāpanikā), beside the other regular forms in < -ānī >, would indicate that. Examples: শুনানো < śunānī > *hearing (of a case)*; পারানো < pārānī > *ferrying > fare paid in crossing* (\*pārāpanikā); ঝাঁকানো < jhākānī >, beside ঝাঁকনো, ঝাঁকুনি < jhākānī, jhākuni > *a shaking*; দেখানি < dēkhānī > *sight > money paid for a sight* (=darśanī); তোলানি as in শেজ-তোলানি < śējḥ-tōlānī > *money paid for making or clearing the bed* (তুল √tul *raise*); নিকানি < nikānī > beside নিকুনি < nikuni > *wiping, mopping the floor* (নিক √nik < √nij, nikta); নিড়ানো < niḍānī > *hoeing (in agriculture)* (? ni + dru, drāv); উড়ানো, উড়ুনো < urānī, uruni > *sheet, light shawl* may be a blend of < \*udḍāpanikā > *that which flies or flaps* + ওড়ানো < ōḥānī > = < ava-vēṣṭānikā > (see p. 398); জলুনি < j(w)ālunī, j(w)ālānī > from \*জলানি < \*j(w)ālānī > *burning*, beside জালানি < j(w)ālānī >



causing a burning = firewood (see p. 408); ŚKK. মাতানী < mātānī > *churn-stick* (\*manthāpanikā); etc., etc.

(14) আন (আনি) < -ānā (-ānō) > (ii).

409. The passive participle affix for causative and denominative roots = OIA. < -māna-ka, -y-āna-ka >. (See *infra*, under Verb: 'Causatives.') Examples: করান < kārānā > *done, caused to be done* (< \*kārāwāṇā > for < \*kārāpana-ka, \*kāra-yāna-ka >); দেখান < dēkhānā > *shown*; ঠেগান < ṭhēgānā > (*caused to be*) *beaten with a stick* (ঠেগা ṭhēgā); etc., etc. It is sometimes difficult to determine whether the form with < -ānā > is the verbal noun (p. 664), or the passive participle: e.g., শোনান হইয়াছে < śōnānā hāiyāchē > *it has been reported*, which may be either (a) *a-causing-to-be-heard has-taken-place*, or (b) *caused-to-be-heard it-has-been*.

(15) আনী (আনি) < -ānī (-āni) >.

410. This is a Bengali formation, from an earlier পানী < pānī > *water* (= pāniya) in compounds: < -pānī > becomes < -wānī > and then there is dropping of < w >. Examples: ঐষানি (see p. 349); চৌষানি < cōṣānī > *water that leaks out* (চৌ, চৌ √ cōṣ, cō = cyav); চৌষানি < cōṣānī > *sousing water, a sousing* (চৌষ √ cōṣ *to cause to dash into water, to plunge, duck into water*); চৌষানি < cōkhānī > *water from the eye, tear* (চৌষ cōkh < চউষ cāukhṣ < cakṣuh); ধোয়ানি < dhōānī > *washings* (ধো √ dhō = dhāv); নোকানি < nōkānī < nākhānī > *water stirred by the finger-nails (and so not fit for drinking)* (nakha + pāniya-); নাকানি < nākānī > *rheum or water from the nose, water reaching to the nose* (নাক < nākṣ > *nose*); ছিটকানি < chitṣkānī > *water scattered about* (ছিটকা < chitṣkā > *scatter*; there is another ছিটকানি meaning *bolt to a door*, which shows the < -ānī > affix under [13a] *supra*).

(16) আন, আন, য়, ম, আনী (আনি), অনি, ওনি, উনি, মি < -āmā, -āmā, -mā, -mā, -āmi (-āmi), -āmi, -ōmi, -umi -mi >.

411. A common affix to form abstract nouns, or nouns indicative of a characteristic or profession. It has been confused or connected wrongly

with the *ts.* affix «-iman» > ইম, ইমী «-imā, -imā», which is found in Bengali, as in other NIA. The source of this affix is an OB. কাম «kāma» *work* (karma), with extensions: «karma»-kamma > -kā mā > -āmā > আম -āmā; karma-ka»-kamma-a > \*-kā māwa > -āmā > আম -āmā; karmika, karmikā > -kammia > \*-kā mī > -āmī > আমি -āmi». The strong initial stress, as well as MB. mutation, has brought about the loss of the «-ā-» in LMB. and NB., and reduced the form to ম, ম, মি «-mā, -mā, -mī» etc. In MB., the word কামিনা, কামিনী = কামিনিয়া «kāminā, -inyā < -iniyā» occurs, meaning *a labourer*, and a form আমিনী, আমিনি «āminī, āmini» also is found (as in the ‘Śūnya-Purāṇa’): the latter word, explained as meaning *a female devotee of Dharma*, may be connected with কাম «kāma» *work, service*. Examples: ঠাকাম «ṭhākāmā» *cheating, roguery* (ঠক «ṭhākā» *cheat, ‘thug’*); পাকাম, পাকামি «pākāmā, -mī» *behaving like a ripe (i.e. aged) person, precocity* (পাক «pākā» *ripe*); so জেঠাম «jēṭhāmā» *behaving like a respected elder uncle = impertinence on the part of a boy or youth* (জেঠা «jēṭhā» *father’s elder brother*); নেকাম, -মি «nēkāmā, -mī» *playing a fool* (নেকা «nēkā» *idiot, fool*); ছেলেম, -মি «chēlē mā, -mī» *childishness* (ছেলে = ছালিয়া «chēlē, chālīā» *child*); বড়াম < বড়াম্ «bārām < bārāmā» *playing a big man, boasting* (বড় «bārā» *big*); বুড়াম, বুড়ম, বুড়ামি «burāmā, burāmā, burāmi» *behaving like an old man*; গিন্নাম, গিন্নম «ginnāmā, ginnāmā» *matronly talk and ways* (গিন্নি «ginni» = গৃহিণী «gṛhiṇī» *mistress of the house*); ঢেঁটাম, -মি «ḍhēṭāmā, -mī» *perversity* (ঢেঁটা «ḍhēṭā» < «ḍhṛṣṭa-»); বাঁদরাম, -মি «bādārāmā, -mī» *trickishness (used of children)* (বাঁদর = বানর «bādārā = bānārā» = «vānara»); কচকেমি, কচকাম «phācāḥkēmi, phācā-kāmā» (কচকিয়া «phācāḥkiyā» *chatterbox, over-smart fellow*); কিচলাম কিচলম, কিচলামি, কিচলিম «phicāḥlāmā, -lāmā, -lāmi, -limi» *acuteness, trickery* (ফিচাল «phicāḥlā» *an acute one*); পেজোম, পেজোমি «pējōmā, pējōmi» *viciousness* (পাজী «pāji» *mischievous character* > পাঞ্জা + আমি «pājua + -āmi»); গোঁয়ারতামি, -তামি «gōārātāmi, -tāmi» *churlishness, rashness, brusqueness* (\*গোঁয়ারত «gōārātā» *one behaving like a churl* [see p. 668], with «-ātā» affix, see §397, + «-āmi»); ছোটলোকমি «chōṭā-lōkā-mi» *meanness*; etc., etc.

The word ঘরামী «ghārāmī» *house-builder, maker of a hut* (= ঘর + কাম > আম + দে «ghārā + (k)āmā + I») comes under this.



- (17) আর, আরী (আরি) < -ārṣ, -āri (-āri) >, অরি, ইরি, উরি < -āri, -iri, -uri >, রী < -rā > (i).

412. From < -kāra, -kārin (-kārika) >, forming agent nouns : দোহার, দোহার < dō(h)ārṣ < < \*dhuāra > *member of a chorus* (dhruva-kāra); পূজারী < pūjārī > *worshipper* (pūjā-kāri-); কাঁসারী < kāsārī > *brass or bell-metal worker* (kāṣya-kārika); কুমার < kumārṣ > *potter*, by Vowel Harmony কুমোর < kumōrṣ > (kumbha-kāra); চামার < cāmārṣ > (carma-kāra); শাঁখারী < śākhārī > (śaṅkha-kāri-); ভিখারী, ভিখিরি < bhikhārī > bhik(b)iri > *beggar* (bhikṣā-kāri-); জুয়ারী < juārī > (dyūta-kāri-), beside জুয়াড়ী < jūārī > (dyūta- + √vṛt); MB. বাণিজ্যর < bāṇijyār > (vāṇijya-kāra); কুশারী < kuśārī > *a class of Brāhmaṇas* (kuśa-kāri-); MB. চূণারী < cūṇārī > *lime-worker* (cūrṇa-kāri-); MB. খেয়ারী < khēyārī > *ferryman* (kṣēpa-kāri-); ডুবারী < ḍubārī >, by Vowel Harmony ডুবুরী < ḍuburi > *diver* (ডুব √ḍub = MIA. buḍḍa); ধুনারী < dhunārī >, beside ধুনার < dhunuri > *cotton-carder* (ধুন √dhun *shake*); পিয়ার < piyārṣ >, fem. পিয়ারী < piyārī > *beloved* (priya-kāra, -kārikā); ছুতার < chutārṣ > *carpenter* seems to be a blend of < sūtra-dhāra > and < \*sūtra-kāra >; সেকরী < sēkārī > *goldsmith*, see pp. 194-195; উয়ারী < uārī >, বার-উয়ারী < bār-uārī >, see p. 325; গোয়ার < \*gāwār > < gāwārṣ < gāwāra > *hoor* (grāma + kāra); etc.

The word কামার < kāmārṣ > *black-smith*, in Pali < kammāra >, represents the Vedic < karmāra > (which is probably connected with the Dravidian [Tamil] < karumā > *smith, smelter*: cf. P. T. Srinivas Iyengar, 'Life in Ancient India, etc.' Madras, 1912, p. 15); and the Skt. কৰ্মকার < karma-kāra > is an artificial formation, which is now used by members of the black-smith caste as a surname.

- (18) আর, আরী (আরি) < -ārṣ, -āri (-āri) > (ii).

413. From < -ākāra- >, slightly modifying or altering the sense of the word. It occurs only in a very few words. পয়ার < pāyārṣ > *a metre* (< padākāra >, see pp. 285, 288); কিশোরী < jhiyārī > *daughter* (কৈ < jhi > < < dhītā, duhitā >: the affix has only a pleonastic force here: probably through analogy of বহুরী < bāhūrī > = বোহারী < bauhārī > [for which see p. 345], which is wrongly connected with বহু < bāhu > = < vadhū >, after the

metathesis of the « h » took place); মাঝার « mājhārā » *middle*, মাকারী « mājhārī » *middling-sized* (« madhyākāra », pleonastic; « \*madhyākārika »).

(19) আর, আরী ( আরি ) « -ārā, -ārī (-āri) » (iii).

414. From « -āgāra, -āgārin (-āgārika, -ikā) »: ভাঁড়ার « bhāṛārā » *store* (bhāṇḍāgāra); MB. কাঁড়ার, beside কাণ্ডার « kārārā, kāṇḍārā » *keel of boat* (kāṇḍāgāra); সাতার « sābhārā » *place-name* (? sabhāgāra); মেহার « mēhārā » *place-name* (? mahāgāra); ভাঁড়ারী « bhāṛārī » *store-keeper* (bhāṇḍāgārika); কাণ্ডারী « kāṇḍārī » *helmsman* (kāṇḍāgārika); মেহারী « mēhārī » *palace* (? mahāgārikā); etc.

(20) আর « -āru ».

415. Found in a few MB. words, seems to be from « -āra » (i), with addition of « -u » (i.e. « -ū < -uka »): দিশার « diśāru » *pilot* beside দিশারী « diśārī » (diśa = dik- + kārā-); ডুবাক « ḍubāru » *diver* beside ডুবারী « ḍubārī »; sts. বন্দার « bāndāru » *bard, panegyrist* (< √ vand); sts. বাগার « bāgāru » *talkative person* (vāg = vāc).

(21) আল, আল « -ālā, -ālā » (i), modified to অল, ওল « -ālā, -ōlā ».

416. The OIA. source of this is « -ā-l-a », also probably « -ā-l-u », both of which are found in Sanskrit, the sense being 'possessing,' 'pertaining to.' It has the « -l-a » affix (for which see *infra*) as its base. Examples: বাঙ্গাল, বাঙাল « bāṅ(g)ālā » *man of East Bengal* (vaṅga + -ālā); পাঁকাল « pākālā » *belonging to mud > a fish* (paṅkāla); ধারাল « dhārāl(ā) » *sharp-edged* (dhāra edge); দুধাল « dudhāl(ā) » *yielding milk* (dugdha + -ālā); মাথাল « mātthālā » *with a head, prominent, chief* (mastaka + -ālā); আঁড়াল « āṛālā » *obstruction* (আড় « āṛā » *slanting*); তেজাল « tējālā » *spirited* (tējas); পেঁচাল « pēcālā » *with twists* (পেঁচ « pēcā » < Pers. « pēc »); ভাটিয়াল « bhāṭīyālā » *belonging to the down-country > a folk-melody* (< ভাটি « bhāṭī » *flow of water* = South Bengal); বাচাল « bācālā » (vācāla); দাঁতাল « dātāl(ā) » *with (big) teeth* (danta + -ālā-); ছিনাল « chinālā » *characterless woman* (MIA. chinūla-); MB. পাক্যাল « pākālā » *heroism* (« pākā » *soldier*, see p. 353).

This affix has the usual extensions: অলা > লা « -āl-ā > -lā »: e.g., বাঙ্গালা, বাঙালা, বাংলা « bāṅ(ḍā)lā » *Bengali (speech, land)* (vaṅgāla + -ā); আলী



«-āl-ī», feminine and masculine (-ī < -ikā, -ikā), as well as abstract: e.g., বাঙ্গালী, বাঙালী «bāṅ(g)ālī» (Old Bengali = feminine = a woman of East Bengal; NB. = masculine = a man of Bengal, belonging to Bengal); নগরালী «nāḡār-āl-ī» city manners; নগরালী «nāḡār-āl-ī» gallantry, refined ways (nāḡara gallant); ঠাকুরালী «ṭhākūrālī» ways of a god, divinity; চতুরালী «cātūrālī» smartness; মেয়েলী «mēyēlī» < \*māīālī» belonging to women; ছিনালী «chinālī» coquetry; রূপালী, রূপোলী, রূপুলি «rupālī» rūpōlī > rupulī > silvery; সোনালী «sōnālī» golden; নিদালী, নিদালী «ni(n)dālī» sleepiness; সূতালী «sutālī» thin as a thread; etc.

(22) আল «āl» (ii).

417. This affix, like the preceding one, denotes connexion. It is also used to form words indicative of trade or profession. It comes from OIA. «pāla» keeper, guardian by the dropping of «-p-> -w-»: «-pāla»-wāla»-āl» . Examples: রাখাল «rākhāl» , MB. রাখোআল «rākhoāl» herdsman, (rakṣā-pāla); কেশল < কাশীয়াল «Kēśal < Kāṣīyāl» low class Brāhmaṇ from Benares (Kāṣī-pāla); কোটাল «kōṭāl» , Hind «kōṭwāl» head of the police, holder of a fort (koṭṭa-pāla); বাটীয়াল «ghāṭīyāl» holder of a pass or passage (< ghāṭī); ঠাটীয়াল, বাটোআল «ghāṭāl» , ghāṭōāl» man in charge of a 'ghāṭ' (ghaṭṭa-pāla); কুঠীয়াল «kuṭhīyāl» belonging to an office > a clerk (kuṭhi kōṭhī < kōṣṭhikā); ঘড়ীয়াল «ghaṛīyāl» man in charge of a clock > ঘড়েল «ghoṛēl» acute one (ghaṭikā); etc.

There is an extension to আল «-āl-ā»: গোয়াল, গুয়াল «gōāl» > gāyl» (gōpāla-); বাড়ীআল «bāṛīāl» landlord, owner of a house; কাপড়আল «kāpār-āl-ā» cloth seller; চুড়ীআল «cuṛīāl» bangle seller; পাহারাল «pāhār-āl» watchman (prahara). Also to আলী «-āl-ī», masculine and feminine (= -ikā, -ikā): গয়ালী «gāyālī» Brāhmaṇ from Gayā (Gayā-pāl-ikā); পেটলী «pēṭēlī» < পাটিয়ালী «pāṭīyālī» maid-servant (pāṭa, pāṭī order, arrangement, domestic work); বাড়ীআলী «bāṛīālī» land-lady; etc. Abstracts are formed from «-āl» by adding the «-ī» of abstraction, e.g., রাখালী «rākhālī» the work of a herdsman; কেঁড়েলী «kēṛēlī» impertinence, roughness < কাড়ীয়াল «kāṛīyāl» rough < soldier, archer (? kanda arrow); etc.

The « -ālā, -āl-ā » of Bengali has within recent times been influenced by the cognate form in Hindōstānī, which is « -wālā »: the latter is substituted in many Bengali words in « -ālā », and ordinarily « -wālā » is reduced to ওলা « -ōlā »: e.g., কাপড়ওলা, কাপড়ওলা « kāpāṛ-ōlā (-wālā), -ōlā »; so গাড়ীওলা « gārī-ōlā » *cabby*, পাহারওলা « pāhār-ōlā » *constable*, etc. The feminine of « -wālā » is « -wālī », which, by Vowel Harmony, is reduced to উলী « -ulī » in Bengali: e.g., বাড়ীউলী « bārī-ulī » = native Bengali বাড়ীআলী « bārī-ālī ».

Through Bihārī or Hindī influence, we have also ওয়ারা « -ōārā = -wālā » in মাতোয়ারা « mātōārā (mātwārā) » *wild, mad, elated, pleased* (e.g., with perfume) = « mātwārā »: the Bengali forms are মাতাল, মাতল, মাতল « mātālā, mātālā, mātālā » *drunk* = Hind. « mātwāl ». The name বনওয়ারী « bānwārī » (see p. 521), from the Hindōstānī, can be equally from « vana-mālī » *garlanded with wild flowers* or « \*vana-pālīka » *dweller in woods*.

(23) ই < ঐ « -i < -ī » (i).

418. A secondary affix, forming nouns and adjectives. Three separate affixes of OIA. seem to converge into this single NIA. form: (i) « -ī < -in »: « mālin > NIA. mālī » *gardener*: but the force of the nominative form seems to have been only of secondary importance in the evolution of the NIA. affix; (ii) « -īya »: « dēśīya > NIA. dēśī » *native*; and (iii) « -ika »: « grāmika » > গাঁই gāī » *village name, clan name*: the feminine form of this « -ikā » is also ঐ, ই « -ī, -i », which is the most popular feminine affix of NIA., for which see below. Later in NIA. this affix was strengthened by the « -ī » of Persian.

Examples: « -ī > -i » with the sense of 'possessing, having': ভারী « bhār-ī » *heavy*; sts. রাগী « rāg-ī » *full of passion* > *choleric*; দামী « dām-ī » *costly* (dramma < Gk. drakhmē); দাগী « dāg-ī » *stained* (Pers. dāg); গুণী « guṇ-ī » *man of parts, artist* (cf. Skt. guṇin); ঢাকী « ḍhāk-ī » *drummer* (ḍhakkā); বেগুনী « bēgun-ī » *purple* (= bāḡān-ī < vātingaṇa-); OB. নোবাহী « nau-bāh-ī » *boat-man*; গাঁঠী জাল « gāṭh-ī jālā » *net with knots* (granthi-); গোলাপী « gōlāp-ī » *rose-coloured* (Pers. gul-āb = gul); হিসাবী « hisāb-ī » *careful, attentive to details* (Perso-Arabic « hisāb »); sts. মরামী « mārām-ī »



with a heart (sts. mārāmṣ < marman); ts. আলাপী < ālap-I > *courteous talker, acquaintance* (cf. Skt. ālapin); দরদী < dārād-I > *sympathetic* (Pers. dard);

With the sense of 'pertaining to, coming from': দেশী > দিশি < dēśi > diśi > *belonging to the country, country-born or made, native* (cf. Skt. dēśiya); রাঢ়ী < Rāṣi > *belonging to Rāḍha*; MB. কানড়ী, কানাড়ী < kānārī, -nārī > (Karnāṭiya); মারহাট্টী < Mārāḥāṭṭī >, মারাহী, -টী < Mārāṭ(h)ī > (Mahārāṣṭrīya); গুজরাটী < Gujārāṭī > as if from \*Gūrja-rāṣṭrīya > (গুজরাট < Gujārāṭ >, for গুজরাত < Gujārāt > < Gūrjara-trā >, through influence of < rāṣṭra >); কটকী < Kāṭṭkī > of Cuttack (Kāṭakiya); বনারসী, বেনারসী < Bānārāsī, Bēnārāsī > (Vārāṇasīya); বৃন্দাবনী < Bṛndābānī > of Brindāban; ঢাকাই < Ḍhakāi > of Dacca; ক'লকাতাই < Kālāṭkātāi > of Calcutta; etc.;

With the sense of 'connected with,' generally forming names of professions: হাড়ী < hārī > a low caste (haḍḍika); কেরানী < \*kārāṇī > clerk (karaṇika + kīraka); MB. গাড়ুরী < gārūrī > snake-charmer (gārūḍika); বেহাই < bēhāi > son's or daughter's father-in-law (vāivāhika), an inherited word, affix and all; শুড়ী < śūrī > wine-dealer (śnūḍika, śānūḍika); রাধুনি, রাধুনি < rādhānī, -dhuni > cook (see ante, p. 658); sts. নখকুণি < nakhā-kuṇi > cut or sore in the nails (nakha-kōṇa + ī); etc.

It occurs also as অই < -ai > উই < -ui >: বাড়ই, বাড়ুই < bārāi > bārui > carpenter (cf. Skt. vardhakin); বারই > বারুই < bārāi > bārui, OB. বাররী < bārāyī >, (see p. 188) grower of the betel vine (cf. Skt. < vāru-jivin >: \*বার < bārā >, \*বার < bāru > betel, an Austric word: cf. J. Przyluski in the BSLP., XXIV, p. 257). It is pleonastic in ভারুই < bhārui < \*bhārāi > a bird (bharata: \*bhāratika); চড়ুই < cārui < cārāi > sparrow (caṭaka, \*caṭakika), beside চড়া, চড়াই < cārā, cārāi > (\*caṭāka, \*caṭākika); etc.

(24) ই < ঈ < -i- < -ī- > (ii): Feminine, Diminutive, Abstract.

419. Presents an < -ikā > of OIA., and is the most common feminine affix of NIA. Examples: রাই < Rāi >, MB. রাহী < Rāhī > a name (Rādhikā); বুড়ি < \*bōḍī < ghūrī < \*ghōṛī > mare (\*ghōṛikā); মামী < māmī > maternal uncle's wife (māmā + -ī); কাকী < kākī > father's younger brother's wife (kākā + -ī); খুদী < khudī > a tiny girl > name for girls (kṣudrikā); বুড়ী < buṛī > old woman (\*vṛddhikā = vṛddhā); পাগলী < pāgālī >

*mad woman* (pāgālā + -I); বাননী < bāmaṇi > (\*brāhmaṇikā = brāhmaṇi); *sts.* বটমৌ, বটমৌ < bāṣṭāmī, -umī > (\*vāṣiṣṭhāvikā = vāṣiṣṭhavi).

A number of *sts.* forms show this < -I > of Bengali, e.g., স্ববচনী < subācāni > a form of *Durgā*; অপরী < āpsāri > (apsaras); দিগবরী < digāmbārī > a name of *Kālī*; সুনয়নী < sunāyāni > with beautiful eyes, etc., with are solecisms from point of view of Skt.

The Skt. feminine affixes < -inī, -āni > had an influence in restricting the Bengali ঙ্গে, ঙ্গে < -ī, -ī > < < -ikā >: see *infra*, under < -ni >.

With names of inanimate objects, the original feminine force is lost in Bengali. In Western Hindi, Panjābī, Rājasthānī etc., the grammatical gender, however, is preserved in the < -ī < -ikā > forms. The feminine < -ikā > also expressed a diminutive or petty aspect of an action or an object. The diminutive has become obscure in many words in Bengali, so that < -ī < -ikā > has been reduced to a mere pleonastic affix. Examples: বুলী < buli > talk (bōlla + -ī); রুটী < ruṭi > bread (cf. rōṭikā); চুয়ী < cuṣi > baby-soother (cuṣa + -ī); মটী < māṭi > (mṛṭṭikā); গলুই < \*গলহী < gālui < \*gālāhi > prow of a boat (gala-vahikā); চুরী, চুরি < churi, -ri > knife, beside ছোরা < chōrā > dagger (churikā); রাই < rāi > mustard (rājikā); পাই < pāi > a fourth, pice (pādikā); পুথী < puthi >, পুঁথি < pūthi > Indian MS., book (pustikā), beside MB. পোথ < pōthā > (pustaka-); বাতী < bāti > candle, light (vartikā); লাঠি < lāṭhi > (\*yaṣṭikā = yaṣṭi); কাঠি < kāṭhi > a thin stick (kāṣṭhikā); ছাতী < chāti > umbrella (\*chattrikā), beside ছাত < chāt > roof, ছাতা < chātā > umbrella (chattrā-); ধুতী < dhuti > 'dhoti' (\*dhōtrikā = dhōtra); যাতী < jāti > small double knife to cut betel-nuts (yantrikā), beside যাতা < jāta > mill, quern (yantra-); বড়মানুষী, বড়মানষী < bārā-mānuṣī > living like a rich man, high style (-mānuṣa + -ī); রাখালী < rākhalī > work of a herdsman (rakṣāpāla + -ikā); ডাকা(ই)তী < dākā(i)tī > robbery (see *supra*, p. 655); কেঁড়েলী < কাঁড়িয়ালী < kēṛēli < kāṛiyālī > imper-tinancy, rovediness (= kāṛiyālā > archer ? [< kāṇḍa-] > soldier, rough + -ī); পণ্ডিতী < paṇḍitī > belonging to a Pundit > a Pundit's character or ways, scholasticism; etc. Cf. Hindi < lālī > redness, < hariyālī > green colour, greenness, < rakhwālī > work of a herdsman, etc. In Late NIA., the Persian < -ī > affix of abstraction or connexion greatly reinforced this suffix.



In some stereotyped words, « -l » represents the OIA. « -ī » : e.g., রানী, রানী « rānī » (« rājñī » : or < « rāñña < \*rājñikā » ?).

(25) হৈ « -i » : Verbal Noun.

420. This affix, occurring in OIA., is practically lost to NB. It is found only in some epenthetic forms in dialectal Bengali, and it has practically become a dead suffix; only some Skt. words in « -i » help to perpetuate it. Examples : গাঁট, গাঁইট « gā(i)t » (granthi) ; মার, মাইর « mā(i)r » a beating < মারি « māri » (\*mār-i) ; সারি > সা(ই)র « sārī » sā(i)r » row (sār-i) ; MB. হাস « hāsā » (« hās-i », which occurs as a *ts.* in NB.) ; গাল, গাইল « gā(i)l » abuse (\*garh-i ? cf. Skt. garh-ā) ; শা(ই)ল « śā(i)l » a kind of paddy (śāli), also occurs in the *ts.* form in « -i » ; etc. Cf. also the OIA. suffix « -ti » in বা(ই)ট « bā(i)t », MB. সাত্তি « sātṭhi » (saṣ-ṭi), সত্তর « sātṭār » (sapta-ti), পাঁত, পাইত beside the full form পাঁতি « pā(i)t, pāti » row (paṅk-ti), etc.

(26) ইয়া, ইয়া, এ « -iā (-iyā) » > -ē ».

421. This is a compound affix, being from the OIA. « -ikā » > MIA. « -ia » + the affix « -ā », as in § 400. It is used in forming adjectives with the sense of 'pertaining to' or 'possessing' ; and frequently it is used with a slightly disparaging sense ; as well as pleonastically. In NB., it is contracted to এ « -ē », with accompanying modification through the « -i », of connected vowels. Examples : কালিয়া, কেলে « kāliā » > kēlē » the black one (contemptuous) (kāla black) ; হলদিয়া, হলদিয়া > হ'লুদে হ'লুদে « hālādīā, hāludīā » > hōlude, hōldē » yellow (হলুদ « hāludā » turmeric) ; বাইগনিয়া > বেগুনে « bāigāniyā » > bēgunē » purple, of egg-fruit (vātingana) colour ; জালিয়া > জেলে « jāliā » > jēlē » fisherman (jāla net) ; হালিয়া, হেলে « hāliyā » > hēlē » farmer (hāla = hala plough) ; নগরিয়া > নগরে « nāgariyā » > nāgurē » man of the city ; বানিয়া > বেনে « bāniā » > bēnē » merchant (\*vāṇika = vaṇik) ; মাটিয়া > মেটে « māṭiā » > mēṭē » earthen (māṭi < mṛttikā + -ika + -āka) ; (in the word মেটে as in মেটে কিরিঙ্গী « mēṭē phiringī » a Eurasian, a half-caste, we have, however, the French word « métis », approximated to the Bengali word by folk-etymology) ; উত্তরিয়া > উত্তরে

• uttāriyā > utturē > *northern*; দখিনিয়া > দখিনে, দ’খনে < dākhiniyā > dōkhnē, dōkhnē > *southern*; পূবিয়া < পূবে < pūbiyā > pūbē > *eastern*; পশ্চিমিয়া > পশ্চিমে < pāścimiyā > pōścimē > *western*; MB. আভাগিয়া < ābhāgiyā > > NB. আবাগে < ābāgē > *luckless*; পাড়াগাঁইয়া > পাড়াগাঁয়ে < pāṛāgāīyā < -gēyē > *rural* (pāṭaka + grāma + -ika + -āka); কাঁদনিয়া > কাঁদনে < kādāniyā > kādunē > *ready to weep*; MB. \*নেয়ার-আঁকড়িয়া < \*nēāyā-ākāṛiyā > > NB. নেই-আঁকড়ে < nēi-ākūrē > *one who clings to argument* (nyāya) > *obstinate*; নাগপুরিয়া > নাগপুরে < Nāgṣuriyā > Nāgṣurē > *of Nāgpur*; ওড়িয়া > উড়িয়া, উড়ে < Ōṛiyā > Ūṛiyā > Ūṛē > *Ōṛiyā, of the Odra country*; MB. (ŠKK.) নাতিয়া < nātiyā > = নাতী < nāti > *grandson* (naptṛ-); কহনিয়া > কহনে, কউনে < kāhāniyā > kō(h)unē > *talker*; জাগানিয়া > জাগানে < jāgāniyā > jāgānē > *one who awakens*; দেখনিয়া, দিয়নিয়া > দিউনে < dēāniyā, diyāniyā > diunē > *a giver*; etc.

Although one of the most common affixes in Bengali, it is frequently disguised in the Standard Colloquial by contraction and by mutation of vowels.

(27) ইএ, ইয়ে < -ie, -iyē >.

422. This NB. affix denotes ‘one who is accustomed to do a thing, a habitué.’ Typical words are খাইয়ে < khāiē > *a (good) eater*, গাইয়ে < gāiē > *a good singer, a professional singer*, বাজিয়ে < bājīē > *a clever musician*, নাচিয়ে < nāciē > *a good dancer*, খেলিয়ে < kheliē > *a clever player*, করিয়ে < kariē > *an adept*, বলিয়ে < baliē > *a conversationalist*, কহিয়ে > কইয়ে < kā(h)iē > *a good talker*. Forms like the above are used as adjectives or predicatives, and in some cases they have become nouns. They recall Western Hindi forms like • khawaiyā, gawaiyā, kabaiyā > etc. Earlier Bengali forms, not attested, would be • \*khāāiyā, \*gā(h)āiyā, \*bājāiyā, \*nācāiyā, \*khelāiyā, \*kāṛāiyā, \*bōlāiyā, \*kāhāiyā > etc. The Hindi affix < -aiyā, -awaiyā >, and the source of the NB. < -iē > are apparently identical; and it is not unlikely that the affix in NB., which is found mainly in the colloquial, is a recent borrowing from Hindi, with the usual West Bengali contraction. There is no corresponding affix in Ōṛiyā and in Assamese. Maithili has the pleonastic • -aiyā >, which, however, is different in meaning.



Hoernle takes this suffix to be «-awaiyā» and thinks that «-aiyā» is a contracted form of it; and «-awaiyā» he derives from an «-āw» from MIA. «-avva» (< OIA. «-tavya») + a pleonastic «-aiyā» (< -aka + -ika + -ka) (Gaudian Grammar, §314). But it would be more reasonable to regard the suffix to be «-aiyā», and the «-w-» only as a euphonic insertion (cf. J. T. Platts, 'Grammar of the Hindūstānī or Urdū Language,' London, 1873, p. 208). The OIA. basis of it apparently is an agentive in «-aka» (khādaka > khāaa, khāwaa, gāyaka > gāaa, gāwaa [\*gāthayaka > \*gāhaaa, \*gāheaa], \*vādya-ka [=vādaka] > \*vajjaa > \*bājaa, etc.), to which the «-ika» > -ia» and then the «-āka» > -āa, -ā» affixes were added, pleonastically, in the Early NIA. stage: «\*kathaka + -ika + -āka» > «\*kahaaīā» > «\*kāhāīyā» (Hindōstānī «kahaiyā») > कहिये «kāhiē» > कहिये «kāīyē» [koie].

(28) ইত «-it-».

423. The affix ইত «-it-» is derived from the OIA. present participle base «-ant-» (see *supra*, pp. 653-4). In Bengali, it forms the present participle in an adverbial or conditional sense, with the locative affix «-ē» : e.g., মেঘ চাইতে ভল «mēghā cāitē (< \*cāhantahi) jālā» (*on one*) asking for the cloud, (there is) rain; or করিতে করিতে «kāritē kāritē» (< \*karantahi) while doing; and it gives the base for the past habitual or past conditional (and in some East Bengal dialects, for the future) tense.

See also *supra* p. 663, under আইত, আত «-āitā, -ātā».

(29) ইব «-ibā».

424. Base for the future, and for a verbal noun, with an extended form ইবা «-ib-ā». From OIA. «-itavya-» > MIA. «-iabba-» > «\*ēbba, -ibba». See *infra*, under 'Verb.'

(30) ইল «-ilā» (i).

425. In MIA. «-illa», from OIA. pleonastic and adjectival affix «-i-la» (cf. Pāṇini, V, iii, 79), forming nouns and adjectives in Bengali, from nouns. It is not a living affix in NB., but is fairly common in MB. Cf. Hindī «chail» handsome, accomplished (chāilla, chavila).

Examples: পাতিল *pātilā* > *an earthen-pot for cooking* (*patta, pātra*); কুঁচিল *kūcila* > *crooked* (কুঁচ  $\sqrt{kūc} < \sqrt{kuñc}$ ); *sts.* †আঙিল *āṅḍila* > *strong one, chief* (*aṅḍa + -illa*); MB. *sts.* আরতিল *ārāti-lā* > *filled with a great desire* (*ārati + -ila*); পাকিল *pākila* > *ripe* (*pakva + -ila*); etc. Cf. *ts.* কুটিল *kuṭila* > *crooked*. The *ts.* word *śarira* > is vulgarly pronounced as শরীল, শরিল [*śoril*], as if it had the *-ila* > affix.

(31) ইল < -ilā > (ii).

426. Past base, also (specially in OB. and MB.) passive participle adjective. From OIA. < -(i)ta > + pleonastic affix < -i-la > whence Late MIA. < \*-iailla- > \*-illa-, in Eastern Magadhan. (OIA. < -(i)ta + -alla > probably gave < \*-alla- > -alā >, in Central and Western Magadhan). See below, under 'Verb.' This < -ilā > occurs also in a few nouns and adjectives in Bengali, although the adjectival and nominal use of < -ilā > forms from verb roots is almost obsolete in the language. Examples: MB. ভূখিল *bhukhila* > *hungry* (*bubhuṣita + -ila*); স্তিল *stila* > *sleeping* (*supta + -ila*); ভাঙ্গিল *bhaṅgila* > *broken* (*\*bhaṅgita + -ila*); OB. (Caryā 33) দুহিল দুধ *duhila dudhu* > *milk that has been milked off* (*\*dubita + -ila*); NB. গেল *gēlā* > *last < gone* (*gata + -ila*); etc.

The affix ইলে < -il-ē > forming the conjunctive, is the old locative form of it: চলিলে *calilē* > *on having walked* (*\*calillahi*).

(32) উ < উ < -u < -ū > (i).

427. From an OIA. < -u > (adjectival and nominal) + < -ka >. It implies a pettiness and loveliness of the object indicated, and is found in familiar and affectionate forms, specially of names: e.g., *sts.* দুষ্ট *duṣṭa* > *the little naughty one* (*duṣṭa-*); *sts.* ধুত *dhutta* > *the little sly one* (*dhūrta*); বল *Bālu* > affectionate for < Balarāma >; খুকু *khuku* > *tiny little baby, darling of a child* (< খোকা *khōkā* > *baby*); পাঁচু *Pācu* > (*Pañcānana* a name); so নরু *Nāru* > (*Narēndra*), হরু *Hāru* > (*Harēndra*, *Hara-nātha*, etc.), রাধু *Rādhū* > (*Rādhā-kānta*, etc.), কানু *Kānu* > (*Kṛṣṇa*); বড়ু *Bāru* > *title for a Brāhmaṇ* (*vaṭuka = vṛta + -u + -ka*); etc., etc. It occurs also (peonastically in some cases) in the formation of nouns



and adjectives, like গাড়ু < gāru > *water-jar with spout* (\*gaḍḍuka); লাড়ু, নাড়ু < lāru, nāru > *sweetmeal* (laḍḍuka); নীচু < nīcu > *down, in a low position* (nīca); উচু < ūcu > *high* (ucca-), etc. The < -u > affix of Śaurasēnī Apabhraṁśa, from OIA. < -aḥ >, seems to have influenced this affix in the formative period of Bengali (see *supra*, p. 311).

(33) \*উ, উ > ও > অ < \*-ū > -u > -ō > -ā > (ii).

428. This is a primary affix, and the forms with it are generally repeated in NB. the meaning is 'about to do something,' 'on the point of doing.' *E.g.*, ডুবু-ডুবু < ḍubu-ḍubu > *about to sink*; উড়ু-উড়ু < uru-uru > *about to fly away, filled with a longing*; নিবু-নিবু > নিবো-নিবো < nibu-nibu > nibō-nibō > *on the point being extinguished* (also নিভ-নিভ < nibhā-nibhā >); কাঁদো-কাঁদো, কাঁদ-কাঁদ < kāḍō-kāḍō, kāḍā-kāḍā > *about to burst into tears*; পাকো-পাকো < pākō-pākō > *nearly ripe*; দাউ-দাউ ক'রে জ্বালা < dāu-dāu kōrē jwālā > *to burn fiercely*, etc. The form হবু < hābu > [fiobu] *about-to-be, future* (*e.g.*, হবু-জামাই < hābu jāmāi > *the son-in-law to be*, হবু-রাজা < hābu-rājā > *the future king*) seems to be for \*হো-উ < \*hō-u >, with euphonic insertion of < b >: similarly খাউ-খাউ > খাবো-খাবো করা < khāu-khāu > khābō-khābō kārā > *to be eager to eat*, etc. (Cf. আদোবে < ādōbē >, p. 511).

In Hindōstānī, there is an affix < -ū > which appears to be the same as the Bengali one: < bēc-ū > *seller*, < kīn-ū > *buyer*, < ḍāk-ū > *robber*, < jāg-ū > *watcher*, < urā-ū > *causer to fly > spendthrift*, < bigār-ū > *spoiler*, < jhagṛ-ū > *quarrelsome person*, etc. Hoernle connects it with the Skt. < -tṛ > + pleonastic < -ka > (*op. cit.*, § 333). But a likelier derivation would be from an OIA. < -u-ka > (cf. J. T. Platts, *Hindustani Grammar*, p. 209). This affix is found in Skt., in words like < ghāt-uka, kām-uka, bhāv-uka > etc., 'having the meaning and construction of a present participle' (see Whitney, *Skt. Grammar*, § 1180). There was also an < -ūka > rather rare, in OIA.: cf. Skt. < jāgar-ūka >.

Oṛiyā has the present participle affix < -u > (< kār-u, khā-u, jā-u > etc.), which seems to be the same affix as the Bengali and Hindōstānī ones (Hoernle derives the Oṛiyā < -u >, however, from the present participle < -anta >, *op. cit.*, § 301: this is precluded phonologically).

(34) উৰা > উও, ও < -uā > -uō, -ō.

429. This is an extension of the preceding with the < -ā >, used, like < -iyā > (p. 674), to indicate relation or connexion. It is also added to proper names, to indicate contempt. When affixed to an ordinary noun, it turns the latter to an adjective. There is the usual mutation of the vowels, and this fact often disguises this affix in the NB. Standard Colloquial. Examples: জলুয়া > জলো < jāl-uā > jōlō > *watery*; ঘরুয়া > ঘোরো < ghār-uā > ghōrō > *domestic*; হাটুয়া > হেটো < hāt-uā > hētō > *of the market*; জ্বরুয়া > জরো < j(w)ār-uā > jōrō > *suffering from fever*; MB. শরুয়া < śār-uā > *like a reed* > slender (NB. সরু, শরু < śāru, śāru > *lean and thin* < < śārṣ + -ū >); ধানুয়া > ধেনো < dhān-uā > dhēnō > (i) (land) *growing rice*, (ii) *rice-beer*; কাঠুয়া > কেঠো < kāṭh-uā > kēṭhō > *made of wood*; দানুয়া > দেনো < dān-uā > dēnō > *given as a gift*; \*দীয়াখুয়া > দেখো < \*dīā-rākh-uā > dērkhō > *a wooden or earthen lamp-stand*; \*কাঠকুয়া > কেঠকো < \*kāṭhāk-uā > kēṭkō > *a wooden vessel*; টাকুয়া > টেকো < ṭāk-uā > ṭēkō > *bald-pate*; so মেছো < mēchō > *fishmonger*; বাটুয়া > বেটো < bāt-uā > bētō > *belonging to the road* (bāṭa < vartman) > *a hack*; পানুয়া > পেনো < Pānū > Pēnō > *contemptuous or familiar form of a name* (= Prāṇa-nātha, Pānnā-lālṣ, etc.); কালুয়া > কেলো < Kālū > Kēlō > (Kāla-), রেমো, শেমো < Rēmō, Śēmō > (Rāma, Śyāma); যদুয়া > ব'দো < Jādū > Jōdō > (Yadu), etc., etc.; \*মাউশুয়া > মেসো < \*māus-uā > mēsō > *mother's sister's husband* (< māusi = māṭṣvasṣ- >: cf. \*পিউসিয়া > পিসে < \*piusiā > pisē > *father's sister's husband*); etc., etc.

(35) ক, অক < -kā, (-kṣ), -ākṣ >, ইক < -ikṣ >, উক < -ukṣ > (i).

430. This affix is quite a common one in Bengali, and is employed primarily to form nouns (abstract, conerete, or onomatopoeitic), generally from verb roots: e.g., মোড়ক < mōṛ-ākṣ > *packet* (মুড়/ṣmur fold); টনক < ṭān-ākṣ > *jerk, blow, striking* > *remembrance* (টন ṭanṣ *sense of lightness*, টান/ṭān pull); চড়ক < cār-ākṣ > *a raising aloft* > *swinging by hooks from a high post, the hook-swinging festival* (চড়/ṣcār ride); ছলক < chāl-ākṣ > *splash, spill of water* (ছল chāl *onomatopoeitic for splashing of water*); so ঢলক < cāl-ākṣ > *spilling of water*; মড়ক < mār-ākṣ > *pestilence* (< maṛa = mrṭa); সড়ক < sār-ākṣ > *road, highway* (\*saṛa = srṭa); ক(ট)ক < phāt-ākṣ, phāt-ākṣ >



*gate* (cf. ফাট  $\sqrt{\text{phāt}}$  *split*); আটক  $\langle \text{āt-ākṣ} \rangle$  *confinement* (cf. আড়  $\text{ārḍ}$  *obstruction*); ঝলক  $\langle \text{jhāl-ākṣ}$  *flame* (ঝল  $\sqrt{\text{jhāl}}$ , p. 479); চটক  $\langle \text{cāt-ākṣ} \rangle$  *brilliance*; ভমক  $\langle \text{jām-ākṣ} \rangle$  *pomp*; বৈঠক  $\langle \text{bāiṭh-ākṣ} \rangle$  *a stand* (bāiṭṭha  $\langle$  upaviṣṭa); ফুক, ফুঁক  $\langle \text{phukṣ}$ ,  $\text{phūṣṣ} \rangle$  *puffing, blowing* (cf. phutkāra); ঝিলিক  $\langle \text{jhil-ikṣ} \rangle$  *sparkle*; ছিলিক  $\langle \text{chil-ikṣ} \rangle$  *spilling or scattering of water*; চুক  $\langle \text{cukṣ} \rangle$  *mistake*; সুরুক  $\langle \text{sur-ukṣ} \rangle$  *sound of quick motion*; etc.

The MIA. forms of the affix would be  $\langle \text{-akka} \rangle$ :  $\langle \text{*mōḍakka}$ ,  $\langle \text{*ṭaṇakka}$ ,  $\langle \text{*maḍakka}$ ,  $\langle \text{*jhalakka}$ ,  $\langle \text{*uvaṭṭhakka} \rangle$ , etc. In Śaurasēni Apabhraṇśa, as a matter of fact, we find such forms as  $\langle \text{sāsāṇala-jhalakkiāu} \rangle$  (= śvāsānala-jhalat-kṛta),  $\langle \text{khuḍukkaī} \rangle$  (= śalyāyatē),  $\langle \text{ghuḍukkaī} \rangle$  (= garjati),  $\langle \text{cavēḍa-caḍakka} \rangle$  (= capēṭa-caṭat-kṛta),  $\langle \text{phukki-janta} \rangle$  (= phut-kriyamāṇa) (in the Apabhraṇśa verses in Hēma-candra: cf. Pischel, 'Materialien zur Kenntniss des Apabhramśa,' Berlin, 1902). Following the indication of the Prakrit grammarians, the NIA.  $\langle \text{-akṣ} \rangle$  and the MIA.  $\langle \text{-akka} \rangle$  can be well affiliated to an OIA. compounding of a root or its participle base in  $\langle \text{-a(n)t-} \rangle$  with  $\langle \text{kṛta}$ ,  $\sqrt{\text{kṛ}}$ : চমক  $\langle \text{cāmākṣ} \rangle$  (also চৌক  $\langle \text{cāūkṣ} \rangle$ , চড়ক  $\langle \text{cāṛākṣ} \rangle$  in MB., the proper *tbh.* forms)  $\langle$  MIA.  $\langle \text{camakka}$ ,  $\langle \text{*camakkaa}$ ,  $\langle \text{camakkia} \rangle$   $\langle$  OIA.  $\langle \text{camat-kṛta} \rangle$ ; so চুক  $\langle \text{cukṣ} \rangle$  (cyut-kṛta); থক, থাক  $\langle \text{thākṣ}$ ,  $\text{thāḥṣ} \rangle$  *remain, be arrested* (stabh-kṛta), beside থমক  $\langle \text{thāmākṣ} \rangle$  *sudden stop* ( $\langle \text{*thambhakk[i]a} \rangle$   $\langle$  stambha + kṛta  $\rangle$ : here apparently we have a generalised  $\langle \text{-akka} \rangle$  added to a noun form in MIA.). A connexion with OIA.  $\langle \text{-a-ka} \rangle$ , apparently introduced as a *ts.* in Second and Late MIA. (the phonetics of which changed it to  $\langle \text{-akka} \rangle$ ) can also well be inferred: e.g., MIA. (Māgadhi)  $\langle \text{haḍakka} \rangle$  =  $\langle \text{*hṛd-a-ka}$ ; haggē =  $\langle \text{*ahakkē} \rangle$  =  $\langle \text{ahakam} \rangle$   $\langle$  aham; lēḍ(h)ukka =  $\langle \text{lēṣṭuka}$ ; ṇāakka =  $\langle \text{nāyaka} \rangle$ , etc. (See  $\langle \text{-ka} \rangle$  [ii] below. Cf. Pischel, § 194; Hoernle, Gaudian Grammar, § 338; JASB., 1880, I, p. 37, 'Hindi Roots'; also cf. Jules Bloch, 'Langue Marathe,' § 94). It has also been suggested, by Bloch, that the affix in part goes back to the OIA. adjectival and pleonastic  $\langle \text{-kya} \rangle$ , as in  $\langle \text{pārakya} \rangle$   $\langle$  para  $\rangle$  (cf. also  $\langle \text{māṇikya} \rangle$   $\langle$  maṇi  $\rangle$ ). Further, Bloch draws our attention to the  $\langle \text{-kk-} \rangle$  (also  $\langle \text{-k-}$ ,  $\langle \text{-g-} \rangle$ ) affix which is such a common one in the Dravidian languages, in which, apart from other functions, it is used in forming verbal nouns from

roots: e.g.,  $\sqrt{\text{naḍ}}$  > *to walk* >  $\text{naḍ-akk-ai}$ ,  $\text{naḍ-akk-al}$ ,  $\text{naḍ-akk-udal}$  > *walking*;  $\sqrt{\text{iru}}$  > *to be* >  $\text{iru-kk-ai}$  > *being*;  $\sqrt{\text{śāy}}$  > *to do* >  $\text{śāy-gai}$  > *doing*, etc., as in Tamil, and  $\sqrt{\text{unṇu}}$  > *to eat* >  $\text{unṇike}$  > *eating*, as in Kannada (Bloch, ‘Langue Marathe,’ p. 105; Caldwell, ‘Comparative Grammar of the Dravidian Languages’, 1916, pp. 542-543).

In its origin, it would thus seem that this affix is derived from  $\text{ḱṛta}$  and other forms of  $\sqrt{\text{ḱṛ}}$ . There seems also to have been present the influence of the Skt. affix  $\text{-a-ka}$ , which was Prakritised into  $\text{-akka}$ . And it is not improbable that in MIA. times a  $\text{-kk-}$ ,  $\text{-g-}$ ,  $\text{-k-}$  affix existed in North Indian Dravidian dialects (now superseded by IA.), and this affix of Dravidian was not without its influence in the establishment of  $\text{-akka}$  in MIA. of the Second and Third stages.

The ইক, উক  $\text{-ikṣ}$ ,  $\text{-ukṣ}$  forms seem to be due to Vowel Harmony, the  $\text{-ā-}$  changing to  $\text{-i-}$ ,  $\text{-u-}$  when the root or base form had these vowels, by attraction.

Extensions of ক, অক  $\text{-kṣ}$ ,  $\text{-ākṣ}$  in Bengali:

(অ)ক  $\text{-ṣkā}$ , i.e.  $\text{-ākṣ} + \text{-ā}$ : adjectival and pleonastic, with an implication of biggishness or coarseness: পটক  $\text{pāṭṣkā}$  > *cracker, squib*, beside পটক  $\text{pāṭṣkṣ}$  > *a throwing down with cracking noise*; ঢলক  $\text{caḷṣkā}$  > *a dash and a fall of liquid through overflowing*; ফটক  $\text{phaṭṣkā}$  > *dry, making a crackling noise when broken*; হাঁৎক  $\text{hōṭṣkā}$  > *grunting, ugly, rude person*; হড়ক  $\text{huṛṣkā}$  > *a bar, a bolt*; etc.

অকী, (অ)ক  $\text{-ākī}$ ,  $\text{-ṣkī}$ : with adjectival  $\text{-ī}$ : বৈঠকী  $\text{bāiṭhākī}$  > *polite, of good society* < *belonging to the drawing room*.

(অ)কী, (অ)ক  $\text{-ṣkī}$ ,  $\text{-kī}$  <  $\text{-ākī}$ : feminine > diminutive > pleonastic in NB., generally names of concrete objects: সড়কী  $\text{sārṣkī}$  > *javelin* (that which moves quickly and strikes: <  $\text{sṛta}$  <  $\sqrt{\text{sr}}$ ); হেঁচকি  $\text{hēṇṣkī}$  > *jerk* > *yawn, hiccup* (cf. হেঁচকান  $\text{hēṇṣ-ṣ-ṛā-nā}$  > *pull*); কুঁচকি  $\text{kūṇṣkī}$  > *groin* (cf. কুঁচকান  $\text{kūṇṣkānā}$  > *to be curled up*); ছিটকি  $\text{chiṭṣkī}$ , beside ছিটকিনী  $\text{chiṭṣkīnī}$  > *bolt, latch*; etc.

The affix আক  $\text{-ā-kṣ}$ , in forms like তড়াক  $\text{tārṣkṣ}$  > *with a sudden bound* (<  $\text{ṭṛta}$ ), পড়াক  $\text{pārṣkṣ}$  > *with a crack*, সড়াক  $\text{sārṣkṣ}$  > *with a quick glide*, কড়াক  $\text{kārṣkṣ}$  > *with a crackling sound*, etc., which are mostly



used with the indeclinable conjunctive করিয়া, ক'রে « *kāriyā, kōrē* » *having done* (see *supra*, p. 655, for a similar formation in আং « *-ātṣ* »), to indicate quick and abrupt movement or sound, is undoubtedly connected with the « *-ākṣ* » affix, the base apparently being a strong form in « *-ā* ».

Bases in « *-ākṣ, -ṣkā* » (the latter preferably in NB.) are used for the denominative in Bengali: e.g., MB. চমকে, চঙকে « *cāmākē, cāṅgākē* », NB. চমকার « *cāmāṣkāy* » *is startled*; ছিটকার « *chitāṣkāy* » *sprinkles*; etc.

(36) ক « *-ṣkāṣ* » (ii) > কা « *-ṣkā* », কী « *-ṣkī* », কিয়া « *-kiyā* », কুয়া « *-kuā* ».

431. This is an adjectival affix, also used pleonastically: it is also found in the strong form in কা « *-kā* », with its feminine কী, কি « *-kī, -ki* », and also in its extensions formed by superposing other affixes, ইয়া « *-iyā* », উয়া « *-uā* » etc. Examples: ধনুক « *dhānuṣṣ* » *bow* (*dhānuṣka, dhanuṣka*); ঢোলক « *ḍhōlākṣ* » (*small*) *drum* (MIA. *dholla-*); শামুক « *śāmuṣṣ* » (*\*sambukka=śambu-ka*); দোফরকা « *dō-phāṣṣ-kā* » *with two blades* (*phala-*); dialectal Bengali আমকা, তোমকা « *āmāṣkā, tōmāṣkā* » *of us, of you = our, your*; গদকা « *gādāṣkā* » *Indian club, cudgel* (< *ts. gadā*); দমকা « *dāmāṣkā* » *a rush of wind, a strong puff of wind*, beside দমক « *dāmāṣṣ* » *puff, jerk* (Pers. « *dam* » *breath*); বড়কী « *bārāṣkī* » *eldest daughter-in-law (= wife of the eldest one)*; so মেজকী « *mējāṣkī* » < « *mājhuā + kī* », ছোটকী « *chōṭāṣkī* », etc.; কেটকো < \*কাঠকুয়া « *kēṭāṣkū* < *\*kāṭh-āk-uā* » *a wooden vessel*; পুটকে « *pūṭāṣkē* < *\*pūṭ-āk-iyā* » *a tiny one* (cf. পুটি « *pūṭī* » *a tiny girl, a small fish*); মুনকে « *munāṣkē* » < মণকিয়া « *māṇ-āk-iyā* » *a maund in weight, one who can eat food-stuffs weighing a maund*; so সেরকে « *sērāṣkē* < *\*sēr-āk-iyā* » *weighing a seer*; শটকে « *śāṭāṣkē* » < \*সটকিয়া « *śāṭāṣṣ-iyā* » *plain numeration table upto 100* (from \*সটক, সড়ক « *\*sāṭāṣṣ, sāḍāṣṣ* » *plain movement?* seems wrongly to be connected with শত « *śāṭā* » *hundred*, and turned into শতকিয়া « *śāṭā-k-iyā* » as a « *sādhū-bhāsā* » equivalent); কড়াকিয়া « *kārā-k-iyā* » *numeration table by fours and quarters* (কড়া *kārā*) *upto 100*; গণ্ডাকিয়া « *gāṇḍā-k-iyā* » *numeration table by fours* (গণ্ডা *gāṇḍā*) *and eighties, upto 400*; so বড়কে < বুড়কিয়া « *burāṣkē* < *burī-k-iyā* » *numeration table by twenties* (*burī* *বুড়ি*) *upto 2000*; পণকে < পণকিয়া « *paṇāṣkē* < *pāṇā-k-iyā* » *numeration table by eighties* (পণ *pāṇṣ*) *upto 8,000*; etc.

This affix would seem to be the Skt. pleonastic and adjectival «-ka» (see Whitney, Sanskrit Grammar, § 1222), introduced into Second and Late MIA. as a *ts.* form, and normally becoming «-kka». In Magadhan, it seems to have been used for the genitive, as, *e.g.*, in Maithili «ghōrā-k» *horse's*, in Oṛiyā «puroṣaṅ-kā» *men's*, and in early and dialectal Bengali as well. In the other NIA. languages, like Western Hindi, however, the genitive affix «-kā, kau» etc. seems to have come from «kaa < kṛta» ; but it is not unlikely that there was some influence of this very common and resuscitated OIA. affix. An adjective-genitive use of «-kka» is found also in Śaurasēnī Apabhraṃśa as in Hēma-candra: *e.g.*, «bappi-kī bhūmbaḍī» (= pāitṛkī bhūmiḥ). In the Avahatṭha of the 'Prākṛta-Paingala,' the «-ka» for the adjective genitive figures largely.

There is a pleonastic use of this «-kṣ», mainly after verbs, in Bengali and in other Magadhan languages (see *infra*, Verb: 'Pleonastic Affixes'): *e.g.*, হইবেক «hāibē-kṣ» *it will be*; করুক «kār-u-kṣ» *let him do*; খালেক «khālē-kṣ» *he ate*; নাইক «nāhi-kṣ», MB. নাইকর «nāhi-k-āy» *is not*, beside Early Assamese নাইকর «nāhi-k-āntā» *they are not*; and Magahi «√hī-k», Maithili «chi-k» *to be*. These last instances would show that «-kṣ», like the «-r-» affix (iii) below, was added to the root: probably here was some confusion with «-kṣ» (i) (<√kṛ), as in ঠা «thā» (<√sthā) beside থাক, থাক «√thāk, thāk», Maithil «√thik» (<√stabh+√kṛ). But «-ka» was used after other words also: *e.g.*, কিন্তুক «kintu-kṣ» *but* (kintu); etc.

See *infra*, under 'Tatsama Suffixes: «-ka»'.

(37) কর «-kārṣ».

432. Found in দোকর, তেঁকর «dō-kārṣ, tē-kārṣ» *two-fold, three-fold*, is the Skt. noun «kara», which is also partly the source of the genitive, and of one of the dative affixes of Bengali, as well as of the common plural affix «-rā».

(38) গোছ, গোচ «-gōc(h)ṣ» < গোছের «gōch-ērṣ».

433. This is compounded with adjectives and nouns, and is used, like the English *-ish*, to mean 'like, resembling, of the group of.' The



word is the Skt. « gūccha » *bundle*; and গোছ(ী) « gōchṣ (gōchā) » occurs as a numerative in Bengali. The use of the genitive form is apparently the older one: লম্বাগোছের মানুষ « lāmbā-gōchēṛṣ mānuṣṣ » lit. *a man of the 'tall-group' = a tallish man*, which was shortened to লম্বাগোছ মানুষ « lāmbā-gōchṣ mānuṣṣ »; so মাঝারী-গোছের > -গোছ « mājhārī-gōchēṛṣ, -gōchṣ » *about middling-sized*; ছোট-গোছের > -গোছ « chōṭā-gōchēṛṣ » > -gōchṣ « *rather like a lad, youngish*.

(39) চ, আচ « -cṣ, -ācṣ ».

434. In a few words like কানচ « kānācṣ » *belonging to the edge, edge*, কোণচ « kōṇācṣ » *belonging to a corner, aslant*, ঘামাচী « ghāmācī » *prickly heat*,—the « -c- », or « -āc- » affix seems to be from the OIA. « -tya » forming adjectives (= karṇa-, kōṇa-, gharma- + -tya).

(40) জা « -jā ».

435. From « jāta », found in some familiar forms of surnames: = 'son of.' *E.g.*, ঘোষজা « Ghōṣṣ-jā » *of the Ghosh family*; বোসজা < \*বসুজাত « Bōṣṣ-jā < Bāsu-jāta » *of the Bose or Basu (Vasu) family*; মিত্রজা « Mittirṣ-jā » *of the Mitter (Mitra) family*.

(41) ট « -(ā)ṭṣ » (i), and its extensions.

436. This affix, found in other NIA. speeches, forms quite an important group with its extensions, and indicates either some resemblance, connexion or modification in a general way, or trade or habit. In some cases it has become merely pleonastic, like the « -ḍ- » > -ṛ- » suffixes (see below, §§449, 450), which seem to have influenced it in its pleonastic use. It represents a MIA. « \*vaṭṭ- », from the OIA. formations « varta, vartika, vartikā; vṛtta, vṛttika, vṛttikā » from « √vṛt ». This affix occurs in Hindōstānī as « -āwaṭ, -āhaṭ », and in other forms of NIA. also.

ট « -ṭṣ » < « vartta »: abstract or concrete nouns: দাপট « dāpāṭṣ » *power, puissance, rule, high-handedness* (darpa-varta); সাপট « sāpāṭṣ » *being in a fury, indulging in heroic gestures, seizing boldly* (sarpa-varta); ঝাপট « j(h)āpāṭṣ » *gripping, splashing, struggling, dashing as with wings*

(\*jhampa-varta); আতট, আতট < āṇ(g)ātṭṭ > *entire, not torn (as of a plantain leaf)* (< āṇḡa-varta > : আতট < āṇ(g)ātṭā > *ring of a vessel*, আতট < āṇṭī > *finger ring represent* < āṇḡṣṭha >); বাথট < mātḥātṭṭ > *capital levy* (\*masta[ka]-varta), etc.; and other words like উতট, হোতট < ucātṭṭ, hōcātṭṭ > *stumble* (? ava-tya + varta) also seem to have this affix. Cf. কেওট, ক্যাওট < kēōṭṭṭ > [kəōṭ] (kēvaṭṭa < kāivarta).

ট < -ṭṭṭ > from < vṛtta >, forming adjectives and nouns: ধোয়াট < dhōāṭṭṭ > *smoky, mass of smoke* (dhūma- > dhūā, dhōā + ṭṭṭ < vṛtta); ঘোলাট < ghōlātṭṭ > *muddy, muddiness* (< ghōlā > *muddy, turbid* < ghūrṇa + vṛtta); ভরাট < bhārātṭṭ > *filled-up, well-filled, a filling-up* (bhara- + vṛtta); জমাট < jāmātṭṭ > *congealed, frozen, compact* (< jāmā > < Perso-Arab. < jam > + < vṛtta >); etc.

টা < -ṭā > (= < -ātṭṭ > above + < ā >): forms adjectives and nouns, and denominative bases from forms with < < -ṭ- >: চেপটা < \*cipṭā > < \*cipātā > *flat* (< √cip > *press, flatten* + < vṛtta >: cf. MIA. < cividāa >. Skt. < cip-ṭaka > = চিড়ি, চিড়া < ciṛā, ciṛā > *flattened rice*, with the affix < -ḍ- > -ṛ-, see p. 689); ঝাপটা < jhāpṭṭā > *spray of water, an ornament for the head with tassel of pearls* (cf. < jhāpātṭṭ > above); নেওটা by Vowel Harmony নেওটা < nēōṭā > > [nəōṭo] *affectionate, attached* (\*nēhātṭ-ā < nēha-vaṭṭa-, snēha-vṛtta-); ঘষটা < ghāṣṭṭā > *getting rubbed, or rubbing continuously*, as opposed to ঘষ < √ghāṣ > *to rub* (gharṣa-varta-); শুটুকা < \*śūṭṭkā < \*śūkhātṭā > *lean and thin, dried up, shrivelled* (śuṣka + vṛtta); উকটা < ukṭṭā > *rummage, eagerly search* (\*utka-varta-); কসটা, কচটা < kāsṭṭā, kācṭṭā > *rinse* (karṣa-varta-); খেমটা < khēmṭṭā > *a kind of style in dancing and singing* (? + varta); নেঙটা < nēṅṭā >, †নেংটা [nəṅṭo], লেগটা < lēṅṭṭā > *naked* (\*naggawātṭa-, naggavaṭṭa-, nagna-vṛtta-); পাঁজটা < pāṣṭṭā > *ashen or grey in colour* (pāṇṣu-vṛtta-); চিমটা < cimṭṭā > *tongs, pincers* (MIA. ? \*cimma + vṛtta); etc.

টি, টি < -ṭī, -ṭi >, generally = the feminine form of the < -ṭ- > affix (< -vaṭṭi = vartikā, vṛttikā). In MB. and NB., the feminine force is absent, and < -ṭī, -ṭi > has become either merely pleonastic, or vaguely diminutive: e.g., বাপটি, ঘুপটি < ghāpṭṭī, ghupṭṭī > *lying in wait to waylay* (? MIA. \*ghappa, \*ghuppa = ghōppa- + vṛttikā; cf. dialectal Bengali



†ঘোপ(ী) < ghōp(ā) > *corner, nook*; চিম্টি < cimṭi > (MIA. \*cimma + vṛttikā); গুম্টি < gumṭi > *bastion, sentry-box, tower* (gulma + vartikā); \*শুখ্টি > শুটকী < \*śukḥṭi > śūṭṭkī > *dried fish* (? śuska-vṛttikā); ছিপ্টি < chipṭi > *whip* (kṣipra-); similarly we have this affix in words like খুনসুটি < khunṣuṭi > *bickering, picking up a quarrel*; etc.

টা < -ṭā > and টা, টি < -ṭi, -ti > have given the so-called post-fixed 'Definite Articles,' or 'Enclitic Definitives' of Bengali,—< -ṭā >, the original strong masculine base, implying biggishness or erudeness of the object, and < -ṭi, -ti >, originally feminine, implying smallness or daintiness. Thus, we have একটা < ēkaṭā > *one piece, a big or ungainly article*, একটি < ēkaṭi > *one piece, a small and nice one* (= \*ēkka-vaṭṭa-, \*ēkka-vaṭṭia < ēka-vṛtta-, -vṛttikā): so দু(ই)টা > দুটো, দু(ই)টি > < du(i)-ṭā > duṭō, -ṭi >; তিনটা > তিনটে, তিনটি < tinṭā > tinṭē, -ṭi >, etc. The affix has gradually become a distinct definitive in Bengali, being added to names of persons and things and to adjectives: e.g., গাছটা < gāchṭā > *that tree, that big tree*, but গাছটি < gāchṭi > *that tree, that nice little tree*; রামটা < Rāmṭā > *that ungainly, awkward, or bad fellow of a Rāma*, but রামটি < Rāmṭi > *our good fellow Rāma*; so ভালটা, ভালটি < bhālā-ṭā, bhālā-ṭi >; etc. টা, টি also occur dialectally as ডা, ডী < -ḍā, -ḍi >. The source of this টা, টি < -ṭā, -ṭi > has been suggested as being গোটা, গুটি < gōṭā, guṭi > *piece*: but the latter is a different word. See *infra*: under 'Numeratives or Enclitic Definitives.'

টিয়া > টে < -ṭiyā > -ṭē > (-ṭ- + -i- + -ā < -vṛtta + -ika- + -āka), indicating 'habit' or 'nature,' or 'resemblance': e.g., আমটে < āmṭē < \*ā(w)isṭiyā > *smelling of rank fish and flesh* (āmiṣa-vṛttika + āka); বোলাটে < ghōlāṭē > *muddy-like* (see বোলাটে < ghōlāṭṭā >, p. 685); ভাড়াটে < bhārāṭē < bhārāṭiyā > *tenant, (cab) plying for hire* (bhāraka-vṛtta + -ika + -āka); ধোয়াটে < dhōāṭē > *smoking-like* (see ধোয়াটে < dhōāṭṭā >, p. 685); তামাটে < tāmāṭē > *copper-red in colour* (tāmā < tāmra-); রাঙ্গাটে < rāṅ(g)āṭē > *reddish* (রাঙ্গা rāṅgā red); পাগটে < pāṣuṭē > *greyish* (see পাগুটা < pāṣuṭā >, p. 685); রোগাটে < rōgāṭē > *sickly, lean and thin like* (< রোগা < rōg-ā > *sick*, see p. 659); বগড়াটে < jhāgḍāṭē > *quarrelsome* (< jhāgḍārā); হিংস্ফটে < \*hiṅṣṭi > hiṅṣṭi < *ts.* \*hiṅsuka + -ṭiyā >, beside হিংস্ফটে < hiṅṣuṭē > *envious and spiteful*; etc., etc.

Connected with this «-t-» affix is ড «-ḍ-» > -r-» (i) below.

(42) ট «-ṭ-» (ii).

437. In a few words, which may be called disguised compounds : from Skt. or OIA. «paṭṭa». Examples : লেঙ্গট, ল্যাঙ্গট «lēṅgāṭṭ, lāṅgāṭṭ» (\*laṅga-paṭṭa, liṅga-paṭṭa), see p. 347 ; মলাট «mālāṭṭ» *cover of a book*, literally *dust-board* (মলা «mālā» + পাট «pāṭṭa» < «paṭṭa») ; a feminine > diminutive-pleonastic extension as in কষটী «kaṣṭṭī, kāṣāṭṭī < kāṣāṭṭī» *assaying stone* (karṣa-paṭṭikā, Hind. kasauṭī) ; etc.

(43) ট «-ṭ-» (iii) > আট «-āṭṭ», also আটি «-āṭi», উটি «-uṭi», ইটি «-iṭi», টি «-ṭi».

438. Like some of the other suffixes noted above, this is really a decayed word figuring in a number of disguised compounds. The source of it is «\*mṛtta, mṛttikā» *earth*, Beng. মাট, মাটি «māṭṭ, māṭi». Examples : ধোলাটি «dhōlāṭṭ» *soil washed down by rains* ; ধরাটি «dhārāṭṭi» *earth heaped up for an embankment* (dhārā+māṭi < mṛttikā) ; পেটোটি, পেটুটি «pēṭōṭi, pēṭuṭi» *earth and bits of jute mixed, for plastering mud huts* (pāṭṭ+māṭi > \*pāṭāṭṭi, \*pāṭuāṭṭi) ; তুষাটি, তুষুটি «tuṣāṭṭi, tuṣuṭi» *chaff and earth mixed* (tuṣa-+mṛttikā) ; খড়িটি «khāṛiṭi» *chalk and earth* (khaṭikā *chalk*).

(44) ড «-ḍ-» (i) > -ড়া «-ṛā», -ড়ী «-ṛī», ডিয় > -ড়ি «-ṛiyā» > -রে «-re».

439. The «-r-» affix in a number of words indicates habit or profession, or some sort of connexion : e.g., বাসাড়ে < বাসাড়িয়া «bāsāṛē > bāsāṛiyā» *dweller in a lodging house or hired apartments* (< bāsā *lodging house*, < vāsa-) ; যোগাড় «jōgārṭṭ» *arrangement, supply* (< ts. yōga) ; যোগাড়ি «jōgārṭṭi» < -ṛiyā» *an organiser, a man clever at arranging things* ; তুখড় < \*তুখড় «tukhārṭṭ < \*tikhārā» *sharp one, clever one* (< tikkha=tikṣṇa) ; বাকুড়া Bākura» *name of a person* in MB. «bāṅka, vaṅka, vakra» : when the place name, = Bankurah, the affix would seem to be of different origin : see under «-r-» [ii] below ; আগড় «āgārṭṭ» *basket-work door of hut* (agra-) ; ফাঁসড়িয়া > ফাঁসড়ে «phāsāṛiyā > phāsāṛē» *one who strangles and robs*



*travellers* (phāsā *halter-rope with loop*); বাসিয়াড়া > বেসেড়া < ghāsīārā > ghēsērā > *grass-cutter* (ghāsā, \*ghāsī *grass*); নৌড়ে < nāūrē < \*nāwārīā > a *boat-man*; MB. দাউড়, দাউড়িয়া < dbāurā, dhāuriyā > a *runner*; খেলোয়াড় < khēlōārā > a *player, an expert* > a *smart and sharp person* (slang); জুয়ারী < jūrī > *gamester*, see p. 668; \*সাপড়িয়া < সাপুড়ে < \*sāpāriyā > sāpurē > *snake-charmer*; লুঠেরা < \*লুঠিয়াড়া < luṭhērā < \*luṭhiārā > < √luṭh > *plunder*, cf. Hindi < luṭērā > *robber*; ভাঙড় < bhāṅ(g)ārā > *one who indulges in 'bhāṅg'*; কেওড়া < kēōrā > a *low caste* (\*kēvaṭa-), beside কেওট < kēōṭā > (< kēvaṭṭa, kāivarta); etc.

The source of this < -r- > would seem to be the OIA. < √vr̥ >, in a form like < vr̥tā > = *work, labour, movement*, found in the Rig-Vēda, which would give a MIA. < \*vaṭā > \*vaṭā > \*vaṭā > By extension with < -ā, -iyā, -ī < -ika > etc., we get the ডা, ডিয়া, ডী etc.

(45) ড < -r- >, ডা < -rā >, ডী < -rī > (ii).

440. This occurs in some place-names, and it comes from a Late OIA. and Early MIA. < vāṭa > *enclosure* which is found in Sanskrit as a < guṇa > formation from < vaṭa < vr̥-ta >, < √vr̥ > to *cover, to enclose*. ডা, ডি < -rī, -rī > as an affix in Bengali would therefore represent < vāṭikā > compounded with words. Examples: আখড়া < ākhārā >, Hind. < akhārā > *enclosed ground for physical exercise, club* (akṣa-vāṭa-); ভাগাড় < bhāgārā > *place outside village where dead cattle are cast away* (? < bhagna + vāṭa > : connexion with হাড় < hārā > *bones* is popularly suggested); গোয়ারী < gōārī > *place-name = Gowari near Krishnagar in Nadiya* (gōpa-vāṭikā); খোঁয়াড় < khōārā > *pig-sty* (? Persian < xug > *swine* > Bengali < \*khōgā, \*khō, khō > + < vāṭa >). The Sanskritised < nāu-vāṭa > a *fleet of boats or ships, a dock*, met with in old Bengal inscriptions, represents an Old Bengali < \*nāwa-wāṭa >, which was Persianised into < nawwārah > by the Mohammedans: < \*nāwa-wāṭa > may be connected with the dialectal word নৌড়ে above (§449).

The word < vāṭa > may equally be the source of ডা < -rā > in place names, although a non-Aryan origin, Kōl or Dravidian, for that affix is not unlikely (see *supra*, p. 66).

The word बाटोराड़ < bāṭōrāḍ > *high-way robber* (bāṭa < vartman) has nothing to do with < r >, (i) or (ii), although < -r- > (i) might have been confused with it: it comes from MB. बाटिपाड़ < bātā-pārṣa >, in which form it still occurs in NB. (< causative root < pātaya- >).

(46) ड < -r- >, ढ < -rā >, ढी < -rī > (iii).

**441.** Pleonastic affix, derived from < -ḍa- >, which was widely used in Late MIA.: *e.g.*, < vaccha-ḍa (vatsa), diaha-ḍa (divasa), gōra-ḍ-I (gāurī), nēha-ḍ-ā (snēha), hiya-ḍ-ā (hṛdaya), dōsa-ḍ-ā (dōṣa), pārakka-ḍ-ā (parakīyā), bhumha-ḍ-I (bhūmi), tēva-ḍ-u (tadvat), bh(r)anta-ḍ-I (bhrānti), nidda-ḍ-I (nidrā), dēsa-ḍa (dēśa), sandēsa-ḍā (sandēśa) >, as in the Apabhraṃśa fragments in Hēma-candra; < dukkha-ḍ-ā (duḥkha) >, as in the 'Saṃjama-mañjarī'; etc. The < -ḍa- > affix seems to have come into special prominence in the *spoken dialects* of Northern India in the closing centuries of the 1st millennium A. C. It is also very likely that it was largely used in the spoken language in the earlier stages of MIA., but the remains of First, Transitional and Second MIA. do not use it lavishly; and in Third MIA. literary remains, where the style is exclusively artificial and is modelled on the Prakrit *kāvya*s (as in the Jaina works like the 'Bhavisatta-Kaha'), it is not so common either. The Ap. verses in Hēma-candra's grammar form specimens of genuine popular poetry, and hence the < -ḍ- > words are so much in evidence there. All NIA. speeches show numerous forms with < -ḍa- > < -r- >; and some kinds of NIA., *e.g.*, the Rājasthānī dialects, employ it more lavishly than the rest, affixing it to passive participles quite freely.

The Second and Third MIA. < -ḍa- > rests on a First MIA. < -ṭa- >, which would normally represent an OIA. < -ṭa- > (or a dental < -ta- >, with or without a < r > or < ṛ > to cerebralise it). (Cf. Pischel, §599.) In Skt., we have a number of words with a < -ṭa- > affix, words which are mostly late, but a few like < marka-ṭa > undoubtedly go back to pre-Buddhic times: *e.g.*, < marka-ṭa (regarded as being Dravidian in origin: cf. Tamil < maram > *tree*); < kaṇka-ṭa, karka-ṭa (see p. 368); < karpa-ṭa > *rag* (< \*√[s]karp); < parka-ṭa; < karva-ṭa; < kukku-ṭa; < lak-u-ṭa > < lag-u-ḍa;



muk-u-ṭa (?) ; cip-i-ṭa *flattened rice* ; vadhū-ṭi ; kula-tā (explained as being from « kula + √aṭ ») ; barba-ṭa » ; etc. This « -ṭa » is not found in Vedic. There is nothing in the non-Aryan languages, Dravidian and Kōl, to warrant any influence from that side. And such a characteristic IA. suffix, so persistent in all the forms of NIA., can reasonably be expected to have an OIA. source. It seems quite possible that this « -ṛa < -ḍa < -ṭa » is only a form of a « -ta », undoubtedly the same as the passive participle affix, which was used as a secondary affix in some noun and adjective formations in Vedic (cf. Whitney, Sanskrit Grammar, § 1176, § 1245 ; Macdonell, Vedic Grammar, § 209) : e.g., « eka-tá, dvi-tá, tri-tá ; muhūr-tá ; ava-tá *well* ; raja-tá ; párvata ». Some sense of connexion with or modification of the original idea is implied by this « -ta », which also is not absent in the NIA. « -ṛa ». By spontaneous cerebralisation (see *supra*, pp. 487-488), « -ta » can very well give « -ṭa » in dialectal OIA. and in Early MIA. Thus we have OIA. « vibhī-ta-ka (beside « vibhīdaka » : < « √bhid » ?) » > \*vibhī-ṭa-ka » > MIA. « bahāḍaa- » > NIA. « bahērā » ; OIA. « āmr-ā-ta-ka » > \*āmrā-ṭa-ka » > MIA. « ambāḍaa- » > NIA. अम्र[ḍā] « āmrāḍā » ; and OIA. « śṛṅg-ā-ta-ka, śṛṅg-ā-ṭa-ka- » > NIA. « śigārā ». Throughout the whole history of IA., « -ta » > -ṭa > -ḍa > -ṛa » would seem to have been fairly common in the *spoken* language ; and after phonetic decay had put an end to most of the characteristic OIA. affixes in the Second NIA. stage, the « -ḍa » affix, with its strong cerebral sound, seems to have become quite a prominent and a popular one. The large number of names in « -ḍa », Sanskritised to « -ṭa » during the Second and Third MIA. periods (see *ante*, p. 89), would also indicate its popularity in the Indo-Aryan speech from the early centuries of the first millennium A.C.

Hoernle's derivation of this affix from a Skt. « -dṛṣa » (Gaudian Grammar, § 218) is phonologically inadmissible ; there is also the fact that the earlier form of « -ṛa < -ḍa » was « -ṭa ».

Examples of « -ṛa » from Bengali : OB. (Caryā 38) « nāva-r-i » (nāva, nāu) ; (Caryās 10, 20) « bāp-u-r-ā » a *Kāpālīka* (cf. Śaurasēni Ap. vappuḍā) ; (Caryā 10) « pākha-u-r-i » *petal* (pakṣa = parva) ; MB. (ŚKK.) मृद[ṛ] « mudāṛi » beside मृदि « mudi » *ring* (mudrā) ; MB. निद्र[ṛ] « nidrāṛi »

• diyārī > *lamp* (< dīpa); মাকড় < māḱāṛṣ > (*markaṭa*); কাপড় < kāpāṛṣ > (*karpaṭa*); রাজড়া < rājāṛā > *king, rich men* as in রাজা-রাজড়া < rājā-rājāṛā > *kings and swells*; so গাছ-গাছড়া < gācchā-gācchāṛā > *plants and herbs* (*gaccha*); কাঠ-কাঠড়া < kāṭhā-kāṭhāṛā > *wood and timber* (*kāṣṭha*); পাতড়া < pātāṛā > *leaves and sticks* (< patra); আঁকড়ী < āṅḱāṛī > *loopy writing* (*aṅka*); শাশুড়ী < \*শাশড়ী < śāśūṛī < \*śāśāṛī > *mother-in-law, beside* শাশ < śāśāṣ > in compounds (*śvaśrū*); চামড়া < cāmḱāṛā > *hide, skin* (*carma*); পাখড়া < pākḱāṛā > *scapular-bone* (*pakṣa*); খাগড়া < khāḱḱāṛā > *reed, marsh plant with sharp edge* (*khadga*); বাগড়া < bāḱḱāṛā > *obstruction* (*sts.* < vyāghāta + -rā); ঝগড়া < jhāḱḱāṛā > *quarrel* (see p. 478); আতুড়ী, আতুড়ী < āt(u)ṛī > *entrails* (*antra*); বহুড়ী < bā(h)uṛī > (*vadhūṭī, vadhūṭī, vadhūṭikā*); বিউড়ী < \*বিউড়ী < jhiuṛī < \*jhiāṛī > (< dubitṛ); মোহড়া < mōhāṛā < mubāṛā > *vanguard* (*mukha*); কেওড়া < kēḱḱāṛā > (*kēṭaka-*); চিড়া, চিড়া < cīṛā, cīṛā > *flattened rice* (*cipiṭa-*); হুমকুড়ী < cumkuṛī > *making the sound of kissing > assuring* (as a horse) (*cumba-*); ফুসকুড়ি < phuskuṛī > *a small boil* beside কোসকা < phōskā > *a large boil or sore*; মামড়ী < māmḱāṛī > *crust on the surface, as on a healing sore* (*marman sensitive or exposed part*); চুপড়ী, চুবড়ী < cupḱāṛī, cubḱāṛī > *basket* (from a *dēśī* root meaning *to cover*? cf. চুপ < cupḱ > *quiet, hidden*; চাপ < √cāp > *press*); চাঙ্গড়া < cāṅ(g)ḱāṛā > *large basket*; হিজড়া < hijḱāṛā > *hermaphrodite* (< Pers. < hīz >); etc.

The < -r > affix also figures in verb-roots: দৌড় < √dāu-r- > *run* (*davaḱa, drava-* < dru); see *infra*, under 'Verb: Roots.'

In some cases, < -r > figures as র < -r > apparently through originally dialectal pronunciation: e.g., কাঠরা < kāṭhāṛā >, see *supra*; গাঁঠরী beside গাঁঠড়ী < gāṭhāṛī, -rī > *baggage* (*granthi*); টুকরা < ṭukḱāṛā > *a piece*, beside Hindōstānī < ṭukṛā > (see p. 489); ছোকরা < chōḱḱāṛā > *a boy* (conn. with < śāba > > ছা < chā > ?); চাঙ্গারী < cāṅ(g)āṛī > *little basket*, beside চাঙ্গড়া < cāṅ(g)ḱāṛā > *above*; পেটরা < pēṭḱāṛā > *box* (\*pēṭṭa = pēṭṭa = pēṭṭa-); বাঁশরী < bāśāṛī > *bamboo flute* (*vañśa*); ছায়রা < chāyṛā > *shade* (see p. 342); ভায়রা < bhāyṛā < bhāi > *wife's sister's husband*; etc.

(47) ত < -tḱ >, তী < -tī > (i).

442. Found in a few words, in the abstract sense. From MIA.



« -tta » < OIA. « -tva » : *e.g.*, MB. আইহত > আয়ত > NB. এওং « āihātā » > ঐয়ত > ঐত (avidhavatva), also with তী « -ti » with « -i < -ikā » ; *sks.* ‡ « raizot » (= rājya + tva) in the 'Crepas Xaxtrer Orthbhed.' This affix was later reinforced by the Perso-Arabic affix noted at p. 656.

(48) ত « -tā », তা « -tā », তী « -ti » (ii).

443. From « patra- » as well as « pātra- », a decayed word figuring in some disguised compounds in which it has acquired the force of an affix : *e.g.*, নামতা « nāmātā » *multiplication table* (nāma-patra-); রাঙ্গতা « rāṅ(g)ātā » *linen, copper-foil* (raṅga-patra-); চাকতি « cākṣti » *some flat or mashed object cut into a ring* (cakra-patra + -ikā); চূনাতি « cūnāti » *lime-box (for betel)* (cūrṇa-pātra + -ikā); MB. চামাতি « cāmāti » *thong* (carma-patra + -ikā) : cf. also করাত « kārātā » *saw* (kara-patra).

(49) ত « -tā », তা « -tā », তী « -ti », উতি « -uti » (iii).

444. From « -putra, -putrika, -putrikā » : a decayed word in disguised compounds : *e.g.*, জেতৃত, খুড়ৃত, মাতৃত, পিতৃত « jēṭhut(ā), khurūt(ā), māsut(ā), pisut(ā) » respectively, = *son of father's elder brother, father's younger brother, mother's sister, father's sister*, also with তা « -tā » (see p. 508); MB. (ŚKK) একুইতি « ēkūiti » (ēka-putrikā); বালতি « bālṣti » as in « rārī bālṣti » *widow, and having small children only* (bāla-putrikā); চাটুতি « cāṭuti » *a surname = Chatterji* (« caṭṭa-putra- » : see p. 409).

(50) নী, নি « -nī, -ni », ন « -nā » ; ইনি « -i-ni » ; অনী, অনি, উনি « -ānī, -āni, -uni ».

445. In OIA. « -nī » and « -ānī » are two feminine suffixes which occur with a number of forms, *e.g.*, « pat-nī » (< pat-i) ; « paruṣ-ṇī » (paruṣa) ; « rōhi-ṇī (fem. of « rōhi-ta » : may be from « \*rōh-in ») ; asi-k-nī, har-i-k-nī » ; and « indr-ānī, varuṣ-ānī, rudr-ā-ṇī, bhav-ānī, upādhyāy-ānī, māstul-ānī », etc. (Cf. Whitney, § 1176 d, § 1223 b, c.) Here « -i » is the proper feminine-indicating affix, and the « -n-, -ān- » apparently belonged to the base of the noun. Practically no form in NIA. has come down with

this « -nĪ, -ānĪ » of OIA. (cf. the word সৎ, সত্য « sātā, sātā », Hind. « saut » < MIA. « savatti » < OIA. « sa-patnī »).

The OIA. feminine affix « -ā » was lost (see *supra*, pp. 305 ff.), and « -ī » also has generally not come down to NIA.,—it was weakened to « -i » in Late MIA., and when not after a vowel, it has dropped off in Bengali (see *supra*, pp. 307 ff.). OIA. « -ikā » gave, through Late MIA. « -iā », the most common, it may be said the most characteristic feminine affix of NIA., namely « -ī, -i » (cf. pp. 307, 672).

But there was the large class of nouns in OIA. with the attributive suffix « -in », giving in the masculine nominative singular « -ī » (« māli, yōgī » etc.), and feminine nominative singular « -in-ī » (mālinī, yoginī). This supplied to MIA. numerous feminine forms differentiated from the masculine only by « -inī, -inī », especially when the nominative came to be used for all the cases in the masculine, the « -in- » of the base being totally lost. Some common isolated words like « raṇṇī », NIA. « rānī » (rājñ-ī), fem. of « rāa, rāja » (rājan, rājā) also helped to establish this « -nī » as a feminine affix. So that in Late MIA., « -inī (-nī, -anī, -nī) » also was a well-marked feminine affix, side by side with « -ia < -ikā ». Moreover, « -inī (inī) » was partly generalised, and came to be attached to nouns to which it did not properly belong; and when added to masculine nouns in « -ā », the « -i- » was dropped, making it « -ā-nī ». NIA. thus inherited this « -inī, -a-nī (-inī, -a-nī) », although more restricted than « -ī », from Late MIA. In most NIA. of the recent period ('New' NIA.), the final vowel « -ī, -i » has dropped, leaving the affix at « -n (-n) »; and when in a language like Bengali, we have the full form in « -nī, -nī », it is due only to the influence of *ts.* feminine words in « -in-ī, -ānī ».

The « -i-nī, -a-nī » affix in the older periods of NIA. was not so common, and its improper use (that is, in the « -a-nī » form with original OIA. vowel bases) was less frequent; in the older periods we have commonly « -ī ». Gradually the « -n- » form, as more distinctive, came to dispute the field with « -ī », and to oust it from many words, and now it may be said to be equally important with « -ī » in most NIA. speeches; and in some, it is even more important. The loss of the gender sense



in the *adjective* in Bengali is also partly responsible for the curtailment of «-I», and «-nI» is becoming more prominent in distinctive feminine *nouns*.

Examples : cases of «-nI<-in-I» in OB. : «jōinI» (yōginI) ; «kariṇi», masc. «kariṇā» (kariṇI), cf. «hariṇI», masc. «hariṇā» (hariṇa) ; «ghariṇI, MB., NB. ঘরণী gharāṇI» (gṛhiṇI) ; «śunḍini» («śunḍin-I» ; also «śāṇḍika» > \*śonḍia, \*śunḍi», fem. «śunḍi-nI») ; MB. and NB. examples : NB. গোয়ালিনী, গয়ালনী «gōālīnI, gāylānI», fem. of গোয়ালী, গয়লা «gōālā, gāylā» *milk-man* (the old feminine form is গোআলী «gōāl-I», which occurs 15 times in ŚKK., whereas the new form গোআলিনী «gōālīnI» is found in the same work 12 times) ; MB. (ŚKK.) কালিনী রাত্রি «kālinī rāti» *black night* ; চোরনী, চুরনী «cōraṇI» > euraṇI, ŚKK. চুরণী, চুরিণী «curaṇI, curiṇI» *woman thief* ; NB. চাঁড়ালনী «cāṇḍālānI» *Caṇḍālā woman* (OB. = চণ্ডালী caṇḍālī) ; NB. st. অভাগিনী «abhāgini», besides the older অভাগী, আবাগী «āb(h)āgi» (< abhāgya) ; MB. টেটনী «ṭeṭānI», *bad woman* beside older টাটী «ṭhāṭ-I» (< dhṛṣṭa ?) ; NB. ডোমনী, ডুম্বনী «ḍōmḍ-nI, ḍum-nI» *Ḍōm woman* (= OB. ডোম্বী ḍōmbī) ; NB. পাগলিনী «pāgālīnI» beside older পাগলী «pāgālī» *mad woman* (the first is a literary word, the second commoner, and is used also affectionately—পাগলিনী would be regarded as being from পাগল *mad, mad one*, and পাগলী from পাগল *the mad one, madcap*) ; NB. মেছুনী «mēchunI» < \*māchuā-nI» *fish-wife* ; NB. বেহাইন, বেহান, বেহান্ «bēhāin, bē(h)ān» (vāivāhika > বেহাই bēhāi + -nI) ; NB. বাঙ্গালিনী «bāṅgālīnI» *Bengali woman*, a new, literary form, beside বাঙ্গালনী «bāṅ(g)ālānI» *woman from East Bengal* (but OB. বঙ্গালী «baṅgālī» *woman from East Bengal*, as in the Caryās, < বঙ্গাল «baṅgāla» *East Bengal people, or land*) ; সোহাগিনী «sōhāgini» *woman beloved by her husband*, beside older সোহাগী «sōhāgi» (< sūubhāgya-) : ননদিনী «nānāḍini», a new formation, literary, beside the proper word ননদ «nānāḍḍ» (nanandṛ) ; সতিন «sātin» *co-wife* (sapatnI + -nI), also সতিনী «sātinī» : cf. Bibāri «sawatiniyā», Hind. «sautin» beside Bengali সং, সতা «sātḍ, sātā» and Hind. «saut» ; নাতিন «nātin», MB. (ŚKK.) নাতিনী «nātinī», also নাতনী «nātnI», *grand-daughter* feminine of নাতী «nāti» (naptṛ-) : here we have NB. loss of final «-I» of MIA. ; so মিতিন্ «mitin» *girl friend* (< mitra), ঠাকর(ত)ন, ঠাকরন, ঠান্ < ঠাকুরাণী «ṭhākraṇ, ṭhākraṇ, ṭhān < ṭhākura-āṇI» *Madam, Lady* (< «ṭhākura +

-ānī > the wife of a < ṭhākura > a cook, or a *Rajput* would be ṭhākura < ṭhākura-nī >, a modern formation); ঘুড়নৌ > গুন্নি (Chittagong) < ghur-nī > gunnī > = < \*ghōḍa-nī > mare, beside older ঘুড়ী < \*ghōḍī > ghurī < \*ghōḍī > (= \*ghōḍī-ikā); বাঘিনী < bāghinī > tigress (< vyāghra); সাপিনী < sāpinī > female snake (< sarpa); সিংহিনী < siṅhinī > (< siṅha); etc.

(অ)নৌ < -ānī > has become the common affix to denote a woman of a particular caste or profession: সেকরানৌ < sēkārānī > woman of the goldsmith caste (< sēkyakāra >, see pp. 194-195); ধোবানৌ < dhōbānī >, woman of the washerman caste; কায়েতনৌ < kāyetānī > a Kāyastha woman; বড়িনী < bādyī-nī > woman of the Vaidya caste; কুমোরনৌ < kumōra-nī < kum(h)ārā-nī > woman of the potter caste (< kumbha-kāra); চামারনৌ < cāmārā-nī > woman of the leather-worker caste (< carmakāra); মেথরনৌ < mēthār-nī > sweeper-woman, beside মেথরাণী < mēthārānī > (< Persian < mihtar > prince, by euphemism, commonly spelt like রাণী < rānī > with the cerebral < ṛ >); চৌধুরাণী < caudhūrānī > lady of the Chaudhuri family; ডাক্তারনৌ < ḍaktār-nī > Lady Doctor; মাস্টারনৌ < māṣṭār-nī > school-mistress.

A great many common forms, however, have retained the old < -ī > and have not taken up the < -nī >: e.g., মামী < māmī > mother's brother's wife has not been ousted by MB. (ŠKK.) মামুলানৌ < māmūlānī > (mātulānī); কাকী < kākī >, খুড়ী < khurī > father's younger brother's wife; জেঠী < jēṭhī > (= jyēṣṭhikā), জেঠাই < jēṭhāi > (= jyēṣṭhāyikā) father's elder brother's wife; শালী < śālī > wife's sister; খুকৌ < khukī > girl baby (< khōkā); রামী < Rāmī > (< Rāma), শ্রামী, শামী < Ś(y)āmī > (< Śyāma), বামী < Bāmī > (Vāmā + -ī), forms of women's names among the lower classes; দুলালী < dulālī > darling, etc. In many feminine adjectives, the MB. < -ī > has now been dropped with the weakening of the gender-sense, as in MB. (ŠKK.) বিতপনৌ < bitāpānī > (= vitapanā), পাতলী < pātālī > slim (< īpatra-la-), বিকলী < bikālī > (= vikalā), দারুণী < dāruṇī > (= dāruṇā), কৌমলী < kōḷālī = kōḷālī > (= kōmalā), আনাথী < ānāthī > (= anāthā), etc. In Late MB. and in NB., when through the influence of Sanskrit, the < -ānī, -inī > affix was regarded as an elegant form, *ibh.* formations like ননদিনৌ, পাগলিনৌ, etc., etc., were evolved by the dozen in the literary language, as well as *sts.* ones like নাগিনী, চণালিনী and চণালনৌ, বিহঙ্গিনী, চাতকিনী, কাশ্মিনী, প্রেতিনী (> colloquial



পেতুনী), পণ্ডিতানী, অনাধিনী, হতভাগিনী, ব্রজকিনী, নাপিতানী (colloquial নাপিতনৌ, নাপিতিনী), ভিক্ষুণী (< MIA. Pali « bhikkhunī »), ষ্ণ্যানী (Śūnya-Purāṇa), etc., and quite a host of others, some of which are not Sanskrit at all (e.g., বন্দিনী « bāndinī » *woman prisoner* from Persian « bandī »); but they are very freely used. (See Lalit-Mōhan Banerji, 'Vyākaraṇ-Vibhīṣikā,' Calcutta, San 1320, pp. 40 ff.)

The « -nī » affix is not to be confused with « -ānī » (13a, 14) discussed before, and also with the « -nī » in some isolated words, like রানী « rānī » (see p. 674), কাহিনী « kāhinī » *tale* (< \* kathinikā = kathānikā), etc.

(51) পনা « pānā ».

446. This well-known NIA. affix, indicating state or function, is from OIA. « -tvana- ». From the change of « tv- » > -pp- », it would seem to have originated in the South-western IA. region during the First MIA. stage, whence it spread elsewhere (see p. 508, *supra*). Examples; চোটেপনা « ḍhṛṣṭa-pānā » (dhṛṣṭa + -tvana-); গিন্নীপনা < গৃহীণীপনা « ginnī-pānā < grhīṇī-pānā »; etc.

There is an affix পানা, পনা « -pānā, -pānā » meaning 'like,' 'resembling,' 'similar to,' which seems to be a blend of পনা « -pānā » (in an extended, adjectival use) and the *sts.* word পারা « pārā » *like* < \* parāa < prāya- »: e.g., চাঁদপানা « cāḍḍa-pānā » beside চাঁদ-পারা « cāḍḍa-pārā » *moon-like*; কুলাপানা, কুলোপনা, কুলোপনা « kulā-pānā, kulā-pānā, kulō-pānā » (*flat and broad*) *like a winnowing fan*; লালপানা « lālā-pānā » *reddish*; etc.

(52) মত « -mātā, -mātā », মন « -mānā » < মন্ত « -māntā ».

447. Occurring in some pronominal adjectives and adverbs, like এমত « ē-mātā » *like this* (যেমত « jē-mātā » *like that*, etc. The form in « -nā » is due to influence of MB. « kēhānā, jēhānā » etc. See *infra*, under the 'Pronoun.' It is used as an independent word as well, e.g., আমার মত « āmārā mātā » *like me, of my sort*. A blend মতন « mātānā » = « mātā + mānā » is also found. It is from MIA. « -manta » (< OIA. « -mant- »), which figures also as a stereotyped form in some adjectives and some names, e.g., শ্রীমন্ত « śrī-māntā » *prosperous*, পরমন্ত « pāyā-māntā » *lucky*,

*luck-bringing* (pada status, position), হানুমন্ত(ী) < Hānumānt(ā) > *Hanuman*; etc.

The MIA. affix < -vanta >, influenced by the Skt. form of it, also gave the Bengali বন্ত < -bāntā > in words like গুণবন্ত < guṇā-bāntā >, ভাগ্যবন্ত < bhāgyā-bāntā >, etc.

Persian < -mand >, cognate with the Indo-Aryan < -mant- >, reinforced these affixes in Late MB., e.g., < \*aql-mand, dāniš-mand >, etc.

(53) র > র > উর < \*-rū > -ru, -ur > .

448. Originally implying 'similarity, intensity,' from OIA. < rūpa > *form, shape* > MIA. < -rūva >, this affix is generally used pleonastically in NIA. in which it occurs in only a few words: e.g., \*গোর > গোক, \*gō-rū > gō-ru > *ox, cow, cattle*, wrongly spelt গর in Bengali: cf. Hindī गोर < gō-rū > (< < gō-rūpa >, originally meaning *buffalo*); মাকার < sājā-ru > *porcupine*, beside the simple form †সেঁজা, হেঁজা < sējā, bēzā > (śalyaka- + rūpa: p. 476); বাছুর < \*bāch-ur < \*bācha-rū > (cf. Hindōstānī < bach-rū >, Marāṭhī < vās-rū >), beside MB. বাছা < bāchā > *calf* (vatsa-rūpa); MB. শশর < śāśā-ru > *hare* (śāśa- + rūpa); MB. ঘোড়ার < ghōrā-ru > *a kind of deer* (ghōṭaka- + rūpa); also MB. তুলার < tulā-ru > *a kind of deer* (<?); †গাবুর, গাবুর, MB. গাবর < gāb(h)-ur < gābhā-ru > (cf. Hindōstānī < gabh-rū >) *young person* (< garbha-rūpa > *children, young persons* as in the 'Divyāvadāna'); MB. (ŠKK.) জিঙ্গালর < jingālā-ru > *the 'Jingini' or 'Jiger' tree*; MB. কাউর, কাউর < Kā-ur < Kāw-ur < OB. কামর < Kāmaru = \*Kāma-rū > (as in Caryā 2: < Kāma-rūpa > i.e. West Assam: see *supra*, p. 299). Cf. also Marāṭhī < pākḥ-rū > *bird* (pākṣa-rūpa), Bhōjpurīyā < meherā-rū > *wife*, beside < meher > (mahilā-rūpa, mahilā), Skt. < hṛṣṭa-rūpa > *exceedingly glad*.

(54) ল < -lā >, লী < -lā >, লী < -lī > .

449. A common OIA. affix (with a variant < -ra >), < la > is found in the adjectival sense, meaning also 'possessing.' The pleonastic (svārthē) value also is very common; as well as a slightly modifying sense. The affixes < -ila > (see pp. 676-71) and < -ula > (< MIA. < -ulla >, Bengali



«-ulā», as in MB. লাজুলী «lājāuli» = «lajjā-sīlā», and রাতুল «rātulā» *red* < MIA. «\*rattulla» = OIA. «rakta + -ula») are forms of this affix, with «-i-» and «-u-» themes. The affix is in some cases found in the form of «-r-», due probably to Bihārī influence, original Māgadhī «-l-» becoming «-r-» in Bihārī (see *supra*, pp. 536-538). Examples: আদল «ādālā» *resemblance (as of one face to another)* (OB. ādaa < advaya + -la), beside আদরা «adārā»; আধলা «ādhālā» *half, half-piece*, beside আধেলা «ādhēlā» (*ardha*); MB. উতরলী «utārālī» (fem. in «-ī < -ikā»), NB. উতরোল, উতরল «utārōlā» < utārālā» *anxious* (uttvara-la); ছাওয়াল «chāwālā» *child*, ছাওয়ালিয়া > ছালিয়া, ছেলে «chāwāliyā» > chāliyā, chēlē *boy* (śāba- + -la- + -iyā); পোলা «pōlā» beside পো(রা) «pō(ā)» *son, child* (pōta-la-); MB. ছেলি «chēli» Bhōjpuriyā «chēri» *she-goat* (chagalikā < chaga); গাড়ল, গাড়র «gārālā», gārārā» *sheep* (cf. Late Skt. «gaḍḍalikā» < gaḍḍala» *rolling animal, as in the entire flock*); দীঘল «dīghālā» *long* (dīrgha-la-); OB. fem. আগলি «āgali» *advanced* (Caryā 32: «agra-la-); পাকল «pākālā» *ripe, well-ripened* (pakva-la-); হাঁড়ল «hārālā» *big, open-mouthed pot* (cf. হাঁড়ী, হাঁড়া «hārī, hārā» *large pot*); পাতলা «pātālā» *lean and thin* < like a leaf (patra-la-), MB. fem. পাতলী «pātālī»; MB. নহলী = নঅলী «nā(h)ālī», fem. *fresh, new* (\*navali-kā); MB. (KKC.) সোহাগলী «sōhāgālī» *wife beloved by her husband* (sāubhāgya- + -lī); MB. বিজুলী, NB. বিজনী «bijulī» > bij(ā)lī, also বিজুরী «bijurī», beside Hindōstānī «bij, bijlī» (MIA. vijjulia, OIA. vidyut + -la- + -ikā); কটল «phātālā» *crack (on a wall, on the roof)* (কটি √/phātē *split*); \*সহিলা > সহেলা > সরলা, সহিলী > সহিলি, সহৈলি «\*śāhilā» > śāhēlā > śāylā, śāhili > śāhili, śāli > *friend (among women)* (sakhī + -lā, -likā); MB. মাতল «mātālā» (matta-la-); ধকল «dhākālā» *strain* (cf. ধাকা «dhākkā» *push*); বাঁধুলী «bādhulī» *a flower* (bandhuka + -likā); দাঁদলান «dādālānā» *to be on the aggressive, to be fighting and quarrelling, to oppress* (dvandva-la-); ফাঁদল «phādālā» *circumference* (< ফাঁদ «phādā», cf. Late Skt. «phaṇḍa» < \*phandra» *belly*); হাতল «hātālā» *handle* (hasta-); পয়রা «pāyā» *liquid (as of treacle)* (< payas); etc., etc. We have this affix apparently in বাদল, বাদলা «bādālā, bādālā» *cloud, rainy weather* (Late Skt. vardala-), মাদল «mādālā» *a deep-toned drum* (mardala), কাতল, কাতলা «kātālā, kātālā» *carp fish*; etc.

(55) স < -śā >, সা < -sā >, ছা, চা < -chā, -cā >.

450. This affix, meaning 'likeness, similarity, resemblance,' is derived by Hoernle from OIA. < sadṛśa > (Gaudian Grammar, § 292); but this derivation is not tenable phonologically. As a source of this NIA. affix, I suggest the OIA. affix < -śa >, as in a limited number of words in Skt., e.g., < lōma-śa, kapi-śa, karka-śa, yuva-śa, arva-śa, ēta-śa, lōpa-śa, ? giri-śa, ? kala-śa >. This < -śa > affix was both pleonastic and adjectival, with an implication of similarity: e.g., < kapi-śa > *tawny*, 'monkey-like,' < karka-śa > *harsh, grating*, 'gravel-like.' (This < -śa > is derived from an Indo-European < -ko [-kō] >: cf. Brugmann, 'Vergleichende Grammatik der idg. Sprachen', II, Strassburg, 1889, § 83.)

Examples: < -a + -śa > < -āsā >, feminine < -ās-ī >: খোলস < khōl-āsā > *covering, slough of snake* (< khōlś cover); মুখস *ts.* < mukha > + < -śā > *mask*; তড়স < tāṛā-śā > *force, influence, sympathy, as in fever due to a pain or wound* (< তাড় √tāḍ drive, beat); ধেড়স < dhēṛā-śā > *a vegetable, 'lady's fingers,'* beside ঢেড়ি, ধেড়ি < dhēṛi, dhēri > *a kind of ear-ornament*; আপস < āpā-śā > *friends, people of the same group or family* (appā < ātman, \*ātma-śa); *sts.* রূপসী < rūpāsī > *a beautiful woman* (\*rūpa-śa- + -ikā).

< -ā-śa + -āka > < -ās-ā > < -āśā >: also altered to the affricates ছা < -chā >, চা < -cā >, in the feminine, সী, চী < -sī, -cī >: e.g., পরসী < pāysā > *pice* (< pāi-sā, Hind. paisā); আলিসা > আলসা, আলসে < āli-sā > ālīsā, ālsē > *parapet on a terrace* (< āli, ālī embankment); চিপসা, চূপসা < cipśā, cupśā > *lean, pressed* (√cip press); ভাপসা < bhāpśā > *foetid, rank, dank (like vapour) with a bad odour* (\*bhāspa-śa-); পানিসা > পানসে < pāni-sā > pānsē > (by Vowel Harmony) *watery* (pāniya + -śa-); চামসা < cāmśā > *like untanned hide in smell* (\*carma-śa); চকসা < cākśā > *clearing of the sky* (cf. চকচক < cāk-cāk > reduplicated form = *to be bright*); করসা < phārśā > *light, dawning*, beside Chakma dialect < pār = phār > *light* (see p. 512); ঝাপসা, ঝাপসা < jhāpśā, jhupśā > *hazy* (cf. ঝোপ < jhōpś > *wood, grove*); আবছা < ābchā > *hazy, < cloudy* (cf. †আভ < ābhś > = < abhra > *thin cloud*); লেঙচা < lēṅś-cā > *to limp, to be like a lame man* (cf. লেঙড়া < lēṅḡḡā > *lame man*, লেঙ < lēṅ > *kick, foot, shin*); ভেংচা, ভাবচা < bhēṅ-cā, bhāṅ(g)ś-cā > *make faces or wry-*



*mouth* (cf. *bhaṅgi*); *কপচা* « *kāpṛcā* » *to chatter* (√*k|p*, *kalp*); *ঘুমসী*, *ঘুঙ্গী* « *ghumṣ-sī*, *ghuṅ-sī* » *waist-string*, 'winding thread' (< √*ghum* to wander about); *আলগোছা* « *ālāgōchā* » *without touching*, from a distance might be from « *\*ālāgā-śā* » *distinct-like* (*alagna* + *-śa*): cf. however *আলগোছে* at p. 551; *একসা* « *ēkṣā-sā* » *rolled or united into one* seems to have been influenced by, if not actually derived from, the Persian « *yak-sān* ».

There are extensions of this affix: *আসিয়া* > *চে* « *-ā-s-iyā* » > *-cē* », and *আসিয়া* > *আসে* « *-ā-s-iyā* » > *-āsē*»: *লালচে* « *lālṇcē* » = *\*lālā-siyā* » *reddish*; so *কালচে* « *kālṇcē* » *blackish*; *ফাকাসিয়া* > *ফেকেসে* « *phākāsiyā* » *phēkāsē* » (also without nasalisation) *pale, colourless*, cf. *Hindōstānī* « *phakk* » *colourless*.

In the words *সাতাসে*, *আটাসে* « *sātāsē*, *āṭāsē* » *a child prematurely born after seven months or after eight months*, the « *-āsē* » represents *মাসিয়া* « *mās-iyā* » < « *māsa* » *month*. In a few onomatopoeics, however, we have an *আপ* « *-āṣṣ* » and *উস* « *-usṣ* » which seem to be connected with this « *-sṣ* » affix: e.g., *ধপাস্* « *dhāpāṣṣ* », *ধড়াস্* « *dhārāṣṣ* » *with a loud thud*, *পটাস্*, *কটাস্* « *pātāṣṣ*, *kātāṣṣ* » *with a crack*, *ধুপুস্* « *dhupus* » *with a gentle thud* etc. Cf. « *-ātṣ* » (p. 655) and « *-ākṣ* » (pp. 681-682).

(56) *সই*, *সহি* « *sāi*, *sāhi* ».

451. OB. « *\*sāhi* », from OIA. « *sahita* », as in *জলসই* « *jālṣ-sāi* » *immersed in water*, *বুকসই* « *bukṣ-sāi* » *reaching up to the breast*, *এলসই* « *rūṣ-sāi* » ('*Hutōm-Pēcār Naksā*, 1862, p. 74) *belabouring with a cudgel* (« *rulṣ* < English *ruler*): etc. This is confused with another *সই* « *-sāi* » from the Perso-Arabic, for which see below.

(57) *সর*, *সরা* « *-sārṣ*, *-sarā* ».

452. From OIA. « *sara* < √*sr* » *moving*. This affix forms ordinals, and a few other adjectives and nouns: e.g., MB. *একসর* « *ēkāsārā* » *alone, by one self* (wrongly Sanskritised in MB. to *একেধর*, also *একধর* « *ēkēśwārā*, *ēkāsārā* »); *দোসর* « *dōsārṣ* » *a second, a supporter, a double, second*, *দোসরা* « *dōsārā* » *second, second day of the month*; *তেসর*, *তেসরা* « *tēsārṣ*, *tēsārā* » *third (day of the month)*; *চোসর* « *chōsārṣ* » *fourth, square*; MB. *সোসর* « *sōsārā* » *equal*, lit. *moving along with* (= *sama-sara*); etc. Hoernle

derives this from « spta » (Gaudian Grammar, § 271), but in MIA. this would give either « saṭa > saṭa », or « sata, sita > sa(d)a, si(d)a ».

(58) সোআ « -sōā ».

453. Found in MB., as in (ŠKK.) কানাসোআ « kṇā-sōā » *reaching the brink* (= karṇa- + -sama-).

(59) হার, হারা « -hārṣ, hāra ».

454. It occurs in a few words like একহারা, দোহারা, তেহারা, চৌহারা « ekṣhāra, dōhārā, tēhārā, cāuhārā », to mean 'fold.' (দোহারা « dōhārā » also means *stout, robust, 'double-sized'*). The source seems to be the Skt. « hāra » *division, portion* (Yōgesh Chandra Vidyānidhi, Bengali Grammar, VSPd., p. 178). Cf. MB. বাট্টিহার « ṣāṭhi-hāra », \*বাট্টিহার « ṣāṭhihārā » > NB. ষেটেরা « ṣēṭērā » *sixth-day ceremony and worship after child-birth*. The affix occurs in Hindōstānī also, where it is agentive: e.g., « sirjan-hār » *Creator*, « dēnō-hārā » *giver*, « pālan-hār » *one who maintains*, etc. The Hind. « hār(ā) » is commonly derived from « kāra- » *doer*: but the aspiration in this case would be difficult to explain. There seems to have been a confusion between « kāra » > -āra » and « hāra » in Early NIA.: cf. Bengali জোকার, জাঁকার « jōkārṣ, jākārṣ » *shout or song of triumph*, beside জোহার « jōhārṣ » *salutation*, Hind. « juhār », found also in Kōl as « juhar » *salutation*; দোহার « dōhārṣ » < « \*dhuārā » *singer in a chorus* (< dhruva-kāra).

In দেহারা « dēhārā » < দেহরা « dēhārā » *temple*, we have « ghara, gr̥ha »; and দোহার « dōhārṣ » *of two* is from « dōṇha, dōṇṇa + (k)ara ». Hoernle derives « hārṣ » from Skt. « vidha + ra » (Gaudian Grammar, § 412), but this derivation offers phonological difficulties.

455. There are in addition a number of affixes which are in most cases mutilated forms of words forming parts of compounds, and these are found mainly in place names (e.g., আস, সা, সৌ « -āsṣ, -sā, -si » < « āvāsa, -vāsa- », as in ইন্দাস, « Indāsṣ » = « Indrāvāsa », পাকড়াশী « Pākṣṛāśī » *a surname* = « Parkaṭāvāsa + -ika »; দৌ, দৌরা > দে « -di, -diyā » < -dē » as in ন'দে < নদৌরা « Nōdē < Nādīyā », from « dvipa- »; etc.);



but as these are not found in derived verbal or nominal forms of the language, and have long lost all force of affixes, they are not considered here. (See Y. C. Vidyānidhi, *Bengali Grammar*, VSPd., pp. 188-199). Affixes like ভর, ভরা < -bhārāḥ, -bhārā > (e.g., পেট-ভরা < pēṭṭa-bhārā *belly-full*, দিন-ভর < din-bhārā > *all day long*), করা < -kārā > (as in শত-করা < śatā-kārā > *by the hundred, per cent*, where < kārā > = Bengali passive participle of কর < √kār >, corresponding to < kṛta > : Hindōstānī has < kaḍa > as in < sai-kaḍā, sai-kaḍī >, where < kaḍa > curiously enough preserves the old Māgadhī equivalent of < kṛta > which is lost to Bengali) are but compounded words, and are self-explaining; and they need no further discussion.

## [II] TATSAMA SUFFIXES.

456. From the large and ever-increasing *tatsama* element in Late MIA. and in NIA., a number of common Sanskrit affixes were familiarised, and gradually these have been adopted into the language, their naturalisation being indicated by the formation of hybrids with *lōk.* or foreign roots or words. There seems, moreover, always to have been present in the minds of speakers of Late MIA. and Early NIA. a sense of some vague connexion between the < -ā, -ā > of nouns and adjectives and Skt. < -ākā, -ākā >, and between the < -a-, -ia- > of the passive participle with < -ta, -ita > : a connexion which the scholars have always noted and indicated.

In Second and Late MIA., as a single unvoiced stop would not be allowed intervocally (at least in orthography), the < -k- > or < -t- > of the *ta.* affixes would be written < -kk-, -tt- >, and free use of this device would be made for purposes of metre or rime. This practice was continued to the Early NIA. stage: the 'Prākṛta-Paṅgala' has spellings like < rūakka (rūpaka), Mēṇakkā (Mēṇakā), Sāraṅgikkā (Sāraṅgikā), ghitta (ghṛta), āatti (āyati) >, and in Old Hindī, Old Rājasthān, etc. we find instances where this tradition is carried on, like < matti (mati), Sarasatti (Sarasvati), Manmaththa (Manmatha), sukkha (sukha), hayaggaya (haya-gaja), jagga (jagat), uṛaggana (uḍa-gaṇa), saddāi (sadā) > etc., and even in foreign borrowings like < surattāna (sultān),

Arabbi (Perso-Arabic «arabī »), Turakkī (Turkī) », etc. There are, however, also cases of doubling of other consonants than stops and aspirates in Late MIA. and Early NIA. In OB. of the Caryās we find also a few cases (see below, under «-ta, -ita »).

(1) ইমা «-imā ».

457. From OIA. «-iman », with the force of the English *-ness*: found also in MIA., e.g. «munisima (=manuṣyatva), gahirima (gabhīratva), vaḍḍhimā (vṛddhi-bhāva) », etc. OB. (Caryā 34) «pārima » (=pāra); MB., NB. বক্রিমা «bāṅkimā » (vakra-tva), লালিমা «lālimā » *redness*, রাক্তিমা «rātimā » *redness* (raktiman), beside কালিমা «kālimā » *blackness*, নীলিমা «nīlimā » *bluish tinge*, চাঁদিমা «cādimā » *moon-light, moon-sheen*. This affix is found in other NIA. languages, but it is literary rather than popular. In Bengali, «-imā » has also a slightly diminutive force.

(2) ইয় «-Iyā » [io, io].

458. This is affixed to foreign and other names, forming adjectives: রুশীয় «Ruṣīyā » *Russian*, আরবীয় «Ārabīyā » *Arabian*, মিসরীয় «Misrīyā » *Egyptian*, খ্রীষ্টীয় «Khrīṣṭīyā » *belonging to Christ, Christian*, ইটালীয় «Itālīyā » *Italian*, ডেনীয় «Dēnīyā » *Danish*, হেগেলীয় «Hēgēlīyā » *Hegelian*, etc.

(3) ক «-ka ».

459. It is sometimes difficult to decide whether the pleonastic «-ka » of Bengali comes from MIA. «-kka » (see p. 683), or is an OB. or MB. employ of the *ts.* affix. The Skt. «-ka » undoubtedly sustained in Bengali this MIA. borrowing from it, and helped to extend its use. When it is in connexion with *ts.* words, the «-ka » might be regarded as the *ts.* affix: e.g., রাজনৈতিক «rājānaitikā » beside -নৈতিক «-naitikā » *political*; আদিক «-ādi-ka- » > দিগ «-digā » in the oblique plural base of nouns; Skt. words with «-ka, -ika », like «bāla-ka, pañca-ka, saḥāya-ka, māsa-ika, pākṣa-ika, daiva-ika, dōla-ka, sthāpa-ka, māpa-ka, jñāpa-ka, pāṭṭya-ka, vāṣay-ika, lāukika, sāgni-ka, tirth-ika, māṅkh-ika », etc., etc. form a whole host in Bengali,



and since many of these words are freely used in the colloquial, «-ka, -ika (with modification of root vowel)» have become quite familiar as adjectival affixes.

In a few words like পেটুক «pēt-ukṣ» *glutton*, মিতুক «miṣ-ukṣ» *sociable*, লাজুক «lāj-ukṣ» *shy*, মিথুক «mithy-ukṣ» *liar*, we have probably the Skt. affix «-uka» ; cf. also হিংসুক «hiṁs-ukṣ» *envious*.

See also below, under 'Verb : Pleonastic Affixes.'

(4) ত, ইত «-t(ā), -it(ā)».

460. The passive participle affix of OIA. (Skt.), it is in very common use. It was apparently re-introduced in the Late MIA. period, in which it was written «-tta, -itta». This affix is frequently used with *tbh.* and *sts.*, as well as foreign roots and words, showing its complete naturalisation. Examples: OB. (Caryā 8) ভরিতী «bharitī» *filled*, fem. in «-ita» + «-ī» ; (Caryā 9) নিবিতা «nibitā» (nirvṛta, MIA. \*nivvitta-); so (Caryā 12) পরিনিবিতা «parinibittā» ; (Caryā 30) উইতা «uittā» (MIA. «\*uitta-» for «uia» = «udita»); MB., NB. থকিত «thakit(ā)» *astonished* (thakka < \*stabh-kṛta + -ita), খলিত «khālitā» *slipped* (√skhal), লখিত «lākhitā» *seen, noticed* (√lakṣ), জানিত «jānitā» *known* (see p. 654), করিত «kār-it(ā)» as in করিত-কর্মী «kāritṣ-kārmā» *experienced* (=kṛta-karmā), জন্মিত, জন্মিত «jānmit(ā), jānmit(ā)» *begotten*, উজলিত «ujālitā» *brightened* (< ujjala), অবিবৃত «ābiyātā» *unmarried* («ā- + biyā < vivāha + -tā» : cf. Hindi «byāh-it» *married*); এলায়িত «ēlayitā» *dishevelled* (where «ēlā» < আলা, আউলা «ālā, āulā» = «ākula-», see p. 383, + «-itā»); etc. ; নিকাহিতা স্ত্রী «nikāh-itā stri» *woman or wife married in the nikāh form* (< Perso-Arabic «nikāh»); বাপ্তাইজিত «bāptāij-itā» *baptised*; and even আইনামুসারে রেজেষ্ট্রিত «āinānusārē rājēṣṭritā» *registered in accordance with law* (Perso-Arabic «ʿaln» : রেজেষ্ট্রিকৃত «rājēṣṭrikṛtā» is more common, however). A number of wrong forms in «-i-tā», created by Bengali writers, have become well-established in the language, like খনিত «khānitā» (=khāta), ইচ্ছিত «icchitā» (=iṣṭa), দংশিত «daṁśitā» (daṣṭa), অনুবাদিত «ānubādītā» (anūdita), সিকিত «siñcitā» («sikta», causative «sēcita»), নমিত «nāmitā» (nata), আহরিত «āhāritā» (āhṛta, āhārita), একত্রিত «ēkātṛitā» (=ēkatra), নিঃশেষিত «niḥśēṣita»

(<niṣṣeṣa), etc., etc. The < sêṭ > and < an-iṭ > bases of the Sanskrit grammarians have been entirely ignored. (See *supra*, p. 201).

(5) তব্য < -tābyā > [-tobbo].

461. The Skt. < -tavya > is combined in the colloquial rather than in the literary speech with a few *tbh.* roots, through an extension of its employ in *ts.* forms : বলতব্য < bālā-tābyā >, কহতব্য < kāhā-tābyā > (√bāl, kāh=brū, kathaya-), সহতব্য, সহিতব্য < sāhā-tābyā, sāh-i-tābyā > for < sōḍhavya >; rarely with other roots, as *e.g.*, like ঋতব্য < khātābyā > (khāditavya), imitating < dātavya >.

(6) তা < -tā >.

462. The affix of abstraction, used mainly with *ts.* and *sts.* words, often wrongly : *e.g.*, সখ্যতা < sākhyā-tā > *friendship*, আধিক্যতা < ādhikyā-tā >, colloquially among women আদিখ্যেতা < ādikhyētā > *excess, effusive or gushing affection*, জাতীয়তা < jātiyā-tā > *nationalism*, রোমান্টিকতা < rōmāṇṭikā-tā > *Romanticism*, মানবিকতা < mānābikā-tā > *human character*, ভদ্রতা < bhādrā-tā >, সৌজন্যতা < sāujānyā-tā > beside সৌজন্য < sāujānyā > *courtesy*, etc.

(7) ত্ব < -twā > [-tto].

463. Quite common in Bengali with *tbh.* and even foreign words : *e.g.*, নতুনত্ব, নোতুনত্ব < nātunā-twā, nōtunā-twā > *newness* (< nāutunā : p. 345); হিন্দুত্ব < hindu-twā > *Hinduism, Hindu ideas and practices* (Persian < hindū >); বামুনত্ব < bāmūnā-twā > *Brahmanism, Brahmanishness*; মুসলমানত্ব < musāl-mānā-twā > *Mohammedan notions and ways*; ছোটত্ব < chōṭā-twā > *smallness*, বড়ত্ব < bārā-twā > *bigness*; একঘেয়েত্ব < ēkaḡhēyē-twā > *monotony* (< ēkaḡhā-iyā > *with the same beat*); কর্তৃত্ব, কত্তাত্ব < kārtā-twā, kāttā-twā > *domineering manner* (< kārtā >, *sts.* < kāttā > = ‘boss’ + < -twā >), which, through influence of words ending in consonant + < -yā > changing the final syllable into < -i > (like সত্যি < sātyi > [jōtti], পথি < pāthyi > [potthi], অবিশি < ābiśyi > [obiṣṣi] = < satya, pathya, avāśya >, see p. 406), is frequently found as কত্তাতি [kōttatti] in the Standard Colloquial.



(8) পাৱা &lt; -pārā &gt;.

464. A *sts.* form, form Skt. < prāyah > > \*parā, meaning 'like,' 'almost as': see under পান < -pānā >, p. 696. In Oriyā, this appears as < pārā >. Example: পাগল-পাৱা < pāgālā-pārā > like a mad person, also পাগলের পাৱা < pāgālērā-pārā >; < pārā > is thus used as a separate word, as it is also in Oriyā.

(9) ময় &lt; -māyā &gt;.

465. In the sense of 'full of,' 'spread about in or with': জলময় < jālā-māyā > covered with water, পথময় < pāthā-māyā > throughout the street, কাদাময় < kādā-māyā > all covered with mud, দেশময় < dēśā-māyā > all over the land, ইউরোপময় < Iurōpā-māyā > all over Europe, etc.

(10) সহ &lt; -sāhā &gt;.

466. The Skt. particle is loosely compounded with nouns to indicate inclusion: কাপড়-সহ < kāpāṛā-sāhā > with the garments on, বাছুর-সহ গোরু < bāchurā-sāhā gōru > a cow together with the calf, ঢাকীসহ বিসর্জন < ḍhākī-sāhā bisārjanā > casting the image (of Durgā or other goddess or god, after the annual worship) into water, with the drummers and all = making a thorough end of an affair; also ঢাকীসহ < ḍhākī-śuddhā >, see below; etc.

(11) শুদ্ধ &lt; -śuddhā &gt;, শুদ্ধা &lt; -śuddhā &gt;.

467. Also used in the inclusive sense: আমি-শুদ্ধ < āmi-śuddhā > including me, সব-শুদ্ধ(1) < sābā-śuddhā, -ā > including all, সাজশুদ্ধ ঘোড়া < sājā-śuddhā ghōṛā > horse with harness and all, etc. This usage apparently originated from the sense of entire, complete which the Skt. word has. The word is also spelt with a dental স < s- >, and a *sts.* or *th.* from শুধু or শুধু < sudhu, śudhu > also occurs, meaning 'only.' In Hindōstānī we have the same word in < suddhā >, also < sūdhī >; in Sindhi it occurs as < sūdhā > along with. Hoernle derives it from a MIA. < \*saūddha, \*saūddha >, from Skt. < sam-ā-dhā > (Gaudian Grammar, p. 226), but does this not look likely.

See also under 'Post-positions,' *infra*, under 'Noun.'

[III] FOREIGN SUFFIXES: PERSIAN.

468. Persian suffixes, and some words which have almost become like suffixes in Bengali, are given below.

(1) আন, ওয়ান < -ān, -wān > *possessing* (< -wān, -bān >): গাড়োয়ান, গাড়োয়ান, গাড়োয়ান, গাড়োয়ান < gārān, gārīwān, gārīwān, gārān > *cab-man*; বাগান < বাগোয়ান < bāgān < bāgwān > *garden* (= bāgwān); the word কোচুয়ান < kōcūān > beside কোচমান < kōc-mān > *coachman* seems to be the English word, with influence of the Persian < -wān >, found in দরওয়ান < dār-wān > *gate-keeper* (darwān, darbān).

(2) আনা < -ānā > *pertaining to, having the nature of* (= -ānah): with an extension আনী, আনি < -ān-i, -ān-i > (= -ānah + -i), indicating abstraction: e.g., বড়-ঘরানা < bārā-ghār-ānā > *pertaining to rich or high families*; হিন্দুয়ানী < hindu-ān-i >, হিঁদুয়ানী < hīdu-ān-i > *Hindu ways*; বাবুয়ানী < bābu-ānā >, বাবুয়ানী < bābu-ān-i > *the ways of a gentleman, luxury and dressiness*; সাহেবীয়ানী < sāhēbi-ānā > *Europeans ways, extravagance and haughty ways, etc.*, etc. See p. 592 for the intrusive < -i >, giving rise to the form < -iānā >.

(3) খানা < khānā > *place, abode* (= xānah): শুঁড়ীখানা < šūrt-khānā > *vintner's shop*; মূদীখানা < mudī-khānā > *grocer's shop, oilman's store*; ডাক্তারখানা < dāktār-khānā > *dispensary*; ছাপাখানা < chāpā-khānā > *printing establishment*; বৈঠকখানা < bāiṭhāk-khānā > *drawing-room*; etc.

(4) খোর < khōr > *eater* (= xōr): গুলিখোর < guli-khōr > *opium-smoker*; অপিম-খোর < āpim-khōr > *opium-eater*; ঘুষ-খোর < ghuṣ-khōr > *bribe-taker*; etc.

(5) গর < gār > *maker* (= gar), frequently altered to an Indian কর < -kāra >: কারিগর < kārigār > *artisan, craftsman* (Skt. < kārū > *maker* + Pers. < gar >) beside কারিকর < kārikār >; বাজীগর, -কর < bājī-gār, -kāra > *magician, acrobat*.

(6) গিরি < giri > *business, craft, trade; manners, ways* (= Pers. < gar-i >; also < gir > *taking, holding, seizing* > *taker, holder* + nominal affix < -i >): মুচিয়া-গিরি < muṭiyā-giri > *the calling of a porter*; মুচিগিরি < mucī-giri > *a shoe-maker's calling*; বাবুগিরি < bābu-giri > *the ways of a gentleman* = *soft living*; কেরানীগিরি < kērānī-giri > *the profession of a clerk*; etc.



(7) চী, চি < -ci, -ci >, a diminutive affix, a modification of the Persian < -cah > > চা < cā > with feminine or diminutive < -i >: ধূনাচী < dhūnāci > *small incense-burner*; পাতিচী < pātañci > *a carpet or mat*, from words like দেগচী, ডেকেচী < dēgeci, dēkeci > *a caldron* < < dēgeah > >; বাগিচা < bāgicā > *small garden* < < bāgicah > >; চাম্চা, চাম্চে < cāmeā, -cē > *spoon*, etc.

(8) তর < -tārā > *like* (< Perso-Arabic < tarāh > *plan, mode, manner*): এমনতর < ĕmānḍ-tārā > *such* (beside এমন-ধারা < ĕmānḍ-dhārā >); কেমনতর < kēmānḍ-tārā > *in a peculiar way*; যেমনতর < jēmānḍ-tārā > *like that*; etc. After some *ts.* words it has an intensive force, as in গুরুতর < guru-tārā > *in a very excessive way*, ঘোরতর < ghōrā-tārā > *in a very terrible manner*, বহুতর < bāhu-tārā > *manifold*, etc., where it seems this suffix of foreign origin has been confused with the Skt. comparative affix < -tara >. The affix is found mainly in some pronominal adjectives and adverbs, and this use seems to be modelled on Hindōstānī (Urdū) forms like < is-tarāh, jis-tarāh, kis-tarāh >, etc.

(9) দান, দানী < -dān, -dān-i > *receptacle*: নস্রদান < nāsyā-dān > *snuff-box*, পিকদানী < pikḍ-dānī > *spittoon*, on the model of কলমদান < kālām-dān > *pen-stand* (qalam-dān), আতরদান < ātār-dān > *scent-bottle* (ʿīṭr-dān), etc.

(10) দার < -dār > *holder, one in charge of*: বাজনদার, extended to বাজন-দারিয়া > বাজুন্দারে < bājānḍ-dār, bājānḍ-dār-iā > bājundērē > *musician*; চোকাঁদার < cāuki-dār > *watchman* > চোকাঁদারী < cāukīdār-i > *work of a watchman*: চড়নদার < cārānḍ-dār > *passenger* (✓cār ride); ফাঁড়ীদার < phāṛī-dār > *person in charge of a police station*; ছড়িদার < chāṛī-dār > *rod-bearer*; সমকদার < sāmājhḍ-dārḍ > *possessing discrimination*; অংশীদার < āṁśī-dār > *for অংশ-দার* < āṁśā-dār > *shareholder in a firm*; etc.

(11) নবিশ < -nābiś > *writer* (= navīs): নকলনবিশ < nākāl-nābiś > *copyist* (naql-navīs). In the word শিকানবিশ < śikṣā-nābiś > *apprentice* (especially in some learned trade), we have the influence of the English word *novice*. নবিশ < nābiś-i > is the abstract form of the above.

(12) বন্দ < -bandā > > বন্দি < bāndī > *shut, enclosed* (= Pers. < band >): চিঠাবন্দি < ciṭhā-bāndī > *entered in a ledger*, পেটরাবন্দ, -বন্দি < pēṭrā-bāndā, -bāndī > *shut inside a chest*, বাক্সবন্দ, বন্দি < bāksā-bāndā, -bāndī > *locked in a box*.

(13) বাজ < -bāj > *one accustomed to do a thing* (< bāz), an abstract formation from which is বাজী < bāj-i >: রাঁড়বাজ < rāṛḍ-bāj > *one who associates with courtesans* (slang); ধড়ীবাজ < dhāṛi-bāj > *acute fellow, swindler*; ধোঁকা-বাজ < dhōkā-bāj > *a swindler*; গলা-বাজী < gālā-bājī > *speech-making*; etc.

(14) সহি, সহৈ < -sāhi, -sāi > *proper, attached to* (Perso-Arabic < sāhih >): as an affix, this has been confused with the similar *lbh.* affix (p. 700); e.g., মানান্-সহি, -সহৈ < mānānḍ-sā(h)i > *agreeable, suitable*; প্রমাণ-সহি < pramāṇḍ-sāhi > *of full size*; চলনসহি < cālānḍ-sāi > *serviceable*; মাপসহি < māpḍ-sāi > (*article*) *to measure*; টেকসহি < ṭēkḍ-sāi > *durable*; etc.

Some Persian words, being cognate with Sanskrit ones, are so very similar to the latter that their Indian or Indianised forms are employed: e.g., Persian < -istān > in names of countries occurs in Bengali in the Sanskrit form < sthāna >: e.g., হিন্দুস্থান < Hindu-sthānḍ >, আফগানিস্থান < Āphḍgāni-sthānḍ >, তুর্কীস্থান < Turki-sthānḍ >; Persian < -mand > often becomes মন্ত < māntā >, e.g., দৌলতমন্ত < dāulāt-māntā > beside শ্রীমন্ত < śrī-māntā >, and Persian < nāmāh > is hardly felt to be foreign in the Bengali নামা < -nāmā >.

Other Persian affixes or words like < -yandah, -andāz, pōš > appear only in Persian words borrowed in the language, and as they are not used with native words, they cannot be said to have as yet become naturalised.

## [B] PREFIXES

### [I] PREFIXES OF NATIVE ORIGIN: TADBHAVA AND TATSAMA.

469. Bengali has a few prefixes which are living ones, employed in forming words. The following are the *lbh.* and *ts.* prefixes found in use.

(1) অ, আ < ā-, ā- >, অনা < ānā- >: Privative, Pejorative.

OIA. initial < ā- > normally became < ā- > in Bengali (see *supra*, p. 314), but the influence of Skt. restored the < ā- > [=a] in most cases. This prefix অ [a] is not mutated to [o] even when the following syllable has [i] or [u] (see p. 396). Examples: আলুনি < ā-luni < \*ā-lōṇ-i > *not*



*salted (as of curry)* (a-lavaṇ-ika); আকাচা < ā-kācā > *not washed (as a dhōti)*; অবন্তি < ā-bānt-i > *disagreement* (বন  $\sqrt{\text{bān}}$  to make up); আকাঁড়া < ā-kārā > *not cleaned (as of rice)* (a-kaḍḍhia, \*a-kaṇḍia = a-kṛṣṭa); MB. sts. আবুদ্ধি < ā-buddhiyā > *without intelligence*; অন্তব < āśudhā >, *mourning, ceremonial uncleanness*, often written শুভ < ōśudhā > (a-śuddha); MB. (ŠKK.) আদেখ < ā-dēkhā > *not seen*, আদিবস < ā-dibāsā > *bad day*, আবেলা < ā-bēlā > (NB. অবেলা < ā-bēlā >) *bad time*; আধোয়া < ā-dhōā > *not washed*; অকাজো < ā-kējō < \*ā-kāj-uā > *good-for-nothing*; MB. আকারণে < ākāraṇē > *without any reason*; অজান(ী), অজানা < ā-jān(ā), ā-jānā > *unknown*; অঘর < ā-ghārā > *bad family*; আঘাট < ā-ghāṭā > *a bad 'ghāt'*; অবিয়ত < ā-biyā-tā >, see p. 704; etc.

We have also hybrids like অহিন্দু < ā-hindu > *non-Hindu, un-Hindu*, অখুশী < ā-khuṣī > *displeased* (Persian < xūšī >), অহিসাবী *unmethodical* (Perso-Arabic < hisāb > *accounts*).

OIA. < ān- >, before vowels, is the source of the Bengali অন < ānā >, through the occurrence of forms like < an-āgata, an-āvr̥ṣṭi > etc.: sts. অনামুখ < anā-mukhā > *evil-face*, অনাছটি, অনাত্টি < anā-chaṣṭi, anā-sṛṣṭi > *extraordinary (in a pejorative sense)*.

(2) অ, আ < ā-, ā- >: Intensive > Pleonastic.

470. It is found in some MB. and dialectal NB. words. See *supra*, p. 378. Possibly it is a semantic development of the negative অ, আ above. The OIA. particle (later prefix) < ā > could not continue its force in NIA., as it was assimilated through phonetic decay in MIA. Examples: অমন্দ < ā-māndā > *bad*; অব্থা, আব্থা < ā-br̥thā, ā-br̥thā >, < obretha > in the 'Crepas Xaxtrer Orthbhed' (see p. 284) = < vr̥thā >; অবোর নিদ্রা < ā-ghōrā nidrā > = < ghōra nidrā > *deep sleep*; অরঙ্গা, আরঙ্গা < ā-rāṅgā, ā-rāṅgā > *coloured*; অকুমারী, আকুমারী < ā-kumārī, ā-kumārī > *virgin*, < ocumari > in the 'Orthbhed.'

Connected with the above would seem to be an অ < ā- > prefix, indicating 'similarity' or 'resemblance': e.g., আকাঁড়, -ট < ā-kāṭ(h)ā > *like a log* > *idiotic*; আখ(ী)ড়া < ā-khāmbhā, -khāmbhā > *like a pillar* (slang);

আতাজা < ā-bhājā > *slightly fried* < *not properly fried* (here = the privative or pejorative < ā- > ?).

(3) কু < ku- >.

471. Pejorative, from OIA. < ku- >. This prefix also is used as a noun in Bengali, meaning 'something bad.' Examples: কুকাজ < ku-kājā > *bad deed*, কুচাল < ku-cālā > *bad ways*. There are also hybrids—কুনজর < ku-nājar > *bad sight* > *eye of displeasure* (or of sensuality) (Perso-Arabic < nazar >), কুকেছা < ku-kecchā > *scandal* (Perso-Arabic < qissah >), etc. (The OIA. < duṣ-, dur- > *bad* has not been naturalised in the same way.)

(4) দর < darā- >.

472. A diminutive prefix, meaning *half, a little*, from MIA. < dara > (cf. Pischel, 'Grammatik der Prakrit-sprachen,' § 222) from OIA. < √dṛ > *to break*: e.g., দরকাঁচা < darā-kācā > *half unripe*, also ‡ দরকচা, দরকোচা < darā-kācā, darā-kōcā >, *not properly matured*; দরপাকা < darā-pākā > *half-ripe*. It is a rare and practically an obsolete affix.

(5) নি < ni- >, sts. নির < nir- >.

473. Privative affix, from OIA. < niḥ, nir >. Through Skt. influence this affix also occurs as নির < nir >. Examples: নিভুল < ni-bhulā > *faultless, without a mistake* beside নির্ভুল, 'নিব্ভুল' < nir-bhulā, nibbhulā >; নিৰ্ভূত < ni-khūtā > *without a blemish*; নির্গাঁই, নির্গাঁঞি < ni-gāi, nir-gāi > *without any village home*; নিখাতি, নিখাতিস্তি < ni-khā-(u)nti >, feminine from < \*ni-khā-wantā > *one who does not eat*; নিনাই, নিনায়, নিনাও < ni-nāi, ni-nāy, ni-nāo > *one without a boat*; sts. ‡ নিউদ্ভিশ < ni-uddiśā > beside নিরুদ্ভেশ, নিরুদ্ভিশ < nir-uddēśā, nir-uddiśā > (= nir-uddēśa); ‡ নিখাইক < ni-khāikā > *one who does not eat*; MB. (ŚKK.) নিমাত্তি, নিমাত্তিতী < ni-māthi, ni-māthiti > *woman without protector* (ni + mātthā < mastaka- + ikā, etc.); নিলাজ < ni-lājā > *shameless*; নিদয় < ni-dāyā >, নিকরুণ < ni-kāruṇa > *pitiless*; etc., etc.

It is found also in verbs and other forms, like নিবা < nibā > *to extinguish* (nir-vā), where its force as a prefix is now lost.



(6) বি « bi- », rarely বে « bē- ».

474. Privative and pejorative = OIA. « vi- »: e.g., বিবোধ « bi-jōṛṣ » *without a match, odd*; MB. বিবুধি « bi-budhi » (=dur-buddhi); বিকরণ « bi-kāraṇā » (=niṣ-karaṇa); বিহড় « bihāṛā » *to turn wrong* (=vi-ghaṭa-); sts. বেজন্মা « bē-jāmmā » beside বিজন্মা « bi-jānmā » *bastard* (=vi-janman); etc. Cf. OB. (Caryā 32) « khāla-bikhalā » = « khāta- + vikhāta ».

(7) স « sa- ».

475. Skt. « sa- », *along with*, is used in Bengali in an intensive or ameliorative sense: e.g., সঠিক « sâ-ṭhikṣ » beside ঠিক « ṭhikṣ » *true, correct*; সকাল « sâ-kālṣ » *early, morning* (as opposed to বিকাল « bi-kālṣ » *afternoon, evening*); so সবেল « sâ-bēṛṣ » *morning, early*, as opposed to অবের « â-bēṛṣ » (< vėlā); sts. সাবকাশ « sâbakāśṣ » (=avakāśa), সক্ষম « sâ-kṣāmṣ » (=kṣama); etc. From the Persian « nâbâliq » > নাবালক « nâbâlākṣ » *minor*, a form সাবালক « sâ-bâlākṣ » *major*, as if with this prefix, has been formed.

The old sociative or instrumental use of « sâ- » has been partly revived in Bengali, and we have even a hybrid form like সবুট « sâ-butṣ » *with boots on* (< English *boot*, as in সবুট পদাঘাত « sâ-butṣ pādāghātṣ » *a kick with the boot on*), সজোরে « sâ-jōrē » *with force* (Persian « zōr »), on the model of ts. forms like « sa-vastra, sa-bala, sa-daya », etc.

(8) সু « su- ».

476. Ameliorative affix, used also as a noun = *something good*, (like « ku »). Examples: সুছাঁদ « su-chhādṣ » *of good-shape*; সুজন « su-jānṣ » *good man*; সুমন « su-mānṣ » *good-minded* (predicative adjective), *good mind* (su-manas); সুদিন « su-dinṣ » *good day*; সুনাম « su-nāmṣ » *good repnte*; সুডোল « su-ḍōlṣ » *of good shape*; etc. Hybrids—সুনজর « su-nājārṣ » *good glance, kindly glance* (Perso-Arabic « nazr »), সুখবর « su-khābār » *good news* (xabr), etc.

(9) হা « hā- ».

477. Explained as the interjection হা « hā » *alas*, which is a very likely source. It might have, however, originated from a MIA. « haa »

(=bata). Used with a few words to indicate absence of something, and a consequent yearning for it: e.g., হাপুতি < hā-puti > a woman who mourns or longs for children; হাততিয়া > হাবাতে < hā-bhātiyā > hābātē > a beggar for bread (lit. rice); হাবরিয়া > হাব'রে < hā-ghāriyā > hāghōrē > homeless vagrant; হাপুস as in হাপুস নরনে কাঁদা < hā-pusā nāyānē kādā > weep with flooded eyes, where হাপুস may be from হাউস < hā-wusā > from < hā, ha(t) > + < √vr̥ > rain; etc.

Some independent words like ভর < bhārā >, as in ভর-সাঁঝ or -সন্ধ্যা < bhārā-sājhā, -sāndhyā > in the middle of the evening, আধ < ādhā > (ardha) as in আধ-ফোটা < ādhā-phōṭā > half-open (flower), etc., occur in compounds, and these strictly speaking are not prefixes.

## [II] FOREIGN PREFIXES : PERSIAN.

478. (1) গর < gār- >, from Perso-Arabic < gair > without; গরমিল < gār-milā > disagreement; cf. গরহাজির < gār-bājir > absent (gair-hājir).

(2) দর < dār- > under, within; দরপত্তানী < dār-pāttānī > sub-tenancy.

(3) না < nā- > not: e.g., না-পাখিমানো < না + পাখিমাণো < nā-pājjimānē < nā + pāryamāṇē > when one is not able, on the model of নাইক < nā-hāk > without reason, without right (nā-haqq), নাবালক < nābālāk > minor (nā-bālig), etc. In forms like না-টক না-মিষ্ট < nā-ṭākā nā-miṣṭi > neither sour nor sweet, we have, however, the native Bengali negative particle rather than the Persian affix.

(4) ফি < phi- >, from Perso-Arabic < fi >, used in Bengali to mean each: ফি-লোক < phi-lōkā >, ফি-জন < phi-jānā > (for) each man, ফি-হাত < phi-hātā > at each hand, at each step, etc.

(5) বদ < bād- > evil (Persian < bad >): বদ-রীত < bād-rit > bad ways, বদ-রাগী < bād-rāgī > one who flies into a passion, বদ-গন্ধ < bād-gāndhā > bad odour, etc.

(6) বে < bē- > without: also used pejoratively. This affix is assimilated to the cognate Skt. < vi- > > বি < bi- >. Examples: বেহাত < bē-hātā > out of reach; বেচাল < bē-cālā > evil ways, waywardness; বেরসিক < bē-rāsikā > one who is impervious to witticism; বে-হেড < bē-hēḍ > (slang) off one's head, losing control over oneself (< hēḍ > < English head); বে-টাইম, -টাইন



« *bē-tāim*, -*tāin* » *in improper time* (< English *time*); etc. The word বেতাই « *bēāṛā* », of course, represents the native « *vikāṭa* ».

(7) হর « *hār* » *each*, from Persian « *har* » : হরবোলা « *hārṣ-bōlā* » *ventriloquist*; হর-দিন « *hār-dinṣ* » *daily*; etc.

There are other Persian words like « *bar*-, *sar*-, *kam*- », but these have not as yet acquired the force of an affix, at least so far as native words or roots are concerned.

#### ENGLISH.

479. The English words *head*, *full*, and *half* are used in a number of compound forms with Bengali words, and have almost become affixes : e.g., হেড-পণ্ডিত « *hēḍ-pāṇḍitṣ* » from the Anglo-Indian *Head Pundit*; so হেড-বাবু « *hēḍ-bābu* » *chief Indian clerk in an office*; হেড-মুহুরী « *hēḍ-muhurī* » (Pers. « *muḥarrir* », see p. 610); হেড-গোমস্তা « *hēḍ-gōmāstā* » (Pers. « *gumāstah* »); হেড-মৌলবী « *hēḍ-māulābī* » *Head Moulvi*; ফুলবাবু « *phul-bābu* » *a fop, a 'Full Babu'*; ফুল-আখড়াই and হাফ-, হাপ-আখড়াই « *phul-ākḥṛāi*, *hāp(h)-ākḥṛāi* » *two styles of poetical and singing contest much in vogue in mid-19th century Bengal* (*full, half* + « *ākḥṛāi* » *gathering* < « *ākḥṛā* = *akhārā* » *club*). The prefix *sub*- (as সব, সাব « *sāb*-, *sāb*- ») is quite well-known through the occurrence of words like *sub-division*, *sub-deputy*, *sub-assistant*, *sub-overseer*, *sub-inspector*, *sub-registrar*, etc., etc., which are familiar to Bengali speakers everywhere, but it has not yet been used with an Indian word.

## CHAPTER II

### DECLENSION OF THE NOUN

#### [A] STEMS.

480. Bengali like most NIA. languages may be said to have started *de novo* in its morphology, having preserved but very little of the declinational system of OIA.; and the little that it has preserved consists of a few inflexions which have been generalised. MIA. considerably curtailed the elaborate declension of the noun of OIA. The various vowel and consonant stems of OIA. (as in Vedic), considerably over a dozen, were reduced to a bare six (◀ -ā, -ī, -ū; -ā, -ī, -ū ▶ stems) in Early MIA., when ◀ ɾ ▶ became ◀ -ā, -ī, -ū ▶, and final consonants dropped off; and there were just a few relics of the other stems. They were further simplified in Late MIA., when the final long vowels were shortened (see *supra*, p. 301), and there was a general tendency to bring all declensions under the ◀ -ā ▶ type. Stems in ◀ -i, -u ▶ were gradually approximated to the ◀ -ā ▶ declension; ◀ -i, -u ▶ nouns were often extended to ◀ -ia, -ua ▶ by adding of ◀ -ā < -kā, -kā ▶; and new affixes in ◀ -a ▶ replaced older ones in ◀ -i, -u ▶, like ◀ -ira ▶ in literary Apabhraṃśa of Gujarat removing affixes like ◀ -in, -ālu ▶ (cf. R. G. Bhandarkar, 'Wilson Lectures,' pp. 111-114; Jacobi, 'Bhavisatta-kaha,' pp. 30\* ff.; C. D. Dalal and P. D. Guṇē, 'Bhavisayatta-kahā,' Baroda, 1923, Introduction, pp. 17 ff.). Final ◀ -i, -u ▶ even tended to disappear from the stem, giving place to ◀ -ā ▶: so that Early NIA. could inherit from Late MIA. (and from MIA. changing to NIA.) many stems in ◀ -ā ▶ like ◀ rāsā (= rāsi); munā (= muni); dhunā (= dhvani); gurā (= guru); sāhā (= sādhu); bāhā, bāhā (= bāhu); sūdhā (= śuddhi); dēvā, dē (dēvi < dēvi) ▶, etc. The OIA. stems were in this way reduced to the bare ◀ -ā, -ī, -ū ▶ stems in Early NIA., with ◀ -ī, -ū ▶ taking up the affixes of the ◀ -ā ▶ stem and at times even being suppressed in favour of the ◀ -ā ▶. This is what happened in all OIA. words inherited through MIA. Late MIA. ◀ -āā, -āā, -iā (-iā),



-uā (-uā) > became the long vocalic stems < (-ā), -ā, -ī, -ū > of Early NIA., and these long stems are preserved in most MIA. In Bengali, however, these final long vowels became weakened: < -ā > of course remained as অ < -ā > in writing (as the original short < ā > sound had become a vowel of a different quality, অ = [o]), but it was not, and is not pronounced fully long; and < -ī, -ū > became < -i, -u >, indifferently written long or short.

In MB., we have frequent examples of this levelling of the < -ī, -u > stems to < -ā >. The nominative, through the influence of Sanskrit, may preserve or may even have restored the original vowel; but the stem, forming the basis of the other cases, is plainly an < -ā > stem. Even *ts.* words follow this tendency. Thus, we have commonly ধূলি < dhuli > beside ধূল < dhulā, dhūlā > *dust*, nominative and accusative, but in locative it is ধূলে < dhulē > (= dhulā + -ē); দিঠি < diṭhi > *sight*, nominative, but locative দিঠে < diṭhē > (= diṭha + -ē); বেলি < bēli < \*bēli > *time of the day*, (= \*vēlikā) (beside বেল < bēlā >, as well as বেল < bēlā > with < -ā > from Skt.), locative বেলে < bēl-ē >; *ts.* nominative বুদ্ধি < buddhi >, locative বুদ্ধে < buddhē >, genitive বুদ্ধের < buddhērā >; *ts.* অপমৃত্যু < āpa-mṛtyu >, locative and instrumental অপমৃত্যু < āpā-mṛty-ē > (as in the 'Caitanya-bhāgavata' of Vṛndāvana-dāsa); so in the 'Crepax Xaxtror Orthbhed,' we find < xotro > = শত্রু < śātru >, but locative < xotre > = শত্রে < śātrē >; etc. Such modifications of < -ī, -u > to < -ā > in the oblique are fairly common in MB. In MB., epenthesis no doubt gave to original < -ī, -u > nouns (*lkh.* or *sts.* and *ts.*) the appearance of being < -ā > nouns in the inflected forms: e.g., চকু, চখ < cākkhu, cākhu > *eye* > চউখ, চ'খ < cāūkh, cāīkh >, genitive চকের < cāk-khērā >, চউখের, চ'খের, চোখের < cāūkhērā, cāīkhērā, cōkhērā >; সাধু < sādhū >, genitive সাধের < sāīdhērā >, instrumental সাধে, সেধে sīdhē, sēdhē >, etc., which would suggest as stems \*চ'খ \*cāīkhā >, \*সাধ < \*sāīdhā >; so বাসি < Sāṭhi > *the Goddess of children* (sāṭhi, sāṭhikā) gives বাসিঠের, বেসিঠের, বাসিঠের < sāīthērā, sāīthērā, sāīthērā > as if from \*বাসিঠ < sāīṭhā >; and quite a number of similar cases.

481. The inflexions of the seven (or eight, including the vocative) cases of OIA. tended to disappear in NIA., but some occur as survivals. Although we have in NIA. here an old instrumental or there an old

locative affix preserved, the two characteristic forms from point of view of most NIA. are (i) the nominative, and (ii) the oblique. The former roughly represents the old nominative, and the latter, frequently the sole representative of other case inflexions of OIA., rests on the original genitive or dative, locative or instrumental inflexion, to which the new case-forming post-positions are added. The juxta-position of these two stems, nominative and oblique, is the regular rule in Western and Central NIA., in Marāṭhī, in Gujarātī and Rājasthānī, in Western Hindī, in Panjābī, in Lahndī, in Sindhī, and in Western and Central Pahārī. It is much confused in Eastern Pahārī. In Eastern Hindī, it has fallen into disuse in the singular noun; and it is absent in the Eastern languages, Bihārī, Bengali, Oṛiyā and Assamese. The declension of the noun has thus become considerably simplified in the last group.

Distinction between masculine and feminine forms is absent in Bengali and other Magadhan languages. The same inflexions serve for both masculines and neuters as well as feminines. Thus the instrumental « -ē, -ē » is found in feminine nouns like « ghaḍiē, āliē, kāliē » in the Old Bengali of the Caryās; and the old feminine inflexions (although at times found in a form like « samāhia » [= samādhya], which is a sporadic survival in the literary language) are entirely lost.

482. Bengali nouns thus have come to have one declension only, irrespective of stem and gender. There are in the NB. Standard Colloquial just a few phonetic modifications in the inflexions, and these are noted below. We have in Bengali—

(1) Consonantal stems = mainly « -ā (-ā) » bases of Early MB. and OB., and Late MIA., and partly also OIA. « -i, -ī, -u, -ū » bases (see pp. 301, 305, 307, 308, 310); and *ts.* words with quiescent « -ā »; and also foreign words ending in a consonant.

So long as the final vowel was pronounced, the genitive affix was « -rā < -ārā » (kāṛā), as *e.g.*, MB. হাতর, রামর « hātārā, Rāmārā », as well as « -ērā < -kēra » (kārya), as in হাতের, রামের « hātērā, Rāmērā »; but NB., which has dropped the final vowel, now does not use « -ārā > র -rā », but only « -ērā > এর -ērā ».



(2) Vowel stems, simple and diphthongal :

[i] < -ā > or < -o, -ō > stems, in *tbh.* forms, representing an earlier < -awa > ; and in *ts.* and *sts.* forms, the Sanskrit < -ā > (see *supra*, pp. 302, 304, 347) ;

[ii] < -ā > stems, in *tbh.* nouns representing < -āā, -āā, -āā' > of MIA. (see *ante*, pp. 302, 307) ; in *ts.* nouns, representing Skt. < -ā > ; and in foreign nouns ending in vowels [-ā, -a], etc., normally changing to < -ā > in Bengali (see *supra*, under 'Phonology of the Foreign Element') ;

[iii] < -ī, -ī > stems, representing, in *tbh.* words, the MB. < -i > after a vowel or after < -h- > (= OIA. < -ī, -ī > : see pp. 308-309), or the OB. < -ī > < -ikā, -ikā > of OIA. (see pp. 302, 303, 352) ; in *ts.* stems, the Skt. < -ī, -ī, -in > are properly represented by < -ī, -ī > ; and in foreign words, < -ī, -ī > remain as < -ī, -ī > (see *supra*, 'Foreign Element') ;

[iv] < -ū, -ū > stems, the history of which is parallel to that of the < -ī, -ī > stems : they represent in *tbh.* words the MB. < -u > after a vowel or after < -h- > (= OIA. < -ū, -ū > : see p. 310), or the OB. < -ū > < OIA. < -ukā, -ūpā, -ukā, -ūpā > (see pp. 310, 311, 352) ; in *ts.* words, Skt. < -ū, -ū > remain < -ū, -ū >, pronounced [u] in Bengali, as well as foreign < -ū, -ū > ;

[v] a few < -ē > nouns ; and

[vi] < -ō > nouns ; both in *tbh.* forms representing the contracted < -ā > bases of Late MIA. (cf. pp. 311, 352, 353).

Foreign words with < -ē, -ō > bases are also found.

In addition, there are [vii] diphthong stems, in *tbh.*, *ts.* as well as foreign words (see *supra*, pp. 415 ff., under 'Bengali Diphthongs.')

NB. *tbh.* vowel stems in < -ā, -ā, -ē, -ō > as a rule take the < -rā > affix for the genitive, and not < -ērā > : e.g., ভালর, পনেরর, বোড়ার, কালোর, আলোর, দের (= the surname, < dēva >) < bhālā-rā, pānērā-rā, ghōrā-rā, kālō-rā, ālō-rā, dē-rā > ; but monosyllabic words in < -ā > can take both < -rā > and < -ērā > : e.g., মারের, ঝীরের, বারের < mā-ērā, jhī-ērā, ghā-ērā > (of a blow or sore) beside মার, ঝীর, বার < mā-rā, jhī-rā, ghā-rā >. OB. and MB., of course, used both < -ārā = -rā, -ērā = -ērā >, the < -rā > form being found compounded with Late MIA. bases in < -ā >. In OB. and

MB. (unlike NB.) « -ērā » seems to have been preferred with *lôk*, as well as *ts.* forms in « -i, -ī, -u, -ū »: *e.g.*, Caryā 19 « dōmbīrā » = NB. ডুম্বীর « dūmḍinīṛā » of a *Dōm* woman; মূনিরের beside মূনির « muni-ērā, muni-rā » of a sage; বহুরের beside বহুর « bāhu-ērā, bāhu-rā » of many; etc. Except in the case of diphthongs ending in « -i, -u », and in the diphthongs « -ao, -āo » with which euphony in NB. demands that « -ērā » is to be used, all NB. « -i, -ī, -u, -ū, -ē, -ō » words take « -rā ». *Tatsama* or foreign words in « -ā », however, can use either « -ērā » or « -rā ».

The instrumental-locative in Old and Early Middle Bengali was « -ē, -ē », in the case of all nouns ending in « -ā » or in any other vowel. NB. continues the « -ē » in what were originally « -ā » nouns (now nouns with a consonant ending through loss of the « -ā »); and in the case of nouns originally ending in other vowels, it uses the post-positional affix তে « -tē » rather than the organic one « -ē » for the instrumental and locative cases, to avoid the hiatus, always after « -i, -u, -ō » vowels, and optionally after « -ā »<sup>1</sup>: *e.g.*, লোকে « lōk-ē < lōkā » on, by or with a man; but বোড়ার, বোড়াতে « ghōṛā-ē > ghōṛāy, ghōṛā-tē » on or with a horse; মায়ের কাছে « māē jhīē » mother and daughter both (instrumental and nominative), beside মাতের কাছে and মায়েরে কাছে « mā-tē jhī-tē, mā-ē-tē jhī-ē-tē »; Early Bengali বাবুরে « bābu-ē », NB. বাবুতে « bābu-tē » on or by a gentleman; Early Bengali মূনিএ « muni-ē », NB. মূনিতে « muni-tē » on or by a sage, etc. Assamese, and numerous dialectal forms of Bengali as well, stick to the instrumental, and avoid this further confusion between the locative and the instrumental by importing the « -tē » which has now come in the « sādhu-bhāṣā » and the Standard Colloquial.

The above are the slight alterations which are noticed in the use of some of the inflexions with the Bengali noun stems, and being recent, and essentially phonological, they cannot be said to mark out any distinction in the stem of the noun in Bengali.

<sup>1</sup> One may compare the importation of [t] in the popular French of Paris to avoid the hiatus (cf. Henri Bauche, 'Le Langage populaire,' Paris, 1920, p. 58). See *infra*, under Cases—Nominative, Instrumental, Locative.



## [ B ] GENDER.

483. It has been noted above that the tendency in Apabhraṃśa was to generalise the inflexions of the masculine < -ā > stem. This considerably weakened the grammatical distinction between masculine and feminine nouns, and this distinction has been entirely dropped in Bengali, in its *ts.* element. Adjectives qualifying feminine nouns (grammatical or natural) are sometimes furnished with an < -ā > or < -ikā > (*tatsama*) or an < -ī, ī > or < -nī, -nī > (*tatsama* or *tadbhava*) affix, e.g., পরমা সুন্দরী < *pāramā sundarī* >, তরুণী স্ত্রী < *tāruṇī strī* >, বৎসহারা গাভী < *bātsā-bārā gābhī* > a cow which has lost her calf, † ভাগিমানী মেয়ে < *bhāgyimānī mēyē* > a woman happy in her husband's love (a form used by women in the Standard Colloquial, < = *bhāgyavatī strī* >); but these feminine forms are confined to *ts.* and *sts.* words, and are entirely against the spirit of the language. (Cf. Lalit Mohan Banerji, 'Vyākaraṇ-Vibhīṣikā,' pp. 27 ff., for examples of wrong use of the Skt. feminine affixes in Bengali). In the Western Magadhan dialects, predicates referring to nouns or pronouns in the feminine gender have the feminine affix < -ī, -ī >, but in the declension there is no distinction, such as we find for instance in Western Hindi and Marāṭhī.

Grammatical gender may be said to be preserved in all NIA. except Magadhan. In most of them, however, the neuter has merged in the masculine: in some, like Marāṭhī, Gujarātī and Sinhalese, the neuter is preserved. Thus in Western Hindi, < *pōthī, bāt* > are feminine, as they represent the earlier < *potthiā, vattā = pustikā, vārtā* >, and verbal predicates referring to them (in the past participle or future) as well as genitive and other adjectival forms qualifying them must be put in the feminine. This is thus a survival of MIA. conditions; and there is no survival of this kind now in the Eastern Magadhan speeches, Bengali, Assamese and Oṛiyā, although it exists in the older phases of the above speeches, and is still found to some extent in the Central and Western Magadhan speeches. We have in OB., and to some extent also in Early MB., a state of things almost identical with that obtaining in Western Hindi or in Apabhraṃśa. In the Caryās, there are numerous cases showing that nouns in < -ī, -ī < -ikā > and in < -ā = *ts.* -ā > preserved their grammatical gender, and were in the

feminine: e.g., « diṭi (= diḍhi < \*dṛḍhikā) ṭāggī » *strong axe* in Caryā 5 ; « sōnē bharitī nāwī » *boat filled with gold* (Caryā 8) ; « mēlilī kācchi » *the hawser was loosened* (Caryā 8) ; « tōhōri kuḍiā » *thy little hut*, « tōhōra antarē mōṣ ghalilī hāḍēri māli » *for thy sake the chaplet of bones has been cast away by me* (Caryā 10) ; « tōhōri bhābhariāli » *thy coquetry*, « ḍombi-ta āgalī nāhi cchiṇāli » *before the Dōm woman there is no (greater) wanton* (Caryā 18) ; « māi dibi piricchā » *a question (or statement) is to be rendered by me* (29) ; « ṭuṭi gēli kaṅkhā » *the desire was destroyed* (37) ; « lāgēli āgi » *the fire caught* (47 : āgi = āgi < aggia = agnikā) ; « nia gharinī caṇḍāli lēli » *as (thy) own wife, a Caṇḍāla woman has been taken (by thee)* (49) ; « phitilī Śabarāli » *the Śabara's nature was destroyed* (50) ; etc. These would indicate that the sense of grammatical gender was quite strong in the language. Inanimate nouns, abstract, material or concrete, like « kaṅkhā, piricchā, nāwī, āgi, māli, ṭāggī » etc., are feminine only because of their affixes,—as much as names of persons of the female sex like « cchiṇāli » and « caṇḍāli » ; and they as a matter of course take feminine forms of the genitive-adjective (tōhōr-i, hāḍ-ēr-i) or attributive adjective (āgal-i, diḍh-i), or verbal predicate of participial and adjectival origin (dib-i, gēl-i). But in Early MB., this is changed, and names of inanimate objects cease to have any grammatical gender, in spite of the affix. Grammatical tradition yields to reason. In Early MB. (ŠKK.) there are cases like গেলী or চলিলী রাহী « gēli, cāḷilī Rāhi » *Rādhā went*, তার পিসী নিয়োজিলী « tāra piśi niyōjilī » *her aunt was appointed*, রোষিলী রাধিকা « rōṣilī Rādhikā » *R. angered*, etc., where predicates take the fem. affix « -ī, -i » when they qualify feminine nouns, names of sentient beings. In other MB. and NB., occasional cases of similar use crop up : e.g., VSP., p. 166, ব্রাহ্মণের নারী « brāhmāṇ-ēr-i nārī » *a Brāhman's wife* ; and there are also in MB. stray relics of grammatical gender, like ŠKK. (p. 381) চুড়ী « curī » *bracelet* being qualified by the feminine adjective জড়ী « jāṛī » *encrusted with gems* (jaḍita + -ikā), and বরণে উজলী কনক বউলী « bāraṇē ujālī kanakā-bāulī » *a floret of gold shining in its lustre* (KKC., p. 64).

This early abandoning of grammatical gender in the eastern speeches has been regarded as a heritage from the non-Aryan languages current in the East, and has been connected with conditions in Tibeto-Burman, which



does not possess grammatical gender (cf. Jules Bloch, 'Langue Marathe,' § 180). The dropping of the neuter affix \* -am > for the masculine \* -ē < -aḥ > characterises the eastern Aryan speech at least as early as the time of Aśoka, and in literary Māgadhī of the Second MIA. period (\* phalē < phalaṁ >, like \* dēvē < dēvaḥ >). The differentiation of the grammatical feminine from the grammatical masculine, or masculine-neuter, as we can see from the relics of OB. and eMB., continued in full force to the 12th century, and was even existent in the 14th. Postulating a specific Tibeto-Burman influence in doing away with the grammatical distinction of the feminine from the masculine-neuter in Late Middle Bengali and other Eastern Magadhan speeches therefore appears rather problematical. Although Assamese and East Bengali are within the sphere of Tibeto-Burman influence, West Bengali and Oṛiyā are removed from it. The Kōl speeches were to a large extent current in Bengal and in Northern India, and Kōl does not differentiate between masculine, neuter and feminine nouns by means of affixes. It is quite likely that in the tendency towards the elimination of the gender affixes in grammar there was the influence of Kōl speakers adopting the Aryan speech in North-eastern India from very early times. It is equally likely that the simplification was a normal development in the Aryan speech of the East, apart from questions of outside influence. On the other hand, differentiation of masculine, feminine and neuter nouns by means of affixes is characteristic of Dravidian: Marāṭhī and Gujarātī thus in this respect agree with Dravidian, while at the same time they preserve an OIA. conservatism. There are relics of the neuter in Western Hindi also.

Magadhan speeches including Bengali preserved the common NIA. differentiation between animate and inanimate nouns in the accusative case. This peculiarity is undoubtedly derived through contact with Dravidian (see p. 172; Caldwell, 'Comparative Gram. of the Dravidian Languages', p. 271).

#### [ C ] NUMBER.

484. The dual of OIA. fell into disuse by the First MIA. period. The distinction between the singular and the plural has been maintained

intact up to Late MIA., and it continues down to the present day in a number of NIA. speeches. It is through phonetic decay (loss of final vowels) that the old plural inflexions could not be preserved everywhere in NIA. The Western languages, Marāṭhī, Gujarātī, Rājasthānī, Sindhī, Lahndī, Panjābī and Western Hindī, have to a greater or lesser extent retained the plural affixes, nominative or otherwise, inherited from MIA. and OIA. Thus in Marāṭhī, in masculine nouns originally ending in «-ā», the nominative plural has lost its affix through phonetic decay and has become identical with the singular («dēvāḥ, dēvāḥ > MIA dēvō, dēvā > dēvu, dēvā > NIA. Marāṭhī «dēv», both sg. and pl.), but the feminine and neuter nouns preserve their affixes in the plural nominative, although in an attenuated form (*e.g.*, «iṣṭā, iṣṭāḥ > MIA. iṣṭhā, iṣṭhāo > Marāṭhī sg. «iṣṭ», pl. «iṣṭā»; «mālā, mālāḥ > MIA. mā|ā, mā|āo > Marāṭhī «māl, mālā»; so Marāṭhī sg. «rāt», pl. «rāṭi»; neuter singular «sūtram > sūt», plural «sūtrāṇi > sūtā»; Sindhī nom. sg. «ḍ'ēh = dēśāḥ», nom. pl. «ḍ'ēha = dēśāḥ»; nom. sg. «piu = pitā», nom. pl. «piura = pitarāḥ»; Western Hindī sg. «bāt < vārtā», pl. «bāt-ē», where «-ē» is explained as being from the neuter pl. affix «-āni», transferred to feminine nouns; etc.). The nominative affix is entirely lost in most other NIA. languages, and plural oblique cases in some instances are extended to the nominative (*e.g.*, Western Hindī «ghōṛē = ghōṛahi = \*ghōṛēbhiḥ», instrumental > nominative plural). Instrumental plural and genitive plural are the two forms which survived in NIA., and these two were used for the nominative plural. (The accusative, dative, and ablative plural forms were lost in Late NIA., although Literary Apabhraṃśa used the locative plural.) Typical NIA. started, therefore, with three forms to indicate the plural number: the original nominative plural, which had weakened considerably and was fast disappearing in most places; the instrumental plural in «-hi, -hī < -bhiḥ»; and the genitive plural in «-ṇa, -na».

485. In most NIA. languages there is no confusion between the nominative and the genitive plurals, the latter being kept distinct as the oblique form: *e.g.*, W. Hindī «camār» (= carma-kārāḥ, carma-kārāḥ) sg. and pl., but oblique plural, never nominative, is «camārō, ṛcamārā»



(= carma-kārāṇām). The instrumental supplies the nominative plural affix « -ē » of W. Hindi, as noted above ; but the genitive plural never invades the domain of the nominative plural. This distinction is preserved in Marāṭhī, Sindhī and other Western speeches, and also in the Eastern speeches ; although in the latter, the old genitive > oblique is found in some cases to encroach into the domain of the nominative ; e.g., Eastern Hindi nom. sg. « ghōṛā », nom. pl. « ghōṛawan = ghōṭakānām », beside « ghōṛawē = ghōḍa(w)ahi = \*ghōṭakēbhiḥ » ; Maithilī « lōkani » pl. genitive originally, is commonly used as plural affix ; however, it may be said that the plural oblique is used for the oblique only. Thus in Oṛiyā, we have « puruṣā », plural « puruṣē < \*puruṣahi = puruṣēbhiḥ » but « puruṣāṅ-kā(rā) » where the form « puruṣān- < puruṣāṇām » retains its genitive function.

Evidence of Western Hindi and the Eastern languages would show that in Northern India, from the Panjab and the Midland eastwards, the instrumental assumed the place of the lost nominative, at least in masculine « -ā » nouns, from the Early NIA. or Late Apabhraṃśa stage. But in Bengali, this instrumental « -ahi, \*-ai, -ē » no longer figures as an affix, although it is found in its immediate neighbour and relation Oṛiyā, as well as in forms of the Bihārī speeches. It is just possible that in a NB. expression like লোকে বলে « lōk-ēḥ bālē » *people say* we have in Bengali the plural « -ē < -ahi ». Cf. also expressions like চল সবে « cālā sâb-ē » *come all* ; সবে মিলি ভারত সন্তান « sâb-ē mili Bhārāta-sāntānā » *all united Sons of India* ; দশে মিলি করি কাজ, হারি জিতি নাহি লাজ « dâś-ē mili kâri kaj, hâri jiti nâhi lāj » *ten people united we do the deed, we lose or we win there is no shame* ; ŚKK., p. 192, সবই কহিব আইহনের মাএ « sâb-ē kâhibā Āihānērā māē » *we shall all tell Ā's mother*. But this form can also be explained as a sg. instrumental-nominative « -ē < -ē < -ēna ». Cases of instrumental nominative like the above can thus be regarded as representing both « -ēna > -ē > -ē, -ē » in the singular and « -ēbhiḥ > -ahi > -ai > -ē » in the plural. In the ŚKK. there occur two cases সবই, সবজৈ « sâbâi, sâbâi » (pp. 66, 336), which may represent the « \*-a(h)i » stage, rather than the emphatic particle « hi » (saba + hi) ; for in MB. the latter is commonly preserved as « hi ». Relics of the instrumental plural are found in the pronoun (see *infra*) ; but

in general, it can be said that the plural instrumental affix of OIA. is lost to Bengali and Assamese.

486. The genitive plural affix  $\langle -\tilde{a}n\tilde{a}m \rangle$   $\langle -n\tilde{a}, -n\tilde{a} \rangle$  is better preserved in Bengali. It is found (though as a rare form) in nouns in dialectal MB. and NB., and also occurs in the pronouns; but in the noun, its proper genitive force is now lost. It is used mainly as a secondary affix added to the nouns of multitude which are used to form the plural: *e.g.*, Standard Bengali গুলিন, গুলান  $\langle -gul-i-n\tilde{a}, -gul-\tilde{a}-n\tilde{a} \rangle$  beside গুলি, গুলা  $\langle -gul-i, -gul-\tilde{a} \rangle$ , plural affix ( $\langle$  Skt. *kula*-); dialectal (East Vanga) Bengali আইন  $\langle$  আনি  $\langle -\tilde{a}in \langle -\tilde{a}ni \rangle$  as in সকলাইন, হকলাইন  $\langle s\tilde{a}kk\tilde{a}l-\tilde{a}in, h\tilde{a}- \rangle$  *all*, হোলাইন  $\langle h\tilde{o}l-\tilde{a}in \langle *p\tilde{o}l\tilde{a}ni \rangle$  *sons*; Western Bengali (LSI., V, I, pp. 89, 100) মিতান-রা-কে  $\langle mit-\tilde{a}n-r\tilde{a}-k\tilde{e} \rangle$  *to friends*, সাংগানগার  $\langle s\tilde{a}ngg-\tilde{a}n-g\tilde{a}-r\tilde{a} \rangle$  *of friends*, etc. We have also in MB. সভান  $\langle s\tilde{a}bb\tilde{a}-n\tilde{a} \rangle$  *all*, gen. সভানের  $\langle s\tilde{a}bb\tilde{a}n-\tilde{e}r\tilde{a} \rangle$ . The genitive force is preserved in the pronoun: *e.g.*, তান  $\langle t\tilde{a}n\tilde{a} \rangle$  *his* (honorific), but even in the pronoun, the genitive in  $\langle -n\tilde{a} \rangle$  has supplied the (honorific) nominative, as তিনি  $\langle tin-i \rangle$ . The forms  $\langle -n-i \rangle$  and  $\langle -\tilde{a}n-i \rangle$   $\langle -\tilde{a}in \rangle$  have their  $\langle -i \rangle$  apparently from the old instrumental plural  $\langle -hi \rangle$  which in this way modified the genitive before being itself lost. Maithili, Magahi and Bhōjpuriyā as well as Western Hindī also show this  $\langle -n-i \rangle$  for the plural. We have another modification of  $\langle -na \rangle$  in Bengali, viz.  $\langle *-nha \rangle$   $\langle -h\tilde{a}, -h\tilde{a} \rangle$  as in pronominal forms like যেহ, তেহ, ইহ  $\langle j\tilde{e}h\tilde{a}, t\tilde{e}h\tilde{a}, i\tilde{h}\tilde{a} \rangle$  *who, he, this* (honorific), দোহ  $\langle d\tilde{o}h\tilde{a} \rangle$  as in দোহে  $\langle d\tilde{o}h\tilde{e} \rangle$  *two* (nominative), দোহার  $\langle d\tilde{o}h\tilde{a}r\tilde{a} \rangle$  *of two*, which may be compared with the Eastern Hindī  $\langle -nha, -nhi \rangle$  as in Tulasī-dāsa. The  $\langle -ha, -hi \rangle$  is difficult to explain: but it can well be due to contamination with the instrumental plural  $\langle -hi \rangle$ , or the singular locative  $\langle -hi \rangle$  which became the accusative (oblique) in Bengali (see under 'Locative' below).

The  $\langle -na, -n-i, -nha \rangle$   $\langle -h\tilde{a}, -h\tilde{a} \rangle$  form is practically obsolete in Bengali as a plural affix for the noun, agglutinated words of multitude having taken its place. In the respectful form of the verb, which represents an original plural, we have ন  $\langle -n\tilde{a} \rangle$ : করেন, গেলেন, দিবেন, বলিতেছেন  $\langle k\tilde{a}r\tilde{e}n\tilde{a}, g\tilde{e}l\tilde{e}n\tilde{a}, d\tilde{i}b\tilde{e}n\tilde{a}, b\tilde{a}l\tilde{i}t\tilde{e}c\tilde{h}\tilde{e}n\tilde{a} \rangle$  *gives or give, went, will give, is or are telling*: this  $\langle -n\tilde{a} \rangle$  represents the OIA.  $\langle -anti \rangle$ , but phonologically it



cannot be the Bengali development of « -anti », we would expect « -āt » or « -ât » or « -it » (*supra*, p. 502); it is certainly the genitive plural « -na » extended from the noun to the verb to indicate the plural or the honorific. In certain forms of MB. (as for example in the 'Padmā-Purāṇa' of Baṇṣī-dāsa), this verbal affix occurs as *অঁহৈ, অঁহি* « -āi, -āñi », *e.g.*, *দিলাঁহি* « dilāñi », *করিলাঁহি* « kārilāi »: here it is unmistakably a modification of the nominal « -nā » > « -ni » as added to the verb.

The genitive « -ña, -na » certainly existed in OB., but no sure example is found in the Caryās. (Cf. Caryā 18, « kājaṇa kāraṇa » = « kāryāṇām kāraṇam »?). So far as NB. is concerned, it occurs only sporadically, in some stereotyped plural forms, like « gulā-nḍ, guli-nḍ », and it figures in a few forms like *নানান্* « nānā-nḍ » *many, several* (nānā). Words like *ভোতান্* « Bhōtānḍ » *Bhotan country* < 'Bhōt' or Tibetan people, *কোলহান্* « Kōlhānḍ » *tract inhabited by the Kōls* (see *supra*, p. 2) are instances of this « -nḍ » < « -ānām »; phonetically a form like *ভোতান্* « Bhōtānḍ » cannot represent a Skt. « Bhōtānta » *Bhōta frontier*, as it has been suggested by some.

487. In the word *সবাই* « sabbāi » *all* (MB. *সদ্ধাই, সদ্ধাহি* « sāmḥāi, -āñi », as in the ŚKK.) beside an emphatic *সবাই* « sabbāi » (see *supra*, p. 448), we have possibly a unique relic of the OIA. nominative plural affix: « sarvê hi » > sabbā hi (generalised « -ā ») > sab(b)āi ». The force of the « -hi » > « -i » is no longer present. The form *সবে* « sabbē » noted above (p. 724), may be a contracted form of it, rather than « \*sabbāhi ».

In the ŚKK. (p. 176) we have the following: *মারন্তাক যেনা মারে । তার পানী না লএ পীতরে ॥* « mārāntā-kā jē nā mārē, tāra pāñi nā lāē pītārē » *the fathers do not accept the water (offered in the Śrāddha) of him who does not strike an aggressor*. Here of course *পীতরে* is merely a *sts.* form from the Skt. « pitarah », familiar in many a *ślōka* current among the people.

488. Original nominative plural affix was lost to OB. Original plural instrumental certainly was used for the nominative, but it also became obsolete in OB. itself. Original genitive plural had only a very restricted use for the plural of all cases down to Early MB. To indicate the plural, which had come to be indistinguishable from the singular, some new devices came in. Of these, the most noteworthy was the affixing of

some noun of multitude to the noun. This method of indicating the plural by composition is already found in OB. as in the Caryās. Where the noun was qualified by a plural numeral, there was no necessity of compounding with a noun of multitude: e.g., « pañca vi dāla » (*with five branches indeed* (Caryā 1); « bēni pakḥā » *two wings or sides* (pakṣa: Caryā 4); « cau-saṭṭhi pākhuḍi » *sixty-four petals* (Caryā 10); « pañca janā » *five men* (Caryā 12: « janā = jana + ā », see pp. 658-659; it is not the MIA. plural nominative « -ā »: cf. NB. একজন *ekja janā* » *one man*, সে জন *sē janā* » *that man*, and পাঁচ জন *pācḥ janā* »); « pañca tathāgata » (Caryā 13); « pañca kēḍuāla » *five oars*, « dui māga » *two ways* (Caryā 14); « batisa tānti » *thirty-two strings* (Caryā 17); « tini bhuana » *the three worlds* (Caryā 18); « tia dhāu » *three natures* (dhātu) (Caryā 28); etc. But in the other cases, where it was felt necessary for the plural idea to be specified, we have compounding or periphrasis: e.g., « maṇḍala-saēla bhājai » *all the maṇḍalas are broken* (Caryā 16); « kuḷiṇa-jaṇa » *people of good family*, « bidujaṇa-lōa » = « vidvajjana-lōka » (Caryā 18).

« Saēla = sakala, jaṇa = jana, lōa = lōka » seem to have been established as plural-forming words in OB. In MB. we find গণ « gāṇa », সকল « sākāla », সব, সভ, সঙ্ঘ « sabbhā, sabbā, sammhā » (see p. 319), আদি(ক) « ādi(ka) » and কুল « -kulā », among others. The last is the source of the common pan-Bengali affix for the plural, গুল « -gulā » (-kula-ka > MB. -kulā, -gulā), extended to গুলী « gul-ā » (< « \*kulāka »: by Vowel-Harmony গুলো « gulō »), গুলান « gulā-nā », †গুলটিন « gulāin < \*gulā-n-i » with the « -na » from the old genitive (see p. 725), and গুলি « -guli » (to denote pettiness, loveliness or prettiness of the object whose plural it indicates is really the feminine: < « \*kulikā »: see pp. 672, 673, 686), and we have further an extension গুলিন « -gul-i-nā ». In addition, we have extensions of « -gulā » with the pleonastic ক « -ka » (গুলাক « -gul-ā-ka », গুলিক « -gul-i-ka ») which are found mostly in West Rāḍha. This *sts.* form with the « -k- » in an intervocal position softened to « -g- », seems to have been quite common from Early MB. times; but literary Bengali preserves the *ts.* « kulā » > kulā » as well, as in আলিকুল « āli-kulā » *bees*, কামিনীকুল « kāmīnī-kulā » *ladies*, ধেনুকুল « dhēnu-kulā » *cows*, পাখীকুল « pākhi-kulā » *birds*. In dialectal



Bengali, « -gulā, -gulā, -gulā » become গুনো « -gunō » (Calcutta and surrounding tracts), গিলা, গ্লা « -gilā, -glā » (North Bengali), and উন্, গিন্ « -un, -gin » (Chittagong).

489. There is in NB. the affix দিগ « -digā », genitive দিগের « -digērḍ » which is used with names of animate, preferably sentient and intelligent beings, in the plural forms of the *oblique* cases. The affix is never used for the nominative. দিগ, দিগের « -digā, -digērḍ » are « sādhu-bhāṣā » forms; in the specimens of prose in the Late MB. and Early NB. periods, a form দিগর « digārḍ » also occurs side by side with দিগ « -digā ». The equivalents of দিগ, দিগের « -diga, -digērḍ » are common in West Bengali, specially in the Standard Colloquial, and are দি, দিন্ and দেব « -di, -dig-, -dērḍ ». The affix seems to have been of Central Rāḍha origin: it is not found in East and North Bengali dialects, where its occurrence at the present day can without difficulty be explained as being due to the influence of the « sādhu-bhāṣā » as well as of the Standard Colloquial. The use of this affix, both with organic inflexions and with post-positions, is indicated below, with the word মানুষ « mānuṣḍ » *man*.

*Accusative and Dative*: Sādhu-bhāṣā মানুষদিগকে « mānuṣḍ-digā-kē », মানুষদিগেরে « mānuṣḍ-dig-ēr-ē », archaic মানুষের দিগরে « mānuṣ-ērḍ digār-ē », মানুষের দিগরকে « mānuṣērḍ-digārḍ-kē »; Standard Colloquial মানুষদিকে « mānuṣḍ-di-kē », মানুষদিগে « mānuṣḍ-dig-ē », মানুষ'দগকে « mānuṣḍ-dig(ā)-ke », also « mānuṣḍ-dikkē », beside the genitive মানুষদের, মানুষেদের « mānuṣḍ-dērḍ, mānuṣēdērḍ », and the genitive *plus* the dative or accusative post-position কে—মানুষ(ে)দেরকে « mānuṣ(ē)-dērḍ-kē »;

*Instrumental*: Sādhu-bhāṣā মানুষদিগ-দ্বারা, -কর্তৃক « mānuṣḍ-digā-dwārā, -kārtṛkḍ » মানুষ, মানুষের দিগর (দিগের) দ্বারা « mānuṣ(ērḍ) -digārḍ (-digērḍ) dwārā », etc.; Standard Colloquial মানুষদের দিগে < দিয়া, -দ্বারা « mānuṣḍ-dērḍ-diyē < diyā, -dwārā », etc.;

*Ablative*: Like instrumental, with হইতে, হ'তে « hāitē, hōtē », থাকিয়া, থেকে « thākiyā, thēkē » etc., in the place of instrumental post-positions.

*Genitive*: Sādhū-bhāṣā মানুষদিগের, মানুষেরদিগের « mānuṣ(ēṛḍ) -digēṛḍ », মানুষদিগর « mānuṣḍ-digārḍ », archaic and rare মানুষের দিগরের « mānuṣēṛḍ digārēṛḍ »; Standard Colloquial মানুষদের, মানুষদের « mānuṣ-ēdēṛḍ, mānuṣḍ-dēṛḍ », মানুষেরদের « mānuṣēṛḍ-dēṛḍ, mānuṣēddēṛḍ »;

*Locative*: Sādhū-bhāṣā মানুষদিগতে, -দিগেতে « mānuṣḍ-digā-tē, -digē-tē », archaic মানুষের দিগে, মানুষের দিগরেতে « mānuṣēṛḍ digār-ē, -digār-ētē »; Standard Colloquial মানুষদেরতে « mānuṣḍ-dēṛḍ-tē », মানুষদিগেতে « mānuṣḍ-digētē » (rather uncommon for the locative: the Standard Colloquial would prefer the form মানুষ-গুলিতে, গুলিতে « mānuṣḍ-gulī-tē, -gulā-tē » etc.)

The affix is thus in three forms, -দি -দ « -di-, -d- », দিগ « -dig(ā)- » and দিগর « -digārḍ ». The last form apparently has a র « -rḍ » which is not the genitive affix. It is frequent in letters and documents and in prose generally from the 18th century onwards, but it became obsolete by the middle of the 19th century. This দিগর « -digārḍ » is only an artificial form built on the proper genitive দিগের or দিগর « -dig-ēṛḍ, -dig-ārḍ ». It came to be established through a confusion with the Persian « digar » *another, more, and the rest*, etc. Persian « digar » occurs frequently in the highly Persianised Bengali of the law courts: a form like মানুষের দিগরকে « mānuṣēṛḍ digārḍ-kē » *to men* arose probably in the early 18th century in the law courts; and when a prose style came into being in Bengali about that period, it had to be based as a matter of course on the only prose that was current, viz., in legal and epistolary documents. The curious form দিগর « digārḍ », which is thus merely the native দিগ-র, দিগের « -dig-ārḍ, -dig-ēṛḍ » mistaken for the Persian word, in this way came to be accepted in the « sādhū-bhāṣā » in its formative and early periods. The confusion between the native affix দিগ « -digā » and the Persian « digar » is plain: we have তাহাদিগকে, তাহাদিগের « tāhā-digā-kē, tāhā-dig-ēṛḍ » *to them*; and a Persianised expression তাহার দিগরকে « tāhārḍ digārḍ-kē » *to the others of his (group)* > *to them* could easily be evolved when the form « -dig-ārḍ » was handy in the language. With the decay of Persian influence upon Bengali, the form দিগর « digārḍ » has become obsolete.



The persistent use in many Late MB. and Early NB. prose documents of the form *দিগর* < *digārṣ* > as a separate plural forming post-position, like *সব, সকল* < *sābṣ, sākālṣ* > and the rest, has thrown some Bengali scholars off their guard, and has been responsible for the assumption that *দিগর* < *digārṣ* > and *-দিগ, -দিগের, -দি, -দের* < *-digā, -dig-ērṣ, -di, -dērṣ* > etc. are derived from the Persian word.

There is no affix corresponding to *-দিগ, -দিগের, -দি, -দের* < *-digā, -di, -dig-ērṣ, -dērṣ* > in any other NIA. language. It does not occur in OB. There has been some speculation about the origin of this group of affixes. (Cf. Beames, 'Comparative Grammar of the Modern Aryan Languages of India,' II, London, 1875, p. 200, Bengali Grammar, Oxford, 1894, p. 20; R. G. Bhāṇḍārkar, Wilson Philological Lectures delivered in 1877, Bombay, 1914, pp. 238-239; A. F. R. Hoernle, Gaudian Grammar, pp. 190-191; Chintāmaṇi Gāṅguli, Bengali Grammar, Bengali year 1288, p. 40; Rabindranath Tagore, 'Śabda-tattwa,' pp. 85-90.) But there is nothing in MB. to warrant an affiliation to an obsolete genitive affix < *-dā* > (Hoernle), to a plural form < *\*-nhi-kēra > \*-ndigēra > -digērṣ* > (Rabindranath Tagore), or a derivation from a Skt. < *diś, dik* > *direction* (Beames and Bhāṇḍārkar), or from a Skt. < *dirgha* > (Gāṅguli).

The proper source of *-দিগ, -দি* < *-digā, -di* > is undoubtedly the *ts.* word < *ādi* > which came into wide use in Eastern Rāḍha from the Second MB. period. Rai Bahadur D. C. Sen suggested < *ādi, ādi-ka* >, so commonly found in MB. literature from the 16th century onwards (and certainly earlier still) as having developed into the NB. affix. (Cf. 'Varga-bhāṣā Ō Sāhitya', pp. 33, 34, 235, 332). It would be noted that in MB., *আদি* < *ādi* > and its extension *আদিক* < *ādi-ka* > are used for the nominative as well. The words are used in MB. mainly after proper names, but they are found with other nouns, masculine as well as neuter. The sense is not exactly of the plural, but of 'and the like,' 'and the rest.' Thus, in the 'Narōttama-Vilāsa' of Narahari Cakravarti (c. 1614-1625), we have—

ঐছে কত কহি অব্যাপকে স্থির কৈলা ।

প্রাতঃকালে স্নানাদিক করি সজ্জ হৈলা ॥

বিনা বানে রাজা অধ্যাপকাদি সনে ।

গেলেন খেতরি শীত গৌরাদ প্রাজপে ॥.....

মহাবিজ্ঞ রামচন্দ্র গোবিন্দাদি তথি ।

কৈল সমাদর সবে হৈলা রুই অতি ॥ (VSP., II, pp. 1244-1245)

- śicē kātā kahi, ādhyāpakē sthirā kailā |
- prātāh-kālē snānādika kārī sajjā hailā ॥
- binā yānē rājā ādhyāpakādi sānē |
- gēlēnā Khētari śighrā Gaurāṅgā-prāṅgāṇē ॥.....
- māhā-bijñā Rāmā-candra Gobindādi tāthi |
- kailā sāmādarā, sabē hailā hr̥ṣṭā āti ॥

*In this way saying a great deal, he made the scholars quiet ;  
In the morning-time, having finished his bath and other duties, he was dressed ;  
Without a vehicle the king, with the scholars and the rest,  
Went quickly to Khetari, to the courtyard of Gaurāṅga ;  
The very wise Rāma-candra, and Govinda and the rest there  
Did honour, and all were very glad.*

In some cases, we find the phrase *আদি করি সবে* « ādi kārī sabē » *all with so-and-so at the head=so-and-so and others*, rather than the simple *আদি* or *আদিক* « ādi, ādi-kā ». This « ādi-kārī » must have had something to do with the evolution of *দিগর* « digārṣ » discussed above.

As yet the more common plural-affix is *গণ* « gāṇṣ », at least in literature ; but the « ādi, ādi-ka » > « -dā, -digā », for the plural oblique seems to have been well-established by the end of the 15th century : *তোমাদের* « tōmāderā » *your*, for instance, is found in Kṛttivāsa's 'Rāmāyaṇa, Ayōdhyā-kāṇḍa' (pp. 29, 30, VSPd. edition, MS. of c. 1602 A. C.) as well as in 'Uttara-kāṇḍa' (e.g., p. 194 ; MS. of c. 1580 A.D. ; the MSS. are late, and it cannot be ascertained whether « -derā » was actually in use in Kṛttivāsa's time, 15th century, but in all probability it was).

MB. *ts.* « ādi » would naturally become « āidā, āid » by epenthesis : *মানুষাদি* « mānuṣādi » would become *মানুষ্যদ* « \*mānuṣāid », genitive *মানুষ্যদের* « \*mānuṣāiderṣ », whence NB. *মানুষদের* « mānuṣēderṣ », which is still common, and then by dropping of the « -ē », *মানুষদের* « mānuṣṣ-derṣ ».



We even now invariably say *রামেদের* « *Rāmēdērā* » of *Rāma and his people* = « \**Rāmāldērā* < *Rāmādi*, *Rāmāld* + -ērā »; and *রামদের* « \**Rām-dērā* » is not heard at all: the old full form is preserved in this case, where we have a proper name, and the sense too is the old one of a group rather than of the plural. The «-ā-» of «*ādi*, *āld*» came to be linked with the preceding word, and gradually «-di, -d-» alone had the force of an affix. Then it came to be used with nouns ending in vowels like «-i, -u»: *e.g.*, *পাখীদের* « *pākhi-d-ērā* » of *birds*, *গোরদের* « *gōru-d-ērā* » of *cows*. The intermediate stages are not preserved in MB. literature, as the literary language scorned to have colloquial forms as yet not fully established. The form *দি* «-di» without epenthesis, is found, but it is rather rare in the Standard Colloquial (see under accusative above, p. 728). *আদিক* « *ādi-kā* » became *আদিগ* « *ādiga* » by voicing, as in the case of *গুল* < *কুল* «-gulā < *kulā*». The «-ā» was assimilated with the ending of the preceding word, and there was not much scope for epenthesis here (to a possible « \**āldigā* »): and the «-kā» form seems to have been rather a learned and artificial one than colloquial—the result of an attempt to give a respectable look with the all-useful «-ka» to a vernacular form in «-di, -ādi». *দিগ* « *digā* » also came to be generalised, like *দি*, *দ* «-di, -dā» with words in «-i, -u» vowels. The genitive form of *দিগ* is *দিগের* « *digērā* » = *digā* + -ērā; and *দিগর* « *digārā* » = *digā* + -ārā also is found. It would not be correct to derive *দিগের* form *আদি-কের* « *ādi-kērā* », regarding the case as one of retention of the older MIA. form of the common Bengali genitive affix «-ērā»; the occurrence in MB. of *আদিক* « *ādi-kā* » is against such a derivation. Rai Babadur Y. C. Vidyānidhi, while accepting «*ādi*» as the source of the Bengali affix, suggests that «*ādi* + *kāra*» > *দিগার* « \**digārā* » was the original form of *দিগের* « *digārā* » (Bengali Grammar, VSPd., p. 196), which has the «-ā» changed to «-ē» through Vowel Harmony (see pp. 400 *supra*); but the need to postulate a MB. « \**digārā* » is equally unnecessary.

490. The *lkh.* word *সব* « *sābā* », strengthened in MB. by the *sts.* *সভ* < *সভা* « *sābhā* < *sābhā* », the *lkh.* or *ls.* words *কুল* > *গুল* « *kulā* > *gulā* », *জন* « *jānā* » and *গণ* « *gāṇā* », and the *ls.* or *sts.* *আদি*, *আদিক* > *দি*, *দিগ* « *ādi*, *ādi-kā* > -di, -digā », have thus furnished to Bengali a set of new

agglutinated plural affixes. There are other *ts.* words of multitude loosely agglutinated to indicate the plural in the « sādhu-bhāṣā »—*e.g.*, « samasta, sakala, samūha, varga, lōka, caya, nicaya » etc. The Perso-Arabic « maḥal » is also similarly used, though in a restricted way, *e.g.*, বন্ধু মহল « bāndhu-māhāl » *society of friends = friends*, রাজনৈতিক মহলে « rājñaitikā-māhāl-ē » *among politicians, etc.*

The case affixes and post-positions are placed after the noun of multitude agglutinated, and this system has its parallel in the agglutinative system of Dravidian, *e.g.*, মাহুব-গুল-কে « mānuṣṣ-gulā-kē » *to men*, cf. Tamil « manidaṅ-ga]-ukku ». Here of course we have only a fortuitous resemblance, there being no genetic connexion whatever between the very late Indo-Aryan « -gulā, -kē » and the Dravidian « -ga], -ukku ».

Of the above nouns of number, সব « sābṣ », সকল « sākālṣ » sometimes সমস্ত « samastā », and অনেক « ānekṣ » (MB. আনেক « āṇēkṣ ») which indicate merely number and not grouping, are loosely compounded with nouns as attributives to express the plural. This is found from the oldest period of Bengali: *e.g.*, Caryā I, « saala-samāhia » *with (all) samādhis*; ŚKK., p. I, সব দেবী মেলা সভা পাতিল আকাশে « sābā-dēbē mēli sābhā pātīlā ākāṣē » *the Gods having met held a gathering in the sky*; *ibid.*, p. I, ব্রহ্ম সব দেব লইয়া গেলান্তি সাগরে « Brāhmā sābā-dēbā lāyīā gēlānti sāgārē » *B. taking the Gods went to the sea*. In NB., the noun qualified can optionally take a second word at the end, or the affix « -ērā, -rā » (see *infra*).

Other forms of periphrasis are found from the Early MB. period: the pronominal adjective জত, যত « jātā » *as much* is used attributively, singly or with সব « sābā », গণ « gāṇā » etc.: *e.g.*, Early MB. (ŚKK. p. 19), বত নানা ফুল পান করপুর সব পেলাইল পাএ « jātā nānā phulā, pānā kārāpurā, sābā pēlāilā pāē » *all the various flowers, betel-leaves, and camphor she scattered with her foot*. *ibid.*, p. 237, কাহ্নাঙ্কিৎ দেখি যত গোপগোপীগণে । হরষে হইলা তবৈ সজল নয়নে ॥ « Kāhñāṅikā dēkhi jātā gōpā-gōpī-gāṇē, hārāṣē hāyilā tābē sājālā nāyānē » *Seeing Kṛṣṇa, all the herdsmen and herdswomen through joy then had moistened eyes*. The loss of a genuine plural-forming affix had placed the language in this difficulty.



Plural nouns qualified by demonstratives solve the difficulty by adding the noun of multitude to the pronoun: *e.g.*, সে-সব কাজ « *sē-sābā kāja* » *those works*, এই-সমস্ত কথা « *ēi-sāmastā kāthā* » *these talks, etc.* This usage is found in the ŚKK.: *e.g.*, p. 18, এতেকি এ সব কাজের প্রকার জাগহ আশেবে বিশেষে « *etēkē ē-sābā kājēra prākāra jāgahā āśēṣē biśēṣē* » *in this way know thoroughly and in detail the method of these works*; p. 33, এ সব গোপবধূজন লজা কথা না বাসি বড়ায় « *ē-sābā gōpā-bādhū-jānā lajā kāthā nā jāsi bāṛāyī* » *taking all these wives of the herdsmen, where indeed dost go, old mother!* p. 58, এ সব চরিতে « *ē-sābā cāritē* » *with these deeds; etc., etc.*

491. The commonest NB. affix for the plural is রা or এরা « *-rā, -ērā* » which is now organic or inflexional in its nature, although in origin it is post-position. রা, এরা « *-rā, -ērā* » are only extensions of the genitive bases in র, এর « *-rā, -ērā* » by means of the আ « *-ā* » affix. Originally, there was a noun of multitude after the strengthened genitive in « *-ā* ». This stage is still found in the Maithili « *hamarā-sabh, tōharā-sabh* » *we, ye*; and in Bengali, the noun of multitude can be optionally used, and as a matter of fact is still frequently used in the colloquial as well as in the literary language (of both prose and poetry); *e.g.*, আমরা সব « *āmārā-sābā* » *we*, তোরা সব « *torā-sābā* » or তোমরা সব « *tōmārā-sābā* » *ye*, বামুনেরা সব « *bāmunērā-sābā* » *Brāhmins*, রাজারা সব « *rājārā-sābā* » *kings*, পাখীরা সব « *pākhīrā-sābā* » *birds, etc.* It is like « *mama gaṇaḥ* » or « *māmakāḥ sarvā* » for « *vayam* ». In NB., however, the noun of multitude is ordinarily felt to be superfluous. The genitive form with its « *-ā* » of definitiveness (see *ante*, pp. 658-659) could be easily distinguished from the ordinary genitive of connexion which does not have the « *-ā* ».

The use of the strong genitive with the noun of multitude came into being with the pronouns of the first and second person, when the old plurals আমি, আঁকে, আমি « *āmi, āmhē, āmi* » and তুমি, তুঁকে, তুমি « *tumbi, tumhē, tumi* » first became honorific singular and then ordinary singular. New plurals were found out; either by mere juxta-position, as nominative আমি সব, আমি সব « *ām(h)i-sābā* », তুমি সব, তুমি সব « *tum(h)i-sābā* », oblique আঁকা (আঁকা) সব « *ām(h)ā-sābā* », তোঁকা (তোঁকা) সব « *tōm(h)ā-sābā* », the case affixes

and post-position being added to সব < sâbā >; or by means of the strong genitive, e.g., আক্ষারী, আমারী, আমরা সব < āmhār-r-ā, āmār-r-ā, āmār-r-ā sâb(h)ā > *we*, তোক্ষারী, তোমারী, তোমরা সব < tōmhār-r-ā, tōmār-r-ā, tōmār-r-ā sâb(h)ā > *you*. Both the types are found in MB. literature. With the demonstrative and other non-personal pronouns, however, < sâbā > is employed in NB. only to indicate inanimate objects, and to indicate animate objects সব < sâbā > must be used with the রা < -rā > form: e.g., এ-সব < ē-sâbā > *these things*, সে-সব < sē-sâbā > *those things*, and এরা < ē-rā >, এরা-সব < ē-rā-sâbā > *these people*, তারা < tā-rā > *they, those people* (but এ-সব লোক < ē-sâbā lōka > *these men*, সে-সব ছেলে < sē-sâbā chēlē > *those boys*). The method by simple juxta-position of < sâbā > to the base has not yet become obsolete in NB. The simple strong genitive, without adding the noun of multitude, already came into being in the 14th century. But it was still not very popular, and was confined to the first and second personal pronouns apparently. In the ŚKK., there are only 3 instances of it:

- p. 202, আজি হৈতে আক্ষারী হৈলাহৌ এক মতী ।  
 < āji haitē āmhārā hāilāhō (= hāilāhō) ēka-māti >  
*From to-day we have become of one accord.*
- p. 232, পুছিল তোক্ষারী কেহে তরাশিল মনে ॥  
 < puchilā tōmhārā kēhē tārāsilā mānē >  
*Why did ye ask with a mind afraid?*
- p. 263, আক্ষারী মরিব শুণিলে কাশে ।  
 < āmhārā maribā śuṇilē Kāśē >  
*If Kaśa were to hear, we shall die.*

The < -rā > plurals for the pronouns seem to have been well-established in the 15th century: তোমরা, তারা, ইহারা, মোরা, আমরা < tōmārā, tārā, ihārā, mōrā, āmārā > etc. are quite frequent in the 1580 and 1602 MSS. of the Uttara and Ayōdhyā-Kāṇḍas of Kṛtīvāsa's 'Rāmāyaṇa.' It was during this century also, apparently, that the < -rā, -ērā > affixes were extended to nouns. Thus in Vijaya-gupta's 'Padmā-purāṇa' (last quarter of the 15th century: edition by Pyāri-Mōhan Dās-Gupta, Calcutta, 1318, from late MSS., modernised to a great extent), we find ছেলেরা < chēlē-rā > (for



• *chālā-rā* » *children* (p. 12), কালীরা « *kālīrā* » *the Qāzīs* (p. 55), বাপুৱা « *bāpurā* » *good men, fathers* (a term of address: p. 149), কামারেরা « *kāmārērā* » *black-smiths* (p. 169), শিবেরা বাপে ঐ « *Śibērā bāpē jhi* » *they together, Śiva the father and (Padmā or Manasā) the daughter, lit. the Śivas, father and daughter* (p. 219), etc., beside তালীরা « *tāl(hā)rā* », মোরা « *mōrā* » (pp. 53, 54), তোরা « *tōrā* » (p. 71), etc., etc. In MB. from the 16th century the use of « -rā, -ērā » is steadily on the increase, although it looks as if it was not favoured by literary Bengali of the Late MB. period. The « *sādhū-bhāṣā* » of the 19th century similarly preferred compoundings with « *gāṇḍ, sāmūhā, śākālā* » etc.; but « -rā, -ērā » are at the present day commonly used both in the « *sādhū-bhāṣā* » and the Standard Colloquial and it is found in all the dialects. In the « *sādhū-bhāṣā* » and the Standard Colloquial « -rā, -ērā » are used only for the nominative, but in many forms of dialectal (colloquial) Bengali, we have the « -rā, -ērā » bases employed for the genitive as well by adding the usual « -rā »: e.g., Standard Colloquial *nomi ative* তারা « *tārā* » *they*, genitive তাদের « *tādērā* » *their* (= « *sādhū-bhāṣā* » তাহারা « *tāhārā* » and তাহাদিগের « *tāhādigērā* »), but East Bengali তারা « *tārā* », genitive তারার « *tārā-rā* »: the last is therefore a double genitive form. Similarly, there is Western Bengali (Dhalbhum) আমরাকে « *āmārā-kē* » *us, to us* = Standard Colloquial আমাদের « *āmāderā* »; so Malpaharia চাকররাকে « *cākārā-rā-kē* » *to servants*, মিতানরাকে « *mitān-rā-kē* » *to friends* (LSI., V, I, p. 100), etc.

The use of a form of the genitive for the nominative plural is not an isolated fact in Bengali. Apart from the genitive plural in « -rā, -ērā », we have in Bengali itself, in the Western dialects, plural forms by extension from the obsolete genitive in « -kā »: e.g., Western Bengali (Dhalbhum, LSI., V, I, p. 79) ইগা « *i-gā* » < \* *i-kā* » *these*; (Malpaharia, Santal Parganas, LSI., V, I, p. 100) বেহিগা « *bēhiyā-gā* » *courtesans*, ইহাগা « *ihā-gā* » *these*, সাজানগার « *sāṅgāṇḍ-gā-rā* » *of friends*; (Manbhum, LSI., *ibid.*, p. 97) হাৎগা « *hāt-gā* » *hands*; S.W. Bengali (LSI., *ibid.*, p. 110) ইগা « *i-gā* » *these*; etc. Among the sisters and cousins of Bengali we have similar instances, e.g., Magahi « *hamar-nī* » *we* < « *hamar* » *of us* + genitival affix « -nī »; Bhōjpuriyā « *hamanī-kā, hamaran* » *we*, « *unhā-kā* » *they*,

« kēkañt, kekant-kā » *who* ? (pl.); in the Baghelkhandī form of E. Hindi, we have similarly « hamārē, tibārē » *we, ye* (cf. Kellogg, ‘Hindi Grammar’ p. 193). In Eastern Pabārī (Khas-kurā or Nēpālī), the plural affix is « -hēru, -haru » and « -ēru », with which are connected the dialectal Rājasthānī (Mālvi) plural affix « -hōr, -hōrō, -hōnō » and the Early Kanaujī (W. Hindi) plural affix « -hwār » (cf. LSI., IX, IV, p. 23; IX, II, p. 55). The source of the above would seem to be the old genitive and adjectival post-position of MIA., namely « -kara, -kēra »,—the source equally of the Bengali « -rā, -ērā »: the « h-, hō-, hē- » being possibly the « -h- » of the old oblique (cf. Hoernle, Gaudian Grammar, pp. 191, 192).

The evolution of the « -r-ā, -ēr-ā » affix for the plural is comparatively a late thing in Bengali, and its derivation from « kara, kēra < kārya » is clear; and it cannot be in its origin a Dravidian borrowing, nor should it be compared with the Dravidian plural « -ār, -ār », found in Tamil as well as in the Dravidian speeches adjoining Bengali, viz., Oraon and Maler.

492. In dialectal Bengali there is an affix for the plural, মীন « mīnā » (West Bengali, Manbhum Dist.), or মন « mānā » (South-Western Bengali of Midnapur). This is undoubtedly the same as the affix « -māna- » which is found in Oṛiyā as a common plural affix (in the nominative « mānē »): e.g., « puruṣā », pl. nom. « puruṣ-ē, puruṣā-mānē », genitive pl. « puruṣāṅ-kā(rā), puruṣa-mānāṅ-kā(rā) ». In the Early Oṛiyā of the 15th century inscriptions (see *supra*, p. 107), the form occurs as both « māṇa » (with a cerebral « ṇ ») and « māna ». The source of this form is the OIA. « mānava », compounded to indicate the plural, like « jana, lōka ». The *tōl.* form in Oṛiyā gave « \*māṇā = \*māṇā » (« ava, aṇa > ā »: see p. 346): but when it became an affix, it was possibly confused with a *ts.* « māna » *measure*, and this has led to the spelling with a dental « -n- » which obtains now: « \*māṇavahi, māṇābi » gave « māṇē, mānē ». In OB., the word is found with the « -ā » affix, e.g., in Caryā 46: « mōha-vimukkā jāi māṇā, tabē tuṭai avañā-gamaṇā » *when a man is freed from ignorance, then (his) coming and going (= saṁsāra) is broken*. The word is found in the Haijong dialect of East Bengali (Maimansing) as মন « mānā » *man*, and possibly it occurs in other dialects. In Bhōjpuriyā, we have « manai », a common word for *man in general*, which



represents either a « \*mānavika » or the old Māgadhī nominative singular « mānavē » \*mānavī » : and « man » for the plural is found in the Nāgपुरiyā dialect of Bhōjपुरiyā, as well as in the contiguous Chattisgarhī form of Eastern Hindī. We have thus a tract of IA., embracing the Oṛiyā, West Bengali (in part), South-eastern Bhōjपुरiyā and Chattisgarhī speeches, in which « mānava » has come to be a plural indicating word : and considering that « mānē » is in full force in Oṛiyā, it may be presumed that this employ originated in the old West Rāḍha form of Māgadhī Apabhraṃśa, which was the source of Oṛiyā, and thence it spread to the contiguous dialects.

493. Early Assamese uses the words « gaṇa, saba (samha, sama), sakala » etc. to indicate the plural, just like Bengali. The use of these affixes has become obsolete now. New Assamese employs instead the words « -bilākṣ, (-blākṣ), -bōrṣ » and « -hātṣ ». All these are rare in Middle Assamese. « -bilākṣ » is of obscure origin. North Bengali has a dialectal form for the Common Bengali « -gulā, -gulākṣ », namely, « -gilā, -gilākṣ, -glā », and a connexion between « -gilākṣ » and « -bilākṣ » has been suggested ; but apart from the phonetic difficulty of the change of « -gi- » to « -bi- », there is a wide difference in the employment of this word — « -gulā » in Bengali is contemptuous, but « -bilākṣ » in Assamese is honorific. In Early Assamese, again, « -gulā(ka) » is not found at all. The Skt. work « vilōka » has been suggested as the source of « -bilākṣ » (Devānanda Bharāli, 'Asamiyā-bhāṣār Maulik Vicār,' Dibrugarh, 1912, p. 85). The use of the *ts.* « lōka » as an honorific plural affix in Assamese lends support to this derivation (*e.g.*, « tai » *thou*, « tumi » *you*, honorific « tumi-lōkṣ » ; so « mantri-lōkṣ » *ministers*), but the change of « ō » to « ā » is not justifiable, and this precludes the above derivation.

« -bōrṣ » may be from an IA. « bahula » or « bahala » *many*, rather than from « bhūri » (as suggested by Devānanda Bharāli, *op. cit.*) Or can it be that « -bōrṣ » and « -bilākṣ » are connected with each other, and are to be referred to a non-Aryan (Tibeto-Burman) source ? There is the common Boḍo plural affix « frā, for, fūr » which comes up in this connexion : Boḍo formed an important (if not the largest) non-Aryan element in Western Assam where the Assamese dialect was characterised.

Assamese «-bātā» represents «\*ahanta», present participle of «√ah = as», corresponding to Bengali হৈতে, হইতে «hāitē», apparently used as a genitive-ablative post-position in the Eastern Magadhan dialects, and later stereotyped into the plural affix in Assamese.

494. By reduplicating the adjective, we have the sense of the plural distributive in Bengali, as in other NIA. languages : *e.g.*, বড় বড় ঘোড়া «bārā bārā ghōrā» *horses, each a big one*; OB. (Caryā 28) «ūcā ūcā pābata (sta.)» *hills, each a high one*; MB. (ŚKK., p. 388) বড় বড় গাছের «bārā bārā gāchērā» *of trees, each a big one*.

[D] CASE INFLEXIONS : INHERITED FROM MIA., AND NEWLY CREATED.

495. Following the method of the Sanskrit grammarians, the Bengali noun is declared to have seven cases (eight, including the vocative), which are formed by adding both inflexions and postpositions. The following are the case affixes which are added to the noun in New Bengali, like organic inflexions, as distinct from the detachable post-positional words :

Nominative : এ, য «-ē, -yā» ;

Instrumental : এ, য «-e, -yā» ;

Locative : এ, য «-e, -yā» ; † তে, তে «-tā, -t-ē», এ-তে «-ē-t-ē», extended also to the Instrumental and the Nominative.

Oblique-Locative : এ, য «-e, -yā», occurring as the Accusative and Dative, and also in the Instrumental with the post-positional verb করিয়া «kāriyā» or করে «kōrē» ;

Genitive : র, এর «-rā, -ērā» : in the plural, † গা, গো «-gā, -gō» ;

Dative : তে, তে, এর «-k-ē, -r-ē, -ēr-ē».

496. Of the above, the Genitive, Dative, and Locative affixes «-rā, -ērā, -gā, -gō» ; «-k-ē, -r-ē, -ēr-ē» ; «-ta, -t-ē» are of recent, Late MIA. origin, having developed, not from OIA. case inflexions, but from help-words which came to be combined with the stems or inflected forms of the noun in the period immediately before the NIA. stage. The other affix, the affix এ «-ē», occurring also as য «-yā» after the «-ā» and «-ō» vowels in New Bengali, which is found in the Nominative and Instrumental, and in the



Oblique-Locative and Accusative, is the sole representative in Bengali of the OIA. case affixes, into which several OIA. cases have merged.

#### NOMINATIVE.

497. Bengali and Assamese nominative affix has the characteristic affix « -ē ». It has become rather obsolete in West Bengali, but it is still a living form in East Bengali and in Assamese. Instances are exceedingly common in the OB. of the Caryās and in MB. of all periods. In other Magadhan Languages, « -ē » as the nominative affix (singular) is obsolete now, but the older literatures of Oṛiyā and Maithilī show that it was formerly as much a living form as in Bengali and Assamese. See *infra* for examples.

In the old Prācya or eastern speech of the First MIA. Period, the OIA. nominative masculine and neuter affixes « -aḥ, -am » both became « -ē ». The specimens of the Eastern dialect that we have all show this « -ē »—Aśōkan Eastern speech, Old Māgadhi as in the Śūtanukā inscription (see p. 59), 'Māgadhi' and 'Ardha-māgadhi' as in Aśvaghōṣa's dramas (p. 59), Jaina Ardha-māgadhi, and Māgadhi of the Sanskrit drama. In Late MIA., i.e., during the Apabhraṃśa Stage, this « -ē » in all likelihood became « \*-i », as we find from the evidence of some of the Prakrit grammarians. Thus Mārkaṇḍēya (17th century) in his 'Prākṛta-sarvasva' notes for Māgadhi that « sāu puṃsy ēd-itāu : puṃsi sāu parē 'kāra ēd-itāu syāt »: i.e., in -su, or nominative singular, masculine (and neuter), the final « -ā » becomes « -ē » and « -i »: e.g., « śili muṇḍidē=śiraḥ muṇḍitam » (Vizianagram ed., p. 102); and further, he says that in the Śābarī dialect, a form a Māgadhi, « -ā- » in the nominative singular becomes both « -ē » and « -i », and this is a rule which is common to both masculine and neuter nouns: « māṇuṣē, māṇuṣī; vaṇē, vaṇi » beside « māṇuṣō, vaṇaṃ », for Skt. « mānuṣaḥ, vaṇam » (p. 108: « ataḥ sāv ēd-itāu ca, puṃ-napuṃśaka-sādhāraṇō 'yath vidhiḥ »). Paralleling the weakening of the OIA. locative « -ē » to « -i » in Late NIA. of both the East and the West, and that of Śaurasēnī and Mahārāṣṭrī and other Western MIA. « -aḥ > -ō » to « -u »

in the Apabhraṃśas of the West (see pp. 311-312), the Māgadhi «-ē» can reasonably be expected to have also become «-i», as the grammarian has noticed it. A form like «putra>puttē» would therefore result in Māgadhi Apabhraṃśa as «\*putti», in Māgadhi NIA. (including OB.) as «\*pūti». This «-i» form for the nominative (by extension, serving as the base for the other cases also) seems to have actually survived in a few words: e.g., OB. vocative «Kāuhi» (Caryā 7: <Kāṇhē, Kṛṣṇa); N.B. ‡ পুতি «puti» beside পুত «puta» son; চাটুতি «Cātuti» (see pp. 409, 692); ঠাই «ṭhāi» place < «\*thāwi, ṭhāmē=sthāman» (but cf. W. Hindi «ṭhāw<\*ṭhāwu»); নেই «nēi» indulgence < «\*nēhi=nēhē=snēhaḥ» (but cf. MB. দে «dē» < «dēha»; «dēhi» is found in Early Oriyā); and a few similar forms in MB., NB. A form like «putra-kaḥ» with pleonastic «-ka» would give Māgadhi Pkt. «putta(g)ē» which would become in Māg. Ap. «\*puttai», and the Old Bengali transformation of it would be «pūtē»=MB. and NB. পুতে «putē». And probably in this way the «-ē» is mostly to be derived from a Māgadhi «-aē»=Skt. «-a-kaḥ». Thus, OB.: «jē ajarāmara hōi diṭa-kāndha» (= «diṭha-kāndhē», to rime with «sāndhē» in preceding line) so that he becomes ageless and deathless, and strong in his shoulders (Caryā 3: < \*diṭha-kandhaī < diṭha-kandhaē = dṛḍha-skandhakaḥ); «Bhādē bhanaī» says Bhāda (Caryā 35: < Bhaddaē = Bhādrakaḥ); «kumbhīrē khāi» the crocodile eats (Caryā 2: < kumbhīraē = kumbhīrakaḥ); MB. (ŠKK.) কালের কারণে হএ সৃষ্টির বিনাশে «Kāṣērā kāraṇē hāē sṛṣṭira bināśē» through the reason of K. the destruction of the world takes place (p. 2); বাড়এ মধনে «bāṛhāē mādanē» love increases (p. 30); না ছাড়ে নানের পোএ «nā chārē Nāndērā pōē» Nanda's son does not leave (p. 38); 'Crepas Xaxtrer Orthbhedh'—«xadhue eq crux bhanaia boner moidhe raqhilo» = সাধুয়ে এক ক্রুশ বানাইরা বনের মধ্যে রাখিল the saint made a crucifix and kept it within the forest, «xtrie zigguiaxa corilo» = প্রীয়ে জিজ্ঞাসা করিল the woman asked; etc., etc.;—such instances from MB. and NB. are extremely common. A noun without any verb, in the usual nominal phrase-building of NIA., is frequently found with this «-ē» in Bengali.

Examples from Oriyā: «...Uttāmā-kumārē...upujilā» Prince Uttama was born ('Dhruva-caritra,' p. 4); «bicārā nāśā kāribārē, ētā nōhāi subicārē»



*you think of killing, this is not justice* (Jagannātha-dāsa, 'Bhāgavata,' the Story of the Birth of Kāṇsa, Contai ed., p. 19); « ēmāntā bhāli jānē jānē, buddhi āṇṭilā mānē mānē » *so viewing, each individually formed the plan in his mind* (ibid., p. 7); « bājṛā pāṇilā jēnhē śirē, bādānē nōhilā uttārē » (text = uttārā) *as if a thunder-bolt fell on the head, there was no reply in the mouth* (ibid., Rāsa-līlā, p. 7); « sujānā jānāṅkāṛā hitē, kābhāi bipṛā Jagānnāthē » *for the good of virtuous men, the Brāhman Jagannātha narrates* (ibid., p. 10); « ēkā gōptē āgāsāri jāi, khōjāi puṣpā-bāri » *one herdsman goes advancing and seeks flowers and water* (ibid., p. 12); etc. This « -ē » for the singular nominative has already become rather rare in Early Oṛiyā.

Examples from Maithili: « jani Manamathē mana bēdhala bānē » *as if Love pierced (her) mind with an arrow* (Vidyāpati, VSPd. ed., p. 39); « kāpala parama rasālē » *(he) trembled, filled with love* (ibid., p. 40); « sajanē-hu na purala manaka sādhe, nayana dēkhala Hari, ēta aparādhē » *even in a dream the heart's desire was not fulfilled; (she) saw Hari with (her) eyes, (was that) such a crime?* (ibid., p. 51); « cintāē bikala hṛdaya nahi thirē, bādana nihāri nayana baha nīrē » *the heart agitated with thinking is not steady; seeing his face, tears flow from the eyes* (ibid., p. 52); etc., etc.

An « -i » affix inherited from the Māgadhī « -ē » disappeared in the OB. period, possibly through confusion with the locative « -i < -ē », and « -akāḥ » « -aē » « -aī » « -ē » was fully established. In establishing this « -ē » as the characteristic nominative affix, there was the influence of the « -ē, -ē » affix of the instrumental. The nominative was replaced by the instrumental in the passive construction which occurred in OB. in the past tense of the transitive verb, following the MIA. conditions: e.g., OB. « \* Kānhē (for \* Kānhi) pōthi paḍhaī » *Krishna reads a book* would become in the past tense « \* Kānhē pōthi paḍhīlī ». The difference between the nominative and instrumental affixes in OB. (Kānhē < Kaṇhāē = Kṛṣṇakāḥ, Kānhē = Kaṇhē[ṇa]ḥ = Kṛṣṇēna) was one of nasalisation only, and the cases could be easily confused, and then affixes interchanged. And as a matter of fact, « -ē, -ē » interchange, and are used one for the other from the OB. period. The tendency also was to drop the affixes « -i, -ē » for the nominative when the construction was active: thus, beside

« kumbhirē khāī » (Caryā 2) and « Bhādē bhaṇai » (Caryā 35), we have the simple « -a » base : e.g., « Saraha bhaṇai » (Caryā 32). But this tendency may be said to have been resisted by the « -ē, -ē » of the instrumental nominative of the past transitive : e.g., OB. « cōrē nila » a thief took away (Caryā 2) ; Kukkuri-pāṣē gāḍa » *Kukkuri-pāda sang (ibid)* ; « Kānhē gāi » (= Kṛṣṇēna gītā : Caryā 18) ; « Bājulē dila » *Bājula gave (35)* ; « Ājādēvē saala bihariu » *everything Ārya-dēva has taken away (48)* ; MB. গায়েন চৌদাসে « gāilā Caudāsē » *C. sang, etc.* The nasalisation of the instrumental « -ē » was entirely dropped during the 15th century, and this made the fusion of the two cases complete.

In the gradual merging of the two cases, it is not unlikely that there was some influence of masses of Bengalised Tibeto-Burmans in North and East Bengal, who adopted the Aryan speech of Bengal during the formative period of Bengali. In Tibetan, for instance, the 'verb must be regarded as denoting, not an action, or suffering, or condition of any subject, but merely a c o m i n g t o p a s s, or in other words, they are impersonal verbs, like *taedet, miseret* etc. in Latin, or *it suits* etc. in English. Therefore they are destitute of what is called... the active and passive voice, as well as of the discrimination of persons... From the same reason the acting subject of a transitive verb must regularly appear in the Instrumental case, as the case of the subject of a neutral verb, —which, in European languages, is the Nominative—ought to be regarded, from a Tibetan point of view, as Accusative expressing the object of an impersonal verb, just as 'poenitet me' is translated by 'I repent'... The subject of a transitive verb, in Tibetan, assumes regularly the form of the instrumental, of a neutral verb that of the nominative which is the same as the accusative.' (H. A. Jäschke, 'Tibetan Grammar', London, 1883, p. 40).

The possibility of the « -ē » of the nominative also preserving the Māgadhī Ap. instrumental plural « -ahi » (> nominative, as in Oriyā) has been noticed before (p. 724). The instrumental in MB., through overlapping of function with the locative and through confusion with the « -ē » of the locative, assumed the postpositional affix « -ta, -t-ē » which is proper to the latter : e.g., MB. (ŚKK.) হাতে « hāthētā » in or with the



*hand*, NB. হাতেতে < hātēte >. This as a matter of course was taken up by the nominative in the Second and Late NB. periods, after nouns ending in a vowel (i.e. the vowels < -ā, -i, -u, -ō >, after < -ā > had dropped off) : e.g., বোড়াতে ঘাস খায় < ghōṛā-tē ghāsā khāy > *the horse eats grass*, earlier বোড়ার=বোড়া এ < ghōṛā-yā=ghōṛā-ē > and ঘোড়া < ghōṛā >, which are still used ; so গোকতে < gōru-tē > or গোর < gōru > (the earlier গোরএ < gōru-ē > is no longer found in the Standard Colloquial : see *supra*, p. 719).

Old Bengali shows a number of instances of nominatives in < -u > and < -ō > : these are literary impositions from Western or Śaurasēni Apabhraṁśa ; and although they crop up in the artificial Braja-buli dialect, they are not found in the Bengali speech proper, either in MB. or in NB. (see *supra*, pp. 115-116 ; 103-104).

#### INSTRUMENTAL.

498. The instrumental < -ē, -ē > occurs in numerous instances in the Caryā : e.g., < darē > *in fear* (2), < bēgē > (5 : vēgēna), < mānsē > (6 : mānsēna), < akilē > (9 : =aklēna), < nāvē > (10 : =nāvēna), < bōhē > (12, 35, =bōdhēna), < suraa-pasangē, jōṇi-jālē > (19 : =surata-prasangēna, yōgini-jālēna), etc., etc. This < -ē > is used also for the plural number : e.g., < tiṇiē paṭē > *with or in three beings* (16) ; and it has been generalised for feminine nouns as well, e.g., < sāṇē > (Caryā 2 : saṁjñā + -ēna) < michē > (22 : =mithayā), < hēlē līlē > (18 : =hēlayā līlayā), < bhāntiē > (41 : =bhrāntiā) ; etc., etc. (see *supra*, p. 717).

The < -ē > represents the OIA. < -ēna >, instrumental singular : < -ēna > is found in MIA. as < -ēṇa, -ēṇam, -ēṇ > ; in Old Bengali and Early Middle Bengali it still retains the nasalisation—< -ē > ; e.g., হাতে মারে < hātē mārē > *strikes with the hand*, eMB. হাথে মারে < hāthē mārē >, OB. < hāthē mārāi >, MIA. < hatthēṁ mārēi > = OIA. < hastēna mārayati >.

The change of < -ēna > to < -ē > has been through the nasalisation of the vowel by the < -n- >. The nasalised form already occurs in Apabhraṁśa. A parallel case is the change of < -ānām > of the genitive plural

to the forms «-ā, -ō» in NIA. (See p. 373.) The full «-n» also is preserved, for both «-ēna» and «-anām», in NIA.: *e.g.*, in Awadhī (Lakhimpurī dialect) «*ḍarēn*» *through fear*; and «-n(a), -n-i < ānām» is quite common.

The instrumental «-ē» is the sole relic of a true inflexion of OIA. which has survived in Bengali without contamination.

Instrumental «-ē, -ē» is preserved in Bihārī, *e.g.*, Maithilī «*nēnē*» *by a child*. It is found as «-ē» commonly enough in Early Oṛiyā. Traces of it occur in the Western Languages: *e.g.*, Hindī «*dhīrē calō*» *walk slowly*. For Marāṭhī, cf. Jules Bloch, 'Langue Marathe,' § 193, and R. G. Bhāṇḍārkar, 'Wilson Philological Lectures,' pp. 204-205.

The locative and instrumental were confused through the possession of the common affix «-ē, -ē», and in some cases a form could be equally either locative or instrumental. This resulted in the employment of the post-positional locative affix «-ta» in the instrumental as well, which has been noticed above. The Caryās show one or two instances: *e.g.*, Caryā 1, «*sukha-dukhētē*» *through joy and misery*; Caryā 15, «*biārētē*» *by discrimination* (vicāra-). In MB. and NB. «-ta, -t-ē, -ē-tē» become established for the instrumental, and for words ending in vowels (esp. «-i, -u, -ō»), «-tē» has become the characteristic instrumental affix (see *ante*, p. 719).

In Caryā 14 «*bāha tu cchandā*» *row thou with pleasure*, and in Caryā 45 «*bāḍhaī sō taru śubhāśubha-pāṇī*» *that tree grows through the water of good and evil*, we have exceptional cases of the simple base being used for the instrumental.

#### LOCATIVE AND OBLIQUE.

499. It represents in all probability an old locative suffix, an OIA. «\*-a-dhi», not found in Sanskrit, but attested from MIA. (Pali) «-dhi» and from the Greek «-thi». It has been also surmised that there was in OIA. an affix in two forms, «\*-bhi, \*-bhim» (which is represented in Homeric Greek by «phi, -phin», and is found in Latin in «ti-bi»: it occurs also in Armenian). Its use, as can be seen from the Greek and



other Indo-European languages, was in the sense of 'by, along with,' in the Locative and Ablative, as well as Instrumental, and rarely in the Genitive and Dative : and it was not of a definite number. This « \*-bhi, \*-bhim » would become « -hi, -him » in MIA., and it seems this suffix is partly also the base of the MIA. ablative and locative affixes: the nasalised « -him » would certainly seem to go back to it. (Cf. Wackernagel, 'Altindische Grammatik,' I, p. xx; Herman Hirt, 'Handbuch der griechischen Laut- und Formen-lehre,' Heidelberg, 1912, § 304.) Thus, ঘরে « ghārē » in *the house*, eMB. ঘরে, ঘরē « ghārē, ghārē » = Late MIA. « gharahi, gharahim » < OIA. « \*gṛha-dhi(m), \*gṛha-bhi(m) ».

It is very likely, however, that we have in addition the OIA. locative singular affix « -asmin » here, = « \*-assim, -aśsim, -amhi, -ammi » in Early MIA., which has merged into the Late MIA. « -ahi, -ahim ». There is some difficulty of deriving « ahī, -ahī » from the Eastern form « \*-assi, \*aśsi » as well as the Western « -amhi, -ammi ». The genuine Māgadhī form in the oldest period was « \*-aśsi », and « -amhi » was a Western one (cf. Truman Michelson, JAOS., 1909, pp. 77 ff.); but later Prakrit grammarians note « -ammi » for both Māgadhī and Mahārāṣṭrī. The form « -ahi » is found in Early Maithilī in the locative, and « -e, -ē, -aī, -ahī, -ahī » occur in Old Bengali. Oṛiyā uses now « ṭhā-r-ē » for the locative, but « -ē » is quite common for the locative in Early Oṛiyā.

Old Bengali has also « -i » < « -ē » of OIA. for the locative: this « -e > -i » later dropped off in MB. (see *supra*, p. 312).

Instances of the inflected locative from the Caryās: « cīē » in *the mind* (1); « divasāi » (2); « eku hiāhi » in *one heart* (2: printed text = « ekuḍi ahī », but « -ḍi ahī » must be for « hiāhi », as the commentary has « bṛdayē »); « ghaḍiē, bākalaī » (« bākalē »: Caryā 3: printed text = « bākalaa »); « gharē » (2, 11); « khanahī » (4: « kṣaṇē », or « kṣaṇam »); « mājhē » (5, 14, 18, 30); « hiāhi » (6); « niāḍi » (5), « ṇiāḍi » (7) = « nikaṭē »; « acārē, carāṇē » (11); « pahilē » (12: = *prathamē*); « māṅgē (= *mārgē*), kulē » (14); « caṇilē » on *having mounted* (5) « jīvantē, mailē; jāma-maraṇē » (22); « kauṭhē » (28); « sājhē » in *the evening* (33); « ālē » at *the beginning* (41: < āḍi ); etc., etc.

There is in Bengali from the earliest times an accusative or dative form in «-ē, -ē» : e.g., OB. «sahajē thira kari» *making the sahaja steady* (Caryā 2); «sahajē kahēi» *describes the sahaja* (Caryā 27); «bindhaha parama-nibāṇē» *pierce the supreme Nirvāṇa* (Caryā 28); «balada biāēla gaviā bājhē» *an ox made a barren cow to bear* (Caryā 33); «Bhādē bhaṇai, abhāgē lailā» *Says Bhāda, I have taken bad-luck* (Caryā 35); «sākhi kariba Jālandhari-pāē» *I shall make Jālandhari-pada my witness* (Caryā 36: see p. 121 *supra*); «sadguru-baanē dhara patavāla» *grasp the word of the good master as an oar* (Caryā 38); etc. MB. (ŚKK., p. 46), দেহ মোরে সরস বচনে «dēhā mōrē sārāsā bācānē» *give me a pleasant reply*; *ibid*, p. 100, কান্দিয়া জ্ঞানদ্বিবে কাশে। পাছে কাকাঞি মোকে না দিহে দোষে। «kāndiā jñānyibō Kāśē, pāchē Kāhāñi mōkē nā dihē dōṣē» *I shall cry and inform Kañšo, afterwards Kṛṣṇa will not (be able to) put blame on me*; (Kṛttivāsa, 'Uttara-kāṇḍa') মানুষ হঞা জিনিলে তুমি হেন রাবণে «mānuṣṣ hāñā jinilē tumi hēnā Rābāṇē» *being a man, you could defeat such (a foe as) Rāvaṇa*; (KKC.) শোব নাহি দেখা কেন কব অপমানে «dōṣā nāhi dēkhyā kēnā kārā āpāmānē» *why do you do me insult, seeing no fault?*; *ibid*, বোল উপচার দিয়া ছাগল মহিষে «ṣōlā upācārā diyā chāgālā-māhiṣē» *making the sixteen offerings (and sacrifices of) goats and buffaloes*; NB. অন্ধজনে দয়া কর «āndhā-jānē dāyā kārā» *have pity on a blind person*; etc., etc. We have also an «-ē» in instrumental forms with করে or করিয়া «kōrē, kārīyā», like হাতে করে «hātē kōrē» *with the hand* (never হাত করে «hātā kōrē»), ঝোড়ায় করে «jhōrāy kōrē (< jhōrā-ē)» *in a basket*, etc.

This «-ē, -ē» affix recalls the oblique (accusative, dative, instrumental and locative cases) in «-(a)hi, -(a)hī» which is found in Early Awadhī and W. Hindī: e.g., Awadhī (Tulasīdāsa), «taba Rāmahi bilōki Baidēhi» *then Vaidēhi, seeing Rāma*; «nṛpahi bacana priya, nahī priya prānā» *to the king his word is dear, not dear his life*; «nāi munihī siru, sahita samājā» *having bowed his head to the sage, together with his companions*; «aisē prabhuhī bilōkaū jāi» *I shall go and see such a lord*; «pūchata prabhuhī» *they are asking the lord*; etc.

W. Hindī ('Chatra-prakāśa,' ed., Nāgarī Pracārīṇī Sabhā, p. 88): «utari Narmadā dēsaḥī āyē» *crossing the Narmadā, they came to the country*; p. 91,



« jahā sēvakahī nidrā lāgai, sāhiba tahā saṅgahī jāgai » *where sleeps takes the servant, the Lord even there watches in his company*; etc. The affix is exceedingly common with the pronouns, in the form « -hi », and the present-day Western Hindi oblique « -ai, -ē » is derived from the earlier « -a-hi ». From their nature and employ, it would seem that we have in Bengali « -ē » and the Eastern and Western Hindi « -ahi, -ahī, -ai, -ē » a common inflected form. The use of it has now become comparatively rare in NB., but it was exceedingly common in MB. It is the case of the gradual restricted use in Bengali (as in other eastern dialects) of an oblique form as differentiated from the nominative. We find the same thing in Early Oriyā and in Early Maithilī: what may be called the « -ē » oblique is no longer in use now, but it figures in the older literature in these speeches: as e.g., in Oriyā, Jagannātha-dāsa's 'Dhruva-caritra': « munijki prāṇāmi kāhē mādhurā bācānē » *after saluting the sages says sweet words* (Contai edition: p. 17); « muhī jāī bāsibāku dhāili āucālē » *I went and caught the skirt to sit down* (ibid, p. 19); « Uttāmā putrē sāṅgē lēi » *having taken (his) son Uttama with him*, « Sunīti putrē kōlē dhāri » *S. having held her son in her lap* (p. 61); « sē kānyā Dhrubē dēlā bibhā » *gave that daughter to Dhruva in marriage* (p. 63); « Guhyākā-gaṇē dāyā bāhi, kāhānti Dhrubā-mukhā cāhi » *feeling pity for the Guhyakas, he says looking at D.'s face* (p. 69); « ēmāntē Kubērā-bācānē Dhrubā bicāri tōṣā-mānē » *in this way D., having pondered on K.'s words, glad of heart* (p. 73); etc.; in Maithilī: Vidyāpati (VSPd. edition): « Rāhu dūri basa, niyarō na āvathi, tai nahi karathi garāsē » *R. dwells afar, does not come near, that is why he does not gobble up* (p. 12); « kāmīni karaē sanānē » = « kāmīni karōti snānam » (p. 23); « āōra pēkhala... mōtima-hārē » *further I saw the chain of pearls* (p. 28); « lōbhē garāsali lājē » *desire ate up (destroyed) shame* (p. 38); « sunaha, sundari ! Bidyāpati-bacana-sārē » *hear, O fair one, the precious words of Vidyāpati* (p. 38); « lakhala lalita tasu gātē rē » *O, I saw his handsome body* (p. 39); « tējala guru-jana-lājē » *I have given up shame of superiors* (p. 43); etc.

This oblique « -ē » of Early Bengali and of other Magadhan dialects, < « -ai, -aī, -ahi, ahī », seems to be identical with the locative. The trans-

ference from the locative to the dative, accusative and instrumental sense is perfectly clear and intelligible. It has been suggested that this NIA. oblique, «-ahi, -ahī» is derived from the OIA. genitive «-sya» (Hoernle, *Gauḍian Grammar*, p. 210; Beames, II, p. 221; R. G. Bhāṇḍārkar, *Wilson Philological Lectures*, pp. 243-244); and again, that the instrumental plural of OIA., «-bhiḥ» > Late MIA. «-bhi» has been extended to the singular, and as «-hī, -hi» has become the oblique singular (cf. Baburam Saksena, 'Declension of the Noun in the Ramayan of Tulsidas,' *IAnt.*, 1923, Vol. LII, p. 74; cf. also L. P. Tessitori, 'Notes on the Grammar of Old Western Rājasthān,' § 59, *IAnt.*, 1914, p. 183; see *ante*, pp. 161-162). But the change of «-sya» to «-hi» presents a phonetic problem which is unexplained, considering that «-sya» remains as «-s-» in a number of forms, e.g. Hindi «kis, jis, tis=kasya, yasya, tasya», Bengali কিস- «kis-»=«kasya» (see *supra*, p. 549; Jules Bloch, 'Langue Marathe,' p. 182). The extension of an old plural to the singular, again, would be extremely curious, and certainly it is a very unsatisfactory explanation. The locative singular in «-a-hi, -a-hī» (< \*-dhi; \*-bhi, \*-bbhim; \*-smin) offers the most likely solution of this very characteristic case inflexion of NIA.

In the Bengali dative case forms «-(e)r-ē, -k-ē» we have the same locative affix «-ē», added to the post-positional affixes; and the locative «-t-ē» is case of double locative form (=post-positional locative affix «-ta» + «-ē»). So also the Oṛiyā «-ṭhā-r-ē», W. Hindi «-m-ē». (Cf. Grierson and Hoernle, *JRAS.*, 1903, p. 617).

500. There are cases of use of the simple base for the locative in OB. and in MB.: e.g., «sāsu gharē ghāli, kōncā tāla (=tāli)» *putting the breath inside the room, and the key in the lock* (Caryā 4); «bēḍhila hāka paḍaī cau-dīsa» *the surrounding tumult falls in the four quarters* (Caryā 6); «kulē kula» *from shore to shore* (Caryās 14, 15); ŚKK. গৌহারী করিবো রাজা কংসের দুয়ার «gōhārī karibō rājā kānsērā duārā» *a cry for justice shall I raise at the gate of king Kansa* (p. 328). This is mainly for purposes of rime, and does not indicate any real loss of the vowel, but cf. NB. দোর দোর ভিক্ষা দাও «dōrṣ dōrṣ bhikṣā māṅgā» *to beg from door to door* (see pp. 311-312).



There is no trace of the locative plural affix «-su, -ṣu» of OIA. in Bengali and its sister-speeches : it seems to have fallen into disuse from the Late MIA. stage. Śaurasēnī Ap. uses the instrumental plural «-ahī, -ēhī» for the locative plural : it may be that such was also the case in Māgadhi Ap. in which «-ahī, -ēhī» could easily become confused with the singular locative.

501. The above are the real inflexions of the Bengali declension. The other affixes were independent words compounded with the noun, and then inflected ; but in the genitive, there is in all likelihood an adjectival «-ka».

The locative «-ta» is found in OB. in numerous instances in the Caryās : e.g., «sāṅkama-ta» *on the bridge* (5) ; «māṅga-ta, bāṭa-ta» (8 : mārṅa-, vartman) ; «piṭa-ta» *on the vessel* (14) ; «gaṇa-ta» *in the sky*, «glva-ta» *on the neck* (28) ; «ṭāla-ta» ? *on high*, «hāḍī-ta = \*hāḍī-ta» *in the pot* (33). This «-ta» would seem to be the word «-antaḥ» *within* : it was compounded with the noun-base : «mā(ṅ)gata < \*magganta = mārṅa + antaḥ». The loss of the «-n-» here is unexpected for OB. The present participle in «-anta» still preserves the «-n-», and a post position like «antar-ē» *for*, is as yet not reduced to ত্তর «-tārē» (as in NB.) in the language of the Caryās. The fact of the word being agglutinated with the noun-base may have been responsible for its losing its individuality, and any intermediate stage with the nasalised vowel, like «\*mā(ṅ)ga-ṃ-āta, \*mā(ṅ)gāta» must be pre-Bengali. The «-ta» post-position characterises the Bengali-Assamese group only among Magadhan speeches. This post-position would nevertheless seem to have been a Magadhan (MIA.) inheritance in Bengali. At the present day, it occurs as «-tḥ» in Assamese and in dialectal Bengali (North, East, South-east). Standard Bengali employs «-tē» (which is a locative form «-ta + -ē», i.e., from «\*antahi = antaḥ + dhi»), and also «-ē-t-ē» (=locative in «-ahi» + «antaḥ» + «-ahi»). The word «antaḥ» for the locative is found in Marāṭhi as a recent NIA. formation (see Jules Bloch, 'Langue Marathe,' § 197). R. G. Bhāṇḍārkar's derivation of Bengali «-tē» from the MIA. «tahi» = locative of pronominal base «ta-» (Wilson Philological Lectures, p. 248), cannot be entertained, considering the existence of «-ta, -tḥ» side by side with «-t-ē».

The extension of « -tā, -t-ē » to the instrumental and nominative has been noted before. It has also been used with an ablative force from Early MB. times: *e.g.*, ŚKK., p. 264, মাতা বাপত বড় গুরুজন নাই « māhā-bāpātā bārā guru-jānā nāhi » *there are no greater respected ones than mother and father*; p. 308, আদাত আদিক তোর কে করিবে হিত « āmhātā ādhikā tōrā kē kārībē hitā » *who will do more good to you than I?*; p. 326, আদাতে চাহি বাণী « āmhātē cāhāsi bāṣī » *asked for the flute from me*; Kṛittivāsa, রাজাতে বিদায় মাঙ্গে « rājātē bidāyā māggē » *takes farewell from the king* (cf. R. S. Trivēḍi, ‘Śabda-kathā,’ pp. 102-104).

The Skt. word « madhya » was used as a post-position for the locative in the Apabhraṅśas of Northern India, in the *sic* form « \*maddha, \*madha, \*mādhā » > maha, māha ». This is the source of the NIA. locative post-fix « -mē, -mā, -mā », etc. Dialectal Bengali (Haijong) য়ি « -mi » is in all likelihood derived from this (LSI., V, I, pp. 214 ff.): *e.g.*, দেশমি « dēś-mi ». This post-fix is otherwise unknown to Bengali, and to Assamese and Oṛiyā as well.

#### GENITIVE.

502. The OIA. genitive affixes in the singular have not survived in Bengali, as in most other NIA. speeches. The solitary « -a-sya » of « -ā » nouns was carried down to Late MIA., as a generalised affix for all nouns, and even this fell into desuetude. This « -a-sya » became « -aśśa » in Māgadhī, as we can see from the evidence of the Brāhmī seals found in Magadha (see *supra*, p. 59, foot-note) and from the Prakrit grammarians. Side by side with « -aśśa », Prakrit literature registers a form « -āha » for this form of MIA.: and this « -āha » forms an unsolved problem. A change of « -aśśa » to « -āha » is difficult to explain: the change of « -śśā, -śś-, -ś-, -s- » to « -h- » in MIA. continues to be obscure (see *supra*, pp. 549, 550, 555). It seems « -āha » or some analogous form (-ahō?) is found as early as Second MIA. in Māgadhī, as in the dramas of Aśva-ghoṣa. (H. Lüders, ‘Bruchstücke Buddhistischer Dramen,’ pp. 34-36); and the fact remains that Māgadhī Pkt. has « -āha », Śaurasēnī Ap. has « -āha, -āhō, -āhō », beside « -assu, -asu »; and that Old Bengali shows



«-ā» (and in a few pronouns, «-āha, -ha») for the genitive (examples are given below). Can it be that the real development of Early MIA. «-assa, -āśsa» was a form «-ā, -ā» in Late MIA., through stages like «\*-asse, \*-āśse» > «\*-āse, \*-āśse, \*-āse, \*-āśse» > «\*-ās, -āś, \*-ās, \*-āś» > «-ā, \*-ā», and then the locative affix «-ha < -dha» (as in Skt. «i-ha» = MIA. «i-dha», cf. Avestan «iḍa», etc.) extended to the genitive sense, or an emphatic particle «-ha, -hō < -hu = khu, khalu», was added to it? The transcription in Greek letters of MIA. Brāhmī and Kharoṣṭhī legends in the coins of the Indo-Scythian prince Nahapāna of Malwa of the 1st cen. A. C., so far as it can be restored, would seem to suggest that the pronunciation «\*-as» was current at the time, in Western India at least: the transcription seems to have been

PANNIO KAHAPATAK NAHAPANAK

=ranniō (raññō) Ksaharatas (Ksaharātassa) Nahapanas (Nahapānassa) (E. J. Rapson, 'Catalogue of the Coins of the Andhra Dynasty in the British Museum,' London, 1908, p. cxii), where it would seem as if «-āse» or «-āśe», or «-ās, -āś» was heard.

Be it as it may, in OB. we find «-ā, -āha» as the genitive affix—«-āha» being found with pronouns: thus, «hariṇā hariṇira nīlaa ṇa jāṇī» *the abode of the Stag and of the Doe is not known*, «Bhusuku bhaṇai, mūdhā hihi na paīsaī» *B. says, it does not enter into the heart of a fool* (Caryā 6); «jā ēthu jāma-maraṇē bisagkā» = «yasya atra janma-maraṇē viśagkā» (Caryā 22); «jabē muṣā-ēra cā(ra) tutaī» = «yadā \*mūṣakasya-kāryaḥ cāraḥ trutyati» (21); «jāb-ēra bāna-cihna-rūva na jāṇī» = «\*yasya-kāryakaṁ varṇa-cihna-rūpaṁ na jñāyatē» (29). In MB. the oblique form of the pronouns has «-āha» side by side with «-ā»: e.g., তাহ, তাহা, তা *tāha, tāh-ā, tā-» = «tasya»*. The «-āha, -ā» is thus preserved in the pronoun in Late MB. and in NB., but in the noun it is entirely lost from after the OB. period, except in the verbal noun in «-ibā»—e.g., genitive দিবার, করিবার, বাইবার «dibā-rā, kārībā-rā, jāībā-rā», dative দিবারে, করবারে, বাবারে «dibā-kē, kārībā-kē, jāībā-kē».

503. From the Transitional MIA. Period we find the use of a number of words, either along with the genitive pleonastically, or compounded with the base to indicate the genitive idea. We have «-santa(+ -ka)» (present participle of «√as» *to be*) meaning 'belonging to,' in the Nasik inscriptions of the 1st-2nd century A.C., *e.g.*, «amha-sa(n)taka, pitu-sa(n)taka» *our, of the father* (Senart, 'Nasik Cave Inscriptions,' Ep. Ind., VIII, pp. 73, 78); and the other words which came in during the Second MIA. Period are «kṛta > kada, kaa; kārya > kajja, \*kāira > kēra, kēla; kāra; kara; kṛtya > kicca; \*dita (= Skt. datta) > dida, dia; karṇa > kaṇṇa», etc. These words have become transformed into the genitive and other affixes of NIA. (see pp. 163, 164 *supra*). MIA. literature, however, does not notice all of them, but only a few, although certainly they all occurred in the spoken dialects in different parts of the country. The most popular post-positional or compounded word of genitival import occurring in MIA. literature is «kēra- (kēla-)», which is found all over Northern India in later times. The source of this word is «kārya», and it cannot be «kṛta» (which would give «kaṭa, kaḍa», or «kada, kaa, kida, kia» in MIA.); «kārya» came to be used (apparently as a *semi-tatsama* form with epenthesis) in Transitional or Second MIA., as «\*kāira», before it became «kēra», in Māgadhī «kēla» (cf. Pischel, 'Grammatik der Prakrit-sprachen,' §176). This «kēra-» is found East in Bengal, and West in Rajputana; «kēra-» also occurs in the speech of the European Gipsies who went with their language from North-Western India during the Second MIA. period. A vernacular or *tōk.* form would be «kayya» or «kajja», and the Sindhī affix of the genitive, «-jō, -jī», is certainly from this «kajja». (Grierson: cf. A. F. R. Hoernle, JRAS., 1903, p. 616). Māgadhī Prakrit, like the Prakrits of other parts, took up «kēra (kēla)», side by side with some of the other words. As in other dialects, the form was either used after the genitive, as an adjective qualifying the noun governed, or it was compounded with the noun-base into an adjective; but in either case, the whole sooner or later came to be regarded as one word, which brought about the voicing and dropping of the «-k-» in Eastern Magadhan quite early.



In Bengali forms like মনুষ্যের *mānuṣēṛ*, ঘোড়ার *ghōṛār*, making up with the inflexion a single word, as opposed to the Hindi *mānus-kā, ghōṛā-kā* forming a group apparently of an oblique base and a separable post-position, Grierson sees an inherent tendency in Bengali, as an 'Outer' language, towards a synthetic declension, which presents a contrast to Western Hindi as the 'Midland' speech favouring a separate post-position (see *supra*, pp. 161-164; LSI, IX, II, p. 328). But there is nothing in the Prakrit of the dramas, using *kēra(ka), kēla(ka)*, to suggest that a particular dialect, Māgadhi, or Śaurasēni, specially preferred compounding or mere juxta-posing after the inflected genitive. The pronouns, however, generally seem to retain the old inflected genitive which was strengthened by *-kēra (-kēla)*, and nouns could have mere compounding. Thus we have, *e.g.*, in the 'Mṛcchakaṭṭhika,' Śaurasēni *ajjassa kēraō* beside *vessā-jāṇa-kērakō* and *paḍivēsi-gahavaī-dāraa-kēriāē*, and Māgadhi *ajja-Cāladattāla kēlakē* beside *vappa-kēlakē*: but always *mama, tava, tassa (taśśa), kassa (kaśśa), attañō + kera(ka), kēla(ka)*. The pronominal forms in NIA, like Bengali তার, তারি *tār, tāri* *tā-rā, tāhā-rā* (= *tāya + kara*), মের *mōi* (= *mama + kara*), and Hindi *tis-kā* and *mēraṇ, mēā*, etc. show that the old usage for pronouns still continues. Besides, 'Outer' speeches do not always show a synthesis: *e.g.*, Oriyā *jānāṇ-kā(rā)* (= *jānāṇām kara-*), which is as much post-positional as W. Hindi *ghōṛā-kā*; and European Gipsy, which is based on an 'Outer' speech allied to Western Panjabi, possesses forms like *cōres-kērō, -kēri* and *cōreṇ-(y)ērō, -ēri* (= *cāurasya, cāurāṇām + kēra-*). The preservation of the *-k-* in W. Hindi is no isolated thing: we have *-kar, -karā* (rather than *-rā* as in Bengali) in the Bihārī dialects. The W. Hindi *-kaṇ, -kā* seems to have retained the *-k-* chiefly through two reasons: firstly, it formed the only consonant in the post-position, and as such intelligibility demanded its retention; and secondly, there was in all likelihood the influence of the adjectival *-kka* affix, which also had a genitival force. The loss of *-k-* in the agentive affix *-nē* of W. Hindi (= MIA. *\*kaṇṇahi*, OIA. *\*karṇa-smin*:

cf. L. P. Tessitori, ‘Grammar of Old Western Rājasthāni,’ Ind. Ant. 1915, §§ 70, 71) is to be recalled.

Side by side with ‘kārya > kēra, kēla’, the words ‘kara, kāra’ and ‘kṛta > kaa’ were used in Māgadhi Prakrit and Apabhraṃśa to indicate the genitive. It would seem that in Māgadhi Ap. ‘kara’ was used with the pronoun originally, and then was extended to the noun. Reduced to ‘-ara > -rā, -rā’, it occurs as the genitive affix in Assamese-Bengali and Oriyā, and also in Maithili and other Bihāri speeches in the genitive of the first and second personal pronouns. The unreduced form ‘-kara’ is here and there found as a survival in MB., possibly through Maithili influence; it is met with in Oriyā in the plural, where the ‘-k-’ is preserved by the ‘-n-’ of the genitive plural affix (see *supra*, pp. 137, 124); and it occurs in the forms ‘-kar, -karā, -kārā’ in the genitive and dative of the pronouns other than those of the first and second persons in Maithili, Magahi and Bhōjpurīyā. ‘kēra, kāra’ have become practically doublets of an identical genitive affix. They figure also in Eastern Hindi side by side. ‘kara’ is still found in its unchanged form in Marāṭhi surnames like ‘Hōl-kar, Bījāpur-kar, Ciplaṇ-kar, Tāṭāw-kar’ etc., meaning ‘belonging to, dwelling in’: compare the use of the genitive ‘-kā’ in Mārwarī family names like ‘Khēm-kā, Gōṇ-kā, Himmatśinh kā’, etc.

The affix ‘kāra’ seems to have been rather rarely used in Māgadhi Apabhraṃśa. It is now found in its unreduced form in a few nouns and pronouns in Bengali: e.g., সাকাল্য কাল্য *śākālyā kālyā* ‘of the morning’, হেথাকাল্য *hēthā-kālyā*, এখানকাল্য *ēkhān-kālyā* ‘of here’, বছরকাল্য *bāchār-kālyā* ‘of the year’, সকাল্য *śākālyā-kālyā* and সবাকাল্য, সবাইকাল্য, সবাইকাল্য *sābā-kālyā, sā(b)āi-kālyā* ‘of all’, আপনাকাল্য *āpān-kālyā* ‘of self’. It does not occur in the other Magadhan speeches: and it may well be a modification of ‘kālyā’ itself.<sup>1</sup> The affix ‘kālyā’ is used in NB. with nouns indicating

<sup>1</sup> Hoernle (Gandhian Grammar, p. 236, foot-note) regards this ‘kāra’ as being a double genitive, ‘kā + -ra.’ This explanation cannot be objected to considering that we have ‘-ka’ as a genitive affix in Middle Bengali. But we do not have ‘-kā’ (with the long ‘ā’) with nouns in Bengali: and although in Early Bengali we sometimes find ‘-ka,’ the words which form the genitive with ‘-kāra,’ as above, never employ the ‘-ka’ form.



time and direction, and besides it has a definitive force (cf. Rabindranāth Tagore, 'Sambandhē < kārṣ >' in 'Śabda-tattva').

The form < kṛta > MIA. kaa > is more important. As a word strengthening the genitive as well as the dative relation it seems to have come up in the Transitional MIA. Period, and probably even earlier. We have quite early < tasya kṛtē dattam = tasmāi dattam > in Sanskrit, an idiom apparently borrowed from a Prakrit or vernacular one; and a Buddhist Skt. form like < udyāna-kṛtam āsanam > shows the early establishment of < kṛta > kaa > as a genitive-indicating word. But it is a question whether the < -k- > genitive of the Magadhan languages (Early Bengali < -kā >; New Bengali dialectal < -kā, -gā, -gū >, Oriyā < -kā >, in the plural; Maithili < -k >, Magahi < -k, -kē >, and Bhōjpuriyā < -k, kē, -kāl >) is based on the < kṛta > form. < kaa, kṛta > kaa >, compounded with the preceding noun-base, could be expected to drop the < -k- >, and to be changed to < -aa > as in the case of < -kēra, -kara > -ēra, -ara >. It seems that the basis of the New Magadhan < -k- > of the genitive is the MIA. pleonastic < -kka >, rather than < kaa < kṛta > (see *supra*, p. 688). The < -kṣ > of the Bihārī dialects would derive better from a monosyllabic < -kka > rather than from the disyllabic < -kaa >. The 'Prākṛta-Pāṅgala' (14th century) has some instances of the < -ka > genitive which would seem to be an Eastern form derived from < -kka >: *e.g.*, (in the 'Bibliotheca Indica' edition, ASB.), p. 249, < Khurasāṇa-ka Ollā >; p. 403, < gāi-ka ghittā >; p. 412, < dēva-ka likkhia kēṇa mēṭāvā >; p. 470, < tā-ka jaṇaṇi ki ṇa thakkaū baṇjhaū >, etc. But the presence of a < kaa < kṛta > is not absolutely precluded from consideration; and this < kaa > can of course easily give the Western Hindī < kaū, kō, kā >, and also Eastern Hindī and Bihārī < -kē, -kāl >. The < -kā > in an Oriyā form like < puruṣāṇ-kā > may be either the < -kka > generalised as an affix or help-word and employed by extension with the original genitive plural, or it may equally be the word < kaa > used post-positionally (= puruṣāṇām kṛta-).

About the use of the < -ka > (< -kka, -kaa), there is an agreement between Modern Bengali and Oriyā: it is confined only to the plural (or plural > honorific singular) in Oriyā, and in Bengali now it is found,

although dialectally only, in the plural genitive of the pronouns only. Why this form should be chosen for the plural is not clear: possibly «-ra» and «-ka» (Oṛiyā «-ṇ-ka», Bengali «-kā, -gā, -gā = -gō») were gradually adopted for the singular and the plural respectively in the absence or disuse of an affix distinguishing the two numbers.

Examples of «kēra > -ēra, -kara > -ara, -kka (-kaa) > -ka» for the genitive, from OB. and MB.:

«chānda-ka bāndha» *the bonds of (=from) pleasure* (1); «rukhēra tentali kumbhīrē khāi» *the crocodile eats the tamarind of (=from) the tree* (2); «hariṇā hariṇira nilaa ṇa jāṇi» *the abode of the Stag and of the Doe is not known*, «hariṇāra khura na dīsaī» *the Stag's hoofs are not seen* (6); «tōhōri kuḍiā» *thy hut*, «kāhari nāvē» *in whose boat?* (tava + ha, kasya, + kara-), «tōhōra antarē» *for thy sake*, «hūḍēri māli» *chaplet of bones* (haḍḍa + kēra + -ikā) (10); «tōhōri bhābhariāli» *thy coquetry* (18); «ḍombi-ēra saṅgē» *in the company of the Ḍōm woman* (19); «mōhōra» *my* (20); «muṣā-ēra» *of the mouse* (21); «sō karaū rasa-rasānēri kaṅkhā (text = rasānērē kakhā)» *let him entertain the desire for pleasure and for elixirs* (22); «tōhauri» *thy* (28); «jāhēra» *of which*, «tāhēra» *of that* (29: yasya, tasya + kēra-); «cāndari cānda-kānti (reading of the commentary)» *moon-light of the moon* (31); «bāthēra kāṅkāṇa» *the bracelet of (=on) the arm* (32); «Dhēṇḍhaṇa-pāēra gita» *D.'s song* (33); «mōhērā bādhā» *bound up of (=by, with) ignorance* (34); «pākhi na cabaī mōri pāṇḍiācāē» (see *supra*, p. 121); «kābēri śaṅkā» *whose fear?*, «mahāmudēri kaṅkhā» *desire of the mahāmudrā* (37); «tōhōrē dōsē» *through your fault*, «tōhāra biṇāṅā» *your science* (39); «bāṣaṇā tōrā» *thy desire* (41); «mōra» *my* (49); «tailā bāḍira pāsēra jonhā-bāḍi tālā (=uēlā? bhāēlā?)» *the mansion of moon-light by the side of the third mansion became clear* (50).

It is seen that «-ēra, -ara» like their source-forms in MIA. are adjectives referring to the nouns they qualify, and take the feminine affix «-i = -ī» (see *supra*, pp. 720-721), and also the case-terminations (e.g., «tōhōrē dōsē» in Caryā 39: = \*tava-kērakēṇa dōṣēṇa» in MIA.)

«kēra, kara» occur in a few instances as cases of stereotyped survival in MB.: e.g., ŚKK. নদীকৈর «nādi-kērā»; লাক্ষকৈর «lākṣhē-kērā» *of one*



*lakh*; 'Śrī-Kṛṣṇa-vijaya,' বৎসকের « bātsā-kērā » (R. S. Trivedī, 'Śabda-kathā,' p. 103); 'Mānik Candra Rājār Gaṇ,' কোড়াকর « kōṛā-kārā » of a cowrie, ঘড়কর « ghāṛi-kārā » of an hour (VSP., pp. 63, 65); 'Śūnya Purāṇa,' রূপাকর « rūpā-kārā » of silver (p. 38), তামাকর « tāma-kārā » of copper (p. 39), হীরাকর « hīrā-kārā » of diamond (p. 40), etc. In some of the above instances, e.g., « lākhēkērā, kōṛākārā, ghāṛikārā », the base may be in « -kā »: « lākhēkā » one lakh, « kōṛākā » one cowrie, « ghāṛikā » one hour, so that the inflexion would be « -rā, -ērā » and not the old « kara, kēra ».

The « -ka » affix for the genitive is rather uncommon in Bengali from the oldest times: it has disappeared from Modern Bengali in the singular, but is found in dialectal forms in the plural only. Examples: OB. « chānda-ka bāndha » the bondage of pleasure (Caryā 1), « samādhika pāṭa » the process of samādhī (comm. to Caryā 21); in the ŚKK., জরমক তরে কুলে বন্ধ থইবে « jāramā-kā tārē kulē kālāṅkā thuibē » will put a stain on the family for all life (p. 121); আপন কাজ লাগি সবই বিকলী « āpanā kājā-kā lāgi sabbāi bikālī » every body is anxious for the sake of her own work (p. 253); পরাক লাগিয়া সে হারাইবে নাক কানে « pāṛā-kā lāgiā sē hārāiḥē nākā kānē » he will lose both his nose and his ears for the sake of another (p. 307); নিত্যানন্দ রাম বন্দে রাহীক স্তুত « Nityānanda-rāmā bāndō Rōhiṇī-kā sūtā » I praise N., the son of R. (Lōcana-dāsa's 'Caitanya-mangala'), বিহারক রাজপুরী নামে অমরাবতী « Bihārā-kā rājā purī, nāmē Amrābātī » the capital of Bihār, Amarāvatī by name (Vīra-nārāyaṇa's 'Kirāta-parvan'); গৃহস্থক স্বর্গ এহি পুরাণ কহিছে « gṛhasthā-kā dhārmā ēhi purāṇā kāhichē » this is the duty of the house-holder, so declares the Purāṇa (Śaṅkya's 'Mahābhārata': the last three examples given in R. S. Trivedī's 'Śabda-kathā,' p. 104); etc. NB.: মোর, আমার « mōiḥ, āmāiḥ » my, plural ‡ মো(রা)গো, আমা(র)গো « mō(iḥ)-gō, āmā(iḥ)-gō », আমার, আমগা « āmā-kā, -gā » our; তার « tāiḥ » honorific তাঁর « tāiḥ », his, plural ‡ তাগো, তাঁগো « tā-gō, tāi-gō »; মানুষের « mānuṣēḥ » of man, plural ‡ মানুষগে, -গ, এর-গো « mānuṣḥ-gō, -gō, -ērḥ-gō » of men. The « -gō, -gō » affix for the plural is present in some form or other in the vulgar dialects practically all over Bengal.

504. An affix « -sat-ka », loosely compounded with a noun, with its base (for the singular) or with the genitive (for the plural), is largely found

in inscriptional Sanskrit all over Northern India from the Second MIA. period : e.g., Inscription of Jayanāga of Karṇa-suvārṇa (p. 180, *supra*), « brāhmaṇānām-satka-grāma-sīmā »; Siyadoni Inscription (c. 11th cen. A. C., Lalitpur District, U. P., Ep. Ind., I, pp. 162 ff.) : « samasta-kall-pālā-nām-satka-haṭṭānām-upari (= Hindi « kalwārō-kē hāṭṭ-par), Vigraha-pāla-satka-dramma, bāmana-satka-vithi, caṇḍāla-satkāvā-ānikā », etc., etc. This affix « -sat-ka » is difficult to explain : apparently it is the present participle of « √as »—« santa- + -ka » (pleonastic), such as we find in the Transitional MIA. (see *ante*, p. 753). It is not unlikely that a vernacular from « santa-ka » became « \*santā-ka, \*sant-ka, \*sakka » which was Sanskritised into « sat-ka » in medieval Sanskrit as in the inscriptions. In Early Assamese we have the affix সাক « -sākā », as in the forms আমসাক, তোমসাক « āmā-sākā, tōmā-sākā » *our, your, us, you*, which are obsolete in Modern Assamese. (Dēvānanda Bharālī, ‘Asamiyā-bhāṣār Maulik Bicār,’ p. 32). These would affiliate themselves to a MIA. « \*amha sakka, \*tumha-sakka », Sanskritised into « \*asma-satka, \*yuṣma-satka ». This form সাক « sākā » has not been found in Bengali.

The plural of the genitive has been discussed under ‘Number’ above (p. 725 ff.)

#### DATIVE

505. The « -ka » genitive of Bengali is used for the dative in OB. : e.g., Caryā 4 « mantiē<sup>1</sup> ihākura-ka parinibittā » *the minister (= queen, in chess) has checked the king*; Caryā 21, « nūsa-ka » *for destruction*. This genitive-dative in « -ka » is exceedingly common in MB., as in the ŚKK. and other works : e.g., ŚKK. p. 3, মাহম্ম নিয়োজিল মারিবাক তাএ « mānuṣā niyōjilā mārībā kā tāē » *appointed men for killing him*; সেই উপদেশ দিব তোমহা কা তাকহাণে « sei upādēśa dibā tōmhā kā tākhāṇē » *he will give you advice at that time*; p. 108, বরক মন না জাএ « ghārā-kā mānā nā jāē » *the mind does not turn to home*; etc., etc. This « -ka » occurs as « -kā » now, but it is confined

<sup>1</sup> The printed text reads মতিএ : I accept the emendation proposed by Muḥammad Shāhidullāh in the VSPdP., 1327, p. 151.



to North Bengal and Assam only, and members of the Bengali-Assamese group of dialects in other parts now employ «-k-ē, -r-ē».

«-k-ē» is an inflected form, the final «-ē» being really the locative affix, as has been noted before (p. 749). It can be the locative of the adjective-genitive with pleonastic «-ka» (*supra*, p. 756); it can be equally the locative of the form «kaa < kṛta »: *e.g.*, তাকে দিল «tākē dilā» = Skt. «tasya kṛtē dattam» for «tasmāi dattam» (cf. Grierson in the 'Zeitschrift für vergleichende Sprachforschung,' quoted by Hoernle in the JRAS. for 1903, p. 615). There is a third likely source of «-k-ē»—the OJA. «kakṣa» (see *supra*, pp. 164, 553) which has been suggested by Beames ('Comparative Grammar,' II, pp. 252-259) and Hoernle (Gaudian Grammar, § 375, p. 224), and accepted by Kellogg (Hindi Grammar<sup>2</sup>, p. 130). Hoernle later admitted the «kṛta» derivation (JRAS., 1903, p. 615). R. G. Bhāṇḍārkar would trace the dative «-k-ē» of Bengali and «-kō» of W. Hindi to a MIA. locative «kēhī, kahī» *where, somewhere*, from the interrogative pronoun base «ka» (Wilson Philological Lectures, pp. 246-248).

The last derivation does not at all seem convincing. Against it, and in favour of a derivation from «kakṣa», are the forms «kakhu» in OB. (see below), «kāhū, kāhu» with «-ā-» in Eastern Hindi, and «kahū» as in Western Hindi. (See also the remark in connexion with the derivation of the locative «-t-ē» at p. 750.) The forms «-kū, kahū» etc., as in Western Hindi, «ku» as in Oṛiyā, and «-ka» as in Early and dialectal Bengali, will also go against it: for all these forms accord but ill with «kahī, kaī» the locative of «kaa, kṛta». There cannot of course be any objection to the derivation of «kē» from «kṛta», but the difficulty remains with regard to «kō, kū, ku» and the «-hu» forms. The forms «ku, kū» is not found in NB., but it occurred in OB., and it is now the characteristic dative affix of Oṛiyā only among Magadhan speeches. In Caryā 35, we have «ēbē cia-rāa ma-kū (= mō-kū) ṇaṭhā» = «idānīm cittarājāḥ mama vinaṣṭa(h)», as the commentary explains; and also «Bājulē dila mōha-kakhu (bhaṇiā)» = «Vajrakulēna...mahyam pradattam», also according to the explanation of the commentary.

We have apparently «kakhu» side by side with «kū» here. The Skt. «kakṣa» seems to have been adopted in Late MIA. as a post-positional, and from «kakkha» a weak form «\*kakha» can very well be assumed. This in the transitional stage between Late MIA. and NIA. seems to have become «kaha, kāha». The proper NIA. *tōhs.* «kākha, kākha, kācha» seem to have influenced the lengthening of the «kāha». The change of «-kṣ- < -kkh-» to «-h-» is not isolated: Beames gives «pāhū, pahū» *beside, to*, from Hindi, which he derives from «pakṣa» ('Comparative Grammar,' II, p. 258); Old Western Rājasthānī also has the same word as «pāhī, pāhi» (Tessitori, §72[8]); and Oṛiyā as «pāi, pā» as in «ki-pāi, ki-pā» *why? wherefore?* Pischel also cites a number of instances of change of «-kṣ- > -kkh-» to «-h-» from Prakrit ('Grammatik der Prakrit-sprachen,' § 323). We can also compare the origin of «maha, māhi, mē», NIA. post-position of the locative, from Sanskrit «madhya» introduced in MIA. as a *sto.* «maddha, madha» beside the *tōh.* «majjha > NIA. mājha». The normal NIA. form of «kakṣa», with «-kh-», is certainly preserved in the Sindhi «khē» for the dative, and «khā, khō, khū» for the ablative (although Trumpp derived these from «kabhā < \*katham < kṛtam, kṛtē»: Sindhi Grammar, London, 1872, pp. 115-116): here the initial «-k-» of «kakkha» has been elided, like the «-k-» in «kajja- < kārya» giving «-jō, -jī» for the genitive. The Sindhi «khē, khā, khō, khū», inflected forms of a post-fixed «(ka)kkha», the Old Bengali «kakhu», and the Early Eastern Hindi «kāhū» would all support the assumption that «kakṣa» is the source of Western Hindi «kahu, kau, kō, kū» and Oṛiyā «ku». These are all to be connected with an Apabhraṇśa (Māgadhi as well as Ardha-māgadhi and Śaurasēnī) form for the *ablative*, «\*kakkhabu, \*kakkhabū», or probably «\*kakkhāu, \*kakkhau». (Cf. Māgadhi and Śaurasēnī ablative affix «-ādō», which we would expect to give «-āu, -au» in Apabhraṇśa). Unlike «kē», the present day «kō, kū, ku» is thus not of locative origin.

«-kē» of Bengali can thus be either «kṛta», or «kakṣa», in the locative. It is not unlikely that the two post-positional words have converged into this one form. In the plural of the dative as in তাদেরকে «tādērkē-



-kē > *to them*, we can see that an analysis into \*tasya + ādi-kēra + kakṣē > or into < + kṛtē >, is equally possible. The *tbbh.* form कृते > kṛtē > is still in use in Bengali as a post-position meaning *near, by, with*. The earlier forms of < -kē >, namely < \*-kai, \*-kahi >, are not found in Old Bengali. The Caryās, in addition to < -ka > and < -ku >, give instances of < -kē >: < rūpā thōi mahi-kē ṭhāvi > *putting away the silver, it was placed on the ground*, and < kēḍuāla nāhi kē ki bāhaba-kē pārai (text = pāraa) > *there being no oar, what can one do in the matter of rowing?* (Caryā 18: the text in the second instance is corrupt). < -kē > occurs regularly in MB., NB.; and < kē >, with nasalisation, is rather rare in MB.

Maithilī has < kē >, Magahi < kē >, and Bhōjpuriyā < kē >: all these are identical with the Bengali post-position. Of the E. Hindi dialects, Awadhī has < kā, kā, ka >, Baghelī < kā, kahā >, and Chattisgarhī < kā >. The Baghelī < kahā > is a relic of the older forms < kahū, kabā > etc. of Early Eastern Hindi as in Tulasī-dāsa, and < kā, kā > apparently also are from < kāhū > \*kāhā >. The < kakṣa > derivative is thus found to occur in Bengali, Oṛiyā, E. Hindi and W. Hindi, and Sindhi.

506. The dative < -r-ē, -ē-rē >: it is found from OB. times, e.g., < kariṭā kariṇi-rē risaa (= risai) > *the male elephant is impassioned (?) with regard to the female elephant* (Caryā 9); < kēhō kēhō tōhō-rē biruṇ bōlai, bidu-jana-lōa tō-rē kaiṭha na mēlai > *some call thee (as being) of ugly form, (but) the learned never free thee from embrace* (Caryā 18). It is the locative in < -bi, -hi > of the genitive in < -ra, -ēra >. At the present day, the < -r- > dative is found in East Bengal (W. Vanga specially), and the < -k- > dative is spread from Rāḍha through Varēndra to North Bengal and Assam, and seems to occur also in East Vanga, as in the Haijong Dialect of Maimansing, and in the Chakma of Chittagong.

#### ABLATIVE.

507. Bengali-Assamese does not now possess an organic affix for the ablative, unlike Oṛiyā. In Caryā 4, however, there seems to occur a solitary instance of an ablative form in OB.: < khēpahu (= khēpahū` jōini lēpana jāya > = < kṣēpāt sva-sthāna-yōgāt sū bōdhicitta-rūpā nāirātma-yōgini, mōha-

malāvaliptā bhavati », as the commentary explains. In Oṛiyā the ablative affix is also « hū », as in Early Oṛiyā, e.g., 'Kaṇsa-jaṇma' in Jagannātha-dāsa's 'Bhāgavata': « Ugrasēna-hū nōbē āna » *he is not different from U.* (p. 4, Contai edition), « kāhū utpatti hōilā » *from whom was the origin?* (p. 8, *ibid*). In Modern Oṛiyā it occurs as « -u »: « ghārā » *house*, ablative « ghār-u »; and it figures also in 'S.-W. Bengali.' The genitive form is also put in the ablative: « ghārā-rā, ghārā-r-u ». With proper names, and as an honorific, the post-positional form « ṭhā-r-u » from « ṭhā » *place* is used (cf. « ṭhā-r-ē » for the locative), and « ṭhāu, ṭhu » also are found as ablative post-positions with pronominal adverbs of place. The « -hū, -u », doubtless a Māgadhi form, is apparently the same as that we find in Śaurasēnī Ap., viz « -hu » in the singular and « -hū » in the plural (puttahu, puttahū). The origin of this « -hu, -hū » in Ap. is obscure, but it seems that it was due to the fusing of several case-terminations—« -a-taḥ » > -adō > \*-au » of the ablative, plus « -h-, - » of the locative, for instance. The form « -a-hu, -a-hū » occurs in Sindhī, Panjābī and Western Hindī as « -ō, -ō » (e.g., Hindī « hāthō-hāth » *from hand to hand* < « \*hatthahu hatthi »), and in Marwārī as « -ā » (cf. Tessitori, Grammar of OWR., §61).

The use of the locative form in « -ta, -tē » for the ablative has been noted above (p. 751). In the MIA. and NIA. confusion or interchangeability of the three cases, instrumental ablative and locative, there is probably the influence of Dravidian. (Cf. K. V. Subbaiya, IAnt., 1910, pp. 145ff.)

508. The development of the OIA. noun declension, through the Late MIA. (Apabhraṇśa Māgadhi) into Bengali, as described above, is set forth below, in the declension of the OIA. word « putra » = MIA. « putta »:

Māgadhi Apabhraṇśa	Bengali
Nominative: singular—	Nominative: singular—
(i) *putti, *putta (< Māgadhi Prakrit puttē < putrah).	(i) *pūti, *pūta < পুতি, পুতি puti, putā.
(ii) *puttaī (< puttaē < puttagē, puttakē < putrakah).	(ii) পুত পুতē.



Nominative : plural—

- (i) \*puttā (< puttā < putrāḥ).  
 (ii) \*puttahi (< puttēhi < \*putrēbhiḥ = instrumental).

Accusative : singular—

\*puttā, \*puttarū (< puttaṁ < putram).

Accusative : plural—

\*putta, \*puttāi (< \*puttāṇi, \*puttāni < putrāṇ).

Instrumental : singular—

\*puttē, \*puttēm (< puttē-ṇa[m] putrēṇa)

Instrumental : plural—

\*puttahi, \*puttahi (< puttēhi, puttēhim < \*putrēbhiḥ).

Dative : singular—

- (i) \*puttā (< puttā < putrāya).  
 (ii) \*puttā/ā(ha) (genitive) + kai; + ka(k)khi, ka(k)khī, kahi, kahī; putta-kkaī, -kkaī.  
 (iii) \*puttāha-(k)arahi, -(k)alahi; \*puttāha-(k)ērāhi, (k)ēlahi.

Dative : plural—

\*puttahi, \*puttēhi (< puttēhi [as in Aśōkan inser.] < \*putrēbhiḥ = putrēbhyah) (also Genitive Forms).

Ablative : singular—

\*puttāu, \*puttāu, \*puttahu, \*puttahū.

Nominative : plural—

- (i) পুত puttā.  
 (ii) ? পুত puttē.

Accusative : singular and plural—

Lost.

Instrumental : singular—

OB. \*pūtē, \*pūtē > পুতē puttē, পুত puttē.

Instrumental : plural—

? পুত puttē.

Dative : singular—

- (i) Lost.  
 (ii) পুতকē puttākē, পুতকē « puttākē », পুতক puttākē.

- (iii) পুতরē, পুতরē puttārē, -ērē, পুতরē, পুতরē puttārē, puttārē.

Dative : plural—

Lost.

Ablative : singular—

OB. \*pūtu, \*pūtahu, \*pūtahū; Oriyā putahū, putu.

Ablative: plural—

- (i) \*puttabī, \*puttēhī (< \*putrē-  
bhiḥ = instrumental).

Genitive: singular—

- (i) \*puttā, \*puttā, \*puttaha,  
\*puttāha (= puttaśśa <  
putrasya).  
(ii) \*puttā/ā(ha)-(k)ēra -([k]ēla);  
\*puttā/ā(ha)-(k)ara, -([k]ala);  
\*putta(k)ēra- (-[k]ēla);  
\*putta-(k)ara- (-[k]ala).  
(iii) \*putta-kka- (= putra-ka-).

Genitive: plural—

- \*puttāṇa, \*puttāṇa m,  
\*puttāṇ-i- (< putrāṇām).

Locative: singular—

- (i) \*putti (< puttē < putrē).  
(ii) \*puttabi, \*puttahī.  
(iii) \*putta-anta; \*putta-antahi,  
-antahi; \*puttabi antahi  
(\*puttabī antahī).  
(iv) \*putta-ma(d)dhi, -ma(d)dhami,  
-ma(d)dhami; -mahī, -mahahi,  
-mahahī (< madhya).

Locative: plural—

- (i) \*puttāsu, \*puttēsu.  
(ii) \*puttabi, \*puttēhī (< \*putrē-  
bhiḥ = instrumental)

Ablative: plural—

Lost.

Genitive: singular—

- (i) OB. \*pūtā, \*pūtāha.  
(ii) পুতর, পুতের putārā, putēra.  
(iii) OB., MB. পুতক putā-kā.

Genitive: plural—

- OB. \*pūtāṇa, \*pūtāṇa, \*pūtāni;  
NB. †পুতাইন putāin.

Locative: singular—

- (i) OB. \*pūti (cf. NB. ঘর gharā  
< ghar-i).  
(ii) OB. \*pūtahi, \*pūtahī, \*pūtāi,  
\*pūtē > MB., NB. পুতে putē;  
(iii) †পুত পুতā, পুতে putē,  
পুতেতে putē-tē.  
(iv) †পুতরি putā-mī (cf. Bihārī  
\* pūt-mī, -maī).

Locative: plural—

Lost.



## POST-POSITIONAL WORDS.

509. Use of post-positions to denote case relations is found in IA., Kōl and Dravidian. In OIA., indeclinables like • ā, adhi, anu, pari, pra • etc. are found both as prepositions and as post-positions ; so in Old Greek. In IE., these so-called prepositions were properly adverbs referring to the act, but in all IE. languages, including IA., they came to attach themselves to and to 'govern' particular case forms of nouns (accusative or instrumental, ablative or genitive or locative). The prepositional and post-positional use with the noun of these particles fell into gradual disuse from Late OIA., and they lost their separate and independent existence in the sentence as help words : they were compounded as prefixes or pre-verbals with the verb, the sense of which they modified. Classical Sanskrit shows fewer particles with a prepositional or post-positional employ than Vedic (J. S. Speyer, 'Vedische und Sanskrit Syntax' in the Grundriss, §§ 85-90). In MIA., the number of these old particles as post-positions employed with nouns grew even more restricted. On the other hand, to make the sense clear, especially when in MIA. the case terminations were confused and were being lost, the IA. speech began to employ the accusative, dative, ablative or locative form of some suitable noun (with the sense of location, vicinity, direction, connexion, purpose, or power) along with the principal noun which retained its original inflexion. Classical Sanskrit, following the Prakrit vernaculars, took up this device (Speyer, § 91). This sort of auxiliary and post-positional use was later extended to some verbal formations—passive participles and present participles, and to the indeclinable conjunctive verb. Such post-positional or prepositional use of verb forms is not unknown to other IE. languages : e.g., English *during*, *regarding*, *concerning*, German *während*, French *pendant*, Italian *mediante*, *durante*, etc. But this principle was utilised only to a very limited extent elsewhere outside India, whereas IA., from the MIA. stages downwards, fully employed it to form post-positionals. Classical Sanskrit already took up some passive participles and conjunctive indeclinables as post-positions governing oblique cases (Speyer, §§ 92, 93). In this matter, it seems that IA. was profoundly

influenced by Dravidian (*vide supra*, p. 172; cf. also K. V. Subbaya, 'A Comp. Gram. of Dravidian,' IAnt., 1910, pp. 145ff).

Some of these post-positional words—nouns and verb-forms—through phonetic decay became transformed into organic affixes in NIA., as has been seen before. The conjunctive and participle post-positions, however mostly retained their phrasal character, and in NIA. they remain distinct, as detached words. Bengali has a number of such verbal post-positions. Besides, some nouns (old *tbs.*, as well as *ts.* or *sts.*), are used as separable post-positions in all NIA. Their establishment is apparently post-NIA., and independent in each language or dialect group.

Below are given the more important Separable Post-positions of Bengali.

(1) অপেক্ষা *« apēkṣā »* = *with regard to: ts.*, used either with the base or with the genitive to indicate comparison.

(2) আগে *« āgē »*, locative of আগ *« āgṛ »* < *« agra »*: MB. আগত *« āgātā »* *before*. Used more commonly with the genitive, and occasionally with the=base: cf. ŚKK., p. 65, রাজা আগে করিবৈ গোহারী *« rājā āgē karibē gōhārī »* *shall make a plaint before the king*; p. 127, আমার আগত বীর নাহি কোন জন *« āmharā āgātā bīrā nāhī kōṇā jānā »* *before me (i.e., greater than me) there is no hero*; etc.

(3) করিতে *« kārītē »* > করতে *« kār'tē, kōrtē »* *doing*, present participle of কর *« √kār »* = *« √kr »* *to do* (instrumental or locative: *« kārītē »* < *karantē* < *karantahi, karantāhī »* (see p. 676). Employed with the genitive for comparison, *e.g.*, রামের কর্তে শ্যাম ভালো *« Rāmēr kōrtē Śyāmṣ bhālō »* *Ś. is better than R.* This is a form which is not common in the *« sādhu-bhāṣa »*.

(4) করিয়া *« kārīyā »* > করে *« kār'rē=kōrē »* *having done*: added to the locative oblique in *« -ē »* to denote the instrumental (see *ante*, p. 747). Used with an adverbial force after adjectives and nouns (the commoner practice at the present day being to use it after the base and not after the *« -ē »* oblique): *e.g.*, জোর করে *« jōrṣ kōrē »* *forcibly*, lit. *doing force*; টান করে *« ṭānṣ kōrē »* *tightly*; ভালো করে *« bhālō kōrē »* *well*, etc.; ŚKK., p. 14, এতাল সাধিবে আছে করিয়া যতনে *« ē-kājā sādhibā āmhē kārīā jātānē »* *we shall*



*do this work carefully*; p. 250, তখন রাধা রোষ করিয়া দ্রুত গমনে জাহ্নবী *takhānā Rādhā rōṣā kārīā sātwarā gāmānē jāē* > *angrily then R. goes with quick steps*; etc.

(5) কর্তৃক *kārttṛkṣ* > (generally pronounced [kottṛik]): a *ts.* word, used as an instrumental post-position, either loosely compounded with the stem, or used with the genitive: 'having (the preceding noun or pronoun) as the doer': e.g., বিদ্যাসাগর কর্তৃক লিখিত *Bidyāsāgarā-kārttṛkṣ likhitā* > *written by Vidyāsāgara*; তাঁহা কর্তৃক দৃষ্ট *tāhā-kārttṛkṣ dṛṣṭā* > *seen by him*. A learned form, which became established during the early 19th century.

(6) কাছে *kāchē* > *near by, beside* = locative of কাছ *kāchṣ* > *side, neighbourhood*. Like the other derivative from *kakṣa*, viz. কাঁধ *kākhṣ* > (< MIA. \*kaṅkha = kakkha; cf. pp. 178-179), কাছ *kāchṣ* > also meant *waist* in MB.: e.g., ŚKK., p. 287, কাছের কলসী *kāchērā kālāsī* > p. 250, কাছের কলসী *kāchērā kālāsīē* > *in the jar held on the waist, beside* কাঁখে কলসী করি *kākhē-tā kālāsī kārī* > *placing the jar on the waist* (p. 259). কাছে *kāchē* > is used with the genitive to indicate the locative. The base কাছ *kāchṣ* > (or its genitive কাছের *kāchērṣ* >) + থাকিয়া, থেকে *thākiyā, thēkē* > *having been, or হইতে, হ'তে* *hāitē, hōtē* > *being, verbal post-positionals for the ablative, are also used along with the genitive of the noun or pronoun to indicate its ablative.*

(7) কারণ *kārāṇṣ* > *cause*: used with the genitive, in an instrumental, dative as well as ablative sense: very common from eMB. downwards: e.g., ŚKK., p. 1, কামের কারণে হইল সৃষ্টির বিনাশ *Kāmsērā kārāṇē hāē sṛṣṭirā bināṣē* > *through Kāmsa takes place the destruction of the world*.

(8) ঘর, ঘরে *ghārā, ghārē* > *house, in the house* (gṛha): used colloquially over a great part of Bengal to indicate the oblique cases in the plural. It is used with the genitive of the noun, and optionally with the *-ā* > oblique of pronouns. In the employment of this post-position, there seems to have been some influence of the *-k-, -g-* > genitive for the plural (pp. 756, 757). Variations are ঘোরে *ghōrē* >, গরে *gārē* >. (Cf. the plural use of মন *māhālṣ* >: p. 733).

(9) চাহিতে *cāhitē* >, present participle locative of চাহ *√cāh* > *look at, want*: used in comparison, generally with the genitive and occasionally

with the stem. The beginnings of the post-positional use of this present participle form go back to OB.: « cāhantē » already figures in the Caryās (e.g., Caryā 31): but the old sense of *seeing* is still predominant in « MB. (ŠKK.)

(10) চাহিয়া, চেয়ে « cāhiyā » « cēyē » *having looked at*, indeclinable conjunctive of চাহ « √cāh »: used in comparison, with the genitive. This use seems to be old. Cf. Early Eastern Hindi as in Tulast-dāsa: « kahā dhanu kulisahū cāhi kaṭhōrā: kahā syāmala mṇdu-gūta kisōrā » *where is the bow, more tough than even the thunderbolt, and where the lad, darkish and soft of limb?*

(11) ছাড়ি « chārī » *let loose* = passive participle of ছাড় « √chār » *give up, loosen*: used with the stem in the sense of 'without,' e.g., আমাছাড়ি « āmā-chārī » *without me*, হুক্কাছাড়ি « hūkā-chārī » *without the hookah*, etc.; or 'in addition to,' e.g., তা ছাড়ি « tā-chārī » *in addition to that* < *letting that alone*.

(12) জন্তে « jānyē » *locative*, beside the stem form জন্ত « jānyā » = *for the sake of, because of, caused by*: a ts. word, employed with the genitive to express the dative relation.

(13) ঠাই « thāi » *place* (< sthāma-): dative or locative post-position, used with the genitive of the noun. An old post-position in Bengali: e.g., ŠKK., p. 142, কহ মোর ঠাই « kahā mōrā thāyi » *tell me*; p. 200, এবে আমাক পাঠায়িল তোর ঠাই « ēbē āmhākā pāṭhāyilā tōrā thāi » *now me he has sent before thee*. Cf. NB. সবঠাই মোর ঘর আছে « sabbā-thāi mōrā ghārā āchē » *I have a home everywhere*. A locative of « thāi » — ঠাই-এ « thāi-(y)ē » is also found: this ঠাইয়ে « thāiyē » becomes in the Standard Colloquial ঢায়ে, চেয়ে « thāyē, chēyē », and in Calcutta « thēnē » is changed to ঢেয়ে « thēyē » — the change of « -ñ- » to « -ṇ- » here is curious. ঠাই « thāi » is found in dialectal Bengali as ঢে « thē », ঠি « thi ».

(14) তরে « tāre » *for, for the sake of*, from অন্তরে « āntār-ē », a genuine lñ. form, with regular MB. change « -nt- » to « -t- ». Used with the genitive of the noun, and the oblique of the pronouns of the first and second persons optionally. Found in OB. as « antarē »; e.g., Caryā 10, « tōhōra antarē » *for thee, for thy sake*. In the ŠKK., the word occurs as



the regular form তরে *tārē* only twice, and as আতরে *āntārē* over a dozen times: (for *ā-*, see *supra*, p. 314). The latter is apparently an archaic literary form.

(15) থাকি > থেকে *thākiyā* > *thēkē* > *having stopped at*: also dialectally \*থেকে, থে *thēē, thē* (\**thāiā*): affixed direct to the stem (or to the locative oblique in *-ē* or *-tē*) of neuter nouns, and to the genitive of names of sentient beings, to indicate the ablative. Found in Early MB.: *e.g.*, ŠKK., p. 347, দূরথাকি *dūra thāki* > *from a distance*. Gujarāṭī has the same conjunctive used similarly for the ablative, *viz.*, *thāki*.

(16) থানে, থানত *thānē, thānā-tā*, locative of থান *thāna* (*sthāna*): used with the genitive to express the dative and locative relations. Examples are numerous in the ŠKK and other MB. works. In NB., it is mainly dialectal (in East and North Bengali, where it is found as থনে, তনে, থোন, তোন, থুন, তুন *thānē, tānē, thōn, tōn, thun, tun*).

(17) দিয়া, দিবে, দে *diyā* > *diyē* > *dē* > *having given*. This conjunctive form is used ordinarily with the base of the noun (which is in accusative relation to it), but occasionally also with the genitive, to express instrumentality or intermediacy. Found from early times: *e.g.*, ŠKK., p. 22, হাত দিয়া দেব *hāthā diā dēkhā* > *feel with the hand*, etc.

(18) দ্বারা *dwārā*: *ts.*, instrumental of *dvār* > *door*, = *through the instrumentality of*. Forms the instrumental, with the genitive (and also with the oblique base in *-ā* in the case of pronouns). This is in its origin a learned form, but it has become sufficiently popular to be used in familiar conversation in NB.

(19) নির্মিত্তে *nimittē* (locative), নির্মিত্ত *nimittā* (stem) = *mark, target, sign* > *objective*: a *ts.* word, forming the dative with the genitive of the noun.

(20) নীচে *nicē* > *below*: used with the genitive to express the locative.

(21) পর *pārā* > from *upari* of Skt. = *above, upon*. The full form উপর *upārā* also occurs, as also the Bengali locatives পরে *pārē*, উপরে *upārē*, as if from a base *upara*. Occasionally also strengthened by তে *-tē*, as পরেতে *pārē-tē*, উপরেতে *upārē-tē*. Used with the genitive to form the locative. *E.g.*, ŠKK., p. 377, তনের উপর

« tānērā (*sta.* < *stana*) upārā » ; pp. 388, 389, গাছের উপর « gāchērā upārā » *on the tree*. But cf. ŚKK., p. 80, খোম্পাত উপর « khōmpā-tā upārā » *on the coiffure*, where « upārā » is used along with the locative in « -tā ».

(22) পাশে « pākṣhē » *by the side of*, locative of « pākṣa » (pakṣa) : found in North Bengal : used like পাশে « pāśē » below (See *supra*, p. 121.)

(23) পাছে, পিছে (পীছে) « pāchē, pichē (pīchē) » *after*. Used with the genitive (as in the corresponding Sanskrit expression). OIA. « paścā(t) » > MIA. « pacchā, pacchā » > NIA. « pācha », locative « pāchē ». The form « pīchē, pichē » has an anomalous « -i- », which is found also in the Hindi « pīchē ». Beames explains the « -i- » as follows : « \*paścē » > \*pah(a)cē », on the analogy of « niścaya » > nihacē » : « \*pah(a)cē » > \*pahicē » > pīcē », then « pīchē » with aspiration through influence of « pāchē » (Comp. Grammar, II, p. 297). But there is no need to postulate a *ts.* stage for this *tōh.* word : it is more likely that there was the influence of a word like « piccha » *feathers of the tail*, or « nica » *below down* (also a post-position), or of « pṛsthā » > পিঠ « piṭhā » *back* (cf. পিছমোড়া « pichṣ-mōṛā » *beside* পিঠ-মোড়া « piṭhṣ-mōṛā » *with arms pinioned behind the back*), in altering « -ā- » to « -i- ». The « -i- » form might well be a borrowing from a Western dialect, and not native Bengali : and in the derived adjective and denominative verb in Bengali at least, the « -i- » is resultant, due to Umlaut and Vowel Harmony : পাছ > পাছু, পাছুই « pāchā » > pāchu, pāchuā », adjective, > পেছো, পেছু « pēchō, pēchu » > পিছু « pichu » ; verb পাছুয়ান « pāchuānā » > পেছোনো, পেছুনো, পিছুনো pēchōnō, pēchunō, pīchunō » *to fall back*.

(24) পানে « pānē » *at, towards, in the direction of* : e.g., মুখ পানে « mukḥ(ā)-pānē » *at the face, towards the face*, আমা(র) পানে « āmā(rṣ)-pānē » *at me, towards me*, ঘর or ঘরের পানে « ghārṣ (ghārērṣ) -pānē » *in the direction of the house*. This post-position occurs in Assamese as পানে « pānē ». The origin of it is obscure, but phonetically it can be from either OIA. « prajñā » *knowledge* (cf. p. 305, *supra*), or « panna » (√pad + na) *reached, arrived at*.

(25) পাশে « pāśē » : locative of পাশ « pāśā » *side* (pārśva). Forms the locative of proximity with the genitive : ŚKK., p. 7, এহার পাশে « ēhārā pāśē » *by his side*, রাধার পাশে, কাছের পাশে « Rādhārā pāśē, Kāchērā pāśē »



etc. We have also (in poetry especially) পাস < pāsā >, which is the old locative in < -i >, = \*pāsi < pārsvē > (see p. 312).

(26) বহি < bāi > *without, apart from*, in addition to: apparently from an OIA. < vyatīta >. Used with the base. In MB., this post-position is written বহি, বহী < bāhi, bāhī >, as if from বহ < √bāh > *carry, bear, be carried away* (indeclinable conjunctive forms of which are বহি < bāhi > and বহিয়া < bāhiyā >). The < -h > however is euphonic (see *supra*, p. 341), and the OIA. passive participle < vyatīta > is the source: if it were বহি, বহিয়া < bāhi, bāhiyā >, the Standard Colloquial form would have been ব'রে < bōyē >, which is not the case. This post-position occurred in eMB.: cf. ŚKK., pp. 192, 193, হাটে দান দেহ এ বাটে বহী < hāṭe dāna dēha ē bāṭe bāhī > *pay the tax in the market, apart from (the tax) on the road*, তিন কি দিবোর এ বাট বহী < bhinā ki dibō-rā ē bāṭa bāhī > *what else shall I give, in addition to (that on) the road*.

(27) বাহির < bāhirā >, modern locative বাহিরে < bāhirē >, Standard Coll. বার, বের < bārā, bēār >, বাইরে < bāirē > = *outside* (MIA. \*bāhiri, \*bāhirē < bāhira: cf. OIA. bāhiḥ, bāh-ya). Employed with the genitive.

(28) বিনা < binā >, by Vowel Harmony বিনে < binē >, also বিনি < bini >: from the OIA. < vinā > *without*. This word is found both as preposition (a rare thing in NIA.) and as post-position. Thus বিনা অনুমতি or অনুমতিতে < binā ānumāti, ānumāti-tē > or বিনা হুকুম < binā hukum(ē) >, beside অনুমতি or হুকুম বিনা < ānumāti, hukum binā > *without permission*; বিনা হাতা, হাতা বিনা < binā hātā, hātā binā > *without handle*; etc. বিনি < bini > is a rare form, now occurring only prepositionally in a few expressions like বিনি-সুতার হার < bini-sutārā hārā > *a necklet without a cord*, বিনি দুঃখে < bini duḥkhē > *without sorrow*. It is found both pre- and post-positionally in the ŚKK., e.g., p. 212, বিনি বতনে < bini jāṭānē > *without any trouble*, beside p. 215, কাহ্ন বিনী আভাগিনী গোপযুবাতি < Kāhñā bini ābhāgini gōpā-jubāti > *without Kṛṣṇa, the milkmaid girls are unhappy*. বিনি < bini > may be a locative form, from a nominalised use < \*bina > of the Skt. particle.

(29) বিহনে < bihānē >, OB. < bihaṇi, bihunē > (Early Oṛiyā = bihunā) *without, in the absence of*. It seems to be the Skt. < vibhina > in the locative, with influence of < √bhū > -hu-. Caryā 13, < nūda-bihunē suinā jāisē >

*just as a dream* (suina = svapna) *without sleep*; 23, « jīvantē-bhēlā-bihaṇi maēla » *dead without even having been a living one*; 35, « cia-bihunnē pāpa na punna » *without mind, no sin, no merit*. In MB. and NB., this post-position is used with either the stem or the genitive: cf. ŚKK., p. 172, চুন বিহনে বেরু তাবল তিতা « cunā bihānē jēnhā tāmbulā titā » *just as the betel leaf is bitter without lime*; Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 9, তোমার বিহনে বাছা ছাড়িব জীবন « tōmār(ā) bihānē bāchā chāribā jībān(ā) » *in thy absence, my son, I shall give up life*; etc.

(30) ভিত (ভীত), modern locative ভিতে (ভীতে) « bhitā (bhittā), bhitē (bhītē) » *in the wall, bank, side*: from « bhitti ». Used with the genitive, to indicate direction: e.g., ŚKK., p. 388, যমুনার ভীতে « Jāmunārā bhitē » *towards the Jumna*. Rare in the NB. « sādhu-bhāṣā ».

(31) ভিতর, ভিতরে « bhitārā, bhitārē » *within*, locatives (the first form < \*bhitari < \*abhyantarē): used with the genitive.

(32) মাঝে « mājhē » *in the middle*, locative form (< madhya). Compounded with the stem, or used with the genitive: NB. বনমাঝে কি মনমাঝে « bānā-mājhē ki mānā-mājhē » *in the woods, or within the heart*; MB., ŚKK., ব্রন্দাবন মাঝে « Br̥ndābānā-mājhē » *within Brindāban*, মথুরা পুরের মাঝে « Māthurā-purērā mājhē » *within the city of Mathurā*, etc. This post-position is a characteristic one of Bengali, and is found from the OB. stage: e.g., Caryā 2, « kōri-majhē (= mājhē) ēku-hiahi » *in one heart, in the midst of (= among) 10 millions* (see ante, p. 746); 14, « Gaṅgā-Jaūnā-mājhērē bahaī nāi » *the boat floats in the Ganges and the Jumna*; 30, « uittā gaṅga-mājhē adabhūā » *risen in the sky, wonderful*; etc.

The locative in मि « -mi » in Haijong, from sts. « \*mahī, ma(d)dhi » = « madhyē », has been noted before (p. 751). Haijong has also the forms मिनि « -mini » and नि « -ni » which are difficult to explain: मिनि « mini » may be from « \*mahī » with « hī » changed to « -ni », and « ni » would in that case appear to be a contracted form of « mini ». Or it may be the affix « -hi » as added to the noun—वरनि « ghārā-ni » < \*gharanhi < « gharahi ». Or is it the locative of a help-word « karṇa » *edge, side* (« -kaṇṇahi » \* (k)annaī > -ni ?), which is found for the genitive and accusative in W. Hindi, Panjābi, Rājasthāni, etc.?



(33) লাগিয়া > লেগে < lāgiyā > lēgē >, poetical লাগি < lāgi > = *having come in touch with*: contracted dialectally to লাগে, লগে, লয়ে, লায়, লই, লে < lāgē, lāgē, lāyē, lāy, lāi, lē >. Used with the base, or the genitive, to indicate the dative of interest, 'for the sake of, with the object that.' This post-positional form has become rather rare in the NB. < sādhu-bhāṣā > and in the Standard Colloquial, but it is exceedingly common MB. and in the archaic poetical language: e.g., সুখের লাগিয়া এ ঘর বাঁধিছ < sukhēra-lāgiyā ē gbarā bādhinu > *for the sake of happiness this house I built* (Caṇḍīdāsa); রূপ লাগি আঁধি কুরে < rūpa-lāgi ākhi jhurē > *the eyes shed tears for (a sight of) the beauty* (c. 1590: VSP., p. 1324); এইকণে তোমালাগি ছাড়িব পরাণ < ēi kṣaṇē tōmā-lāgi chāḍibā pārāṇā > *even at this moment for your sake I shall give up my life* (Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 9); etc., etc.

(34) সঙ্গে < sāṅgē >: instrumental or locative-oblique of the *ts*. < sāṅga > *company*: used in MB. and NB. with the genitive, but in OB. with the stem, to mean 'along with': e.g., Caryā 32, < dujjana-sāṅgē > *with a bad man*; ŚKK., p. 169, বড়ারির সঙ্গে < bārāyirā sāṅgē > *with the old dame*; etc.

(35) সনে < sānē > *with*, instrumental of < samam, sama- >. In OB. the base < sama > (pronounced undoubtedly < saṁa >) is used with the instrumental or oblique: e.g., Caryā 10, < ā lō Dombī, tōṣ-sama karibe ma sāṅga > *O Dombī, with thee shall I have companionship*; Caryā 33, < ṣiālā ṣihē-sama jujhaī > *the jackal fights with the lion*. The instrumental or locative < \*sama-hi = sāṁhē > sāṁhē, sāyē > seems to have been in use in OB., and even in Māgadhi Apabhraṁśa, as the Maithili equivalent < saṁē, sayē > would show. By the end of the 14th century, it became সনে < sānē >: e.g., ŚKK., p. 19, দেবসনে < dēbā-sānē > *with a god*; p. 382, দসনের সনে < dāsānērā sānē > *with the teeth*. Dialectally in North Bengali, it occurs as সানে < sānē >. The earlier form সনে < sānē > is also found in the ŚKK. (over a dozen times).

The W. Hindi < sō > and probably also < sē > *with, by* are from < sama >.

(36) সাথ, সাথে < sāthā, sāthē > *with*, from OIA. < sārtha > *having interest in*. Employed with the genitive, to denote association. This word is more commonly used in East Bengali, West Bengali (especially

the Standard Coll.) preferring সগে < sāṅgē >. Not found in the ŚKK., which is in Early West Bengali.

(37) সুদ্ধ, সুদ্ধা, শুদ্ধ(ী) < suddhā, suddhā. (śuddhā, -ā) > is used after the noun or pronoun put in the dative in কে < kē > or দের < -dērē > to indicate the dative of inclusion: e.g., তাকে শুদ্ধ ব'লতে হবে < takē śuddhā bōltē hābē > *one must tell him also*, ছেলেদের(কে) শুদ্ধ নিয়ে < chēlēdērē (-kē) śuddhā niyē > *taking also the boys*, etc. It is compounded with nouns and pronouns as an inclusive affix: see *supra*, p. 706.

(38) হইতে (হৈতে) < haitē > > হ'তে < hōtē > *being*. In MB., this is found also as হন্তে < hāntē >, beside হোন্তে < hōntē >, হইতে < haitē >, হৈতে < hātyē = hāitē >, হোহিতে < hōitē >, হতে < hātē >, হনে < hanē >. With the base, it indicates the ablative. It is the present participle of √হ or অহ < √hā, āh > *to be* = OIA. < √as >: < \*as-ant- > \*ahanta- > \*ahenta- > \*ahita- > hāita- >, locative or oblique < \*ahanatahi > > \*ahitē > > হইতে < haitē >, NB. হ'তে < hōtē >. There are phonological reasons for affiliating হইতে < haitē > to < √as > \*ahitē > and not to < √hō, hū > \*hōitē >: (see *infra*, under Verb: 'Substantive and Defective Verbs.'). The MB. dialectal form হনে < hānē > shows change of < -nt- > -t- > to < -n- > on the analogy of < karanti > করেন kārēṇ > *does, do* (honorific); and possibly there is some influence of সনে < sānē > (No. 35, above). Equivalents of হইতে < haitē > are apparently the Magahī < -satī > and Bhōjpuriyā < -santē > = *from, by* (Hoernle, Gauḍian Grammar, pp. 228, 328), where the sibilant has been preserved.

The use of < -santa- > as a genitival post-position is very old, and has been found, at least in MIA. of the South-west, as early as the Transitional MIA. period (see *supra*, p. 753). At the present day, this employ of < -sant-, -hant- > obtains in the Western languages, Sindhi and Rājasthānī (< -sand- > in Sindhi, and < -handō, -handī > in Western Rājasthānī), and in the Dardic speech of Kashmir (< -hond- >, beside < -sond- < -s handu > with < -s > from the genitive base to which it is affixed: cf. Grierson in 'Lallā-vākyānī,' London, 1920, p. 139). It has been also suggested that the Panjābī genitive post-position < -dā, -dī > has developed out of the same present participle < -handa > (Beames, II, p. 291), but that is exceedingly problematic, and is not at all attested, and it seems that here we have another



post-positional form, in all probability a derivative from OIA.  $\sqrt{\text{dā}}$  'to give' (see *supra*, p. 164). This genitival use is not met with in the Eastern languages. Early Assamese, like Bengali, uses the locative oblique হন্তে 'hantē', beside the base form হন্ত 'hantā' (not found in Bengali), as an ablative affix, either with the noun base, or with the locative in ত 'tā' e.g., দুই-হন্তে 'dui-hantē' from two, মন-হন্তে 'manā-hantē' from the mind, নগরী-হন্তে 'nāgarī-hantē' from the city, beside যেতি-হন্তে 'mō-tā-hantē' from me, ললাট-হন্তে 'lālāṭā-tā-hantē' from the forehead, etc. In later Assamese, however, হন্তে, হন্ত 'hantē, hantā' no longer feature for the ablative. But we have a form ইত 'hātā', certainly from this 'hantā', as a plural affix for rational nouns, to indicate only members of a trade, caste or group (Hēma-candra Barua, 'Asamīyā Vyākaraṇa,' p. 18): e.g., ছাত্র-ইত 'chātārā-hātā' students, কঁহার-ইত 'kāhārā-hātā' bell-metal workers, ডোম-ইত 'dōmā-hātā' people of the Dōm caste, etc. (see *supra*, p. 739). The use of ইত 'hātā' for the plural is possibly based on an earlier use of হন্ত 'hantā' as a genitive post-position (as in Sindhi, Rājasthānī, and Kāśmīrī) in addition to an ablative one, in the Eastern languages: which, in that case, would parallel the development of the Bengali রা, এরা 'rā, -erā' as a plural affix from the genitive র, এর 'rā, -ērā'.

In the form হইতে 'hāitē' there also has been the influence of the present participle of  $\sqrt{\text{bhā}}$  'to be' ( $\sqrt{\text{bhū}}$ ), as both these substantive roots, 'as' and 'bhū', have merged into one form in Bengali. The present participle of  $\sqrt{\text{bhū}}$  = 'bhavant' > 'honta', is found to be employed as an ablative elsewhere in IA.—e.g., in Western Rājasthānī and Gujarātī as 'hūtau, tāū, tu, thāū, thī' (cf. Tessitori, 'Notes on the Grammar of OWR,' § 72), and in Khas-kurā, where it occurs as 'bhandā'. In Western Apabhraṃśa '\*bhavantaū, hontaū' (<  $\sqrt{\text{bhū}}$ ) were undoubtedly in use as ablative-forming post-positions, like 'ahanta-, asanta-' (<  $\sqrt{\text{as}}$ ) in Māgadhī Apabhraṃśa.

These post-positional present participles of Late MIA. are certainly distinct from the Second MIA. ablative affixes '-hip-tō, -sup-tō', which look like compounds formed of the OIA. inflexions ('-hip' = instrumental plural, and locative singular; or '-sup' = locative plural; plus '-tō' < OIA.

-taḥ, -āt + -taḥ > ablative affixes), although the suffixes < -hiṃtō, -sumtō > and the Apabhraṃśa present participles < hontaū, \*santaū > have been sought to be connected with each other (cf. Hoernle, Gauḍian Grammar, § 376).

(39) হইলে, হ'লে < hāilē > hōlē > *on having been*, conditional conjunctive of the substantive verb, is used with the base or the dative in < -kē > to mean 'in that case,' 'on such-and-such or so-and-so remaining.' The negative form নহিলে, নইলে, ন'লে < nāhilē, nāilē, nōlē > is used also with the base or the dative in < -kē > as a post-position meaning *without*.

A number of *iss.* are also used as post-positions: e.g., < anusāra, anukrama, anuyāyī [onuḥṣai], bhinna, viṣaya, vyatīta, vyatirēka > etc., which are mostly put in the locative or oblique and used with the genitive or the mere base.

The Perso-Arabic form সেওয়ার, সওয়ার, সহার, সওয়ার, সহা < sēwāy, sāwāy, sāhāy, sāwā, sāhā > *besides, other than, over and above*, is used in Bengali with the base or the genitive, generally with the demonstrative pronouns, rather rarely with nouns. It has been borrowed from the Hindōstānī, where it is both a preposition and a post-position (Hind. sawā, siwā, siwā-e, sawā-e, < Persian < Arabic siwā [swy] = *extra, additional*). The word বেগর < bēgār > *without* (Perso-Arabic ba-gair) is sometimes found, either as a preposition or as a post-position, exactly like বিনা < binā > (p. 772)

#### [E] ENCLITIC DEFINITIVES OR NUMERATIVES.

510. Bengali like most NIA. languages possesses some post-positional affixes or words which are added to nouns or numerals to define the nature of the object or article referred to. Pronouns other than those of the first and second persons also take these post-positions, which are attached to the words and practically become a part of them, the case-affixes coming after them. These post-positional words, full or attenuated, are commonly described as *articles*. When a noun (or pronoun) is in the singular, the article or definitive comes after it; when in the plural (and pronouns are not used in the plural here), it must be qualified by a numeral, with which the post-positional is combined: where the number is vague or unknown, the definitive is not used. Where the numeral-*cum*-enclitic



precedes the noun, it becomes an attributive adjective, and does not take the case affixes, which are added to the noun : but where numeral-*cum*-enclitic follows the noun, it is loosely compounded with the latter, and the affixes are attached at the end of the entire group. Thus, মানুষ < mānuṣṣ > *man* : একজন মানুষ < ēkṣ-jāṇṣ mānuṣṣ > *one-person man = a man* ; একটা or একটা মানুষ < ēkṣ-tā, ēkṣ-tī mānuṣṣ > *a or one man* ; একজন মানুষের < ēkṣ-jāṇṣ mānuṣṣērṣ > *of a man*, একজন মানুষকে < ēkṣ-jāṇṣ mānuṣṣ-kē > *to a man* ; but মানুষটা, মানুষটি < mānuṣṣ-tā, mānuṣṣ-tī > *the man*, মানুষটার, মানুষটির < mānuṣṣ-tā-rṣ, mānuṣṣ-tī-rṣ > *of the man*, মানুষটাকে, মানুষটিকে < mānuṣṣ-tā-kē, mānuṣṣ-tī-kē > *to the man* ; দুটা, দুটি or দুজন মানুষ < du-tā, du-tī, du-jāṇṣ mānuṣṣ > *two men*, genitive দুটা, দুটি or দুজন মানুষের < du-tā, du-tī, du-jāṇṣ mānuṣṣērṣ >, but মানুষ দুজনের < mānuṣṣ-du-janērṣ > *of the two men*, মানুষ-দুটিকে, < mānuṣṣ-du-tī-kē > *to the two men* ; etc.,

The definitives are used with nouns in the qualifying genitive, *e.g.*, নীচের টার < nīchērṣ-tā-rṣ > *of the one below*, উপরের খানা থেকে < upārērṣ-khānā-thēkē > *from the piece at the top*, পাশের জনকে < pāśērṣ-jāṇṣ-kē > *to the one beside*, etc. When the definitive is placed *before* the numeral, which qualifies the noun, instead of *after* it, the sense becomes, on the contrary, vague and indefinite as to the number : *e.g.*, জনদুই মানুষ < jāṇṣ-dui mānuṣṣ >, or মানুষ জনদুই < mānuṣṣ-jāṇṣ-dui > *about or some two men*, gen. জনদুই মানুষের or মানুষ জনদুইয়ের < mānuṣṣ-jāṇṣ-duiērṣ, jāṇṣ-dui mānuṣṣērṣ >. This usage is certainly old in the language : it is found in the Early Maithili of the 'Varṇa-ratnākara' (*supra*, pp. 102-103). The enclitics টা (টো, টে), টী < -tā (-tō, -tē), -tī > are not used in this way to precede the numeral, as it is not an entire word any longer. To emphasise the vagueness, the indefinite forms of the numerals (with এক < -ēk >) are also used : *e.g.*, জন দুই or জনদুইয়েক < jāṇṣ-dui, -dui-y-ēk >, খান-দশ or দশেক < khāṇṣ-dāśṣ, -dāś-ēkṣ >.

The employment of these enclitic words or fragments of words lacks the range and variety of the numerative or qualifying words of many other languages, *e.g.*, Chinese (cf. R. K. Douglas, 'Chinese Manual,' London, 1889, pp. 64-66), and Japanese (*e.g.*, H. J. Weintz, 'Japanese Grammar Self-Taught,' London, 1904, pp. 32-34), although there is some resemblance in the general principle.

Common Numeratives of Bengali, and their Origin:

(1) খান, খানী < khāṇṣ, khāṇā >, diminutive খানী, খানি < khānt, khāni > (originally feminine: see pp. 672-673) = *a piece* (< khaṇḍa >: see p. 365). In NB., it is used by preference to specialise objects of rectangular or flat form, or objects which have a frame-work. But in the ŚKK., it is used in an expression like নাতিনী খানী < nātini-khāni > *the (little) granddaughter* (p. 11: cf. also note at p. 433 of the ŚKK., where is quoted from Early Assamese কন্যাখানি < kanyā-khāni > *the little daughter*). This numerative was thus established in Bengali by the eMB. period at least. Cf. also বেড়িল কুড়িয়া (= কুড়িয়া > কুড়ে) খান < bēṛhilā kuṛ(h)iā-khāni > *surrounded the cottage* (Kṛttivāsa, ‘Uttara-kaṇḍa,’ p. 58), সাতারিয়া আনে হুগু অর্জুনের শরীর-খান < sātarīyā āne Bhṛgu Arjunēṣ śārīṣ-khāṇṣ > *B. swims and brings the body of A.* (ibid, p. 65), দুইখান হাত < dui-khāṇṣ hāt > *the two hands* (ibid, p. 92); etc.

(2) গাছ, গাছা < gāchṣ, gāchā >, diminutive গাছী, গাছি < gāchī, gāchi > = *a long piece, a ‘stick,’ a ‘tree’* (MIA. < gaccha >: see p. 472): used with reference to thin and long articles. This is not found in eMB., and seems to have been established in its numerative function during the lMB. period.

(3) গোটা < gōṭā >, diminutive গুটী, গুটি < guṭī, guṭi > = *one piece, one whole, one round object*. It occurs also as গোট < gōṭṣ >, and is found in Hindōstāni as an independent word meaning *a pebble or stone, a round object, a piece, a man (as in a game)*. The word is of uncertain origin, but doubtless the Skt. < guṭikā >, Bengali গুটী < guṭī > *a small globe or ball, a pill, a pearl, a pustule, the cocoon of the silk-worm* is the same word. The source of it may be the Skt. root < gr > *to sprinkle, moisten*, which figures in the ‘Dhātu-pāṭhas’: a form like < \*gr-ta > to mean *a drop* could well have given < \*gurta >, whence < \*guṭṭa, \*gōṭṭa >, whence the NIA. forms, as well as the Skt. < guṭikā >. The Skt. word has been also sought to be connected with < gūla > *round* and < guḷa > *molasses*. The word গোট < gōṭā > was derived from < gōṣṭha-ka > by Hoernle (Gaudian Grammar, p. 273), but that should give an aspirate in NIA., e.g., < \*gōṭhā >, whereas all the actual NIA. forms—Western and Eastern Hindi, Bihārī, Bengali, Oriyā and Assamese,



have <-t- > and not <-th- >. The form <gōṭā > figures as a post-positional numerative in Bihārī; e.g., in Maithilī <duhū-gōṭā > *the two pieces*; also in Oriyā, in Bengali, and in Assamese; and consequently it is likely that the numerative employ of this word goes back to Māg. Ap. We have it in Early Maithilī, and it is extremely common in Early Bengali: e.g., ŚKK. বাঁশী শুটি <bāṣī-guṭi > *the flute*, several times, and Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' বাণ গোটা <bāṇḍ-gōṭā > *the arrow* (p. 28). In NB. গোটা <gōṭā > is quite common as a noun meaning *whole*; its numerative use, however, has become considerably curtailed.

(4) জন <jāṇ > *person*, which can be either *both* or *is*, is used to indicate men and women. The use of this word is found in eMB., and in all likelihood it goes earlier: e.g., Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 2, ভাই দুইজনে <bhai dui-jānē > *the two brothers*, lit. *brother(s) two-persons*; 'Uttara-kāṇḍa,' p. 66, মাতাপিতা দুইজনে <mātā-pitā dui-jānē > *the two parents* (or *mother and father both*); etc.

(5) টা <-ṭā > (by Vowel Harmony ঢো <-ṭō > and ঢে <-ṭē >: p. 401), diminutive টি, টি <-ṭi, -ṭi >: used as the post-positional 'Definite Article,' meaning *an object, a whole*. For derivation and use, see *supra*, p. 686. The dialectal forms <-ḍā, -ḍi > have been noted before. In the Haijong (Maimansing) dialect, apparently it is this <-ṭā > <-ḍā > <-rā > that figures in forms like রাজারা <rājā-rā > *the king*, মাগুরা <māgu-rā > *the wife*, কথারা <kāthā-rā > *the word*, etc. (LSI., V, I, pp. 216 ff).

টো, টি <-ṭā, -ṭi > are the most important definitives of Bengali. The employ of these is already well-established in the Early MB. period: e.g., ŚKK., p. 75 সোনার কুঁড়ো দুটি মনিকে পূরাই <sōṇārā kuṇḍu du-ṭi māṇikē purāyā > *causing the two (round) boxes of gold to be filled with gems*; Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 28, চকুটো <caḥu-ṭā > *the eye*; *ibid.*, p. 1, দুইটা ব্রাহ্মণ <dui-ṭi Brāhmāṇḍ > (*the*) *two Brāhmans*, দুটা হাত <duṭi hāt > *the two hands* etc., etc.

The <-ṭā > affix is found as টু <-ṭu > after the numeral এক <ēk > *one* (= <-ṭ- + <-u >: p. 677); and when used post-positionally after a noun, <-ṭu > is extended to টুক <-ṭu-k >, and further strengthened to টুকু <-ṭu-k-u >: <-ṭu, -ṭuk >, <-ṭu, -ṭuku > are all used to denote 'a small quantity

of any thing,’ generally of fluids and of substances which are already in small fragments: e.g., একটু জল  $\llcorner \text{ēkṭu jāḷa} \gg$  *a little water*, but জলটুকু, টুকু  $\llcorner \text{jāḷa-ṭukṣa, jāḷa-ṭuku} \gg$  *the little water*; একটু মুন  $\llcorner \text{ēkṭu munṣa} \gg$  *a little salt, a pinch of salt*, মুনটুকু  $\llcorner \text{munṣa-ṭuk(u)} \gg$  *that pinch of salt*. The  $\llcorner -k \gg$  in  $\llcorner -ṭukṣa, -ṭuku \gg$  looks like being the nominal or pleonastic affix (see *ante*, pp. 679 ff), but it may be from  $\llcorner \text{ēkṣa} \gg$  *one*, as in the dialectal word টুক, টুয়েক  $\llcorner \text{ṭukṣa, ṭuyēkṣa} \gg$  *a little* (e.g., টুক, টুয়েক বাদে  $\llcorner \text{ṭukṣa or ṭuyēkṣa bādē} \gg$  *a little later*, as in West Rāḍha Bengali:  $\llcorner -ṭu \gg$  diminutive +  $\llcorner \text{ēkṣa} \gg$ ).

(6) থান  $\llcorner \text{thāṇṣa} \gg$  *flat piece, round or rectangular piece* ( $\llcorner \text{sthāna} \gg$ ): e.g., কাপড় দুথান  $\llcorner \text{kāpāṛṣa du-thāṇṣa} \gg$  *the two pieces of stuff*, etc. Rather restricted in employ.

A few other words are similarly used as definitives. E.g., the Persian words তাল  $\llcorner \text{tā} \gg$  *sheet* ( $\llcorner \text{tah, tāh} \gg$  *fold, plait*: দুতা কাগজ  $\llcorner \text{du-tā kāgājṣa} \gg$  *two sheets of paper*), and কেতা  $\llcorner \text{kētā} \gg$  *piece* (Ar.  $\llcorner \text{qitā} \gg$  *cutting*: নোট দু-কেতা  $\llcorner \text{nōṭṣa du-kētā} \gg$  *two bank-notes*). But they partake rather of the nature of English words like *head* (‘five head of cattle’), *sail* (‘ten sail of ships’) than of enclitic definitives like the above.



## CHAPTER III

### THE NUMERALS

511. The numerals present one of the difficult phonetic problems of NIA. Their forms show a remarkable uniformity all over the NIA. area, a uniformity which is not in keeping with the several phonetic histories of the various NIA. speeches. The names for the cardinals in the different NIA. languages, instead of going through their proper MIA. forms back to OIA. (i.e., with each group showing independent and distinct forms with characteristic dialectal phonetic history, in general agreement with the phonology of the mass of words in the language), appear rather to be based on some standardised MIA. forms. These standardised forms originally belonged to some particular dialect of MIA., but they were early adopted in a standard dialect, a sort of Hindōstānī of ancient times (when they did not originally belong to it), whence they were imposed upon the vernacular speeches in the different tracts of the country; and the proper native forms in these latter vernaculars were generally superseded, although in some cases they have maintained themselves (*e.g.*, Gujarātī « bē » Sindhi « b'ē » Marāṭhī « dōn » Bengali দুই « dui » *two*, Panjābī « wih » *twenty*). From the very close resemblance between the common NIA. cardinals and those of Pali, the latter may be taken to represent the basis or source of the former. Pali is based on the speech of the Midland, with influences from the East as well as the North-West and the South-West: one Pali form for *twelve* is « bārasa », with « b- » for OIA. « dv- », which does not seem to be a proper Midland treatment of this group of consonants: the native Midland form was certainly « d(u)vāḍasa », also found in Pali, but we do not know when « bārasa » or an earlier « \*bāḍasa < dvāḍasa » from an outside dialect imposed itself in Pali, side by side with the native form in « d(u)vā- ». (Cf. p. 58, *supra*.) The form « bārasa », however, became established in the standard form of the Midland speech, and thence passed on to the other dialects, Ardha-māgadhī and Māgadhī included; although these latter continued to use their

proper forms <duvāśa, \*duvāśa> side by side with <bāśa>, at least as a literary survival down to Second MIA. times. Even though the Pali forms give a sufficiently satisfactory ground work for those of NIA., there are certain irregularities in the development of the latter, which cannot be properly explained. Thus, intervocalic <-s-> became <-h-> in all the forms except those of the 9th decade in Western Panjābī and Sindhi: *e.g.*, W. Panjābī <yārā(h), bārā(h)> = 11, 12; <wīh, ikkī(h), bāī(h)> = 20, 21, 22; <trīh, battīh> = 30, 32; <cālī(h), cutālī(h)> = 40, 44; <pañjāh, aṭhwañjā(h)> = 50, 58; <bāhṭh, chēāhṭh> = 62, 66; <ihattar, pañjhattar> = 71, 75; but <assī, ikāsī> = 80, 81, where the sibilant is retained. In the other NIA. languages, in Marāṭhī, Gujarātī, W. Hindī, E. Hindī, Bibārī and Bengali for instance, we find <-h-> for <-s-> regularly only in the 2nd and 8th decades, but irregularly in other cases (*e.g.*, Hindī <bārah> = 12, <bāhāttar> = 72 but <pacās> = 50, <aṭhwan> = 58); while the <-s-> remains in the third, fourth, fifth and ninth decades (*e.g.*, Hindī <bāīs> = 22, <artīs> = 38, <byāllīs> = 42, <pacāīs> = 85): and Oriyā and Assamese preserve the <-s-> in the eighth decade as well (the <s> in Assamese has become [x]). The Pali forms cannot explain all these anomalies among the NIA. speeches, because Pali represents an earlier state of things in MIA. when <-s-> remained a sibilant. The later Prakrits show a mix-up of <-s-> and <-h-> forms which it is now impossible to refer to local dialects of the Second MIA. stage. Forms like those that we find in Pali would seem to have been adopted in most MIA. dialects by the Second MIA. stage: then after the <-s-> -h-> change took place in one area (probably in N.-W. India: see *supra*, p. 549), that phonetic development also partially insinuated itself into the forms of the standard speech (some form of Śaurasēnī, in all likelihood), and thence also to the other dialects, but not uniformly.

The origin of the NIA. words for the numerals has been discussed by Bloch (cf. 'Langue Marathe,' pp. 214-223). The question is studied here from the point of view of Bengali.

512. One = এক <ēk> [æ:k] from eMB. [e:ko], OB. [e:ko] <MIA <ēkka>, a MIA. *ts.* or *sts.* form, occurring side by side with the *thā*



« ēga, ēa » which occur in Prakrit but which are not so common (Jaina Ardha-māgadhī prefers « ēga », however). The Assamese এ « ē » = *one*, as in এজন « ē-zāṇḍ » *one person*, এটা « ē-tā » *one*, এহেজার « ē-hēzārḍ » *one thousand* (= Bengali একজন, একটা, একহাজার « ēkḍ-jāṇḍ, ēkḍ-tā, ēkḍ-hājarḍ »), shows that the *tbh.* « ēa » was as much a living form in Second and Third MIA. as the *sts.* « ēkka ». A common and exceedingly important word, for the numeral *one*, it could not remain as the colourless « ēa », and hence the *ts.* form could easily come in to meet the necessity of a distinctive vocable.

In composition, « ēkḍ » remains unmodified (*e.g.*, একুশ *ekusḍ* < *ēkuiḥḥ*, *ēkaiḥḥ* = 21; একত্রিশ, ত্রিশ *ēkḍ-t(i)riḥḥ*, *ēkāttriḥḥ* = 31; একচাল্লিশ *ēkḍ-cāllisḥḥ* = 41; একার *ēkāra* = 51; একষষ্টি *ēkḍ-ṣaṭṭi* = 61; একাত্তর *ēkātṭarḥḥ* = 71; একান(ত)ই *ēkānai*, *ēkānābbāi* = 91), except in এগার « ēgārā » = 11. Here the voicing difficult is to account for. It seems to be NIA., from a Late MIA. « \*ēkārāha », a standard form, < earlier « ēkkārāha » which supplanted the *tbh.* « ēārāha ». The « -k- < MIA. -kk- » is preserved in Marāṭhī « akrā »; and Panjābī « yārā » represents the normal MIA. *tbh.* « ēārāha- ». The Ardha-māgadhī « ēga » would only be confined to literature, and cannot be regarded as being responsible for the NIA. « ēgārā, igārā » etc. The 'Prākṛta-Pāṇḍala' form « ēggārāha » seems only to be a Prakritisation of the NIA. word. In forms like « ēk-uḥḥ, ēkḍ-t(i)riḥḥ » etc., an analysis into « ēkḍ + biḥḥ (viḥḥ), ēkḍ + t(i)riḥḥ » was easy, and this analysis seems to have helped to bring in or retain the « -k- »; but there was not much scope for this analysis when « -daṣa » became « -raha » in the MIA. « ēkkārāha, \*ēkārāha, ēārāha » in the dialects, which mostly now have « -g- » or zero for the original « -k- ». In Gujarātī « ōgḍḍis » = 91, « ōgaṇṭis » = 29, « ōgaṇṭālis » = 39, « agṇō-ḥṣi, ōgaṇyāṣi » = 79, however, it is not a case of voicing: « ōgaṇ- » is not from OIA. « ēkōna- », but is rather from a Skt. « \*apagaṇa (-viṇṣati) », etc. (Pischel, § 444).

In Chittagong Bengali, there is the voicing of « -k- » which characterises this dialect: « ēgḥ < ēkḥ »; also « ēkuā, ēkā > ēguā, ēgā, eggā, oggā »; (this « ēguā, eggā » gives in Chittagong Bengali the numerative enclitic « -ggā » or « -gōā »: *e.g.*, « du-ggā » = *two pieces*, « tsāir-gōā » = *four pieces*,

etc., which corresponds to « dui-gō, cār-gō » etc., of the Bihārī dialects); « ēgāiśṣ, ēgōiśṣ = ēkuśṣ, ēkāiśṣ »; etc.

In other compound forms in Bengali, « -k- » of « ēkṣ » is preserved: e.g., একুইতি « ēkuiti » (= ēka-putrikā). The « -k- » is lengthened or doubled in Bengali for emphasis, as in the case of the other consonants: e.g., একেকালে, একেকবারে « ekkē-kālē, ekkē-bāre » *all at once* or *all at the same time*, etc. (see above, p. 448).

513. Two = দুই « dui », from MIA. « duvē », properly the neuter form = « dvē » of OIA., which is already established in the eastern dialect of Aśoka for the masculine as well (e.g., Rock Edict I. Jaugada = « duvē majulā = dvāu mayūrāu »). দুই « dui » is a genuine Prācya and Māgadhi form as preserved in Bengali. It is found in the other Magadhan speeches as well. Other typical NIA. forms, differing from that of the Eastern tracts, are « dō » (W. Hindi and Panjābī), « dōn » (Marāṭhī), « bē » (Gujarātī), « b'ē » (Sindhī) and « dē-ka » (Sinhalese).

In composition with nouns, the equivalent was « dō- » in MIA. In the Caryās, « dō » also occurs (beside « dui ») as an independent or qualifying form: e.g., « dui gharē » (Caryā 2), « dui māra (= mārḡa: Caryā 26), and « dō bhāṣā » (= vartma: Caryā 15). We have also a definitive « duā » as in « phīṭaū duā » *let the two be split or destroyed*. In genuine Bengali compounds, the form « dō » becomes « du » when followed by a high vowel (see under 'Vowel Harmony,' *supra*, pp. 397-398): thus, দুমুখ « du-mukhō < dō-mukh-ā » *two-faced*, দুচুট « du-chuṭṣ » < বোচুট « dō-chuṭṣ » (see p. 472), দুপুর « dupurṣ » < দোপুর « dō-pābārṣ » (dvi-prahara); but দোপাতি « dō-pāṭi » *a flower*, দোআশলা « dō-āślā » *of mixed breed* (dvi + āśla + la-), দোভাষী « dō-bhāṣī » *interpreter*, etc. A common contraction of the adjectival দুই « dui » is দু « du »: e.g., দু(ই)টা > দুটা « du(i)-ṭā > du-ṭō » *two pieces*, দু(ই)জন « du(i)-jānṣ » *two persons*. In such forms, দু « du » is regarded as forming compounds, and this fact influences the original « dō- » in many compounds to be changed to « du- »: e.g., দুহাতা > দুহাতা « du-hātā > du-hāttā », beside দেহাতা « dō-hāttā » *with both hands* (= *to one's best advantage*), দুধারী « du-dhārī » beside দোধারী « dō-dhārī » *two-edged*, etc.



In MB. there is the form দোহ *\*dōhā* *two* (as in দোহে *\*dōhē* nominative and oblique, দোহাৰ, দোহাকার *\*dōhā-rā, dōhā-kārā* genitive, দোহাকে *\*dōhā-kē* dative) which represents an Apabhraṃśa genitive *\*dōṇhā, dōṇṇah*. Variants of this form, with the nasal from the genitive plural of the noun, are দুইহ *\*duihā* (as in the ŚKK.), and দুহান *\*duhānā* (as in the Early Assamese দুহানো *\*duhānō*).

In compound numerals, we find the forms বা *\*bā-* and ব, বি, বে *\*bā-, bi-, bē-* representing the OIA. *\*dvā-, dvi-*: thus বাইশ *\*bāisā* (*\*dvā-viṃśati*), বত্ৰিশ, বত্ৰিংশ *\*bāt(i)riśā* (*\*dvā-triṃśat*), বিয়াল্লিশ, বেয়াল্লিশ, ব্যাল্লিশ *\*biyāllīśā, bēyā-, byā-* (*\*dvi-catvāriṃśat*), বিয়াশি *\*birāśi* (*\*dvy-aśti*). The change *\*dv- > b-*, as has been noted before (see *supra*, pp. 508, 782) is non-Māgadhī: native Māgadhī would have shown *\*dōā-, \*dvi-*.

Bengali দোক *\*dōkā* *twain, with a second* is an analogical formation after এক *\*ēkā* *alone*.

In the OB. of the Caryās we have the word *\*bēni* to mean *two* (Caryās 1, 4, 5). The word in this sense is extremely common in Early Oṛiyā (*bēṇi*). It is the *ts.* word *\*vēṇi* *plait, plait of two bands of hair*, and the Sanskrit word itself would seem to be based on a MIA. formation from *\*dvi-*, with *\*v- < b-* from *\*dv-*.

514. *Three* = তিন *\*tiṇā*, properly তৌন *\*tiṇā* < OB. *\*tini, tiṇi* = *tini* (cf. Caryā 13, *\*tiṇi bhuaṇa* *the three worlds*; also Caryās 7 and 16); Oṛiyā, Assamese and Maithilī = *\*tini*. This form is found in most NIA., excepting in the Western Languages—Panjābī and Lahndī, Sindhī and Gujarātī—which have forms in *\*-r-* (Panj. and Lahndī *\*trai*, Sindhī *\*trē*, Gujarātī *\*trap*) through Dardic influence. The NIA. *\*tini* comes from the OIA. neuter *\*triṇi*, which was generalised in the East for all genders (and, it seems, also in the Midland: cf. W. Hindī *\*tin(i)*). This can be seen from Aśōkan inscriptions: thus *\*tiṇi pāṇāni* in Dhault and Jaugada I, = *\*tiṇi, tini pāṇāni* in Kalsi, for which Girnar has *\*ti, tri prāṇā* and Shahbazgarhi *\*tra(yo) prāṇa, prāṇa-trayo*. OIA. *\*triṇi* seems to have passed through a stage *\*tirṇi* to give Early MIA. *\*tinni, \*tiṇi*. An expected Māgadhī form from *\*triṇi*, without the intermediate stage *\*tirṇi* postulated here, would be *\*ṭini*, and also

\**ti* = *tri* : cf. Hindōstānī *ti-kāṭhī* = *tri-kāṣṭhikā* = *wooden triangular frame to which offenders are tied to be flogged* (= Bengali টিক্‌টিকি *ti-kāṭhī* < \**ti-kāṭh-ikī* > with confusion with the onomatopoeic word টিক্‌টিকি *ti-kṭiki* = *house lizard*) in which *tr* > *t* seems to be a Māgadhism which has survived.

In compound numerals we find ত্র, তি *tē*, *ti* (< *traya*, *tri*): ত্রয় *tērā* (*trayōdaśa*, \**tridaśa*), ত্রৈশ *tēśā* (*trayōviṃśati*), ত্রৈশ্রয় *tēttrīśā* (*trayastrīṃśat*), etc., etc. In compounds generally we have ত্র *tē*, changed to তি *ti* by Vowel Harmony: e.g., ত্রৈশ্র *tēhāi* = *third part* (*tri-bhāgikā*), ত্রৈশ্র *tēpāyā* = *tripod*, MB. ত্রৈশ্র, ত্রৈশ্র *tēōrī*, ত্রৈশ্র *tiurī* = *oven* (*tri-vṛt*), etc. OB. however has *ti-śaraṇa* (*Caryā* 13) and *tia-dhāu* (< *tri-ka* + *dhātu*: *Caryās* 28, 29).

515. *Four* = চার < চৈ, চৈ, চৈ *cār* < *cālr*, *cāir*, *cāri*. This is the form which is found in almost all NIA., except Sinhalese, which has *satara*, *hatarā*. The NIA. *cāri*, *cār* is apparently to be connected with the OIA. neuter form *catvāri*. In the Aśōkan Kalsi dialect, *cat(t)āli*, occurs already for the masculine; but Aśōkan of Girnar shows for masculine *catpārō* (*catvārah*). (This, if it had survived, would have given in NIA., Gujarātī, a form \**cāpar*, through a Second MIA. \**capārō*). Pali has *cattāro* (accusative *caturō*), *catassō* and *cattāri* for the masculine, feminine and neuter respectively. From Second MIA. *catāri*, we come to the Apabhraṇśa *cāri* and the Early NIA. *ciāri*: and the apparent loss of *-tt-* in these later forms is not easy to explain (see *supra*, pp. 254-255). The loss of the *-tt-* may have been due to the form taken by this numeral word in compounds — *caū* < *catuḥ* —; and as Pischel notes (*Gramm. der Pkt.-Spr.*, § 439, p. 313), *cāri* occurs in Apabhraṇśa in compounds (*catuspāda* > \**caūppāa* + \**cattāri-pāa* giving *cāri-pāa* ?).

The form *ciāri* is attested from Early Oṛiyā, from Marāṭhī, and from other NIA. languages (see *ante*, p. 106). It can also be well assumed that Bengali also possessed this *ciāri*, at least side by side with *cāri*. The form *ciāri* appears to be late, and NIA. There is no proper



explanation of the intrusive (?) «-i-», but an Iranian influence here does not seem to be an impossibility (see *supra*, p. 255; also see *infra*, under *Six*).

In compounds, the numeral occurs as চৌ «cāu» = MIA. «caū», OIA. «catuḥ, catu-, catur-». The diphthongal form occurs already in OB.: eg. «cau-disa» (Caryā 6), «cau-koṭṭi» (Caryā 37). In the numerals, «cau» has become contracted to «cō-, cu-»: thus চৌদ্ধ «cōddā» («caturdaśa»: the «sādhū-bhāsā» form চৌদ্ধ «cāuddā» is archaic), চৌব্বিশ «cōbbiśā» (caturviṃśati), চুয়াব্বিশ «cuālliśā» (catuṣcatvāriṃśati), চুয়াত্রিশ «cuānnā» (catuḥpañcāśat), চুয়াতর «cuāttārā» (catuṣṣaptati), চুয়াশী «curāśi» (caturāśīti), চুয়াশ(ক)ই «curā-nā(bbā)i» (caturnavati). The forms চৌত্রিশ «cāu-triśā» (catustriṃśat) and চৌষট্টি «cāu-ṣaṭṭi» (OB. «caūṣaṭṭhi, caūṣaṭṭhi, caūṣaṭṭhi» as in Caryās 8, 12 and 10 respectively: = «catuṣ-ṣaṣṭi») preserve «cāu»: but they are not the normal Bengali forms as expected—the first has *ts.* influence, and the second seems to have been influenced by literary Prakrit from the OB. period. In MB. and dialectal NB., through the common change of «āu» to «āi», we have চৌপার «cāipārā, cōpārā» < চৌপার «cāupārā» (caū-pahara, catusprahara), চৌদ্ধ «cāiddā» (= Assamese চৌধ্য «cāidhyā») beside চৌদ্ধ «cāuddā», etc. (see *supra*, p. 385). Compounds like চৌকাঠ «cāu-kāṭhā» door-frame, চৌবুড়ী «cāu-gburi» four-in-hand, চৌদোল «cāu-dōla» litter, palanquin of state, চৌধুরী, \*চৌধুরী «Caudhuri» < \*Caudhārī «a title or surname < chief (= catur + dhara + -ika), চৌমাথা «cāu-māthā» carrefour, crossing, are archaic in type, and «cāu» is an atrophied form; and in MB. and NB., compositions with the Bengali চারি, চার «cār(i)» are more common: e.g., চার-পেয়ে < চারি-পাইয়া «cārī-pāiyā» < cārī-pāiyā» four-footed, চার-কেলে < চারি-কালিয়া «cārī-kālīyā» < cārī-kālīyā» of the four ages, etc.

516. Five = পাঁচ «pācā» (OIA. pañca). All NIA. speeches agree in retaining the nasal, except Sinhalese, which has the form «paha < pasa < \*paca». In compounds with nouns, «pācā» remains unchanged in Bengali: e.g., পাঁচমুড়া «pācā-mura» five-created, পাঁচ-হাতী «pācā-hātī» five cubits long, etc. In the compound numerals, however, the word occurs in four forms in Bengali, as below:

- (1) পঁচ < pāc- > as in পঁচিশ < pāciśś > (pañca-viñśati), পঁচাত্তর < pācāttārś > (pañca-saptati), পঁচাত্তি < pācāśi > (pañcāśīti), পঁচান(ব)ই < pācānā(bbā)i > (pañca-navati);
- (2) পঞ্চ < pañc- > as in পঞ্চাশ < pañcāśś > (pañcāśat), পঞ্চাশ পাঁচান্না < pañcā-pañcāśśat > : there is a dialectal পাঁচপন < pācś-pānś >), and উনপঞ্চাশ < unā-pañcāśś > ; also contracted to < -āñc- > as in ‡ উনপাশ < unāñcāśś > 49;
- (3) পঁয় < pāyś- > as in পঁয়ত্রিশ < pāyś-triśś > (pañca-triñśat), পঁয়তাল্লিশ < pāyś-tāllīśś > (pañca-catvāriñśat), and পঁয়ষট্টি < pāyś-ṣaṭṭi > (pañca-ṣaṣṭi);
- (4) পন, পান্ন, আন < pānś-, -pānnā -ānnā > as in পনের < pānērā > (pañca-dāśa), and in the fifties—একান্ন, বাহান্ন, তিপ্পান্ন, চুহান্ন, পঞ্চান্ন, ছাপ্পান্ন, সাতান্ন, ষট্টান্ন < ekānnā, bāhānnā, tippānnā, cuānnā, pañcānnā, chāppānnā, sātanā, ṣaṭṭānnā >.

Of the above, < pācś < pācś >, with short < -ā- > through absence of stress in the word in the formative period of Bengali, seems to be the native Bengali form : and < pañc- > in পঞ্চাশ < pañcāśś > etc., has a restored < -ñ- >, apparently through *sa.* influence : the expected native Bengali form would be < \*pācāśś > : cf. Hind. < paśś >. The forms < pāyś (= pañā) > and < pānś, pānnā, -ānnā > are respectively from MIA < pañña > and < panna (paṇṇa) >, from < \*pañja < pañca >. The change < ŋj > nñ, ñ > is found in Maithili in one or two forms (see *supra*, p. 364), but it does not characterise Bengali; and < -ñc- > -ñj- > -nn-, -n- > is equally foreign to Bengali. We find the latter change in the Midland and Eastern inscriptions of Aśoka : e.g., < pañna-dāsa > (= panna-dāsa < pañca-dāśa) and < pañna-vīśati > (= panna-vīśati < pañca-viñśati) in the Delhi-Siwalik pillar, for instance, and < sa-paṇnā > (= \*sappannā[h] < ṣaṭ-pañcāśśat) at Sahasram : where it can well be an imposition from an < -ñc- > -ñj- > nn > (and < -s- > -h- >) dialect, presumably of the North-West (cf. Jules Bloch, J.A., 1912, I, pp. 332 ff.).

517. *Six* = ছয়, ছ < chāyś, chā >, Assamese < chāy > [sōḥ], Oriyā < chāā >. MIA. has the form < cha >. The Bengali, Assamese and Oriyā forms, as well as the Panjābī < chē >, Marāṭhī < sahā >, and the forms < chē, chēy-, chiy- > as in the decades (as compared with Hindi and Gujarātī



«cha-» are apparently based on a fuller form in MIA. than simple «cha». The word cannot have originated from «ṣaṭ» of OIA.: «ṣ- > ch-» would be an inexplicable change in Early MIA., and we should expect the sibilant to remain either as «s-» or as «ś-», as in «ṣōḍaśa, ṣaṣṭi» > NIA. *sōlah, sāṭh* : and as a matter of fact the word for *six* does occur with «s-», in *Aśōkan Prakrit*.

The Indo-European word for *six* was «\*seks, \*sweks». In Indo-Iranian, it became «\*saśs, \*swaśs», the expected OIA. equivalent of which would be «\*saks, \*swaks» > «sak, \*swak», which could change only to «\*saṭ, \*swaṭ» by analogy (Uhlenbeck, 'Manual of Sanskrit Phonetics', p. 88; Wackernagel, I, p. 174): normally it could not certainly be «ṣaṭ», such as we actually find in OIA. In the form «ṣaṣ-» (as in «ṣaṣ-ṭha, ṣaṣ-ṭi»), the second «-ṣ-» is quite regular (< Indo-Iranian «\*s[w]aśtha, \*s[w]aśti» = IE «\*s[w]eks-tho, \*s[w]eks-ti»: cf. Wackernagel, I, § 201, d). This «-ś- > -ṣ-» in the interior of the word may have influenced the initial «\*s-» to «ś-, ṣ-» (Indo-Iranian «\*s[w]aśtha, \*s[w]aśti» > «ś[w]aśtha, ṣ[w]aśti» > OIA. *ṣaṣ-*, Prim. Iran. «ś[w]aś-»: cf. H. Reichelt, 'Awestisches Elementarbuch,' § 160). The Avestan equivalent of Vedic «ṣaṭ, ṣaṣ» is «xəvaś», which represents the Iran. «\*śwaś» (with the «-w-» of IE. «\*sweks»): the prothetic «x-» in «x-əvaś» is regular in Avestan before initial «ś-» *plus* consonant (Reichelt, *ibid.*, § 174). The forms «ṣaṣ (śaś), xəvaś» beside «\*ṣvaṣ (\*śwaś)» occurred in the various ancient dialects of Indo-Iranian, as we can see from Sanskrit, from Avestan, and from the various present-day speeches of the Indo-Iranian borderland—Iranian and Dardic: *e.g.*, Baṣṣālī «śō», Kalāṣa «śōh», Vērōn «uśu» and Šīṣ of Jalkot «śva (ṣva)», as well as Paštō «ṣpaṣ, ṣpəṣ, ṣpag», would seem to be based on a form «\*śwaś» or «\*ṣvaṣ»; Šīṣ «śah, śa (ṣah, ṣa)» and Kaśmīrī «śōh» on «śaś (ṣaṣ)», like the New Persian «śaś», : and the Central Asian Ghalcha forms—Yūdghā «uxšo» and Munjānī «axše» would appear to be based on a form agreeing with the Avestan «xəvaś». But «ṣaṣ, \*ṣvaṣ» cannot explain the MIA. and NIA. «cha-», and the Khō-wār (Dardic) «choi». Could the typically Iranian «xəvaś» have been borrowed, or blended with the Indian «ṣaṣ», in an old Indo-Aryan frontier dialect, in the

form «\*kṣaṣ, \*kṣak»? This form in «kṣ» could well be extended to «\*kṣaka», to make it a disyllabic word like «pañca, sapta» etc.: and «\*kṣaṣ, \*kṣaka» could very well be the source of «cha, chaa», with the North-western or Western MIA. alteration of «kṣ» to «ch» (cf. *supra*, p. 469).

Tokharian of Central Asia (*supra* p. 5) shows some peculiar forms for *six* and *sixth*, which may be noted. In Dialect A, it is «ṣak», ordinal «ṣkaṣt» and in Dialect B the forms are «ṣkas, ṣkaste», cardinal and ordinal. The derivation «IE. \*seks > \*saks > \*sakas > ṣak, ṣkas» has been proposed (cf. A. Meillet, MSL., XVII, 1912, p. 287). But in this connexion, can an Indo-European «\*skes» (or «\*skwes»), as occurring side by side with «\*seks, \*sweks», be postulated? In that case, this «\*sk-» of Indo-European can regularly give the «ch-» of Indo-Aryan.

In the Aśōkan inscriptions, the words for *six* are «cha» (Rūpnāth: «cha-vacharē»), «sa-» (Sabasram: «sa-vachalē, sa-pañnā»), «ṣa-» (North-West and Kalsi), and «saḍu-» (Dehli-Siwalik and Meerut «saḍu-vīṣati»). The occurrence of «cha» and «sa-, ṣa-, saḍ-» side by side is a certain indication that the first is a form independent of the other ones.

The «-h-» in Western Apabhraṃśa «chaha», Marāṭhī «sahā», Sinhalese «saha» is obscure. It may represent the second sibilant in the base form «ṣaṣ», which is seen to occur in Dardic. The forms «chē, chēy-, chīy-» in the compound numerals are easily explained as being from a MIA. «chaa, chaṣa». The Maithilī «chau», earlier «chaō, chahu» (as in the 'Varṇa-ratnākara,' *supra* pp. 102-103; also in the same work, «āḥahu=āḥa > 8, «caubisaō» = «caubisa» 24, etc.), has the affix «-hu» which would seem to be only an emphatic particle.

The words for 16, and the *sixties*, are based on the OJA. (Sanskrit) forms with «ṣ-».

518. *Seven* = सप्त «sātṣ»: regularly derived from OJA. «sapta», and found in all the IA. speeches (Hindī etc. «sāt», Panjābī «satt», Sindhī «sata», Sinhalese «hata, sata»).

In the compound numerals, except in সতের «sātērā» 17, and সাত্তইত্রিশ «sāttriśā» 37, «sātṣ» is unchanged. In Early Bengali, it is likely that the



compounded form was \**sātā*\*, with weakening of \**-ā-*\* to \**-a-*\* through absence of stress: cf. Oriyā \**sātāśā*, *sātā-cāśā* > 27, 47, Hindi \**satāśis*, *sat-hattar* > 27, 77, etc. The \**-ā-*\* is due to initial stress, no doubt; but curiously enough, we have *সতের* \**sātēra*\* and uot \**\*sātārā*\* which would be the expected or normal form for Bengali. In *সাঁইত্রিশ* \**sāitriś*\* (or *সাঁত্রিশ* \**sāyṭtriś*\*) there was certainly the influence of \**pāyṣ* < *pañña*\* of *পাঁত্রিশ* \**pāyṭtriś*\* 35: cf. similar nasalisation in Bengali *চৌত্রিশ* \**cāutriś*\* (beside *চৌত্রিশ* \**cāutriś*\*) 34, and Maithili and Hindi \**tētis*, *cāutis*, *tētālis*\*. Other Magadhan speeches have \**sāi-*\* or \**sāy-*\*; e.g., Maithili \**sāitis*, *sāitālis*\*; except Assamese, which has a borrowed and modified form \**sāttic*\* > [*xattis*]. The analogical \**sāi-*, *sāyṣ-*\* we find also in Hindi \**sāitis*, *sāitālis*\*, and Panjabi \**sāit(r)i*, *sāitāli* > 37, 47. The form of this numeral as \**saṭ* > *saḍ*, *saṛ*, *saṛ*, *sāḍ*\*, as in Hindi \**sar-saṭh* > 66, Gujarātī \**sāḍ-tris* > 37, which is due to the influence of \**aṭh-*, *aḍ-* > 8, is not found in Bengali.

519. *Eight*=*আট* \**ātṭ*\*, *আঠ* \**āṭhā*\* in eMB. and OB. (< *aṣṭa-*). This word remains unchanged in compounds as \**ātṭ*\*, except in *আঠার* \**āṭhārā* > 18, where the old aspiration is preserved. The *৯* *āṭṭ*, *৯টে* \**āṭṭā*, *āṣṭā* > is also common, by itself and also in the forms *৯টে বানো* \**āṭṭā-bāi* > 88 and *আটন(র)ই* \**āṣṭā-nā(bbā)i* > 98, beside the regular *lāks*. *আটানো* \**ātānā* > and *আটান(র)ই* \**ātānā-nā(bbā)i* >.

520. *Nine*=*নয়* \**nāyṣ*\*, from OB. \**\*naṣa*\*, and *ন* \**nā*, *nā*\* = OB. \**nawa*\* mainly in compounds (OIA. *nava*). Oriyā has \**nā*\*. The numeral *নয়* \**nāyṣ*\* does not occur in the decades, the nines being formed, as in OIA., by prefixing \**ūna-*\* (in Bengali *উন* \**ūnā*\*, Oriyā \**unā-*, *ānā-*\*) less to the next ten: e.g., *উনিশ* \**un-iś* > 19, *উনসত্তর* \**unā-sattār* > 69, etc. Cf. \**ōgaṣ-*\* in Gujarātī, p. 784. An exception is *নিরান(র)ই* \**ni-rā-nā(bbā)i* > 99, with altered vowel and intrusive \**-r-*\*. Most NIA. languages agree in having a corresponding compounding of *nine* and *ninety*, Oriyā, however, has \**ānē-śātā*\* (with irregular dental \**-n-*\*).

521. *Ten*=*দশ* \**dāśṣ*\*. The sibilant is preserved in most NIA. except in the Western languages—Lahndī \**dāh*\* beside \**das*\*, Sindhi \**ḍ'ahā*\*, dialectal Gujarātī \**dah*\*, and Marāṭhī \**dahā*\*; and Sinhalese

also has «daha(ya)» beside «dasa(ya)». In the OB. of the Caryās, we find «daśa» side by side with «daha», of which the former alone would seem to be native Māgadhī.

### 522. *The Tens.*

The phonology is peculiar for Bengali in two ways—by change of OIA. «-ś-» to «-h-» (which is dropped in MB.), and by that of «-d-» to «-r-»: «-daśa > \*-ḍaśa, -ḍasa (cf. Aśokaṇ duvāḍasa, pañnaḍasa) > -ḷasa, -ḷasa (cf. Jaina Ardha-māgadhī duvāḷasa), -rasa (as in Pali) > -raha (as in Second MIA.)». The change of «-d-» to «-ḍ-», which could easily alter to «-ḷ-, -l-» and then «-r-», has not been satisfactorily explained. It certainly occurred in a cerebralising dialect *after* the «ḍ» in «ṣoḍaśa» altered to «ḷ, l», as this «ḍ > l» did not participate in the general change of «d > ḍ > l» to «r» of «ĕkāḍasa» and the rest. (Cf. Jules Bloch, 'Langue Marathe,' § 221; see *supra*, p. 488, for the cerebralisation; also p. 549 for «-ś-» > «-h-».)

The final group «-aha» became «-ā» and then «-ā» in Bengali, Oṛiyā and Assamese: and this final «-ā» is also written and pronounced «-ō» in Bengali (*supra*, p. 347); but «-ahā» is retained in Bihārī and in Hindī. In Panjābī, it occurs as «-ā» (yārā, bārā etc.) where it is an oblique plural form used absolutely: so in Sindhī «-an» (yārahan, b'ārahan). Marāṭhī has «-ā» (akrā, bārā), which also is apparently a plural form with dropping of intervocal «-h-» (< \*ĕkkārahā, \*bārahā ?). In Gujarātī, the group «-aha», found in Northern India, is dropped (*e.g.*, bār, tēr, caud, pandar, sōḷ, satar, aḍhār): this apparent dropping of two syllables of MIA. is strange, but it is possible that the Second MIA. source-forms of the Gujarātī tens were, not «bārasa, tērasa, cauddasa» (or «bārāha, tēraha, cauddāha») etc., but rather «\*bāras (\*bārah), \*tēras (\*tērah), \*cauddas (cauddah)» etc., with the final vowel already dropped, through an intermediate stage of «\*bāraso, \*tēraso, \*cauddaso» (or «\*bārahə, \*tērahə, \*cauddahə») etc. (See *supra*, p. 752, on the probable pronunciation of genitival «-asya > -assa» as «-aso, -as» in the Malwa country in the Transitional MIA. period.) Sinhalese preserves rather archaic forms, «ekoḷosa, doḷosa, teḷesa, paḷosa,



so|osa, sata|osa, aṭa|osa », where the «-|-» occurs in all the numbers, and not in the form for 16 alone, as in Northern India.

In NIA. «cau(d)dah», the «-d-» is preserved by the preceding «-r-»: MIA. «cauddaha» is palpably an uncerebralised, non-Māgadhī form. The MIA. doubling is kept up in NB. চৌদ, চৌদ «cauddā, coddā», Standard Coll. [cōddo], although we find চৌদ «cāudā» with one «-d-», (beside চৌদ «cauddā») in the ŚKK. In Assamese চৈধ্য «cāidhya» there has been metathesis of the «-h-», aspirating the «-d-»: the «-y-» indicates only doubling.

### 523. *The Twenties.*

The common Bengali word for *twenty* is কুড়ি «kuṛi» = Assamese «kuri», Oṛiyā «kōriē», meaning *score*. Cf. Bengali এক কুড়ি «ēkṣ kuṛi» *one score*, but never এক বিশ «ēkṣ biṣṣ». In Western Hindi the word also occurs in the form «kōṛī», which is the earlier form (see *supra*, pp. 395-396). Gujarātī has it as «kōṭī, kuṇṭī». Computation is, or normally used to be, by twenties in Bengal: at the present day, this is still the old-fashioned way: thus 25 = এক কুড়ি পাঁচ «ēkṣ kuṛi pācṣ» *one score and five*, 38 = এক কুড়ি আঠারো «ēkṣ kuṛi āṭhārō» *one score and eighteen*, 62 = তিন কুড় দুই «tinṣ kuṛi dui», 85 = চার কুড়ি পাঁচ «cārṣ kuṛi pācṣ», 100 = পাঁচ কুড়ি «pācṣ kuṛi», etc. Counting by twenties is also common in Assam: and the fact that the numerals for the third decade in Assamese show in their spelling চ «c» indicating the [s] pronunciation, rather than শ or স «ś, s» which would be the expected form (with normal change in pronunciation of the original sibilant to the guttural spirant [x]: একইচ, বাইচ, তেইচ, চৌবিচ, পঁচিচ, ছাব্বিচ, সাতাইচ আঠাইচ, also উনইচ «ēkāicṣ, [ekois], bāicṣ [bais], tēicṣ, cānbicṣ, pācicṣ, chābbicṣ [sabbis], sātāicṣ, [xatais], unāicṣ» 21, 22, 23, 24, 25, 26, 27, 28, 19, rather than \*একইশ, \*বাইশ «\*ēkaiṣṣ, \*bāiṣṣ» [ekoix, baix] etc.) indicates that the forms in «-icṣ = -vīsa» were borrowed from some Western dialect, Maithilī or Hindī, into Assamese. In Bengali, the word বিশ «biṣṣ» 20 is by no means common: it occurs only in a few expressions like উনিশ-বিশ «uniṣṣ-biṣṣ» 19 and 20 = *minute distinction*. Counting by twenties is also found in Bihar, and also further west in Hindustan.

It is to be noted that the highest unit for counting among the Kōls is twenty (Santali « *isi* », Muṇḍārī « *hisi*, *isi* », Kurku « *isā* » : the IA. « *bis* », and « *kōṛi* » also are used : *hundred* is  $5 \times 20 = [mōṛṣ \text{ isi}]$  in Santali,  $[mōṛṣ \text{ hisi}]$  in Muṇḍārī, « *mono isā* » in Kurku, « *molloi koḍi* » in Savara : borrowings of the NIA. word « *sai*, *sau* < *śatam* » are also found). Vigesimal counting is found in many languages—*e.g.*, in Dardic (cf. Grierson, 'Piśāca Languages,' p. 37), in French. But it seems that in the case of Bengal, Bihar and the Upper Gangetic plain, probably also in the North-Western frontier (the Dardic tract), Kōl influence was responsible for this habit of computation, rather than that counting by twenties characterised some form of OIA. The word « *kōṛi*, *kuṛi* » occurs in Tamil as « *kōḍi* ». Although any cognate form has not been found in the Kōl speeches, it is still exceedingly likely that « *kōṛi*, *kuṛi* » in its origin is a Kōl word, and not Dravidian or Aryan.

The OIA. « *viṇśati* » gave MIA. « *visati* (Aśōkan and Pali), *vi(n)saī*, *visaī*, *visaīm* (Second MIA.) ». The Pali « *visā*, *visa* », IMIA. « *visa* » are from an OIA. « *\*viṇśāt* » on the analogy of « *triṇśāt*, *cātvarīṇśāt*, *pañcāśāt* ». In the compounded forms, the labial « *-v-* » (where not doubled to « *-bb-* ») has been vocalised in Bengali and other Magadhan ; and besides, the vowel « *-i-* » has been dropped wherever suitable in Standard Bengali, but it is preserved in dialectal Bengali (as in Chittagong), in Oṛiyā, in other NIA. generally : *e.g.*, উনিশ « *uniśṣ* » < « *\*unōiśṣ*, *unāiśṣ* » 19, একুশ « *ēkuśṣ* » < « *ēkāiśṣ*, *\*ēkaviśa* » 21, সাতাশ « *sātāśṣ* » < « *sātāiśṣ*, *\*satāvisa* » 27, etc. চব্বিশ « *cābbiśṣ* » properly for চোব্বিশ « *cōbbiśṣ* » (*caūbbiśa*, *caturviṇśati*) and ছাব্বিশ « *chābbiśṣ* » (< *ṣaḍviṇśati* », with « *ch-* » from the numeral for *six*) are archaic forms, influenced by Prakrit, which retain the group « *-bb-* » (under normal conditions expected to change to a single « *-b-* ».)

#### 524. *The Thirties.*

The native *lōh.* form « *\*tīś* » has been supplanted in Eastern Magadhan (Bengali, Assamese, Oṛiyā) by the *sls.* ত্রিশ « *triśṣ* » or তিরিশ « *tiriśṣ* » ; in Assamese, as the spelling in ৫, ত্রি৫ « *triśṣ* » =  $[tris]$  shows, this supplanting has been recent. In the compound numerals for the fourth decade, the *lōh.* « *\*tīśṣ* » is frequently heard in



Bengali : e.g., বতীস < bātīś > 32, ছতীস < chātīś > 36, etc. (beside the more common বতিশ < bātrīś >, ছতিশ < chātrīś > etc.) : cf. OB. < batīśa, batīsa > (Caryās 17, 27), MB. চৌতিশ < cāutīśa > (see *supra*, p. 228); Assamese < bātīśa > = [botīśa]; and Oṛiyā preserves in the *tōh.* < -tīśa > side by side with the *sts.* < -tīrīśa > in the fourth decade.

The < -r- > forms of Gujarātī (trīs, trīś) and Panjābī (trī, trīh) may be due to the numeral for *three* (traṇ, trai). Sindhī has < ṭīha >. Other NIA., e.g., Hindī, Marāṭhī, keep to the *tōh.* < tīs > (Sinhalese < tiha, tisa >).

#### 525. *The Forties.*

*Forty* is চব্বিশ or চার্বিশ < cālīś, cālīś >, sometimes চালিশ < cālīś > = < catvāriṣat >. The last form with one < -l- > is the genuine *tōh.* form : this single < -l- > is found as the cerebral < -ḷ- > in other NIA. The doubling of the < -l- > is quite optional even now, and is apparently recent in Bengali, absent as it is in Assamese, in Oṛiyā, and in other NIA. The change of < -r- > to < -ḷ-, -l- > in this word shows that it is Prācya or eastern in origin (< cattālīsa), but it spread all over the NIA. area. The group < -tvā- > > Early MIA. < -ttā- > has been dropped as in < cāri > 4, but Sinhalese preserves the dental (< hataḷiha = sataḷiśa < MIA. cattālīsa > : there is also < sāḷiśa >, which is late). The dropping of the < -tt- > is already found in Second MIA., in Jaina Ardha-māgadhī. In the compound forms for the fifth decade, < -c- > remains in একচালিশ or চার্বিশ or চব্বিশ < ēkḥ-cāl(ḷ)īś, -cālīś > 41, (চ)চব্বিশ < chēcālīś, chā- > 46, সাতচব্বিশ < sātḥ-cālīś > 47, and আটচব্বিশ < āṭḥ-cālīś > 48 ; it is dropped in বিয়াল্লিশ < biyālīś > 49 (< \*bāyālīś > etc. : cf. Oṛiyā < bāyālīś >) and চুয়াল্লিশ < cūālīś > 44 (< \*cū-ālīś, \*cū-ālīśa) ; and it is altered to < -t- > in তেতাল্লিশ < tē-tālīś > 43 and পঁয়তাল্লিশ < pāyḥ-tālīś > 45. In Māgadhī, we would expect the < -c- > to remain (see *supra*, p. 468). The form < -tālīś > is found in other NIA., and it is obscure : can it be due to some dialectal shortening of < cattālīsa >, through loss of the initial syllable ?

#### 526. *The Fifties.*

For 49 and 50, we have পঞ্চাশ and উনপঞ্চাশ, † উনকাশ < pañcāś, unā(pā)ñcāś >, where the full < -ñ > is due to *ts.* influence ( see p. 789). In the compound forms OIA. < -pañcāśat > occurs as পর পর, অন্ন অন্ন < -pañña

> -pānnā, -ānnā, -ūnnā >, dialectally *পা* < -pānā >, with one < -n- >, in Bengali. The forms of dialectal Bengali, of Oriyā (e.g., < ākābānā, bābānā, tēpānā, chāppānā > etc.), of Assamese (e.g., < bāuwān; cāuwan; sātāwān > etc. beside < bāuwānnā, cāuwānnā, sātānnā >), of Maithilī (ekāwan, bāwan, tirpan, cāuwan, paepan > etc.), of Hindōstānī, and of other NIA. speeches would show that the double < -nn- > is a late development within Standard Bengali itself. OIA. < pañcāśat > in the form < \*pannāsa > < \*pannāha > < pannā >, already found in the Eastern speech of Aśōkan, became established in some standard form of Early MIA. In Second MIA., it occurs as < paññāsaṁ, paññāśā, pannā, -paññāṁ, -vaññāṁ > (in Jaina Ardhamāgadhī. The contraction of < -āśat > to < -āsa, \*āha > -ā, -aṁ > thus occurred already fairly early in Prācya (Western Prācya): although the change < -ñe- > -nn- > is inexplicable for this dialect. The change seems to have been through < \*pañjāśat, pannāha > (see *supra*, p. 789), and not through < \*pañcāśāt, \*pañcāśat, \*pañcāt >, as Pischel suggests ('Grammatik der Pkt.-Sprachen,' § 445, p. 317). The NIA. < -pan, -wan > in composition comes from this contracted MIA. < -pannaṁ, -wannaṁ >, Aśōkan < -pannā >: the uncontracted form of MIA., viz. < -pannāsa, \*-pannāha > would have given NIA. < \*panā >, in composition < \*-wanā >, which is not found.

In Bengali *বাহান্ন* < bāhānnā > 52 we have euphonic < h > (p. 341; for < \*bāwānā, bāwānā >, cf. Oriyā < bābānā >). In *তিপ্পান্ন* < tippānnā > 53 the doubling is due either to the influence of *ছাপ্পান্ন* < chāppānnā >, or to the Hindōstānī *sts.*, with < r > — < tirpan >, by assimilation in Bengali of the < -r- > with the following consonant (see *supra*, p. 541): the native Bengali form, now obsolete, seems to have been like the Oriyā < tēpānā >. A form *তিয়ান্ন* or *তেয়ান্ন* < tiyānnā, tēyānnā >, also native Bengali, occurs. *চুয়ান্ন* < cūānnā > 54 is for < \*cō-ānā, \*cāu-ānā >: cf. Assamese < cāu-wān >. The dialectal *পাঁচপান* < pācā-pānā > (Central and East Bengal) represents the genuine Bengali form, and not the Standard *পাঁচান্ন* < pāñcānnā >. The other numerals show no anomaly, except the doubling of the < -n- >.

### 527. The Sixties.

The word for *sixty* is *ষাট* = < ṣāṭā > in Standard Bengali, *ষাট্ট* < ṣāṭṭā > *ষোট* < ṣāṭṭi > in Eastern and other dialectal Bengali, = Assamese < ṣāṭhi >.



Oṛiyā «*ṣāthiē*», and it is regularly derived from OIA. «*ṣaṣṭi*». The form with ষ, ষাঠ «*ṣāṭhṣ*» is also found. In the compound numerals, in Bengali the ট «*-ṭ-*» is doubled: একষাট «*ēkṣ-ṣāṭṭi*» 61, বাষাট «*bā-ṣāṭṭi*» 62, পঁয়ষাট «*pāyṣ-ṣāṭṭi*» 65 etc. Oṛiyā has the *lōk.* form «*-ṣāṭhi*». The final «*-i*» in the compound forms, again, is anomalous: contrast ঊনষাট «*unā-ṣāṭṣ*» 59, with proper loss of final «*-i*» (see *supra*, pp. 307 ff.).

### 528. *The Seventies.*

OIA. «*saptati*» certainly first changed to «*\*saptati*» by spontaneous ceberalisation, and then in MIA. (as the source of the NIA. forms) to «*\*sattaṭi*, «*\*sattaṭi*, «*sattari*» quite early. In Pali occur both «*sattati*» and «*sattari*». It is very likely that there was the influence of «*sattaraḥ*» = «*sapta-daśa*» in bringing about the change of the «*-t-*» > «*-ṭ-*» > «*-ḍ-*» to «*-r-*». The double «*-tt-*» is anomalous for Bengali; it is found also in Bihārī, in Hindī, in Marāṭhī. It is quite normal in Panjābī, and the double «*-tt-*» may have been imposed from the Panjab dialects on Hindī and on the rest. Gujarātī has one «*-t-*» (*agnōtēr*=69, *sītēr*=70, *ikōtēr*=71, *b[ō]hōtēr*=72, etc.). It would seem from the Oṛiyā and Assamese forms that in East Magadhan at least, the normal NIA. form with one «*-t-*» was the rule. But Bengali (in common with the Bihārī dialects) seems to have adopted the Western forms in «*-tt-*». In compound forms, «*sattari*» changes to «*-hattari*» in most NIA. This, again, seems not to have characterised Magadhan, at least East Magadhan: the sibilant is preserved as a sibilant in Oṛiyā (*unā-stōri*, *ēkṣ-stōri*, *bā-stōri*, etc.), and undergoes the normal change to [x] in Assamese, although written ন «*s*» (*bā-sātār*, *tō-sātār*, *cāu-sātār* etc.): cf. also Bengali ঊনসাতার «*unā-sāttārṣ*» 69, with the sibilant and not «*\*unā(-h)āttārṣ*». Bengali thus in all likelihood agreed with its immediate sisters Assamese and Oṛiyā in having «*-s-*» and single «*-t-*» throughout in the eighth decade. The «*-h-*» (in what may be called the Western, non-Māgadhī or 'new forms' for the eighth decade of Bengali) is preserved in dialectal Bengali, e.g., ‡ «*ēkṣ-hāttārṣ*, *pācṣ-hāttārṣ*, *sāṭṣ-hāttārṣ*, *āṭṭṣ-hāttārṣ*», but in the Standard Colloquial it is dropped as an intervocal sound, except in বাহাতার «*bāhāttārṣ*» 72.

529. *The Eighties.*

The OIA. «*aṣṭi*» quite regularly gives *অষ্ট* «*āṣṭi*» in Bengali, with change of initial «*ā-*» to «*ā-*» (see *supra* p. 314). The doubling of the «*-s-*» in Panjābī and Hindōstānī «*assī*» is peculiar, and seems to have originated in the Panjab: it was this doubling which possibly preserved it from changing to «*-h-*» in the Panjab dialects (cf. OIA. «*kṛtā*, «*dītā*, «*pītā*» > «*\*kitta-*, «*\*ditta-*, «*\*pitta-*» > Panjābī «*kitā*, «*dittā*, «*pittā*»). The Sinhalese «*aṣṭi*, «*aṣṭi*», with intervocal sibilant preserved, would seem to be based on a MIA. «*\*ass-*» rather than on «*as-*» (cf. W. Geiger, 'Litteratur und Sprache der Singhalesen,' § 21, 22). The Sindhī «*āṣṭi*» would equally be based on an earlier «*\*assī*». It seems that a form with doubled «*-s-*» characterised the IA. speeches of the North-West and the South-West from MIA. times: «*\*assī(m)*»; and it is also extremely likely that there was a nasalised form of it, «*\*aṣṭi(m)*» (through spontaneous nasalisation: see *supra*, pp. 368 ff.), which gave by epenthesis the Marāṭhī «*aṣṭi*, «*āṣṭi*» and Gujarātī «*āṣṭi*, «*āṣṭi*» (cf. Old Western Rājasthānī «*aṣṭi*»: L. P. Tessori, 'Notes on the Grammar of OWR,' § 80).

In the compound forms, Panjābī and Hindōstānī show an intrusive «*-r-*» in «*ti-r-āṣṭi*», which is apparently due to the analogy of «*curāṣṭi*», where it is original (= *catur-aṣṭi*). Bengali has this «*-r-*» form, *তিরাস্টি* (by Vowel Harmony *তিরাস্টি*, † *তিরিস্টি*) «*ti-rāṣṭi*, «*ti-rāṣṭi*, † *tiriṣṭi*»; and the «*-r-*» has been further extended to *বিরাস্টি*, *বিরাস্টি*, † *বিরিস্টি*, «*bi-rāṣṭi*» «*bi-rāṣṭi*, † *biriṣṭi*». Maithilī also has «*bṛāṣṭi*» beside «*bṛāṣṭi*». The «*-r-*» forms for 82, 83 do not seem to be proper for Māgadhī, but rather due to Western influence: cf. Oriyā «*bāyāṣṭi*, «*tēyāṣṭi*», but *ବ୍ରାସ୍টি* «*curāṣṭi*» 84 is quite proper («*cōrāṣṭi* < «*\*caūr-āṣṭi*»). For 89, Bengali has a contracted *উনাস্টি* «*unāṣṭi*» beside a fuller *উনাব্বাস্টি* «*unā-bbāṣṭi*».

530. *The Nineties.*

The word for *ninety* has two forms: *নব্বৈ* «*nāi*», and *নব্বই*, *nābbē*, «*nābbai*, «*nābbui*». The former is the native Māgadhī form: OIA. «*navati*» > «*\*navai*» > «*\*naai*» > «*\*nawai*» > «*nai*» > «*nai*», Assamese «*nai*». The second one with geminated «*-bb-*» is not genuine Bengali: cf. Hindī «*nawē*, «*nawwē*», Panjābī «*nabbē*, «*nawwē*», Sindhī «*navē* <



\*navvāi >, Marāṭhi < navvad > with MIA. < -d- > preserved (< \*navvaddi ?). Bihārī < nabbāi >, Oṛiyā < nābē < \*nabbāi > are similar Western forms. In Pali, the form is < navuti >; and the Ardha-māgadhi < naūim > and Jaina Mahārāṣṭrī < naūi > are based on an Early MIA. form with < -u- > like the Pali one. Gujarātī < nēvū > and Sinhalese < anū(va) > alone represent these attested MIA. forms in < -u- >.

As in the case of the *Eighties*, we find the intrusive < -r- > in বিরান(ব)ই > bi-r-ā-nā(bbā)i > 92, তিরান(ব)ই > ti-r-ā-nā(bbā)i > 93, নিরান(ব)ই < ni-r-ā-nā(bbā)i > 99, on the model apparently of চুরান(ব)ই < curā-nā(bbā)i > 94 (caturnavati). On the analogy of the < -ā- > in the *Eighties* (ēkāśi < ēkāśīti, pācāśi < pañcāśīti, sātāśi < saptāśīti, āṭāśi < aṣṭāśīti), the *Nineties* all over the NIA. area show an intrusive < -ā- >: একান(ব)ই < ēk-ā-nā(bbā)i > Marāṭhi < ekyāṇṇav > 91, Hindi < nawānawē > Gujarātī < nayāṇū > 99, etc.

531. *Hundred* is শ' < śā, sō >, in combination generally pronounced < sō > (e.g., একশ [ækʃo], সত্তাশো [ʃōṭaʃo] = 125, দুশো [duʃo], পঁচিশ [pāñʃʃo] etc.): a regular development out of OIA. < śata- > (śaa, OB. \*śawa, MB. \*śā). Oṛiyā is also < śā >, and Assamese [xə:]. The diphthongal forms < sai, sau > (< sayā, sawa) as in Bihārī, Hindi and Panjābī are now unknown to Bengali, as also the nasalised forms as in Marāṭhi (sē) and Gujarātī (sē), preserving the < anusvāra > of MIA. (pp. 358-359, *supra*). The form শর < śāyṣ > = < sai > of Hindi etc., however, occurred in Early Bengali: thus in the proverbial lines—

নরা গজা বিশে শর। তার অর্ধেক বাচে হয় ॥

বাইশ বলদ, তের ছাগল। শুনে গেছে বরা পাগল ॥

< nārā gājā biśē śāyṣ, tāṛṣ ārdhēkṣ bācē hāyṣ;

bāiśṣ bāḷāḍā, tērā chāḡḡālā: guṇē gēchē Bārā pāḡālā >

A man, and an elephant, hundred and twenty; half of that lives a horse;

An ox twenty-two, a goat thirteen: so has computed the mad-cap Barā (= Farāha-mihira),

where বিশে শর < biśē śāyṣ > = hundred with twenty (< biśē > = either < biś-ā > by Vowel-Harmony, or < biś-iyā >, adjective from < biśṣ > 20, with < -ā >

affix, p. 658 *supra*, or «-iyā» affix, p. 674), is an idiom corresponding to the Hindōstānī «bīsā sau» (J. T. Platts, 'Hindustani Grammar,' p. 53). The form «sau» also occurred in OB : cf. Mayang (of Manipur) «ak-hau-gō» *hundred*, where «hau» < «sau».

532. The word for *thousand* is a Persian borrowing, হাজার «hājār» (< hazār, Avestan hazāra), in Assamese «hēzār», which has superseded the native word (from OIA. «sahasra») in all NIA. Was it because the native IA. word had fallen into disuse in the spoken forms of Late MIA. and Early NIA. when the Persian language came into India with the Turki and Tajik invaders? It is not unlikely that a composition like «daśa-śata» had restricted or made obsolete the single word «sahasra» > *sahasra*, śahaśśā etc. in IA., making it possible for the Persian «hazār» to meet the want of a single term in the popular language. The Sinhalese «dahasa» *1,000*, which seems to be better explained as a composition of «daśa + śata» rather than as a modification of «sahasra = sahasra» (Jules Bloch, 'Langue Marathe,' p. 222), and the use of «das sau» for *1,000*, etc. in Hindōstānī (cf. Platts, 'Hindustani Grammar,' p. 53) and in other NIA. would support this assumption. The native Indian (*ibid.*) word seems to be present in a few compounds, e.g., শাহমল «śāṣṣa-mālā» *a surname* (= sahasra-malla?), সাহসরাম «sāḥasā-rāma» *a personal name* (= «sahasra-rāma»? the *ts.* form is also found as a name).

533. For *100,000*, লাখ «lākḥa» < «lakṣa» is native Indian. For *10,000,000* the word is কোটি, কোটি «kōṭi, kōṭi», of unknown origin, which occurs also in Sanskrit. The forms কোড়, কোড় «krōṛḍ, krōṛḍ» (= Anglo-Indian *crore*) are in common use in Bengali: the corresponding form in Hindi is «karōṛ»: «krōṛḍ, karōṛ = krōṛā» seems to be a false Sanskritisation of a vernacular «\*kōṛa, kōṛi» agreeing with the *ts.* «kōṭi»: cf. Caryā 2, «koṭi-mājhē ēku-hiaht» *among ten millions, in the heart of one only*. In the feeling of Bengali speakers, «krōṛḍ» is the more learned form, a better Sanskrit word than «kōṭi»: we find it in compounds like কোড়পতি, কোড়েশ্বর «krōṛḍ-pāti, krōṛḍēśwara» etc., side by side with কোটিপতি, কোটিশ্বর «kōṭi-pāti, kōṭiśwara».



534. *The Fractional Numbers.*

The following are common to all NIA., and are easily explained. (Cf. S. K. Chatterji 'Prācīn Bāṅgalā "ābūṭha, āṭa" Ō Sārdha-saṅkhyā-bācak Śabdābhāṣī' in the VSPdP., 1930, pp. 113-117).

$\frac{1}{4}$ : পো, পোআ, পোহা < pō, pōā > < MIA. < pāwa-, pāa- >, OIA. < pāda- > The change of < -āwa- > to < -ō- > is against the general phonetic development of this group in Bengali: see *supra*, pp. 349-350: the form expected should have been < \*pā >: cf. Oriyā < pā > *quarter*, < pāē > *one quarter* (cf. also Bengali পাই < pāi > *pie, pice* = < pādikā >). This alteration certainly indicates extraneous influence (cf. Hindi < pāw >; cf. also Bengali conjunction তো < tō > = MIA. < tāva >, OIA. < tāvat >).

$\frac{1}{2}$ : the common Bengali word is অর্ধ < ādhā > *half*, আধা < ādhā > *half portion*, Oriyā < ādhā > *half*, < ādhē > *one-half*; OB. < adha = ādha >: < OIA. < ardha >. The absence of cerebralisation (we would expect < -rdh- > to change to < -ḍdh- >) shows that it is a non-Māgadhī form. The native Māgadhī equivalent seems to occur as অর্দ্ধ < ārdh > in a number of compounds, e.g., অর্দ্ধ-পাণল < ārdh-pāṅāl > *half-mad*, অর্দ্ধ-বীক < ārdh-bīkā > *half aslant*, অর্দ্ধ-মাদল < ārdh-mādāl > *half-drum shaped, not fully oblong*, অর্দ্ধে গেল < ārdh gēl > *swallow half chewed*; cf. besides দেড় < dērdh >  $1\frac{1}{2}$ , সার্দে < sārē > *plus half*, আড়াই < ārai >  $2\frac{1}{2}$ . The Gujarātī < ardhō >  $\frac{1}{2}$  is peculiar, and may be a blend of < aḍḍha > and < addha >.

$\frac{1}{3}$ : তেহাই < tēhāi > (tri-bhāṅika): rather archaic.

$1\frac{1}{2}$ : দেড় < dērdh >, earlier < dērhā > as in Oriyā, = MIA. (Māgadhī) < diadḍha >, OIA. < dvyardha >. Colloquially, we find occasionally ডেড় < dērdh > in Bengali, and there are forms in other NIA. also which show cerebralisation of the initial dental: e.g., Hindi < dēr(h) > beside dārhā, dōrhā, Panjābī < dērh, dēōrhā, dūrhā, dūrh > beside < dōrhā >.

$2\frac{1}{2}$ : আড়াই < ārai >, Oriyā < ārhāi > (with earlier < -rh- >), = MIA. < aḍḍhatiya > (cf. Aśōkan < aḍḍhatiya >: Sahasram), a true Māgadhī form showing also haplology of < -t- > < OIA < ardha-tṛtīya >. A MIA. form < \*aḍḍha-titīya > gave Gujarātī < aṛī, haṛī >; and the Marāṭhī < aḍīc > represents another (Early) MIA. form like < \*aḍḍha-titīya > (= Second MIA. < \*aḍḍha-tījja >, whence < \*aḍḍhijja > < \*aḍhīja > < aḍīc >).

3½ : Early MB. *আহুত্* «*āhuṭṭha*» (as in the ŚKK., pp. 55, 153), Late MB. *আউট* «*āuṭṭha*, *āuṭṭha*» : from OIA. «*ardha-caturtha*», through MIA. «*\*aḍḍha-catutṭha*» > «*\*aḍḍha-yadutṭha*» > «*\*aḍḍha-aṭṭha*» > «*aḍḍha'ṭṭha*» ; then by dissimilation of one the cerebral groups, «*\*ahuṭṭha*», and finally «*āhuṭṭha*» in OB. (The form «*aḍḍhuṭṭha*» occurs in Jaina *Ardha-Māgadhī*, and it has been falsely Sanskritised into «*adhyuṣṭha*»). This word has now become obsolete in Bengali, but its cognate forms are found in the Bihārī dialects, in Hindī, and in other NIA. (Cf. Hoernle, *Gauḍīan Grammar*, §§ 413-416; Kellogg, *Hindī Grammar*<sup>2</sup>, pp. 159, 161).

Plus ¼ : *সৱা* «*sāwā*, *sāwā*», Oriyā «*sāuyā*=*sāuā*» : < MIA. «*savāa*» = OIA. «*sapāda*». It is an adjective, found in all other NIA. (Hindī adjective «*sawā*» = «*sapāda*», noun «*sawā*» = «*sapādikā*»).

Plus ½ : *সার্ধে* «*sārḥe*», also in Oriyā; = Hindī «*sārḥe*». From OIA. «*sārdha*» > MIA. (*Māgadhī*) «*\*śaḍḍha*», NIA. «*sāḍha*». The absence of the «*-rḥ-*» in Oriyā shows that it is not a native form of it. «*sārḥe*» is an oblique or plural form, < «*\*saḍḍhahi*» : cf. also Gujarātī «*sārā*», the expected singular nominative form of which would have been «*\*sārō*».

A quarter less : *পৌনে* «*pāunē*»; also «*pāunē*» in Oriyā. The source is OIA. «*pādōna*» a quarter less. The alteration of «*-ādō-*» > MIA. «*-āō-*» to «*-āu-*» (cf. p. 351 *supra*), and the presence in the Oriyā form of the dental «*-n-*» instead of the expected cerebral «*-ṇ-*», indicate that the word is not proper Bengali and Oriyā, or Eastern Magadhan. «*pāunē*» is an adjective, qualifying the number following it, which is reduced by a quarter: *পৌনে দুই* «*pāunē dui*» = 2 minus ¼ = 1½; *পৌনে আট* «*pāunē āṭṭha*» = 7½; etc. Its use with *এক* «*eka*» is recent, and is found to denote only the hour, e.g., *পৌনে একটা* «*pāunē ekṭā*» quarter to one. The «*-ē*» in «*pāunē*» seems to be the plural «*-ahi*» (*supra*, p. 724): cf. also Gujarātī «*pōṇō*» ¾, but «*pōṇā bē*» 1¾, with «*-ā*» indicating plural. For ¾, the native Bengali is *তিন পাঁচ* (আ) «*tin-pō(ā)*» = Oriyā «*tini pā*».

535. Adjectives are not declined in Bengali, although in the oldest period we find concord between a subject and its predicate (adjective or verb) in so far as the latter takes up the feminine affix if the former is feminine (see *supra*, p. 721). In the Caryās, however, we find that the numerals



sometimes take case-affixes corresponding to the nouns they qualify: e.g., « *tiniē pāṭē* » (see *supra*, p. 743); « *ēkē śara-sandhānē* » with one aiming of the arrow (Caryā 28); « *daśam-i duāra-ta* » in the tenth door (Caryā 2).

### 536. The Ordinals.

The use of the *tbh.* ordinal forms has been greatly curtailed in Bengali. They are now restricted, to indicate the days of the months, and besides occur in one or two stereotyped expressions. The *ts.* ordinals have entirely replaced them in the « *sādhū-bhāṣā* », and these have found a permanent place in the Colloquial also. As there is no native affix in living use to form ordinals, and as *tbh.* ordinals beyond 32 (the largest number of days for a month) are not much used, the language is helpless in expressing ideas like *84th* or *105th*, and must borrow Skt. words—unfamiliar-looking enough for Bengali—like « *caturaśīti-tama* » and « *pañcaviṃśaty-adhika-śata-tama* ». It has been sought to naturalise the Skt. affix « *-tama* » in Bengali, by using it with *tbh.* numerals (e.g., *চুরাশী-তম* « *curaśī-tamā* » *84th*, *এক-শ-পঁচিশ-তম* « *ēk-śa-pāñśiś-tamā* » *105th*), but such hybrids are extremely artificial, and have not succeeded.

In the Colloquial, however, the *genitive of the cardinal numeral* expresses its ordinal: e.g., *দশের পাতা* « *dāśērṣ pātā* » *the tenth page*. Also the word qualified by the cardinal is put in the genitive in a cumbrous construction in some cases, as follows: the cardinal numeral + the word in the genitive + the word itself: e.g., *ষাট দিনের দিন* « *ṣaṭṭṣ dinērṣ dinṣ* » *the sixtieth day*, *তিন-শ বারের বার* « *tin-śābarērṣ bārṣ* » *the 300th occasion*; etc.

The Forms for the Ordinals occurring in Bengali are:

*First* = NB. *পহেলা* < *পহেলা* « *pāyḍlā* < *pahēla* », MB. OB. « *pahila* » (cf. Caryās 12, 20). The source of this form, which occurs in all NIA., is an OIA. « *pra-tha+ila* », becoming in MIA. « *\*paṭhilla*, « *\*pathilla* » > « *\*paḍhilla*, « *\*pahilla* ». The Skt. « *prathama* » is a blend of « *pra-tama* » (cf. Avestan *fratoma*) and « *pra-tha* » (with ordinal « *-tha* », as in « *catur-tha*, « *ṣaṭ-tha*, « *sapta-tha* »). Equivalents of « *prathama* », as well as of an elaborate « *prathama+ila* » occur in the Prakrits. The Bengali form « *pahila* » is non-Māgadhī in origin, as shown by the absence of cerebralisation.

*Second, Third.* The Bengali words in use are দ্বৈত and ত্রৈত  
 « dōṣṭrā, tēṣṭrā », which are probably new Magadhan formations with the  
 cardinal bases *plus* an affix « sar-ā » (No. 57, p. 700). The OIA. forms  
 were « dvitīya (dvitya) » and « tṛtīya ». The former apparently gave (i) a  
 MIA. « \*dutiyya, \*duijja, \*du(y)ajja », whence we have the Early Bengali  
 দ্বৈত (ŠKK.) > দ্বৈত > দ্বৈত « duāṣṭā > dōyāṣṭā > dōṣṭā » and Hindi « dū »;  
 and (ii) a MIA. « biyya, bijja », whence Marāṭhi and Gujarāṭi « biṭ »;  
 besides (iii) the form « doceca, ducca » (< dvitya), which is not represen-  
 ted in NIA. The latter (i.e. the OIA. « tṛtīya ») through MIA. « \*titiyya,  
 tiijja, \*ti(y)ajja » gave Bengali ত্রৈত (ŠKK.) > ত্রৈত « tiāṣṭā, tēṣṭā », besides  
 Hindi, Marāṭhi and Gujarāṭi « tiṭ ». The change of « -īya » to « ijja, -yajja,  
 -aja » (through a doubling of « -y- », which first took place in Early MIA.),  
 is not Prācya, or Śaurasēni: at least it is certainly non-Magadhan (see  
*supra*, p. 476). In Bengali দ্বৈত, ত্রৈত occur in the ŠKK., but they were  
 replaced by *tas*. « dvitīya, tṛtīya », except in the expressions দ্বৈত-বারে, <  
 ত্রৈত-বারে « dōṣṭā-bārē, tēṣṭā-bārē < bār-iyā » = *a bride-groom for the second  
 and third time.*

*Fourth:* চৌত « cāuṭhā » (by Vowel Harmony চৌত « cāuṭhō »),  
 MB. (ŠKK.) চৌত « cāuṭhā- »; in (Śaurasēni) Apabhraṇśa as written in  
 Bengal, it occurs as « cāuṭhṭha = cauṭṭha » (cf. 'Dōhā-kōṣa' of Saraha,  
 p. 117 of 'Bauddha Gān Ō Dōhā'). In Maithili also we have « cāuṭh ».  
 The cerebral « -ṭh- » indicates that it is derived from a Māgadhī  
 « \*cauṭṭha, caduṭṭha » < « catuṭṭha < caturtha ». Other NIA. speeches  
 show the un-cerebralised « cāuṭh », and Bengali has borrowed this form  
 (চৌত « cāuṭhā ») from Hindōstāni and Marāṭhi, meaning the *fourth part of  
 a sum of money in a transaction, and a fourth of the revenue.*

Upto the ordinal for 4, NB. shows diverse ordinal affixes, « -tha + īla »;  
 -sara; -tha »; *plus* the definitive or adjectival « -ā » affix (No. 6, p. 658).  
 For the ordinals for 5 to 18, we have a generalised OIA. ordinal affix  
 « -ma » + NIA. « -i > -ī > -ikā, -ika ». Thus *fifth* is পাঁচই < \*পাঁচই « pācui  
 < \*pācāi » < « \*pañcamikā, -ikā » for OIA. « pañca-ma »; *sixth* = ছুই  
 < \*ছাছই « chāni < \*chāṣṭi, \*chāwāi » < MIA. « \*chaamia < cha-  
 mikā » ( « chā + ma » for « ṣaṣ-ṭha » of Skt. ); *seventh* = সাতই < \*সাতই



• sātui < \*sātāi > < MIA. • sattamika >, for Skt. • sapta-ma >; so to  
 আঠারই < \*āṭhārāi > āṭhārui < \*āṭhārāi > *eighteenth*, representing a MIA.  
 • \*aṭṭhārasamika > (cf. Pali • aṭṭhārasama > = Skt. • aṣṭādaśā >: the  
 Skt. in the ordinals from *11th* to *19th* simply shifts the accent to the last  
 syllable, • -daśā >, which takes the masculine, feminine and neuter affixes  
 as an adjective). The ordinal • -ma > (> Late MIA • -wā >) has lost its  
 nasalisation in Standard Bengali, except in চৌই • chāui > *sixth*: in Hindōstānī  
 the nasal is retained as • -wā (= wā) >; and the nasal also is found in other  
 NIA., either as • -m- > or as a mere nasalisation of the vowel.

From *19* onwards, the affix is ইয় • -iyā >, contracted to এ • -ē >,  
 an adjectival form (= No. 26, p. 674): thus \*উনিশিয়া, উনিশে • \*uniśiyā  
 > uniśē >, dialectal উনইয়া • unaiśyā > *19th*; so পঁচিশে • pāciśē > *25th*,  
 চল্লিশে • calliśē > *40th*. Indication of the ordinals by a definite affix is  
 exceedingly rare beyond the fourth decade.

---

## CHAPTER IV

### THE PRONOUN

537. The Pronoun in Bengali takes the same case affixes and post-positions as the Noun, but it has, unlike the Noun, a definite oblique form to which the affixes ~~and~~ post-positions are added. This oblique form is generally the old genitive, as in Late MIA. There has also been an extension of the new genitive in «-ra» to form a new oblique or plural in MB. and NB.

#### [A] THE PRONOUN FOR THE FIRST PERSON.

538. OIA. «aham» *I* was extended to «\*aha-ka-m» with the pleonastic «-ka-», and in 'Old Māgadhi' «ahakaṁ» was the word for *I*. Aśvaghoṣa employs it in the 'Old Māgadhi' of his dramas (H. Lüders, 'Bruchstücke,' p. 36). In the Prakrit (Māgadhi) of 'Bhāsa,' the form is «ahakē», with the characteristic Māgadhi affix «-ē» (Snkthankar, 'Studies in Bhāsa,' JAOS., Vol. 40, pp. 248-259); and «ahakē» occurs in the Māgadhi of the Second MIA. period, as in other Skt. dramas, as «hakē, hagē» and «haggē», the last being certainly an emphatic form. The loss of the initial syllable is at least as old as the 3rd century B.C., long before the time of Aśvaghoṣa and Bhāsa. In the eastern inscriptions of Aśoka, we have «hakaṁ»: so that «ahakaṁ, ahakē» in the former writers, and «ahayaṁ < ahakaṁ» in Jaina Ardhamāgadhi would appear to be literary and archaic forms. By 300 A.D., it would appear that two forms were to be found in Māgadhi, «hakaṁ (\*hagaṁ), hakē (hagē)» for the OIA. «aham». Against these, New Bengali shows nothing. But in the Old Bengali of the Caryās, there is the form «hāu» = *I*, apparently for «\*hāu, \*haū», which occurs four times: «tu lō dōmbī, hāu kapālī» *thou, oh, (art) a Dōm woman, (while) I (am) a Kāpālīka* (Caryā 10); «hāu sutēli» *I slept* (18); «hāu nirāsi» *I am 'Sans-Esperance'* (20); and «hāu acchilē (= \*āchilē? \*āchila?)»



*I was* (35). OB. < hāu > can be compared with Gujarātī < hū > and Brajbhākhā < hāu > *I*. Of the two Māgadhi forms < hakañ, hakē >, the former can only give OB. < hāu > (see *supra*, p. 359); while the latter could be represented in OB. only by a form < \*haī, \*hai > (< \*haē < hagē). It is just possible that in Māgadhi Apabhraṇśa, < \*haī > was current, side by side with < \*haū >. The nasalised form, however, ousted the other one, and in the struggle the former was in all likelihood strengthened by Western Apabhraṇśa which also had < haū >. At the same time < \*haī > itself may have influenced the formation of the verb substantive first person — < asmi, \*asāmi > \*asami > \*ahimi > \*ahiwi > \*haiwi > \*hai > hai >, and of the affix < -i > for the first person present of the verb. By initial stress, however, Māg. Ap. < \*hāū > could become < hāu > in OB.

In MB., < hāu > as the old nominative fell out of use, and the old instrumental took its place: but < hāu > seems to have (given or at least influenced) the affix for the first person to the bases for the past and future tenses of the verb in Bengali and Assamese (see *infra*, under Verb: 'Personal Affixes').

539. The OIA. instrumental < mayā > occurs in Second MIA. as < maē, maī >, in (Western) Apabhraṇśa as < maī >. The nasalisation in Apabhraṇśa (also preserved in NIA., *e.g.*, Hindi and Panjābī < maī >, Gujarātī < mē >, Sindhi < mū >) would indicate an influence from the instrumental affix for the noun (< -ēna > < -ē: maī < \*may'ēna = mayā). The OB. equivalent is < maī > (= ? < maī >: the nasalisation can well be omitted in Bengali writing, see *supra* p. 362), which is found in Caryās 16, 18, 27, 29, 30, 35 (thrice), 36, 39; and a contracted form < ma > also occurs (Caryās 10, 13). This is as yet instrumental in OB., being used in the passive construction with the past or future (in < -il-, -ib- >) of a transitive verb: *e.g.*, Caryā 35—

< ēta-kāla hāu acchilē (= āchilē? āchila?) sva-mōhē :

ēbē maī bujbhila                      sadguru-bōhē \*

*For such a long time I was in my own ignorance :*

*Now by me it has been understood through the good master's instruction.*

The nominative «hāu», however, became obsolete, and the instrumental «mai (maī)» assumed its function. The confusion between the active and passive constructions, with gradual disuse of the latter, was both a cause and an effect of the interchange of the instrumental and the nominative, or of the use of the former for the latter (see also pp. 166, 742).

The oblique base «mō» (see below, § 541), with the instrumental «-ō» from the noun gave a new instrumental «mōō, mōē», which is found as early as OB.: cf. Caryā 10, «tōhōra antare mōē ghalili hāḍēri māli» *for thy sake the chaplet of bones has been cast off by me*. This quite early became confused with «mai (maī)»; and «mōē, mai» in MB. occur in a bewildering variety of spellings (see § p. 811) as forms of practically one word.

In NB., this instrumental-nominative is found as মূই «mui» (= Assamese «māi», Oriyā «mū»; it occurred in Bihārī as «mē», but there it is now obsolete). The Bengali মূই «mui» is almost archaic, and then it is found only among certain lower classes in different parts of Bengal: consequently it is considered as a vulgar form now (cf. the phrase তুই-মূই করা «tui-mui kārā» = *use insulting or inferior language*, which does not have the sense of affectionate intimacy indicated by the French «tutoyer»).

540. The ordinary form for *I* is আমি «āmi» which was originally the plural of «hāu, maī». It comes from a common MIA. «āmhē» = OIA. (Vedic) «asmē» for «vayam»: «asmē» > \*āmhē > \*āmbhi, \*āmbhi > \*āmbhi, \*āmbhi»: the NB. equivalent of which ought to be \*অম্ «ām», with loss of final «-i» (see *supra*, § 151: we have «-ām» no doubt as an affix for the verb, where, however, there was influence of other forms: see *infra*, under Verb: ‘Personal Affixes’). In the Caryās, we find «āmhē, āhmē, āhmē (= āmhē), āmbhē»: thus, Caryā 4 «āhmē birā» = Skt. comm. «virō’ham» (properly = «virāḥ vayam»); «āmhē sāṇē dīḥā» = «asmābhiḥ saṁjñayā dṛṣṭam» (Caryā 1); «āhmē dēhū» = *I give*, lit. *we give* (Caryā 19): «āmbhē na jāñāhū» *we know not* (Caryā 22). The form in «-i» is not found in the Caryās, although the MIA. «āmhē» is expected



to give \**āmhi* in OB.: and it is seen, the form in \**-ē* is used both for the nominative and the instrumental. In the ŚKK., we have both *আমি*, *আমি* \**āhmī*, \**-i=āmhi* (only 6 times) and *আমে*, *আমে* \**āhmē*, \**-ē=āmhē* (some 30 times): and there is not the least distinction between the two forms. The group \**-hm=mb* represents an aspirated \**-m-*, an inheritance from MIA. which continued down to Early MB. times, to lose its aspiration by the 16th century. Oṛiyā has only the \**-ē* form, \**āmbhē*. The \**-ē* form would seem to represent the Late MIA. instrumental: \**asmābbih* > \**amhabī* > \**āmhē*, \**āmbhē*; and the \**-i* form, the original nominative (see *supra*, p. 309). But already from before OB. times, there was a confusion between them, with the result that \**-ē* practically ousted the \**-i* in OB. and MB., (as we can see from OB., and from the preponderance of \**-ē* forms in the ŚKK., as well as from Oṛiyā), but later this \**-ē* itself seems to have become \**-i* or to give place to the latter.

The transference of \**āmhi*, \**āmhē* from plural to singular took place in OB., as we can see from the Caryās. It became identical with \**māi*, \**mui*, \**mōē* etc. in Early MB. Doubtless, the plural when first used for the singular was characteristic of polite or formal speech: cf. Oṛiyā \**mū* inferior, and \**āmbhē* polite, formal, and respectful. The old plural sense of \**āmi* is still preserved in Assamese, where \**āmi* always = *we*, never = *I*. Cf. also Western Hindi \**haū* (Brajbhākhā), \**maī* (Hindōstānī and Brajbhākhā), plural \**ham*; Gujarātī \**hū*, plural \**amē*; Panjābī \**maī*, plural \**as(s)ī*; Marāṭhī \**mī*, plural \**āmhi*: which still continue faithful to the OIA. in point of number. The Bihārī dialects have now made the original singular obsolete, the plural \**ham* being the one used for *I*. The proper plural use of \**āmi* however is occasionally found in MB., as late as the 16th century: e.g., in the 'Caitanya-Bhāgavata' of Vṛndāvana-dāsa, we find forms like *আমি দুই পাতকীর* \**āmi dui pātākīrā* of us two sinners, *আমার উদ্ধারে* \**āmārā uddhārē* through our salvation, *আমি দ্রোহ কৈলু* \**āmi drōhā kailū* we did offence (p. 258, ed. Atul Kṛṣṇa Gōswāmī).

541. *মুই*, *আমি* \**mui*, \**āmi* are the nominative forms of Bengali, and their history is given above. There are the oblique forms *মে* \**mō-*

and **আমা** « *āmā* », to which the inflections and post-positions (accusative-dative « *-ē* », « *-rē* », « *-kē* », genitive « *-rā* », locative « *-tē* », instrumental « *dwārā*, *diyā* » etc.) are added to form the various cases. « *mō* » is the OIA. genitive « *mama* », which (through Māgadhī Apabhraṣṭa and OB. « *\*maṣā* ») occurs already in OB. Another form is « *ma* », found in OB. side by side with « *mō* ». Following the oblique forms of the other pronouns (see *infra*) and the old genitive of the nouns, which optionally preserve the « *-ha* » (see *supra*, p. 752), « *mō* » took up the « *-ha* » from OB. times, and was thus extended to « *mō-ha* ». Inflected forms on the basis of this « *mō* » (*ma*-), *mō-ha* » oblique in the Caryās are: « *mō-ē* » instrumental (Caryā 10); « *mō-ra* » (Caryās 20, 33, 49), « *mōhō-ra* » (Caryā 20) = genitive forms qualifying masculine or neuter, and « *mō-ri* » = genitive qualifying feminine noun (Caryā 36); and « *mōha-kakhu*, *ma-kū* = *mō-kū* » dative (Caryā 35). In MB., beside **মো** « *mō* », the extended forms of this oblique base are **মোহ**, **মোহো**, **মহ**, **মহো** « *mōhā*-, *mōhō*-, *māhā*-, *māhō*-. The instrumental form « *mō-ē* » occurs in the spellings **মোএ**, **মোএঁ**, **মোঞ**, **মোঞে**, **মোঞ**, **মোঞে**, **মুঞ**, **মুঁ**, **মুঞি**, **মোই** « *mōē*, *mōē*, *mōñā*, *mōñē*, *mōñā*, *mōñi*, *muñi*, *mūhi*, *muyī*, *mōi*, » etc., which are all used for the instrumental-nominative = **মুই**, **মই** « *mui*, *māi* » (see *supra*, p. 809). The inflected forms as usual are **মোর** ( **মোহর** ), **মোকে**, **মোতে** « *mō-rā* (*mōhā-rā*), *mō-kē*, *mō-tē* » etc. Besides there is the locative oblique in « *-ē* < *-hi* » ( **মোহি**, **মোএ** *mōhi*, *mōē* > **মোর** *mōyā*, **মোঞ** *mōñā* etc.), which is used in MB. for the dative-accusative. The original genitive use of « *mō* » seems to have existed in OB. (cf. « *tō* < *tava* » below). In eMB., « *mō* », although the oblique base, itself came to be used for the nominative, through confusion with « *mōē* » and « *mā*, *mu* < *māi*, *mui* ».

The form **আমা**, **আম** « *āhmā* = *āmhā* » (as in the ŚKK.), *āmā* » represents the OIA. base « *asma* », in MIA. « *amba* ». It was strengthened by an « *-ā* », apparently through the influence of the « *-ā*, « *-āha* » of the noun. In Oriyā, it occurs as « *āmbhā* », as in « *āmbhā-rā*, « *āmbhā-ku* » etc. That the extension of « *āsmā* » > « *āmhā* » > « *\*āmhā*, « *\*āmā* » to « *āmhā*-, « *āmā* » is due to a genitive « *-ā* » is seen from the



frequent use of the base « āmhā », without the genitival « -rā », for the genitive in the ŚKK. and other MB. works; and the fact that post-positions are added direct to the « āmhā » base, as if to the genitive, is to be noted.

542. With the old plural « āmhē, āmhi » becoming first honorific and then ordinary singular (the honorific singular sense still obtains in Oriyā at the present day), new plurals were formed, as in the case of the noun, from the Early MB. period, either by adding nouns of multitude like « sāmā (sābā), sākālā », or by extending the strong form of the genitive in « -rā »: thus, in the ŚKK., we have আঁহে সন্নে « āmhē sāmhe », beside আঁহারা « āmhārā » (see *supra*, p. 735); in the 'Caitanya Bhāgavata,' 16th century, nominative মূই-সকল « mui-sākālā », আমি-সব « āmi-sābā », oblique, আমা-সব « āmā-sābā »; beside মোরা, আমরা « mōrā, āmrā ». For the genitive, the use of « -dēṛā » seems to have been established by the end of the 15th century (*vide supra*, p. 731). The « -rā » and « -digā, -dēṛā » affixes are in common use in NB. at present, but « -sākālā, -sābā » are also occasionally found in NB. But « -gāṇā, -gulā, sāmūhā » and the rest do not occur. The position for Bengali is thus the following:

	Singular Forms.		Plural Forms.	
	Old Singular = vulgar, archaic, dialectal.	Old Plural > Honorific Singular > Ordinary Singular.	Regular Plural from Old Singular = poetic, dialectal.	New Double Plural.
Nominative	মূই mui	আমি āmi	মোরা mō-rā	আমরা āmrā-rā (+ সব sābā etc.)
Oblique	মো mō-	আমা āmā-	মোদিগ mō-digā- মোদের mō-dēṛā-	আমদিগ āmā-digā- আমদের āmā-dēṛā-

Double plural forms are found elsewhere in NIA., retaining the

honorific sense where the original singular is preserved and the original plural continues to be used as a plural: thus—

	Old Singular.	Old Plural.	Double Plural (Honorific).
Bengali	মুই mui (vulgar)	আমি āmi (sg.)	মোরা, আমরা mōrā, āmārā
Assamese	মাই (sg.)	আমি (pl.)	আম-লোক
Oṛiyā	mu, mū (vulgar)	āmbhē (sg.)	āmbhē-mānē
Magahī	[lost]	ham (sg.)	ham-anī, ham-ar-nī
Maithilī	मैं (obsolete)	ham (sg.)	ham-sabb, hamrā-sabb
Bhōjpurīyā	मैं (obsolete)	ham (sg.)	hamanī-kā, ham-ar-an
[Khaskurā]	ma (sg.)	hāmi (pl.)	hāmi-haru]

In Western Hindī, Panjābī, Sindhī, and Marāṭhī, as well as Sinhalese, where the old singular and plural forms are preserved intact, there is no room for the double plural: the Hindōstānī « ham-lōg » *we*, with a frequent enough use of « ham » = Bengali « āmi » for the singular, is due unquestionably to Eastern influence.

543. An oblique form like « majh-, mujh- » (as in Marāṭhī, Rājasthānī-Gujarātī and W. Hindī) is not found in Bengali and in other Magadhan speeches: Māgadhi Apabhraṇśa apparently did not possess a form like « majjhaṁ, majjhu » (as in Prakrit and W. Apabhraṇśa), which is found in the ablative as well as in the genitive, but which originated from the OIA. locative « mahyam ». But in the Brajabuli dialect (see *supra*, pp. 103-104) we commonly find a genitive form मज्जु « mājhu » (occasionally also oblique), which is a Western Apabhraṇśa imposition on Bengali, doubtless in the formative period of the language (cf. *supra*, pp. 113-116), at a time when « majh- < majjhu, majjhaṁ » had not altered its vowel to « -u- », as in « mujh » in W. Hindī (on the analogy of « tubhyam » > \*tuhyam > तुज्जभां, तुज्जहु > तुज्ह »). The form मज्जु « mājhu » now and then appears in Vaiṣṇava poetry written in pure Bengali, and that is due to imitation of the Brajabuli style. The MIA. genitive force of « majjhaṁ » is still retained in the Marāṭhī « mājhā, mājhī, mājhē ».

It is a remarkable fact that the genitive of the personal pronoun throughout a great part of the NIA. area should show the adjectival



form with the « -ra (< kēra, kara, kāra) » affix, both in the first and second persons : *e.g.*, in addition to the Magadhan speeches, we have E. Hindi « mōr, hamār (tōr, tohār) », W. Hindi « mērā, mērau, mēri ; hamārā, hamārau, hamāri », Panjābi « mērā, mēri » Gujarati « mārō, mārī, mārū ; amārō, amārī, amārū », Rājasthāni « mhārō, amhārō » etc.; also in the Pabārī languages ; and in the Gipsy dialects outside India. These are based on Western Apabhraṃśa forms like « mahāra, amhāra » (cf. Pischel. 'Gramm. der Pkt-Sprachen' § 434; Jules Bloch, 'Langue Marathe' § 210; Beames, Comp. Gramm., II, p. 312).

In the Bengali poetic diction, the form মম « māmā » for the genitive is quite common. This certainly is to be regarded as a MIA. form preserved by literary tradition and strengthened by the Skt. « mama ».

**544.** The rage for Sankritising Bengali which was in vogue late in the 18th and early in the 19th centuries when the speech was under the guardianship of the *pandits*, finds its expression in the curious form অম্মদাদি « āsmāddādi » *we*, occurring commonly in the genitive অম্মদাদির « āsmāddādir » *our*, pronounced [oʃʃdadir], in which the Skt. base is made to oust the *lōk.* one. In this artificial 'restoration' of the genuine Bengali আমাদের « āmāder » *we*, the source of « -dēr » as « -ādi » has instinctively been hit upon.

**545.** Typical Dialectal Forms for the First Personal Pronoun in New Bengali (*all* forms cannot be given : only some characteristic ones have been introduced) :

## S.W. Bengali.

## West Rāḍha.

Nom. মূই mui—মোরমেনে mōrṣ-mēnē, মোরে mōnnē, আমারে āmānē	Nom. মূই mui—মুইরা « mui-rā »
Gen. মোর mō-rṣ—মোরমনকার mōrṣ- mānṣ-kārṣ, মোরমেনকার mōrṣ-mēnṣ- kārṣ, মোরেকার mōnnē-kārṣ	Gen. মোর, মর mōhā-rṣ, mākā-rṣ— মোরের mō-dērṣ
Dat. মোকে mō-kē—আমারেকে āmānnēkē	Dat. মোকে mō-kē—মোরের mō-dērṣ
Other Cases—মোদিয়া mō-diyā, মোটিহ mō-ṭhinu, etc.	Other Cases—মোদিয়া mō-diyā, মোহ'তে mō-hōtē, মোতে mō-tē, মোদেরে mō-dērṣ-tē, etc.

East Rājha (Standard Colloquial),  
also Varēndra (North Central).

East North Bengali  
(Dinajpur).

Nom. আমি āmi—আমরা āmā-rā	No. আমি hāmi—হামরা hāmā-rā
Gen. আমার āmā-rā—আমাদের āmā-dērā	Gen. হামার hāmā-rā—হামাদের hāmā-dērā
Dat. আমাকে āmā-kē, আমার āmā-y < āmā-ē—আমাদের āmā-dērā, আমাদিকে āmā-di-kē	Dat. হামাক, হামাকে hāmā-kā, hāmā- kē—(plural, same as genitive).
Loc. আমার āmā-y, আমাতে āmā-tē, —আমাদিগেতে āmā-digē-tē, আমা- দেরতে, āmā-dērā-tē, etc., etc.	

North Bengali.

Nom. মূই mui, মই māi, মৌ mōi, আমি hāmi	হামা hāmā, হামরা hāmā-rā, হামাঙলা hāmā-gulā
Gen. মোর mō-rā, হামার hāmā-rā	হামাঙলার hāmā-gulā-rā
Dat. মোক mō-kā, হামাক hāmā-kā	হামাক hāmā-kā
Other Oblique: মো mō-, মোর mō-rā-, হামা hāmā- (Loc. মৌ mōi-tā, হামাত hāmā-tā)	—হামাঙলা hāmā-gulā-

West and South-West Vanga.

South-East Vanga (Chittagong).

Nom. মূই, আমি mui, āmi—মোরা mō-rā, আমরা āmā-rā	Nom. অঁই āi—অঁওরা āō-rā, অঁররা āy-rā, অঁরা ā-rā
Gen. মোর mō-rā, মর mā-rā, আমার āmā-rā—আমরার āmārā-rā, মোরগে mōrā-gō, আমাগে āmā-gō	Gen. অঁরর āy-rā, অঁর ā-rā— অঁওরার āō-rā-rā, অঁররার āy-rā-rā
Dat. আমারে āmā-r-ē—আমরারে āmārā-r-ē	Dat. অঁররে āy-r-ē, অঁরে ā-r-ē— অঁওরারে āō-rā-r-ē, অঁররারে āy-rā-r-ē

The origin of the above dialectal forms is plain in every case. The S. W. Bengali মোরে « mōnnē » is contracted from « \*mō-mānē », and « \*āmā-



mānē-kārṣ > gives আমাৱেকাৱ < āmānnēkārṣ >. Contiguity with Maithili is seen plainly in the forms with initial < h- > in North Bengali (< asma- > amha- > \*hamma- > hām, ham- >, as opposed to the normal development in Bengali < amha- > āmh- > ām- >). The < -m- > has been reduced to a simple nasalisation in Chittagong, through an intermediate < -ṃ- > which is also heard as < -ō-, -o- >.

[B] THE PRONOUN FOR THE SECOND PERSON.

546. The Forms for the Second Person (in the Standard Speech) are—

	Old Singular (= New Singular, contemptuous or affectionate, for juniors and familiars).	Old Plural (> New Singular, inferior and familiar).	New Plurals.	
			Inferior and contemptuous.	Ordinary and familiar.
Nominative	তুই tui	তুমি tumi	তোরা tō-rā	তোমরা tōmṛ-rā (+ সব, সকল sābṣ, sākālṣ etc.)
Oblique	তো tō-	তোমা tōmā-	তোদিগ tō-digā- তোদের tō-dērṣ	তোমদিগ tōmā-digā-, তোমাদের tōmā-dērṣ

The above forms present an exact parallel with those for the first person: only the old singular (with its new plural in < -rā >) is used freely, in all its forms, to express familiarity or contempt, by all classes in society: unlike < mui, mō- >, it has not become archaic, or confined to the lower classes only.

547. OIA. < tvam > *thou* gave the MIA. < tuṃ >, in addition to other forms. This < tuṃ > seems to be the source of the OB. < tu >, which occurs also (through contamination with the oblique) as < tō >. Oriyā has preserved this as < tu >: Early Maithili and Eastern and Western Hindi as < tū >. It is quite possible, however, that the OIA. original of the (Magadhan and Śaurasēnī) NIA. < tu, tū >, without nasalisation (as opposed to the nasalised forms like the Marāṭhī < tū >, Gujarātī < tū >, Rājasthānī < tū >, Panjābī and Sindhī < tū >) was a form like < \*tū >.

as in Avestan (beside «tvəm»), instead of the Vedic and Sanskrit «tvam» (=tū+am).

In OB., «tu, tō» are the nominative forms, and they are found in the Caryās either independently (as *e.g.*, Caryā 18, «Kānhē gāi, tu Kāma-caṇḍālī» *Kṛṣṇa sings, thou art a 'Karma-caṇḍālikā'*; Caryā 6, «suṇa hari[ṇ]ā tō» *hear thou, O Deer*; Caryā 41, «jāi tō mūḍhā acehasi, puceha-tu sadguru pāwa» *if thou art ignorant, ask thou at the feet of the good master*), or loosely agglutinated with the verb in the imperative (*e.g.*, «puceha-tu» *ask thou*, in Caryās 5, 41; «bāha-tu» *row thou*, Caryā 8; «bujha-tu» *comprehend thou*, Caryā 32).

548. This OB. nominative form «tu» has become obsolete in MB. and NB. The form तू «tui», from the old instrumental, corresponding to «mui» of the first person, has taken its place. The typical representative of OIA. «tvayā» in MIA. is «taē»; in the Apabhraṃśa the word shows nasalisation, which is due to the influence of the noun (taī < \*tvay'ēna=tvayā). In the Caryās, we find «tāi = taī», which still retains its old case-value: *e.g.*, «tāi binu» (=tvayā vinā: Caryā 4); «tāi biṭāliu» (=tvayā viṭālitam: Caryā 13). There is also in OB. a new instrumental formation on the basis of the oblique «tō» (tō-ē = tō-ē), which become confused with the original «taī, tuī» in Early MB. The OB. «tāi» occurs in Assamese as «tāi»: in the change of the vowel to «u» in Bengali «tui», there was in all likelihood the influence of the oblique «tō».

549. The oblique तू «tō», the nucleus to which the case terminations and post-positions are added, represents the OIA. genitive «tava». In OB., «tō» is found in its proper genitive sense: «tō muha» *thy face* (Caryā 4); «kin tō mantē, kin tō tantē, kin tō rē jhāṇa-bakhānē» *what is (the good) of thy spells, thy scriptures, and thy meditations and expoundings* (Caryā 34: «kin=kim» is a Sanskritism or Prakritism). It is found as accusative-dative (an extension of the genitive) in «tō puchami» *I ask thee* (Caryā 10). This form is also extended to «tō-ha-, tō-hō-» (cf. «mō-ha», p. 811, *supra*): genitive «tōhō-ra» (Caryā 10), «tōhāra» (Caryā 29), genitive feminine «tōhōri» (Caryās 10, 18), «tōhauri = tōhōri»





Bengali form represents a combination of the MIA. nominative (=tumbhē) and instrumental (=\*tumhahi, tumhēhi). The instrumental use occurs in OB.: *e.g.*, « tumbhē hōiba » = « yuṣmābhir bhavitavyam » (Caryā 5), « tumbhē jāiba » (« jāibē » in printed edition) = « yuṣmābhir yātavyam » (Caryā 23). In Oṛiyā the form is « tumbhē », in Assamese « tumi », = plural.

For the oblique, we have the base তোমা « tōmā- » (Early MB. তোমা « tōmhā- »), paralleling আমা « āmā- », which is derived from the OIA. plural base « yuṣma- ». The forms তুমি, তোম্কে, তুম্হে, তোমা, তোমা « tumi, tōmhē, tumhē, tōmā-, tōmhā- » quite early, in the First MIA. period had taken up the « t- » from the singular « tvam, tvayā, tubhyam » etc., so that we have « tumbhē, tumba- » instead of « \*yumbhē, \*yumba ».

The Aśōkan eastern form « tuphē » (= ? tupphē ? tumpbhē ) is not represented in NIA., any more than « aphē » (= ? amphē ? apphē, =asmē).

551. Through the influence of Śaurasēni Apabhraṇśa in the OB. and Early MB. periods, and of the Brajabuli dialect, we have some peculiar Western forms in the language of Vaiṣṇava lyrical poetry: *e.g.*, তুহু « tuhū » thou (= Western Apabhraṇśa « tuhū », derived by Pischel from « \*tva-kā-m », 'Gramm. der Pkt.-Sprachen,' p. 296; but it may properly be an emphatic form, « tu » + particle « hū, hu », cf. Eastern Hindi and Bihārī, as well as Brajabuli, « hama-hū » *we also*, « saba-hū » *everybody*); তুয়া « tuā » thy (= literary i.e. early Maithilī « tua »: MIA. « tuva », Western Ap. « tuha »: OIA. « tava »); তুজ « tujhā » thy (Western Ap. « tujjhu », Second MIA. « tujjha »: < « \*tubhyam » = OIA. « tubhyam », cf. « mahyam »); and besides, the extended base « tō-ha, tu-ha » is also much used through the example of Maithilī or Brajabuli (as well as Brajbhākhā), in Vaiṣṇava lyrics; *e.g.*, তোহে, তুহে, তোয় « tōhē, tuhē, tōy » accusative, locative and dative; তোহারি, তুহারি « tōhāri, tuhāri » genitive.

552. In the Magadhan speeches, we have the following developments of the old forms for the second personal pronoun, paralleling those for the first personal pronoun:

	Old Singular	Old Plural	New Plural
Bengali	তুই tui	তুমি tumi (sg.)	তোরা, তোমরা tōrā, tōmārā
Assamese	tāi	tumi (pl.)	tā-hātē, tōmā-lōkē (hon. pl.)



	Old Singular	Old Plural	New Plural
Oṛiyā	tu	tumbhē (respectful sg.)	tumbhē-mānē (hon. pl.)
Magahī	(obsolete)	tā, tō (sg.)	tōh-anī tōh-ara-nī,
Maithilī	tū (obsolete)	tō, tōh (sg.)	tō(h)-sabh, tōharā-sabh
Bhōjpuriyā	tē (archaic)	tā (sg.)	tōha-nī(-kā), tōh-ar-au
[Khaskurā	ta (sg.)	timi (pl.)	timi-haru]
[Hiadōstāni	tū, tāi	tum (pl.)	tum-lōg]

## 553. Typical Dialectal Forms for the Second Personal Pronoun :

S. -W. Bengali

West Rāḍha

Varendra

Nom. তুই tui, তুমি tumi —তোরে tōnnē, তোমারে tōmānnē	Nom. তুই tūi—তোরা tō-rā, তুমরা tumā-rā, তোমরা tōmā-rā	Nom. তুই tui— তমরা tāmā-rāh
Gen. তর tā-rā—তমার tāmā-rā, তাদের tā-dērā, তোদের tōnnērā	Gen. তোঁর tō-rā—তোমার tōmā-rā, তোদের tō-dērā, তোঁদের tōrā-dērā, তোঁগের tō-gō-rā	Gen. তোঁর tō-rā— তমার tāmā-rā তুমার tumā-ghārā

North Bengali

West &amp; S.-W. Vagga

East Vagga  
(Chittagong)

Nom. তুই tui—তুমরা tumā-rā	Nom. তর tāy, তুমি tumi —তোরা tō-rā, তোমরা tōmā-rā	Nom. তুই tui, তুই* tui < tumi—তোরা tō-rā, তোঁরা tō-rā < tōmā-rā
Gen. তোঁর tō-rā—তমার tāmā-rā, তুমার tumā-rā, তুমার tumā-ghārā.	Gen. তোঁর tō-rā, তর tā-rā —তোঁর tō-rā-rā, তোঁমার tōmā-rā, তোঁমার tōmā-rā-rā, তোঁ-গো tō-rā-gō	Gen. তোঁর tō-rā—তোঁর tō-rā < tōmā-rā, etc.

## [C] THE PRONOUN FOR THE THIRD PERSON.

The Pronoun for the Third Person (or) 'General Demonstrative': সে, তাহা nominative • sē •, oblique • tā(hā)- •, etc.

554. The Typical Bengali forms as in the Standard Colloquial and the \*sādhū-bhāṣā\* are the following :

	Singular		Plural	
	Old Singular.	Old Plural > Honorific Singular	New Plural > Ordinary	Double Plural = Honorific
Nominative	সে sē, [neuter তা(হা) tā(hā)]	তিনি tini; তেই tēhā, তিই tihā (archaic)	ত(হা)রা tā(hā)rā (+ সব, সকল sabb sākālā etc.) ; সে- সব sē+sabb etc.	তা(হা)রা tā(hā)rā (+ সব, সকল sabb sākālā, etc.)
Oblique	তাহা tāhā-, তা tā-	তাহা tāhā-, তানি tānā-, তেনা tenā-, তা tā-	তা(হা)দিগ tā(hā)- digā-, তাহাদের tā(hā)dērā	তা(হা)দিগ tā(hā)- digā-, তা(হা)দের tā(hā)dērā

555. The OIA. nominative of the pronoun for the third person (the base of which was \*ta-) was \*sa, saḥ\*. In Māgadhi Prakrit it became \*sē\*, and the Māgadhi Apabhraṇṣa form was in all likelihood \*śi\*, which seems to be preserved in the Assamese সি \*si\* (for শি \*śi\*), pronounced [xi] or [çi]. But in Bengali, and in Oṛiyā, and also in the Bihārī group, the pronoun occurs in the nominative as সে \*sē (śē)\* instead of the expected \*śi (śi)\*. The \*-ē\* vowel may be due to an extended form \*śa-ka-h\* (cf. ahakarṇ = aham) : which would give in Māgadhi \*śakē > śagē > śaē > śaī > sē\* (cf. pp. 741-742, *supra*) ; or it may be due to the influence of the instrumental form \*tē\* (< tēna). The OIA. feminine \*sā\* seems to have continued (as \*śā\*) in Māgadhi down to the Apabhraṇṣa period, when it fell into disuse, and the masculine came to be used for the feminine. Already during the Second MIA. stage, the masculine \*śē\* came to be employed for the neuter (like the neuter affix \*-am > -am\* of the noun taking up the masculine \*-ē < -aḥ\* affix : *supra*, p. 622) (Pischel 'Grammatik der Pkt.-Sprachen,' § 423). In Bengali, as in other Magadhan, there is as a consequence no distinction of gender, \*sē (śē)\* being used for masculine, and feminine and also for neuter. For the neuter nominative, however, the form তা(হা) \*tā(hā)\* is



more common. It is really the oblique extended to the accusative and then to the nominative; the accusative employ we find in the Caryās: e.g., « tā dēkhi » *having seen that* (7), « tā śuni » *having heard that* (16).

556. The oblique singular তা(হা) « tā(hā)- » is really the genitive in « -ā, -āha » discussed above, § 502 (pp. 751-752). The genitival use « -ā, -āha » occurred in OB., as we can see from the Caryās. The oblique « tāh-ā » is by extension of « tāha » with the definitive « -ā » affix. By adding the usual affixes and post-positions, we have forms like genitive তাহা, তাহার, তাহের, তাৰ « tāhā-rā, tāhā-rā, tāh-ērā, tā-kā », accusative and locative (or new oblique) তাহে, তার « tāh-ē > tāyā », locative তাহাতে « tā(hā)-tē », instrumental তাহা-দিয়া, -দ্বারা « tā(hā)-diyā, -dwārā », etc.

557. The OIA. plural forms (masculine « tē », feminine « tāḥ » neuter « tāni ») seem to have continued down to Second MIA. (respectively as « tē; tāo; tāṇi, tāīm »). But they have not been inherited in NIA. Already in the Second MIA. stage, the nominative forms « sē, śē » of the singular were extended to the plural, in Ardha-māgadhī and Māgadhī (Pischel, § 423). In OB. we find « tē » in Caryā 22: « jē sacarācara tiśa bhamanti, tē ajarāmara kimpī na honti » *those (Yōgis) who wander through all the world and also through heaven, they do not become in the least ageless and deathless: this « tē » may be a Sanskritism; but it can well be a nominative plural, derived from an instrumental « \*tēhi, tēhi ».* A similar nominative « tē » occurs in Eastern Hindi and Western Hindi. This « tē » (or « tē » ?) nominative of Old Bengali seems to have lingered on till Early Middle Bengali, and then it was dropped from the speech, new forms taking its place: we have one instance in ŚKK., p. 313: গোপীকুলের তোমহে কৈলৈ অপমান....., তে সঙ্গে চোরায়িল বাণী তোর কান্ধ « gōpī-kulērā tōmhē kailē āpamānā, tē sāmḥē cōrāyila bāṣī tōrā Kānhā » *you have insulted the Gōpīs, they have stolen your flute, O Kṛṣṇa.*

The expected form of the OIA. « tē » in Māgadhī Apabhraṁśa and in OB. would be « \*ti », and in an emphatic position it might remain as « tē ». Side by side with « śē, tē », the instrumental and the genitive plural were undoubtedly used for the nominative in Māgadhī Apabhraṁśa

and in OB. (\*tāhi, \*tāhi, \*tāhī; \*tāṇa[m], \*tāhā; \*tān-i), paralleling the usage for the noun.

558. MB. and NB. honorific singular forms come from the plural instrumental and genitive of Apabhraṃśa and OB. In MB., the honorific nominative is তেহ্, তিহ্ « tēhā, tihā », which palpably receives its « ē, i » vowel from the instrumental, and its nasalisation may be due to the influence of the genitive. It is not impossible, moreover, that the « -ē- » of the OIA. genitive « tēsām » should have persisted through some dialectal undercurrent here. The forms তেহ্, তিহ্, or তেহ্ (besides তেহে) « tēhā, tihā, tēha, tēhō » were continued down to the middle of the 19th century, in the « sādhū-bhāṣā ». The ŚKK. has registered তেহ্ « tēhē » is one place (p. 19), and তেহেঁ « tēhō » in another (p. 67): in the ŚKK., the honorific sense is not strong, and we find that the ordinary সে « sē » is joined to তেহেঁ « tēhō » merely as an emphatic form. (e.g., চৌদ চৌ যুগ আয়ু লঙ্কার রাবণ । তেহেঁ সে বজ্রিআ গেল শীতার কারণ ॥ « cāudā cāu jugā āyu Lāṅkāṛā Rāvaṇā, tēhō sē mājiā gēlā Śītārā kāraṇā » *fourteen four-yugas his life, Rāvaṇa of Lāṅkā: even he went to perdition through the reason of Śītā*). The form now actually in use is তিনি « tini », both in the colloquial and in literature, which is not met with except in Late MB.: this « tini » is from an earlier colloquial form « \*tēni » (cf. honorific oblique base তেনা « tēnā- », beside তি « tī », in the Standard Colloquial area: « ē > i » by Vowel Harmony), which looks like a blend of the genitive and instrumental. Assamese has preserved the old « tihā, tēhā » in the form of « tēo ».

The oblique তিহ্ « tihā- » is easily explained. The persistence of the « -h- » may be due to the influence in singular তাহা « tāhā- ». There has been a great deal of cross influence in the development of these forms. There are in the Standard Colloquial area the dialectal obliques তেনা « tēnā- » and তানা « tānā- » (the latter more of a 'folk' form), which retain the vocalism of the instrumental and genitive, and the fall « -n- » of the nominative form « tini » and the genitive-oblique « tānā ». The genitival use of তনি « tānā » (< « tāṇa = tēsām »: see *supra*, p. 306) is found in East Bengali: cf. also Oṛiyā « tāṅ-kā(rā) » (= « tēsām-kara-, -kṛta »), and Maithili « tan-i-k »,



Bhōjpurīyā « tinh- kē ». The full « -n », or nasalisation, from the genitive plural, came to be associated with the plural (and honorific) base, and hence we find in MB. the honorific genitive তাহান « tāhā-nā » ( < tāha- ), Early Oṛiyā « tāhā-nā ». Bengali তাঁ « tā- » can be either from « tāna », or it is merely a new formation by nasalising the singular « tā- = tāha ».

With the Bengali « tēhā-, tēnā-, tini, tā(hā)- » etc. are to be compared the Maithili « tan-ik », Magahi « tinh- », Bhōjpurīyā « tinh »; and Awadhī ten(h) », Bagheli « tenh », Chattisgarh « tin »; Western Hindi tin(h) » — plural or honorific forms, all with similar genitival « -n- ».

559. The old plural becoming singular honorific, new plurals were formed on the basis of their respective genitives in « -ra ». These came in use during the Early MB. period (see *supra*, pp. 734-736).

560. Early Bengali preserves relics of some of the older case forms. The instrumental « tēna > tē » is preserved in the sense of *therefore, consequently* in the ŚKK., as তে, তে « tē, tē » : e.g., p. 38, করলো বড় ব্রত আর জরমত, তে বা কুখিনী মোঞে « kārālō khaṇḍā-brātā āra jārāmā-tā, tē bā duḥkhinī mōḥē » in my previous birth I did an unfulfilled penance, may be for that I am miserable (now); p. 218, বুলি তে আতি বতনে « buli tē āti jātanē » for that I say with great care; p. 367, বাপ নন্দদোষ মাঅ বশোদা, তে কুসী বানী আদ্বারে « bāpā Nandā-ghōṣā, māā Yāsōdā, tē tumbī māmi āmbārē » (my) father is N., my mother Y., therefore you are my maternal uncle's wife; p. 359, গেছান বাণে ছেদিলে মদন বাণ, তে আর না ভোলো তোদ্বার বোবন « gēṣānā-bāṇē chēdilō Madānā-bāṇā, tē āra nā bhōlō (=bhōlō) tōmbhārā jāubānā » with the arrow of wisdom I have shattered the arrow of Love, therefore I do not forget myself through your youth. There is also the phrase তে কারণে « tē kāraṇē » = « tēna kāraṇēna » which occurs more than ten times; and an extension of « tē » occurs as তেএ, তেএ, « tēē, tēē » e.g., এই তোকে দেখিএ রূপে । তেএ মোর বাড়িল আশে « ēbē tōkē dēkhiē rūpāṣē, tēē mōrā bāṛhila āṣē » I see thee now to be so beautiful, therefore my hope has increased (p. 45); যেই দধি গুথ ঘৃত ভাঙত আছএ । পসার দাজিতে তেএ কাহ ক জ্বাএ « jēi dādhi dudhā ghṛtā bhāṇḍā-tā āchāē, pāsārā sājitē tēē Kānhu-kā jāē » the curds, milk and ghee that remain in the pots, K. should make a display for sale with that (p. 179); and as তেউ « tē-ū » ( < tēna + MIA.

hu = khalu) (p. 29). In later MB., this instrumental is very common as a conjunction, in the form তহি *tāhi* > *therefore* (= *tēna + hi*). The form *tāhi* > is archaic and poetic now, and তে কারণে, তে কারণ *tē-kārāṇē, tē-kārāṇā* > also occur in NB. poetry.

The locative in *-hī* >, *tāhī* > (see *supra*, pp. 745-746) occurs in OB. : e.g., *tāhī caḍi nācāi* > *they dance, mounted on that* (Caryā 10). Its use became obsolete as a locative in MB., where it was adopted as noun of place = *there*, to which the case affixes were added. The ŚKK. has যমুনার তীরে কদমতরু তলে তহি বসি কাহু বাএ বাশে *Yāmunārā tirē kādāmā-tāru-tālē tāhī bāsi Kāmbā bāē bāśē* > *by the bank of Yāmunā, under the Kādamba tree, sitting there K. plays on the bamboo flute* (p. 306), beside মৃগমদ কুচযুগ গগন মাঝার। তহিত নক্ষত্রগণ গজমুতীহার॥ *mṛgā-mādā kuca-yugā gāgānā-mājhārā, tāhī-tā nākṣātrā-gaṇā gajā-mutī-hārā* > *your two breasts (smeared) with musk-paste is the vault of the sky, the necklace of elephant (big) pearls is the mass of stars thereon* (p. 154), where *tāhī-tā* > has a pleonastic locative *-tā* >. In ordinary MB., তহির, তহির *tāhī-rā, tāhī-rā* > are not rare, meaning both of *that place* and *his, its*. Oṛiyā also possess *tāhī-rā* > beside *tā(hā)-rā* > as genitive of *sē* >. In Early MB. and in Late MB., the form তথি, তথী *tāthi, tāthī* > *there* (< locative of MIA. *tattha* > = OIA. *tatra* >) is similarly used : তথির *tāthī-rā* > *of him*, তথিত *tāthi-tā* > *in him*, etc.

561. The distinction of gender is now lost in all Magadhi, but a feminine form for the third personal pronoun has been preserved in Assamese and in South-Eastern Bengali (Chittagong) : and traces might still exist in the other dialects. Thus in Assamese beside the masculine *si* >, plural *si-hātē* >, there is a feminine *tāi, tāyē* >, plural *tāi-hātē* >; and Chittagongese shows a feminine তাই *tāi* > (plural *tāi-rā* >), beside the masculine হিতে, তে *hi-tē* (< \**si + tē = sē + tē*), *tē* > (plural *hitē-rā, tārū* > : Basanta Kumar Chatterji, VSPdP., 1326, p. 112). This feminine *tāi* > (the nasalisation in the Chittagong *tāi* > is irregular, and might be through the infection from honorific forms) seems to be based on the Second MIA. instrumental, dative and genitive *tāē* > (< OIA. instrumental *tayā* >), occurring in Māgadhī as well as in other dialects (Pischel, § 425).



The absence of distinction of gender for the personal pronoun of the third person is a defect in the language, and there have been unsuccessful attempts to do away with this defect by employing the Sanskrit « sâ » for the feminine nominative, and the base « tasyā- », from the Skt. feminine genitive « tasyāḥ », for the feminine oblique : তস্যাত্ « tasyā-rā » *of her*, তস্যাকৈ « tasyā-kē » *to her*, etc. In some 18th and 19th century documents the « tasyā- » oblique has been found<sup>1</sup> (Chandra-Śekhara Kālī, VSPd., Kārya-vivaraṇī for 1316, pp. 45, 46 ; and 'Hōmiōpyāthik Bhaṣajyābalīr Siddhi-prada Lakṣaṇa-cay,' Vol. I, 8th edition, Calcutta 1921, pp. 11 ff.)

562. Some Western (Śaurasēṇī) forms figure in OB. and in MB., especially in the Vaiṣṇava lyrics. (See *supra*, pp. 103, 115.) সো « sō » instead of the native স « sē » is found in the Caryās (*e.g.*, 10, 22, 27, 33, 41) : it is the nominative, but is found as an accusative also, *e.g.*, Caryā 21, « kariha sō niccala » *make him motionless* ; Caryā 45, « chēwaha sō taru » *cut down that tree*. This form is fairly common in Vaiṣṇava lyrics and is often a demonstrative adjective, as in OB. Thus « sō » is thrice as numerous as « sē » in the Caryās, a fact which is explicable through Śaurasēṇī literary influence as well as through the MS. being copied in Nepal. The genitive of « sō » in Western Apabhraṇśa has the forms « tassu, tasu » and « tāsu » (=tassa, tasya), beside « tahō ». In the Caryās we have « tasu » (instead of the native « tā, tāha, tāh-ēra »), as in « tasu anga » *its limb* (27), « maṇa taru, pāñca indī tasu sāhā » *the mind is a tree, the five senses are its branches* (45). Maithilī of literature also possesses this form. In MB., Brajabulī as well as ordinary poetic Bengali, it occurs as তছু « tāchu », with « -ch- » for « -s- » (*ante*, pp. 474, 551).

<sup>1</sup> In Early NB. letters and documents, for feminine forms like দেবী, দাসী, ঈমতী 'dēbī, dāsī, Śrī-matī,' the genitive and other cases are on the basis of the Skt. genitive in '-yāḥ' : দেবীত, দাসীত, ঈমতীত 'dēbyār, dāsī-r, Śrī-matyā-kō,' besides the regular 'dēbī-r, dāsī-kō, Śrī-matī-kē' etc. A curious result of this practice has been that in Bengali epistolary and legal language, these '-yā' oblique forms have become established as nominatives, especially with names of widows, and in this way a distinction is made of widows from unmarried girls or women with husbands living.

563. Typical Dialectal Forms for the Third Personal Pronoun :

South-West Bengali

West Rājha

<p>Nom. সে, তিন sē, tin—তারমেনে tārd-mēnē, তানমেনে tānd-mēnē, তারে tānnē, তাঁরে tānnē. Gen. তার, তান tārd, tānd—তারমেনকার tārd-menā-kār, তারেকার tānnē-kār, তাঁরাকার tānnā-kār.</p>	<p>Nom. সে তাই sē, tã—তাহরা tāhā-rā, তাহারā tāhā-rā. Gen. তাহার tāhā-rā—তাহারদের tāhārd-dērd. (The Remote Demonstrative is also commonly employed)</p>
---	--

North Bengali (Rājbañśī)

West Vanga

(Dacca, Maimansingh)

<p>Nom. সে, তাঁ, তাঁর, তানি sē, tã, tãy, tãni—তাম(া)রা tām(ā)-rā. Gen. তার, তাহে, তামার tā-rā, tā-r-hē, tāmā-rā—তামার tāmā-rā, তামরার tāmārārā.</p>	<p>Nom. সে, তাইন, তিনি sē, tãin, tini—তারā, তানরা, তাহানরা tā-rā, tā(hā)n-rā. Gen. তার, তান, তাহান tā-rā, tãnd, tāhā-nā—তারার tā-rā-rā, তাগো tā-gō, তানরার tãnd-rā-rā, (The Remote Demonstrative is employed in Haijong)</p>
---	--

East Vanga (Sylhet, Kachar)

South Vanga (Bakharganj)

S. E. Vanga (Chittagong)

<p>Nom. হে, তাইন, hē, tãin—হেরā, তারā hē-rā, tā-rā. Gen. হের, তার hē-rā, tā-rā—হেরার, hē-rā-rā, তারার tā-rā-rā.</p>	<p>Nom. হিতে, হেতিন, তে hi-tē, hē-tin, tē ; (fem.) তাই tãi—তারā, হিতেরā tā-rā, hi-tē-rā, তাঁইরা tãi-rā. Gen. হেতার, তার, তান hē-tā-rā, tā-rā, tãnd, তাঁইর tãi-rā—তারার tā-rā-rā, তানার tãnā-rā, তাঁইরার tãi-rā-rā.</p>
---	--



S.-W. Bengali has the characteristic «-mēṇṣ» affix for the plural contracted to «-n-». The West Rājha তাই «tāi» may originally have been the feminine form noted in p. 825. North Bengali uses the base তী «tāi» (beside a fuller তানি «tāni») for the nominative; and the form তামার «tāmārṣ», plural তাম(া)রা «tām(ā)rā» are honorific, with «-m-» for «-n-» or «-h-» of other forms of Bengali — a phonetic peculiarity which characterises this dialect: as early as c. 1555 A.C., in a letter from the Kōc king Nara-Nārāyaṇa of North Bengal to the Ahom king Su-khām-phā, we find ইমারাক পাঠাইতেছি «imā-rā-kṣ (= ibā-digā-kā) pāṭhāitē-chi» *I am sending them*, তামার মুখে «tāmṣ-ra-rṣ (= tāhā-digērṣ) mukhē» *from their mouth* (Report of the Third North Bengal Literary Conference, p. 37; VSP., II, p. 1672).

The use of the «-rā» plural for the oblique as well is noticeable in the North and East Bengali dialects. As the forms «imārā-kṣ» and «tāmārārṣ» mentioned above show, such oblique use was established by the 16th century.

The nominative «sē» becomes «hē» in many of the East Bengali dialects; and in South Vanga, «hē» changes «tini» to «\*sini > hini», «tēnā-rṣ» to «\*sēnārṣ > hēnārṣ»; and «sē > hē» is used for the oblique as well: e.g., East Vanga «sē-rṣ > hērṣ» *his*, «sē-rā > hērā» *they*, «sē-rārṣ > hērārṣ» *their*. The Assamese accusative «siyē» [xie, çie] shows a similar though restricted use of the nominative base for an oblique case.

The Chittagongese nominative «tē» seems to be due to the influence of the oblique base in «ta-». A peculiarity of this dialect (and of S.-E. Vanga generally) consists in the double forms «hi-tē, hē-tin = sē + tē, sē + tini».

In the Mayang dialect, the base «tā» is used for the nominative (genitive «tā-rṣ» singular, plural nominative «tānō», plural genitive «tānō-rṣ»).

564. The nominative সে «sē», emphatic সেই < সেহি «sei < sē-hi», is used as a demonstrative adjective, = *that*, for all genders. A noun

of multitude agglutinated to « sē, sēi » indicates the plural. The qualified word takes the case inflections, *e.g.*, সে লোক, সেই লোক « sē, sēi lōkḥ » *that man*, সেই-সকল লোকের « sēi-sākālḥ lōkērḥ » *of those men*, etc.

[D] THE PROXIMATE OR NEAR DEMONSTRATIVE.

565. The typical Bengali forms in the Standard Literary and Colloquial are :

	Singular		Plural	
	Old Singular	Old Plural = Honorific	New Plural	Double Plural = Honorific
Nominative	এ ē (earlier এহা ēhā), neuter ইহা ihā	এই ēhā, ইহী ihā, ইনি ini	এরা ērā, ইহারা ihārā (এসব, এগুলি ē-sābḥ, ē-gulā)	এঁরা, এঁরাঁরা ē(ā)rā, এনাঁরা ēnārā, ইহাঁরা ihārā
Oblique	এ, ইহা ē-, ihā- (earlier এহা ēhā)	এঁ, এঁরা, এনাঁ ē-, ēā-, ēnā-, ইহী ihā-	এদিগ ēdigā-, এদের ēder-, ইহাদিগ, দেৱ ihādigā-, -dērḥ	এঁ-, এঁ(রা)দিগ, দেৱ ē(ā)digā-, -dērā, এনাঁদের ēnāderḥ, ইহাঁদিগ, -দেৱ ihādigā-, -dērḥ

566. In Vedic and Sanskrit there are two pronouns to indicate the near demonstrative = *this, this here*: [i] the pronoun « ē-ta- », (nom. sg. masculine « ē-sah », feminine « ē-ṣā », neuter « ē-tad ») which is a combination of a base « ē- » (= Avestan « aē- », < Indo-Iranian « \*ai- » < Indo-European « \*ei-, \*oi- ») *plus* the third personal bases « \*to-, » (« \*so- »); and [ii] the composite pronoun which is in the nom. sg. masculine « ayam », feminine « iyam », neuter « idam », and which is made up of the four defective pronominal bases: « a- » (as in Sanskrit « a-smāḥ, a-sya, a-syāḥ; ā-bhyaḥ, ā-sām », etc.), « an- » (as in « an-ēna,



an-ayōḥ > ), < i- > ( < i-y-am, i-d-am > ; in *guṇa* forms < \*ai-, ē- >, as in < ay-am >, Vedic < ēnā = \*ai-nā, ayā = \*ai-ā >, ēbhiḥ, ē-śām, ē-śu = \*ai-bhis, \*ai-śām, \*ai-śu >, etc.), and < im- > (as in < im-am, im-ām, im-āḥ, im-ān > etc.). In OIA. dialects other than those which formed the basis of the literary speeches (Vedic and Sanskrit), it is not impossible that each of these bases, namely, < a-, an-, i- (ai- > ē-, ay-), im- > existed in their entire declensions.

The basis or root form of the Bengali proximate demonstrative is < ē- >, dialectally < i-, I- >: the affix < -ha > of the oblique is genitival, and the nasalised forms, or forms in < -n- >, were originally plural genitives. The older form for the nominative seems to be < ē >. The Caryās know < ē > (e.g., Caryā 6, < ē bana cchāḍi > *abandoning this forest*; 28, < ē bana hiṇḍai > *wanders in this forest*; 33 < ē tailōe > *in this threefold universe*; 39, < ē jaga > *this world*), beside < ēha > (Caryā 43, < ēha sahāva > *this nature*), and < ēhu > (Caryā 22, < ja ēhu jaati > for < \*jē ēhu jugati >: cf. Comm., < ēśā hi yuktiḥ >). The eMB. of the ŚKK. also shows < ē >, in the forms like এ, এআ, এহা, এহে, এহি, এনি, এহাএ, এহাক, এহাত, এহার, এহে < ē, ēā, ēhā, ēi, ēhi, ē-si, ēhā-ē, ēhā-kā, ēhā-tā, ēhā-rā, ēhō > occurring some four score of times, while a solitary < i- > form occurs in ইহার < ihārā >. In the NB. Standard Colloquial < ē > also is the word, < ihā > belonging to the literary language and to the dialects.

The source of the Bengali < ē > would thus seem to be the OIA. base < ēta- >. The *guṇa* form of the defective pronoun < i- >, as < \*ai- > ay-, ē- > can of course be equally the source of a NIA. < ē >. But MIA. remains do not register a fully declined < i- > demonstrative: Aśōkan Prakrits and Pali both show that the base < im- > was the one most widely current in the First MIA. period, with the simple < i- > and < a- > bases considerably restricted in use. The same thing is noticeable in Second MIA. as well. The < i-, im- > bases seem to have continued in the Western Apabhraṃśa of literature, specially in the form < āya- >, beside < ēya-, ēa- > = < ēta- >. In the Māgadhi Apabhraṃśa, however, it seems that only the base < ēta- > > ēa- > (genitive < ētasya > \*ēaha >) was current,

which gave the Bengali « ē, (ēhā) ». The base « ima- » of MIA. is not represented in NIA. in which its expected development would be « \*iŵa- ».

Śaurasēnī Apabhraṇśa as written in Eastern India (in the Buddhist Dōhās shows numerous instances of the nominative « ēhu » (= ēṣab). What exactly was the nominative of the « ēta- » base in Māgadhī Apabhraṇśa cannot be determined. The Māgadhī Prakrit forms are « ēśē, ēśā, ē(d)aṁ ». The « -ś- » apparently dropped through influence of the neuter and of the oblique. The genitive « ēha » was strengthened to « ēhā » in Early MB. The genitive plural « ētānām (= ētēsām) > ēāṇa(m) » is the source of oblique honorific bases « ēnā-, ēhā-, ē- » etc. The NB. honorific nominative ইনি « ini » presents a parallel case with তিনি « tini » (p. 823): Early Bengali employed ইহ, ইহো, এহো « ihā, ihō, ēhō », which we occasionally find written in MSS. as ঐহ, ঐহো, এহো « ūihā, ūihō, ūēhō ».

The alternation of « i, ē » is a commonplace thing in NIA. phonology. The « i » forms developed in Bengali quite early: the solitary ইহার « ihā-rā » in the ŚKK. shows that it goes back to the 14th century at least, and ইহার, ইহারে, ইহাকে « ihā-rā, ihā-rē, ihā-kē » etc. are common enough in MB. The Late MB. prose preferred these « i- » forms, whence the NB. « sādhu-bhāṣā » took them up. Oṛiyā preserves the earlier broader vowel, like Standard Colloquial Bengali: « ē, ēhā, ēhi ». In MB. and dialectal Bengali we find a form ইহান « ihān », honorific genitive singular, = « ihā » + « -na » of the plural. In Assamese we have singular nominative « i », oblique « iyā- », plural « i-hāt- »: the honorific is « ēo » = MB. « ēhā »; and there is a feminine form in Assamese, « ēi », corresponding to « tāi » *she* (*supra*, p. 825), which seems to be based on the MIA. feminine genitive « ētāē, \*ēdāē, \*ēāē », agreeing with « tāē » for « tasyāḥ ».

The Bihārī dialects show « I, ī » for the nominative, and « ēh-, ē-, ēhi- » for the oblique; and corresponding to « ēhā-, ihā- » of Bengali are to be found in Maithilī « hina-k < \*inha-ka » (honorific oblique), and Magahī and Bhōjpuriyā « inh- » (plural base).



567. The OIA. « ēta- » base is found to be represented in most other NIA. Typical forms are given below :

	Nominative		Oblique	
	Singular	Plural	Singular	Plural
Awadhī	I, yū (= ēhū)	in, ē	ē-, ēh-, ēhi-, yāhi-	in-
Hindōstānī	yah, yēh, yih ( < *ēaha )	same as Singular	is-	in-, inh-
Brajbhākhā	yah, yih ( < *ēaha )	yē, yaū	is-, yā- (= *ēaha)	ini-, in-, inbaū-
Panjābī (Eastern)	ih, ēh	ih, ēh	ēs-, is-, ih-	ēh-, inh-
Lahndī	ē, ēh, ī	ē, ēh, nēh, in, ī, th	is-, ih-, ī-	inhā-, inhē-
Sindhī	hī, hē, hīu, hīa	hī, hē	hina-	hina-, hinana-
Rājasthānī	yō, yā (ō, ā)	yai, yē, (ē, āi)	ai-, in(i)-, ī-, aṇi-	inā-, anā-, in-, yā-, ā-
Gujarātī	ē	ēō	ē-	ēō-
Marāṭhī	hā [m.], hī [f.], hē [n.]	hē, byā, hī	hyā- (yā-), hī-(ī-)	byā- (yā-)
Khaskurā	yō	ina, in(i)	yes-, yas-	ina-, in(i)-

Of the above forms, the oblique singular in « -s- », as in Western Hīndī (Hindōstānī, Brajbhākhā), Panjābī and Lahndī, as well as in Khaskurā (and the Western Pabārī dialects), is based on the OIA. « ētasya » (genitive of the « ēta- » base), which seems to have become « \*ētissa » in First MIA. (cf. « ētisa » in Aśōkan the Shabbazgarhī: a similar change of the original vowel to « -i- » we note in the instrumental « \*ētina < ētēna », which figures in the Second MIA., Māgadhi and Jaina Mahārāṣṭrī, as

« ēdinā » and « ēinā » respectively): « \*ētissa < \*edissa > \*ēissa » would be the development in Later MIA. It is quite likely that like « kissa, kiśśa, kīsa » = OIA. « kasya » which from the Early MIA. period was specialised from its genitive employ, and became almost an independent form (cf. Bengali কিসে, কিসের 'kisē, kisē-rā' by what, of what : see *infra*, under 'Interrogative'), « \*ēissa » also was specialised, first as an ablative, and then as an oblique. This « \*ēissa » could easily be the source of the NIA. « is-, ēs-, yes-, yas- » etc. In East Bengali (Dacca) when one is at a loss for a word the expletive ইসে « isē » is frequently used (= *namely, this er, what*): this « isē » seems to be the equivalent of the W. Hindi « is- » in Bengali (cf. the similar use of « ēthi » in Bhojpuriyā : p. 834). The normal genitive form in « -ha » gave the oblique in the other NIA. dialects, and in many cases this oblique was shifted to the nominative. The nominative plural « yai, yē, ē », as in Western Hindi, in Rājasthāni and in Panjābi, possibly represents the instrumental « \*ēēhi = ētēhim = ētāih ». In Gujarāṭi « ē » has taken up the sense of the remote demonstrative, and « -ō » is its normalised plural affix. The nasal « ŋ » (or nasalisation of the vowel derived from the nasal) in the Rājasthāni oblique singular comes from the OIA. pronominal base « ēna- » *he, she, it*, which was continued in MIA. (Pischel, § 431); but it is not preserved elsewhere in NIA. In the Apabhraṇśa source of Rājasthāni-Gujarāṭi, the « ēta- » and « ēna- » bases were merged into this demonstrative (Tessitori, 'Notes on the Grammar of OWR,' § 89). The Sindhī oblique *e.g.*, « hina » is probably similarly to be explained. The prothetic « h- » in Sindhī is peculiar, but it may be by metathesis, from the genitive oblique « \*ēha > \*ēha > hē, hī » : « a, ā » are recent masculine and feminine affixes. The Marāṭhi forms present some obscurities (cf. Jules Bloch, 'Langue Marathe,' pp. 162, 208): but can it be that in the formation of Marāṭhi « hā » etc. there was a blending in Mahārāṣṭri Apabhraṇśa of forms like « ēha- » (= ēśab, ētasya) and « āa-, āya- » (= ayam), such as we find in the Western Apabhraṇśa? Gujarāṭi also has « ā » *this*, which is derived from « āya-, āa- » as found in Jaina Apabhraṇśa of the West, = Second MIA. « aya- » < OIA. nom. masc. « ayam ».



Sinhalese has the bases « ū, ē (ē) » for the third personal pronoun : of these, « ū » corresponds to the Remote Demonstrative of Bengali, and is cognate with it (see *infra*), and « ē (ē) » is traced by Geiger to « ayam » of MIA. The proper demonstrative bases of Sinhalese are « ma- » *this*, which is derived ultimately from the OIA. and MIA. « ima- », and « ara » *that*, representing the OIA. stem « āra- » *far* ('Litteratur und Sprache der Sinhalesen,' pp. 66, 67).

568. The differences in gender have not been inherited in NIA. In Bengali and other Magadhan, a possible instrumental « \*ēṭi, \*ēṭi » (= *ētēna*) seems to have merged into the nominative and oblique, and also a possible plural instrumental > nominative, such as we find, for instance, in the Brajbhākhā « yai, ē, yā ». An expected locative in OB. and MB. would be « ēhi, ēhi » : this seems to occur in NB. as এই « ēi », as in এই যে « ēi jē » *here it is*, এইখানে « ēi khānē » *here*, এই হেথায় « ēi hēthāy » *here at this place*, etc.

Corresponding to the form তথি « tāthi », OB. seemed to have possessed « \*ēthi ». We have « ēthi » in Oṛiyā, in the oblique, as an equivalent of « ēhā » ; and « ēthi » occurs in Bhōjpuriyā as an expletive like ইসে « isē » of dialectal Bengali. Connected with this possible OB. « \*ēthi » we have the form ইথে « ithē » in *this* in MB. (from the ŚKK. downwards).

569. Dialectal Forms for this pronoun agree in general with those for the Third Personal pronoun.

S.-W. Bengali has nominative এউ « ēu », really an emphatic form, = « ē + hu ». The expected plural forms of the type of « ē(u)nē, ē(u)mēṇḍ-kārḍ, ē(u)nē-kārḍ » do not feature in the LSI.

West Rāḍha agrees with the Standard Colloquial in having এ « ē », but the vulgar dialect has a preference for ই, ই, « i, i », owing to contiguity with Bihārī ; and the full forms ইহার, ইহাকে, ইহারদের, ইহানিগে « ihā-rḍ, ihā-kē, ihā-rḍ-dērḍ, ihādigē » etc. occur in it.

In North Bengali, ই « i » as well as এই, এও « ēi, ēo » figure for the singular, and ইমরা, ইমরাক, ইমরার « imṛā, imṛā-kḍ, imṛā-rḍ » etc. for the plural, corresponding to তামরা « tāmrā » etc. (p. 828).

In East Bengali, we have এ < ē > in the singular, plural এরা < ē-rā >, genitive plural এরাঁর এরণো < ērārṅ, ērṅ-gō >, and ইনি < ini > is singular, with plural এরাঁনরা, এনাঁরা < ēnārṅ-rā, ēnā-rā-rṅ > etc. for the honorific. The full < -n > rather than the nasalisation is preferred.

570. Like সে, সেই < sē, sēi >, এ < ē >, with its emphatic এই < ēi < ēhi > is used as a demonstrative adjective.

[E] THE REMOTE OR FAR DEMONSTRATIVE ও, উহা < ô, uhā >.

571. The forms in Bengali are—

	Singular		Plural	
	Old Singular	Old Plural	New Plural from Singular	Double Plural from Old Plural
Nominative	ও ô (earlier ওহা ôhā)[neuter উহা uhā]	উনি uni (earlier উই uhā, ওই ôhā)	ওরা ôrā, উহারা uhārā (ওসব, ওগুলো ô-sābṅ, ô-gulā >	ওরা ôrā, ওনাঁরা ônārā, উহারা uhārā
Oblique	ও-ô, ওহা ôhā- উহা uhā-	ও-ô- (ওহা ôhā-), ওনা-ônā-, উই-uhā-	ওদিগ ôdigā-, ওদের ôdêrṅ, উহাদিগ uhādigā, etc.	ওদিগ, -দের ô-digā, -dêrṅ, ওনাঁদের ônādêrṅ, উইদিগ uhādigā, etc.

572. In Indo-Iranian, there were the following demonstrative bases which gave the remote demonstrative in the Indic and Iranic languages: [i] a base \*ava- (= Indo-European \*owo-: Old Church Slav < ovŭ >), giving the Iranian pronoun < ava > *that* as in Old Persian and Avestan (which has become < ô, ū > in New Persian = *he, that*, as opposed to < ē, i > *this* < Old Pers. < ai-ta > = Skt. < ē-ta >, and < in > *this* = Skt. < ē-na >). In Indo-Aryan, this base seems to have been current dialectally, although in the Rîg-Veda alone it is preserved only in the genitive and locative dual form < avôḥ >; [ii] a base < am-ā (am-ā), am-i > which is characteristic of Vedic and Sanskrit. It is obscure in origin, and seems to be an extension of < a-m >, the accusative of the simple pronominal base < ā > (= Indo-European \*ā, \*ō >), with < u > and < i > particles,



into « am-u-, am-I- » which was established as a pronoun (cf. Vedic « tam-u, idam-u; also cf. « imam » < « im », accusative of a pronoun « i », plus particle « -am ».) This base « amu, amI » is not found outside India. [iii] For the nominative masculine and feminine, Indo-Iranian had the forms « \* sā-u, \* sū-u », a combination of the third personal nominative pronouns « sā, sū » plus the particle « -u », beside a neuter « tad- u ». (These are found in the Old Greek as « ho-u-, \*hā-u-, \*tod-u- < tou- » as in « hon-tos, hau-tē, tou-to ».) The masculine « \* sā-u » and the feminine « \*sū-u » apparently were used one for the other. In Iranian these became « \*hā-u, \*hā-u », and Old Persian generalised the masculine (as « hauv ») for both genders, and Avestan the feminine « hāu ». In Indo-Aryan also, the feminine form was taken up for both the genders; and there was prothesis of the pronominal base « ā- », giving « ā-sā-u ». (The proper masculine form from Indo-Iranian « \* (ā-)sā-u » would have been « \* asō » in Sanskrit.) For the neuter, a new formation « ad-as » (= neuter pronominal « a-d », cf. « ta-d, ya-d » etc., and a suffix « -as ») was created in OIA.

Leaving aside the nominative « asāu, adas », it is clear that in OIA. « amū-, amū-, amI- » formed the base for demonstrative, with a possible « ava- » base which is not noticed in Vedic and Skt. except in the dual form « avōḥ ».

The base of this pronoun in Bengali is « ō, ōhā », and not « u », which is later, and dialectal (cf. the case of « ē, ēha » and « I » of the near demonstrative). The ŚKK., however, shows « ō » only in the genitive « ōhā-rā » (twice), and it is « ū, u » in the nominative (thrice). The West Rāḍha dialect even now prefers « u » to « ō ». There is no instance of this pronoun in the Caryaś. The ordinary demonstrative « sē, tāhā » seems to have been more popular than the « ō (u) » demonstrative in OB. and MB. This was certainly the case in some other forms of Magadhan, e.g., Assamese and Ōriyā, which use « sē, sēi » (in Assamese = [xi, xei]) and « sēhi », and do not possess the « ō » form. In the case of some of the pronominal derivatives, Bengali, too, prefers the bases « sē-, tā- » to « ō, ō > ā »: thus, সেখান « sē-khāṇḍ » beside ওখান « ō-khāṇḍ » there, NB. তবে

« tābē » rather than MB. अप्ठ *ābē* » *then*. In the Śaurasēnī Apabhraṃśa, however, as well as in the Avahaṭṭha of the 'Prākṛta-Paṅgala' and of Vidyāpati and others (cf. p. 91), « ō » is found: *e.g.*, Hēma-candra (verse 45, under Apabhraṃśa) « jāī pucchahu ghara vaḍḍāī, tō vaḍḍā ghara ōi » *if thou askest about big houses, then big houses are there* (« ōi » = « \*avē », locative of « \*ava »: Pischel, 'Grammatik der Pkt.-Sprachen,' § 432); verse 97, « ō gōri-muha-nijjiaū baddali lukku miṅku » *that moon, more beautiful than even Gaurī's face, is hid in the cloud*; 'Prākṛta Paṅgala' (ed. Bib. Ind.), p. 139, « ō bakkala, ō pasu, ō pāsāṇa »; p. 348, « sasi ō » (=śaśī saḥ); Vidyāpati (Kīrtti-latā) — « bāla-canda, Vijjāvaī-bhāsā, duhū nahī laggaī dujjaṇa-hāsā: ō Paramēsara-Hara-sira sōhaī, i niccaya nāra-maṇa mōhaī » *the scorn of bad men cannot touch these two — the young moon and Vidyāpati's language: that adorns the crest of the Supreme Deity Hara, this certainly pleases the mind of gallants*; etc. In the Apabhraṃśa which is connected with Gujarāṭī, as in the Jaina writers, the « ō » demonstrative does not occur: neither is it found in Marāṭhī.

The source of NIA. « ō » (and its variants in the different languages, as below) would seem to be the OIA. base « \*ava », which looks like having been current in the spoken dialects, although ignored by the literary speeches—Vedic, Sanskrit, Pali and the various Prakṛites—and came to its own only in Late MIA. literature through occurrence in the popular poetry in Apabhraṃśa. The base « amu- » is quite popular in Pali, it is common enough in Second MIA.; its development in Late MIA. and NIA. would have been « \*aūu-, \*aū- »: this may have existed in Late MIA., but it gave place to the colloquial « \*ava- > ō- ». The « ava, ō » pronoun has always been a living one in Iranian, and it occurs in Dardic (*e.g.*, Šīnā): it can well have been a living one in some OIA. and MIA. dialects.

The oblique, honorific and secondary plural forms run parallel to those for « ē », and there is the alteration between « ō, ū (u) » similar to that between « ē, i (i) ». In the Bihārī dialects, « ū, ũ » are the nominative, and « ōh-, ō-, uh- » are found for the oblique: and corresponding to the honorific « unī, ubā- » etc. of Bengali, Maithilī has « huna-k < \*unha-ka », and Magahī and Bhōjpuriyā have « unh- ».



573. The «ava-» base is thus represented in some of the other NIA. speeches :

	Nominative		Oblique	
	Singular	Plural	Singular	Plural
Awadhī	ū, wai	on, un, ō	ō-, ohī-, ōh-, wahi-	on-, un-
Hindōstānī	wah, wōh, wuh	wē	us-	un-
Brajbhākhā	wah, wuh, wō	wē, wai	wis-, wāhi-, wā-	un(i)-, win(i)-, unhaū-(winhaū-)
Panjābī	uh, ōh	uh, ōh	us-, uh-, ōs-	ōh-, unh-
Lahndī	ō, ū, ūh	ū, ū, ō, ōh, ūbē	us-, uh-, ū-	unbā-, unbē-
Sindhī	hū, hū, huā	hū, hō, hōē	huna-	hune-, hunane-
Rājasthānī	wō, u, wōh, wā	wāī, vī, wai	wāī-, ū-, un(i)-, wāī-	un-, unā-, wāī-, wā-
Khaskurā	u	una, unī, un	us-	una-, unī-, un-

The oblique singular «-s-» forms of Western Hindī, Panjābī and Lahndī, and Pabārī (Khaskurā), are apparently based on the old genitive «\*avasya» > MIA. «\*avussa», paralleling «ētasya > ētiśsa», «kasya > kiśsa». The plural nominatives, Western Hindī «wē», Lahndī «ubē», Rājasthānī «wāī, vī», would be from an instrumental nominative plural, «\*avahi, hī-» > «\*avēbhiḥ». The «-ŋ-, -n-» in the Rājasthānī and Sindhī singular oblique would appear to be by the analogy of the Near Demonstrative. Gujarātī and Marāṭhī do not possess a form corresponding to this «\*ava- > ō, ū». Sinhalese has «u», equally derived from «ava» (Geiger : see *supra*, p. 834).

574. There is a NB. locative adverb «ōi» < «ōi» *there*, which represents either a Māgādhī Apabhraṇśa «\*ōi» < «\*avē» as in Hēma-candra, *supra*, p. 837), or the locative in «-hi» (\*ōhi = OIA. ava + -dhi). «ōi» is

commonly written অই « ai », but that does not alter its « ō » pronunciation. There is no « -thi » form in Bengali as a substitute for the oblique (cf. তথি, ইথে « tāthi, ithē », *supra*, pp. 825, 834), which we see in the Bihārī dialects (e.g., Bhōjpurīyā « ōtthu, ōthuā » *that*, Maithilī « uthī, uthi »).

575. Dialectal forms for « ō, u » run parallel to those for « ē, i », with only substitution of the back vowels proper to this pronoun, and it is unnecessary to describe them. In many of the dialects, for instance in parts of West Rājha as well as E. Bengal, as a characteristic phonetic habit, অ « ā » is substituted for ও « ō ».

576. The emphatic ওই « ōi » < ওহি « ōhi » (frequently written অই « ai ») = *that, that there*, is used as a demonstrative adjective.

577. There is a superficial resemblance between the NIA. demonstrative bases and those of Dravidian, which has the bases « i- » for the proximate, « a- » for the remote and a less common « u- » for the intermediate demonstrative (or « iv-, av-, uv- »: C. P. Venkatarama Ayyar, 'Madras University Dravidic Studies,' I, 1919). But that resemblance is only accidental: the NIA. forms can be easily traced back to OIA., and Dravidian influence here is extremely problematic. The Kōl demonstrative pronouns are more complicated in their construction and employment (cf. Santali, in LSI., IV, pp. 43-44), and here the question of influence is even more unlikely. The question of Tibeto-Burman influence seems to be still more remote.

#### [D] THE RELATIVE PRONOUN.

578. The forms are—

	Singular		Plural	
	Old Singular	Old Plural Honorific	New Plural	Double Plural = Honorific
Nominative	বে jē [neuter বা(হা) jā(hā)]	জেই jēhā, জিই jihā, যিনি jini	বা(হা)রা jā(hā)rā	বা(হা)রা jā(hā)rā
Oblique	বা(হা) jā(hā)-	বা(হা) jā(hā)-, যেনা jēnā-	বা(হা)দিগ jā(hā)- digā-, বা(হা)দের jā(hā)dēṛā-	বা(হা)দিগ jā(hā)- digā-, বা(হা)দের jā(hā)dēṛā-



The pronoun is written with य < y = j > in NB., but in OB. and MB. ज < j > was preferred, although य was also used in MB. through Skt. influence (the OIA. source of the word in Skt. < ya- > being well-known).

**579.** The source of this pronoun is the OIA. relative < ya- >. The nominative ज < jē > = Māgadhi < yē >, OIA. < yaḥ >, has developed like < sē > from < sa, saḥ >: Assamese has < ji > [zi]. A plural nominative < jē > (< \*yahi = \*yēhi >, MIA. instrumental plural: cf. W. Hindi < jē > plural of < jō >) may have merged into the singular. The honorific is based on the plural genitive < yāna(m), yāṇa(m) > = < yēṣām >: the < ē, i > vocalism in जेह, जिह, जिनि < jēhā, jihā, jini > may be due to the nominative. The oblique is the strengthened form of a genitive < jāha >. In Assamese, the neuter oblique has the < i > vowel, being based on the nominative (masc. nom. < ji >, oblique < jā- >: neuter nom. < ji >, oblique < ji-hā >).

Oṛiyā and Bihārī in the main agree with Bengali: thus—

	Old Singular	Old Plural = Honorific	New Plural
Oṛiyā	jē, jāhā-	jēū, jāhā-	jē-mānē
Maithilī	jē, jāhi, ja-	jani-k (genitive)	jē-sabbh
Magahi	jē (jaun), jēh-	jinh- (oblique pl.)	jinh-ak-an-i
Bhōjpuriyā	jē (jawan, jaun), jēh-	jinh-(oblique pl.)	jinh-kā

Eastern Hindi (e.g., Awadhī, Chattis-garhī) shows < jē > in the nominative, representing the vocalism of Ardha-Māgadhi. The form < jaun > (cf. < taun > for the 3rd personal pronoun) agrees with < kaun > (see *infra*, under 'Interrogative'). The OIA. < ya- > is preserved in other NIA., excepting Sinhalese, which has adopted the Dravidian device of employing adjectival relative participles instead of the relative pronoun, and this pronoun has consequently dropped off.

**580.** OB. forms :

Nominative : < jē jē āilā tē tē gēlā > *those who came went away* (Caryā 7) ; < jē jē gēlā > *he who* (or *those who*) *went* (Caryā 15) ; < ja ēhu jaati > (= < \*jē ēhu jugati >, following the Commentary : Caryā 26) : < jē bham-anti > (plural, < \*jahi, \*yēbhiḥ > : Caryā 22) ;

Accusative : « jā ēthu cāhāma » (the printed text has « vāhāma » : cf. Commentary, « yam paśyāmy atra » : Caryā 21) : « jā laī acchama » (Comm. = « gṛhītvā tiṣṭhāmi » : Caryā 29) ;

Instrumental : « jē ajarāmara hōi » (Caryā 3) ; « jēna (archaic) tuṭaI avaṇā-gavaṇā » (Comm. = « tēna yātāyātaṃ truṭyati » : Caryā 21) ;

Genitive : « jā, jāhēra » (see *supra*, p. 752) ;

Locative : « jahi » (Caryā 31).

Besides, there are numerous (some dozen) instances of the Western Ap. nominative « jō » in the Caryās, and one or two instances of the corresponding Western genitive « jāsu » (in one case, as « jasu » in Caryā 40, it is used for the locative). This « jō » figures in Brajabuli poetry, and « jāsu, jasu » occur there as बहू « jāchu » (see *supra*, pp. 473-474).

The locative « jahi » is used as the oblique base in MB., esp. in the genitive, *e.g.*, बहिर « jāhirā » : cf. Oṛiyā neuter « jābī » = masculine and feminine « jā(hā) ». Corresponding to « tāthi » (see p. 825), MB. has बधि « jāthi », as in locative बधित « jāthi-tā », genitive बधिर « jāthi-rā » (see *supra*, p. 297).

581. The dialectal forms correspond to those for the demonstratives. The relative, with its emphatic form বেই « jēi (< jēhi) », is used as an adjective.

#### [G] THE INTERROGATIVE PRONOUN.

582. The following are the forms for the masculine and feminine :

	Old Singular	Old Plural > Honorific	Old Plural	Double Plural = Honorific
Nominative	কে kē [adj. কোন্ kōṇṣ]	কেই kehā, কিনি kini	কা(হা)রা kâ- (hā)-rā	কা(হা)রা kâ(hā)-rā
Oblique	কা(হা) kâ(hā)-	কা(হা) kâ(hā)-	কা(হা)দিগ kâ- (hā)digā-, কা(হা)দের kâ(hā)dêrā	কা(হা)দিগ kâ(hā)- digā-, কা(হা)দের kâ(hā)dêrā- (কেনাদের kēnādêrā)



The neuter has a separate form :

Singular Nominative কি, কী ki, kī (adj. = কোন্ kōṇḍ) ;

Oblique কি ki, কিসে kiśe (from base < kiśa- >) ;

Genitive কিসের kiśerḍ ;

Plural : কি-সব, কি-সকল, কোন্-গুলি ki-sābḍ, ki-sākālḍ, kōṇḍ-gulā, etc.

583. The nominative কে < kē > is the form which characterises all Eastern speeches, Eastern Hindī included. Assamese also shows < kē > instead of the expected < \*ki > < Māgadhi < kē >, and Oṛiyā also has < kē >. The neuter < ki >, from common OIA. < kim > (not < kad >, corresponding to < tad, ṛtad, yad >), is a characteristic form, and this apparently brought about the introduction of < kē > for the masculine.

কোন্ < kōṇḍ > was originally indefinite, and in its emphatic form কোন, কোনো, কোনও < kōṇā, kōṇō, kōṇāō < kōṇā-hō > the indefinite sense still survives. The pronoun is found as < kaṇ, kōṇ, kaun, kōn > in most NIA., and has its parallel in the other bases, like < taun, jaun >. It occurs in Western Apabhraṇśa as < kavaṇ, kavaṇa- >. Hoernle derives < kavaṇ > from an Apabhraṇśa quantitative pronoun < kēvaṇ > ('Gauḍian Grammar,' p. 291) : but this is inadmissible. Pischel traces it to an OIA. diminutive or pejorative base < kava- > (from the old pronoun < ka- >, and from < ku- > *bad* as well) which we find in Skt. forms like < kava-patha > *bad way*, < kavōṣṇa > *slightly warm* ('Grammatik der Pkt.-Sprachen,' § 428). The < -ṇ- > remains obscure still. But < kaun, jaun, taun > apparently form one group : and there is no pejorative sense in this indefinite form. It seems likely that the source of the < -vaṇa, \*-vuṇa, -un > forms is the OIA. indeclinable < punaḥ > : < kaḥ punaḥ >, apparently regarded as one group from Early MIA. times, < \*ka-puna- > > Second and Late MIA. < \*kavuaṇa- > kavaṇa >. It is a noteworthy fact that < kaun, kōn > is found only in the nominative in the Northern Indian languages, although the oblique use is found in Gujarātī and Marāṭhī : thus the genitive of কোন্ < kōṇḍ > in Bengali is কার < kārḍ >, in Hindōstānī < kis-kā >, but in Gujarātī it is < kōṇ-nō > and in Mārāṭhī < kōṇā-cā >. In the ŚKK., the forms are কোণ, কোণ < kōṇḍ, kōṇā >, beside কোমণ < kōmāṇā = kōṇāṇā >, and emphatic কোণোহো, কোঁহো

• kōṇō-hō, kōnhō >. It seems that in the Early MB. of the ŚKK. there was a confusion between the uncontracted কণ, কমন > kāmāṇā, kāmāṇā = kāwāṇā > and the interrogative pronominal adjective কেমন, কেমনত, কেমনত > kē-māṇā, kē-māntā, kē-mātā > (see *infra*). Early Middle Bengali কোণ > kāṇā > has its counterpart in Oṛiyā > kāṇā-si > *only, some*; and the equivalent of > \*kāwāṇā > of MB. (in MB. it is always an adjective) in Oṛiyā is > kāāṇā, kāṇā > = *what*.

584. The oblique > kā(hā)- > is based on the > -ā(ha) > genitive; and the honorific is the genitive plural, MIA. > kāṇa(m) > for OIA. > kēsām >, with vocalism from the nominative.

The neuter base কিস > kisa- > goes back to the Early MIA. genitive > kissa > (which is already present in Pali) or > kiśśa > (as in Māgadhī) (= OIA. kasya). The > -i- > vowel seems to have been due to the influence of the neuter base > ki- > (> \*kisyā > kissa, kiśśa >: cf. Pali locative > ki-smiṁ, ki-mhi >, beside > ka-smiṁ, ka-mhi >). During the Early MIA. period, this form extended its sense to the ablative (in addition to the dative), and became stereotyped into the neuter nominative as well, in the sense of *what*: and > kissa, kiśśa > kisa, kiśa > was loosely compounded with a following noun (especially in the ablative), in Second MIA. (cf. Pischel, § 428). It seems that on the analogy of > kissa >, other forms like > \*tissa, \*ētissa, \*yissa > etc. were built up, which ultimately gave the oblique singular forms of the pronouns in Western Hindī and Panjābī. Of these, the base > kisa- > alone occurs in Standard Bengali: it is found in OB. independently, without an affix: e.g., Caryā 6, > acchahū kisa > *in what am I*; Caryā 29, > kāhērē kiśa (= kisa) bhaṇi māi dibi piricchā > = > kasya kim uktvā mayā siddhāntaḥ pradāstavyaḥ > as the Commentary explains; *ibid*, > Lui bhaṇaī, bhāība (= bhāwiba) kiś (= kisa) > = > Lūyi-pādaḥ siddhācaryō hi vadati, mayā... kim bhāvyam >. In the ŚKK, we have post-positional forms, like কিসক, কিসকে, কিসে (also কীবে), কিসের, কিসেরে > kiśā-kā, kiśā-kē, kiśē (kiśē), kiśērā, kiśērē >. The base form occurs in Oṛiyā as > kiśā >; Assamese has it as > kihā > (< kiśā), neuter pronoun (beside a neuter > jihā > < > jiśā=yasya >). The Bihārī dialects do not, however, show the > kisa > base. The oblique of > ki > is > kiśā- > in NB.



but in eMB. we have also the oblique use of « ki » (*e.g.*, किके « ki-kē » in the ŚKK).

585. The honorific is based on MIA, « kāṇa(m) = kēsām » : the genitive काहान « kāhā-nā » is found in MB. In Maithili, it is the honorific base, « kan-ikṣ ». The « -n- » oblique occurs as usual in other NIA. as well.

586. The locative कहि, कहि « kahī, kahi » of OB., and MB., is found in NB. in the form कहे « kái » *where* : in the Standard Coll., कहे « kái » is used in response to a statement or question, but in E. Bengali, it is a general word for *where*. The use of « kāhi » as the oblique base is found in MB. : *e.g.*, कहिर « kāhi-rā » of *where* = *whose* ; also in Oṛiyā, *e.g.*, « kāhī-rā ». The other locative adverb कथि « kāthi » is found in MB., also as an oblique base : *e.g.*, (ŚKK). कथिर « kāthi-rā » *whose*. As « kathi », it also forms the locative base of the neuter in the Bihāri dialects (especially Maithili).

In NB. there is the form कय « káy » (in the standard language also as क' « ká ») *how many*, which is from OIA. « kati ».

587. The forms in OB. :

Nominative indefinite masculine « kē-hō » (Caryā 18) ; neuter « kāhi kariai » *what is done* (Caryā 1 : locative-oblique used for nominative, « kāha ») ;

Accusative : neuter « kiṣa, kiṣ=kīsa » (Caryās 6, 29) ; « kāh-ē » (Caryā 6) : « kā » (Caryā 39) :

Genitive : fem. « kāhari » (Caryā 10) ;

Dative : « kāhērē » (Caryā 29) ;

Locative : « kahī » (Caryās 7, 31, 49) ; « kāhi » (= « kāha » + locative affix : Caryā 43).

As an interrogative particle, « ki » occurs in OB. in some instances, *e.g.*, Caryā 33 « duhila dudhu ki bēṇṭē ṣāmāi » (see *supra*, p. 263) ; « bhāga (= bhāṅga) taranga ki sōsai sāara » *can broken breakers suck up the sea ?* (Caryā 42). An archaic « kimp » is found in some instances (22, 34, 41). Besides there are the common Western forms—nominative « kō » (16, 29), indefinite « kōē, kōi » (as in 42, 43), genitive « kāsu » (23).

The dialectal forms do not call for any special comment.

[H] THE INDEFINITE PRONOUN.

588. *କେହୋ, କେହ, କେଉଁ* «*kēhō, kēhā, kēu*» occurs only in the singular. It is a nominative Māgadhi form, coming from OIA. «*kaḥ api*» > Māgadhi «*\*kē' pi*» > «*\*kē' vi*» > «*\*kē-va*» > «*\*kē-wa, kē-o*» > «*kēha, kēhō*» (with influence from the emphatic particle «*hu, hō*»): cf. Oṛiyā «*kēi*» (= «*\*kēvi*»). Assamese has «*kēo, kēo*», Magahi «*kēū*», Maithili «*kēo*», Bhōjpuriyā «*kēhū, kēū*»; Eastern Hindī as a Prācya speech shows the «*ō*» vowel: «*kēū, kēhū*». Western Hindī has the proper Śaurasēni «*kōi*» (< «*kō'vi, kō'pi*»). The word «*kēhō*» occurs in Carya 18: «*kēhō kēhō tōhōrē biruā bōlāi*» *some call thee deformed*.

The oblique form of «*kēhō, kēu*» is «*kā(ha)-*» or «*kā(hā)-*» + case-affix or post-position + «*hō, ō*», or «*kā(ha)-, kā(hā)-*» + «*hō, ō*» + case-affix or post-position: e.g., «*kāhā-+rā+ō*» > MB. (ŚKK.) *କାହା* «*kārhō, kāhrō*», NB. *କାରୋ, କାରୁ* «*kārō, kārū*» *whose*; «*kāhā-+ō+ -kē*» > MB. *କାହୋକେ* «*kāhōkē*» > NB. *କାଉକେ* «*kāukē*», beside literary *କାହାକେ* «*kāhā-+ -kē+ō*» > colloquial *କାକେ* «*kākē*» (and ŚKK. *କାହା* «*kākhō*» < «*kāhā-+ -kā+ hō*») *whom*. For the plural forms, the «*-ō, -hō*» comes at the end of the inflected word: *କାରାଓ* «*kārā-ō*», *କାଦେରଓ* «*kādērā-rō*», etc. The NB. genitive has a peculiar form in the colloquial, *କାରର* «*kārurā*» (either = «*kā-r-u*» + additional genitive «*-rā*»; or = «*kā(hā)-+ō+ -rā*» > *କାଉର* «*kā-u-rā*», with euphonic «*-r-*»: «*kā-r-u-rā*»).

589. The neuter indefinite is *କିହୁ* «*kichu*» which is found in other Magadhan (in Oṛiyā, however, as «*kichi*»). The OIA. «*kim + -cid*» occurs as «*kiñchi, kichi*» (= «*kicchi*») in the Central and Eastern inscriptions of Aśoka, with the aspirate «*ch*», as opposed to stop «*kiñci*» of the South-West (Girnar). This aspiration, so old, is peculiar: was it due to the influence of a possible masculine indefinite «*\*kacchi* < «*kaścid*»? The NIA. «*kichu*» also has the emphatic particle «*hu*»: «*kiñchi-hu*» (or «*kiñci-hu*»?) > «*kichu*». (cf. Hoernle, 'Gaudian Grammar,' § 465). The Oṛiyā «*kichi*» may represent the emphatic «*hi*» (< «*\*kiñchi* = «*kiñci* + «*hi*»). The loss of nasalisation is very ancient. In Western Hindī, the form is



« kachu, kuch » (= « \*kañ » used as neuter, + - « -cid, + hu = khu, khalu » ?), also « kichū ».

590. The relative বে « jē », বা « jā » is combined with কেহ কেউ, « kēhā, kēu » and কিছু « kichu » respectively to mean *whosoever, whatsoever*. This combination would seem to be recent in Bengali. The earlier way would be by periphrasis: e.g., বে হোউক সে হোউক « jē hōuk sē hōuk » = NB. বে কেউ হোক « jē-kēu hōk » *whoever it may be*; or by adding the emphatic particle: e.g., কেউ « jē-u », যেহে « jē-hō », as in the ŚKK.

#### [I] THE REFLEXIVE AND HONORIFIC PRONOUN.

591. OIA. « ātman » *self* changed to « atta- » in Early MIA. (Udīcya, Madhya-dēśa, Prācya). From « atta- » we would expect a neo-Māgadhi « \*āta »: but this « atta », in Māgadhi as well as Ardha-māgadhi and Śaurasēnt, appears to have been overlaid by a cognate form « appa- » from South-Western MIA. (cf. « atpā » in Aśōkan Girnar: *ante*, p. 508). Pali shows only the basic Midland « atta- »; and « atta- » is continued in the Second MIA. in Māgadhi and the rest, but by the Second MIA. period, the South-Western form established itself in the North and the East. The Second MIA. forms were: singular nominative « appā », instrumental « appaṇā », genitives « appaṇō », pl. « appāṇa », besides other ones (cf. Pischel, § 401). The nasal of MIA. has been preserved in NIA. in most cases, owing no doubt, to the base being regarded as being, in a vague way, « appaṇa- ».

In the Caryās, we have the following instances of the reflexive use of « ātman » > apā, āpaṇa, āpaṇa »:

3: « āila garāhaka apaṇē bahiā »

*The customer came, journeying all by himself;*

6: « apaṇā māṇsē harinā bairi »

*Because of its own flesh, the deer is a foe;*

22: « apaṇē raci raci bhava-nirvāṇā,

michē lōa bandhāvaē apaṇā »

*Creating again and again being and extinction by himself,*

*For naught man binds himself;*

31 : « na jānami apā kabī gai paithā »

*I know not where the self having gone has entered ;*

32 : « apanē apā bujha tu nia-maṇa »

*By thyself understand thou in thy own mind ;*

39 : « disai para-apyāṇā (= appaṇā) »

*Other and self are seen.*

In the Caryās, as can be seen from the above instances, « apā (= āpā) » is the nominative, « apanē » instrumental, « apaṇā » genitive and accusative. The OB. nominative « apā (= āpā) » is an extended form of « \*āpa » = IMIA. « \*āppā », Second and Early MIA. « āppā » = OIA. « atmā ». The oblique forms are regular OB. derivations of the MIA. « appaṇa » stem. The OB. nominative « āpā, apā (= \*āpā) » is now rather obsolete in NB., the « -n- » oblique having encroached upon the realm of the nominative : « āpṣ », without « -n- », meaning *self*, is preserved in the nominative in Oriyā (āpē). Instances of the old form অপ *« āpṣ » self*, however, are found in Bengali : e.g., অপ ভালো তো জগত ভালো *« āpṣ bhalō tō jagatṭ bhalō » if self is good, the world also is good* (cf. Hindi. « āp bhalā tō jag bhalā ») ; অপ চাইতে পরের উপর দরদ *« āpṣ cāitē pārēṣ upārṣ dārād » anxiety for another more than for oneself* ; cf. also আপি আপি *« āpi-āpi » all by oneself*, in baby language (cf. Oriyā « āpē-āpē »). But in Eastern and Western Hindi, it has been extended to mean the honorific pronoun as well : e.g., Awadhī, both nominative and oblique, singular « āpu » plural « āp » = *your honour*, beside nominative « āpu », genitive « āpan », oblique « apanē » = *self, of self* ; Hindōstānī nominative and oblique singular « āp » *your honour, his honour*, plural « āp-lōg, āp-lōgō- », beside reflexive « āp », oblique « apnē », genitive « apnā, apnē, apnī ».

592. The extension of the sense from the Reflexive to the Honorific (Second) Personal Pronoun is a recent thing in NIA. It is absent in MIA. It is not found in OB. and eMB., nor in the older literatures in the other NIA. tongues. In Early Bengali documents (e.g., in the letter of c. 1555 A.C. from the Kōc king of North Bengal to the Ahom king of Assam, *supra*, p. 828), তুমি, তোমার *« tumi, tōmārṣ »* are used as respectful or honorific forms, not আপনি *« āpāni »* as in NB. or « āpuni » as in Assamese.



The Bihārī dialects employed, and even now employ, words like « āhā, ahā, ahaī ; ais ; raur ; rauwā » (see *infra*), and Eastern Hindī also employed « raur », for the honorific of the 2nd person : these words correspond to the NB. मोशायै, मशाय, महशाय « mōśāi, māśāyā, mähāśāyā » and the Urdū « janāb, huḡūr ». The use of the reflexive for the honorific second person is not an Eastern NIA. innovation : nor is it characteristic of the North-Western, South-Western, and Southern NIA. : *e.g.*, Panjābī (Eastern and Western) uses « tus(s)I », the ordinary plural, for the honorific, and « āp » is an imposition from Hindōstānī ; so Sindhi has « tavhī » (? = \*tusI < \*tussa- < \*tuṣma-, yuṣma-), and the reflexive « pāṇa » (= appaṇa < ātman-) is used as an honorific, as in the genitive « pāḥa-jō », to mean *yours* as well as *yours and mine* ; and in some of the dialects of Rājasthānī, and in Gujarātī, the reflexive base « āpā, āpaṇ- » is used, not to mean *you*, but *you and we* (Gujarātī, however, has « āp » as an honorific second person = *your honour*, declined like a regular noun, but in the plural and in the second person : this use of « āp » is possibly the result of Brajbbākhā or Hindōstānī influence through the Rājasthānī dialects : to denote *self*, New Gujarātī has the base « pōta- » < \*pōpa » < OWR. « apōpa » < Apabhraṇśa « \*appahu-appa- » : cf. Tessitori, 'Grammar of OWR,' § 92) ; and Marāṭhī employs the base « āpaṇ » as an honorific for all the three persons, as well as to denote the inclusive personal pronoun (1st and 2nd persons), like Rājasthānī and Gujarātī. Sinhalese partly agrees with the South-Western speeches in using the form « api, apa » (appa-) for the plural of the 1st personal pronoun, only it does not include the 2nd person. (The reflexive in Sinhalese is « tamā », a *sts.* form from « ātman » : Geiger, 'Litteratur und Sprache der Sinhalesen,' pp. 67, 69). Honorific use of the reflexive seems to be absent in the Himalayan (Pahārī) speeches ; and it is not found in Gipsy dialects outside India.

The Eastern, Northern, Western, South-Western, and Southern NIA. speeches thus do not seem to have developed in themselves the extension of the Reflexive for the Honorific of a special pronoun : in the last two groups, the reflexive was used as an inclusive 1st personal pronoun. On the other hand, we find that the Midland speech, Western Hindī, uses the reflexive

base for the honorific of both the 2nd and 3rd persons. It is exceedingly likely that the Eastern and other speeches borrowed this use of the reflexive from the Midland dialects, and the Magadhan speeches especially restricted it to the 2nd person only, as they possessed an honorific form for the third. Probably this borrowing is not older than two centuries from now.

593. The forms for the base আপন «āpān-» in Bengali are:

	OB.	Early MB. (ŠKK.)	NB. (Standard Coll.)
Nom.	apā (āpā), apaṇā, appaṇā	আপনে, আপুণী, আপুণি āpānē, āpuṇi, -I	আপনি āpāni, আপুনি āpuṇi
Acc.	apaṇā	আপনে, আপনাক, আপনা, আপন āpānē, āpānā-kā, āpānā, āpānā	... ..
Ins.	apaṇē	(as Nominative)	আপনি āpāni
Gen.	apaṇā	আপন, আপনা, আপনার āpānā, āpānā, āpānā-rā	আপন, আপনার, আপন- কার āpānā, āpānā-rā, āpānā-kārā
Dative	...	(as Accusative)	... ..
Oblique base	...	আপনা āpānā-	আপনা āpānā-

The nominative «āpāni» as an honorific has its final vowel through analogy of «tini, ini, uni, jini» etc.: otherwise we would expect «āpānē», and this form does occur dialectally. The plural is made in NB. by adding «-rā, -digā, -dērā» etc. to the oblique, as in the other pronouns. There is a base form, e.g., আপন পর «āpānā-pārā» *self and others*. The genitive আপনা «āpānā» (beside «āpānā») has the definitive «-ā».

594. There is the form আপস «āpāsā» used in the plural, = *among themselves, mutually*, which is found also in W. Hindi and other NIA. The form is obscure, but it can be from a MIA. genitive «\*appassa» (< \*ātma-sya = ātmanah), as Beames suggested (Comp. Grammar, II, pp. 330-331). It is used in Bengali in the locative as well as the genitive, but in a locative expression only: e.g., আপসে «āpāsē», আপসের মধ্যে «āpāsērā mādhya» *among themselves (ourselves, yourselves)*. Can it be affiliated to a MIA. locative plural «appasu = ātmasu», as a solitary survival of a loc. pl. form in NIA.?



595. A blend of « āpa » and the Skt. « ātma- », pronounced [ātta], has given the MB. and NB. আশু « āptā » of *self*, which has quite a currency in some compounds, e.g., আশু-জন « āptā-jāṇḍ » *relations*, আশু-সুখী « āptā-sukhī » *seeing to one's own happiness*, আশু-নারী « āptā-nārī » *one's own wife*, আশু-গরজে < গরজিয়া « āptā-gōrjē < -gārāj-iyā » *selfish* (Perso-Arabic garz, cf. Pers. xṽud-garzi), etc.

596. Among dialectal forms for this pronoun may be noted only the S.E. Vagga (Chittagong) আঁওনে, আঁওনা « āñōnē, āñōnā », or আঁনে, আঁনা « āñē, āñā », with rather long « ā », which show the nasalisation of the NIA. « -p- » : « -p- » > « -w- » > « -w̃- ».

597. The *ts.* word নিজ « nijā, nijā » is used in NB. to denote *self*. It is found as a *bbh.* « nia » in the Caryās in some 3 places, but the *ts.* « nijā » is established in the ŚKK. (over a dozen times).

598. The Bihārī forms « rāur-, raur; rāuwā; āis-, ais-; āhā-, ahā- » may be noted. These are used as honorific terms of address, and also as equivalents of *your honour*. « rāur » is found in Eastern Hindī, and is very common in Bhōjpuriyā : it is from a MIA. « lāūla », occurring, e.g., in the 'Prabōdha-candrōdaya'; the source is an OIA. « rāja-kula- » or « rāja-kulya- » *royal* (cf. Hoernle, 'Gauḍian Grammar,' § 447): the Western equivalent of this word is « rāwal ». The word « rāuwā » is only an extended form of « rāū », which is from « rāja- ». The form « āis-, ais- » occurs in dialectal Maithilī; the source may be a form like « ati-śa » *pre-eminent*, or « atīśa » *supreme lord* (cf. « Atīśa », or « Atīśa », the title of Dīpaṅkara Śrī-jñāna, the Buddhist scholar and saint of Bengal, c. 1000 A. C., whose original name was Candra-garbha: Śarat Chandra Dās, 'Indian Pandits in the Land of Snow,' Calcutta, 1893, pp. 50, 51, 60): this can be compared with the use of « mahāśaya » in Bengali. The source of « āhā, ahā » is obscure : « ahā- » is found in Early or literary Maithilī, as nominative or vocative, and « ahā-, ahaī » are the oblique bases, « -ā-, -aī » of which are the genitive and instrumental plural forms. Connexion with the OIA. « bhavān », MIA. « bhavañ » presents some phonetic difficulties. The form « ahā, ahā-, ahaī- » is used in Maithilī not for superiors

in age or status, but among equals: and it is very likely that the OIA. \*āyusmān > MIA. \*āyasmā (as in Pali) is the source: this would give an Apabhraṃśa \*āmbha, \*āmba, ābhā. There is no form corresponding to ābhā, ābhā, ābhā; ābhā, ābhā, ābhā in Bengali, but it is possible that the personal affix \*-ēhē, -ē for the second person of the verb is connected with it (see *infra*, under Verb: 'Personal Affixes').

### [J] PRONOMINAL DERIVATIVES, ADJECTIVE AND ADVERB.

#### [I] Adjectives of Quality or Manner in যত- < -mātṣ >, যন- < -mānṣ >.

599. These are: তেযত, তেমন < tē-mātṣ, tē-mānṣ > in *that way, like that*; এযত, এমন < ē-mātṣ, ē-mānṣ > in *this way, like this*; ওযত, অযত, অমন < ō-mātṣ, ā-mātṣ, ā-mānṣ > *like that, in that way*; যেযত, যেমন < jē-mātṣ, jē-mānṣ > *like that, in the way that*; কেযত, কেমন < kē-mātṣ, kē-mānṣ > *like what? in what way?* The affix is added apparently to the nominative bases of the various pronouns: for the 3rd personal pronoun the oblique base has influenced the form, though we have সেযত < sē-mātṣ > which is rather rare. For the remote demonstrative the form ও- < ō- > has been broadened to < ā- >. The < -m- > in this affix is often pronounced as [w].

The source of < -mātṣ > in NB. and MB. is OB. < -manta > < OIA. < -mant-, -vant- >: cf. Vedic forms implying likeness or size, like < ētā-vant-, tā-vant- > *so great*, < yā-vant- > *as*, < ī-vant- > *so great*, < ki-vant- > *how far*, and Vedic and Sanskrit quantitatives like < ī-yat, ki-yat > *so much, how much*. The < -manta > affix in this employ seems to be peculiar to the eastern Magadhan speeches only. Oriyā, as being more archaic than Bengali-Assamese, preserves the full form in the adjectives < tē-māntā, ē-māntā, jē-māntā, kē-māntā >. The group < -nt- > changed to < -t- > in Bengali (see *supra*, p. 502). The Oriyā adverbs < ti-māti, ē-māti, ji-māti, ki-māti > also show the < -t- < -nt- >.

The < -mānṣ > forms of Bengali and Assamese are irregular. It seems that quite early in the OB. period, when the full form < -manta > was current, through contamination with the pronominal adjectives of quality in < -hana > (see *infra*, p. 853), < -manta > came to have a variant < \* -mana, \* -maṇa >. It is already well-established in the ŚKK., so much



so that the proper «-mâtâ» affix is much restricted, কেমনে, কেমনে, কেমন, কিমনে «kē-māṇē, kē-mānē, kē-māṇā, ki-māṇē», for instance, occurring some 20 times, and কেমতে «kē-mâtē» only twice. In NB., the «-t-» forms are archaic, even for the «sādhu-bhāṣā», and the colloquial knows only the «-n-» forms.

Bengali has also a form মতন «mâtāṇḍ» like, similar to (see next para), which is a blend of «-mâtâ» and «-mānâ».

This affix «-mâtâ, -mānḍ, mâtāṇḍ» quite early came to be regarded as a separate word in Bengali and Assamese, through confusion with the Skt. «mata, manas < √man>: e.g., আমার মত(ন) «āmārḍ mâtâ(nḍ)» like me, তোমার মত(ন) «tōmārḍ mâtâ(nḍ)» like you, পুরানো মত(ন) «purānō mâtâ(nḍ)» like old, oldish. As a separate word, মত «mâtâ» is now frequently written মতো «mâtō» (< «\*-mantaṭa, manta + ka>), following the pronunciation. The independent use of «mâtâ, mānâ» is fairly common in the ŚKK., where it generally occurs after and strengthens the pronominal adjective of quality in «-hānâ, -hānâ, -nâ>: e.g., কেন মণে, মনে, মতে «kēnâ + māṇē, mānē, mâtē» in what way; এহি মতে «ēhi mâtē» in this way; যেহু মনে «jēnhā mānē» in such a way that; NB. poetic হেন মতে «hēnâ mâtē» in this way.

Early Assamese had the «mâtâ, mānâ» forms: e.g., Śaṅkara-dēva, «hr̥di-sthitā huā tumi jēnâ kārābāhā swāmi, Hr̥ṣīkēśā, kārībā tēmānâ» remaining in my heart, just as you will make me do, Lord Hr̥ṣīkēśa, so shall I do (Dēvēśwar Chaliḥā, 'Asamīyā Sāhityar Burāñji,' Jorhat, Saka 1833, p. 123); «cāri dinā sēhi mâtē thākiyā Iśwārâ» in that way, the Lord, staying for four days (ibid., p. 133). Early Assamese also has forms like «jēntē, tēntē» etc. = «jēwāntē, tēwāntē < jēmāntē, tēmāntē». In Modern Assamese, the full «-m-» or the altered «-w-» forms no longer occur, but contracted ones, «ēnē, jēnē» < «\*ēmānē, jēmānē», pronominal adverbs, which seem to have merged into the «-hānâ, -hēnâ» forms (see *infra*).

With addition of the instrumental «-ē» we have corresponding adverbs: এমতে, এমনে «ēmātē, ēmānē» [æmote, æmone] in this way, কেমনে «kēmānē» [kæmone] how? etc.; but the adverbial use of the simple «mâtḍ, mānḍ», without the «-ē» affix, is also found. There is in NB. also a locative use of the «-mān-ē» forms, in which the «-ē» is certainly the locative affix:

কম্বে < kāmṇē > *where?*, যম্বে, যেম্বে < jāmṇē, jēmṇē > *in the direction that*, এম্বে < ēmṇē > *in this direction*, etc. (the forms < kâ- > etc., rather than < kē- > etc., are probably due to the analogy of কই < kâi > etc., for which see *supra*. Contracted forms of these adverbs of direction are found in dialectal Bengali: e.g., EB. কনে < kânē > (< kâṇē, kâṇnē, kāmṇē); এনে, এয়ানে < ēnē, ēānē > (< ēmānē) etc. Oriyā also has similar forms—< ēṇē, tēṇē > etc.

[II] Adjectives and Adverbs of Quality in হন, হেন, হ্, ন < -hānā > -hēnā > -hnā > -nā >.

600. NB. has the following: হেন, বেন, কেন < hēnā, jēnā, kēnā >, dialectally বেনে, কেনে < jēnē, kēnē > (with instrumental < -ē > affix). Besides there is a rare তেন < tēnā >. Of these, হেন < hēnā > alone is used as an adjective: e.g., হেন কাজ < hēnā kājā > *such work*; cf. also বেন তেন উপায়ে < jēnā tēnā upāyē > *in any way possible, by some means or other*. কেন, কেনে < kēnā, kēnē > simply means *why* < *in what way*, and বেন, বেনে < jēnā, jēnē > is also a conjunction = *so that, in order that*.

In eMB. (ŚKK.), the corresponding forms were (এ)হেন, তেহেন or তেহ্, বেহেন or বেহ্, কেহেন or কেহ্ < (ē-)hēnā; tē-hēnā, tēhnā; jē-hēnā, jēhnā; kē-hēnā, kēhnā >, and these were adjectives as well as adverbs—the instrumental < -ē > affix being commonly used for the adverb: e.g., কি নাম তাহার, কেহেন তার রূপ < ki nāmā tāhārā, kēhēnā tārā rūpā > *what is her name, what is her beauty like* (ŚKK., p. 11). In NB., the adjectives in < -mānā, -mānā > have practically ousted the < -hēnā, -hnā, -nā > forms from adjectival use.

The eMB. < -hēnā > forms correspond to the Maithili < ē-han, tē-han, kē-han > (< \* -hana >: the Bengali change of \* -hā- to < -hē- > is due to the influence of the preceding bases < ē-, jē-, kē-, tē- >).

The Māgadhī Apabhraṇśa source of the Maithili and Bengali forms would be \*āiḥaṇa- (or ēiḥaṇa-?), \*taiḥaṇa-, \*jaiḥaṇa-, \*kaīḥaṇa-; which would represent Second MIA. (Māgadhī) \*āiśaṇa-, \*taiśaṇa-, \*jaiśaṇa-, \*kaīśaṇa- (see *supra*, pp. 95, 555). OIA. has pronominal adjectives in < -dṛśa- >—< tāḍṛśa-, ētāḍṛśa-, yāḍṛśa-, kiḍṛśa- >



etc. This «-dṛśa-» affix became «-disa-, -diśa-», and then «-isa-, -iśa-» through loss of interior «-d-» in MIA. With a pleonastic adjectival affix «-na» (cf. Whitney, 'Sanskrit Grammar,' §§ 1223 g, 1245 f), this affix was extended, either in dialectal OIA. or in MIA., to give «yāśana (jāśana), tāśana (taśana)» etc., beside «jāśa-, tāśa-» etc. The OIA. vocalism of the pronominal bases has been regularised in MIA., through what process we do not know. The change of the sibilant to «-h-» in Maithili and Bengali is peculiar and unexplained. Early Oṛiyā shows forms like «jē-sāṇā», and Old Bengali like «āśana». The «-s-» forms occur in Magahi and Bhōjpuriyā, and in E. Hindī and W. Hindī, and in most forms of NIA. besides. The presence in OB. of the sibilant in these adjectives (as in «āśana, kaisē, jāisō, tāisō, āśa, kaisē» in the Caryās) is certainly due to Western Apabhraṃśa influence (see *supra*, p. 115). Similarly in Early Maithili we have the Western «-s-» forms side by side with the native «-h-» ones. Through the Brajabuli dialect the «-s-» forms were once more introduced into Bengal through W. Hindī influence, and from the 16th century onwards, the «-s-» was written ছ «ch»: e.g., বেছন «yāichāṇā = jāśāna», আইছন ঐছন «āichāṇā = āśāṇā», কৈছে «kāichē = Hind. «kāisē», কৈছন «kāichāṇā = kāśāṇā». The forms without «-n-», corresponding to the Western Hindī «aiśā, aiśī; aiśē» etc., do not seem to occur in East Magadhan.

In the ŚKK. occurs the correlatives জৈসানে, তৈসানে «jāisāṇē, tēisāṇē», as in জৈসানে রতি জাগবো, তৈসানে কাহু আনিবো «jāisāṇē rati jāṇābō, tēisāṇē Kāṇhā āṇibō» *when I shall understand love's sport, then I shall bring Kṛṣṇa* (p. 21). These correspond with Early Asamese «jāisāni» (ŚKK., Comm., p. 447): and they are Śaurasēnī «-s-» forms borrowed in OB. which persisted with the earlier literary tradition in MB. and Early Assamese: probably some sort of confusion with a word like সময় «samaya = saṁaya» also existed here.

[III] Nouns and Adjectives of Quantity in ত «-tā» or তো «-tō».

601. They are তত (তত), এত, অত, যত (যেত), কত < \*কেত «tātā, (tētā [tæto]); etā; ātā; jātā (jētā = [jētāto]); kātā < \*kētā», also ততক,

এতেক, [অতেক], যতেক, কতেক < tātēkṣ, ōtēkṣ, ātēkṣ, jātēkṣ, kātēkṣ >, with pleonastic < -ēkṣ > affix, as in Maithili. These agree with Oriyā < tētē, ōtē, sētē, jētē, kētē >, and Assamese < tētē(k), ōtē(k), kētē(k) > etc. Early Assamese also had forms in < -tā, -tō > like Bengali. Corresponding forms occurs in other NIA. speeches : *e.g.*, Hindōstānī < titnā, tittā ; itnā, ittā ; utnā, uttā ; jitnā, jittā ; kitnā, kittā >.

As sources of these in MIA., we have in Western Apabhraṃśa < tēttiu, ēttiu, jēttiu, kēttiu >, Second MIA. < tēttia, ēttia, jēttia, kēttia >, and First MIA. (Pali) < tattaka, ēttaka, kittaka >. These MIA. forms are derived from, or are connected with, Vedic quantitatives in < -yant- >, like < i-yant- > *so much*, < ki-yant- > *how much*. It seems that formations made up of the pronominal base + the affix < -yant- (-yat-) > + an adjectival < -tya, -tiya > (cf. Pischel, 'Grammatik der Pkt.-Sprachen,' § 153) gave in Early MIA. forms<sup>1</sup> like < i-yatta-, \*a-yatta- (\*i-yat-tiya, \*a-yat-tiya-) ; \*ki-yatta- (\*ki-yat-tiya-) ; \*ya-yatta- (\*ya-yat-tiya-) > etc., which were regularly altered into the Pali (with a pleonastic < -ka > as in < ētta-ka, kittā-ka >), Prakrit and Apabhraṃśa forms. The source-forms of Bengali would seem not to have had the < -ia > ending as in Western Apabhraṃśa (< ēttia, kēttia > etc. should give \*ētī, \*kēti > in NIA.), but rather < -a-ka > ending, as in Pali (ēttaka > ēttaa > OB., MB., ētaṃ, ētā > NB. ētā, ētō [eto]). In Caryā 35 we have < ēta-kāla > (see *supra*, p. 808).

The above forms are also used as nouns in Bengali, as in other NIA., and as such for the genitive they take not the simple < -rā- > affix, but the affix কীর < -kīrṣ >, or the archaic form কের < -kērṣ >.

In Bengali, the form কতক, কতোক < kātākṣ, kātōkṣ > has an indefinite sense (= kātā + ō, hō + -kā pleonastic : cf. kēu, p. 845). MB. has the emphatic কথো < kāthō > (= kātā + hō, hu), which corresponds in formation to the Maithili < kathū >.

<sup>1</sup> OIA. '-(t)tya' would be expected to become 'co' in MIA.; but a *sta.* 'tt' treatment is not unknown, cf. 'sḍitya-vāra > MIA. ālitta-vāra > NIA. (Hindī) āit-wār, it-wār' Sunday. In the present case, the form with intrusive 'i.' (*e.g.*, '\*ya-yat-tiya > yettia, jettia') certainly helped to prevent palatalisation of a corresponding '\*ya-yat-tya.'



[IV] Adverbs of Time in *ৱে* «-bē».

602. These are *তবে, এবে, যবে, কবে* «tābē, ēbē, jābē, kābē»; «ēbē» is archaic and poetic for NB., and it is also found as *ইবে* «ibē», *অবে* «ābē», dialectally in NB. and occasionally in MB. In OB., they were respectively «tabē, ēbē, jābē, \*kabē, \*abē (?)»—the first three actually occurring in *Caryās* 46, 35 and 21 respectively. Equivalents in *Oṛiyā* are «tēbē, ēbē, jēbē, kēbē», while «ābē» is not found. The difference in the vowel of the pronominal base between *Oṛiyā* (tē-, jē-, kē-) and Bengali (tā-, jā-, kā-) is to be noted. Modern Assamese does not possess these forms, but Early Assamese did, and the Early Assamese forms agree with the *Oṛiyā* ones. In Early and Modern Maithili «taba, tabē, tabē; aba, abē, abē, ābē; jaba, jabē, jabē; kaba, kabē, kabē» are found. In Western Hindi, the same forms are found as «tab, ab, jab, kab» (*Hindōstānī*), and as «tabai; abai, abē; jabai; kabai» (*Brajbhākhā*).

The forms in «-ē, -ai» are palpably locatives, with the locative affix «-ē, -ai < -ahi, ahi». The source of the forms in Western Hindi and in the Magadhan speeches would be Śaurasēnī and Māgadhi Apabhraṁśa forms like «\*tabba- (\*tēbba-), \*ēbba-, \*jabba- (\*jēbba-), \*kabba- (\*kēbba-), locative «\*tabbahi, (\*tēbbahi), \*ēbbahi», etc.

In Vedic the indeclinable «ēvā, ēvā» originally meant *thus*; in later Indo-Aryan it became merely an emphasising particle. In the sense of *thus*, however, in later Vedic, the form «ēvām» came in, and this «ēvām» in all likelihood is but an extension of «ēvā, ēvā». In Second MIA., «ēvām» became «ēvvaṁ», in the sense of *thus*. In MIA., «ēvvaṁ» seems to have occurred also as «ēbbam, \*ēbbā» which further seems to have developed a temporal sense from a modal one, and this temporal meaning was strengthened by putting it in the locative (\*ēbbahi, \*ēbbahi). Corresponding to «ēvā, ēvām > \*ēbbam» which in the Apabhraṁśa stage easily affiliated itself to the pronominal base «ū- < ēta-», it is exceedingly likely that other analogous pronominal adverbs were evolved, like «\*tēvā(m), \*yēvā(m), \*kēvā(m)», in Early MIA., which would become «\*tēvvaṁ > \*tēbbam» etc.; or «\*tavvaṁ > \*tabbam»

etc. through substitution of the pronominal bases in «-a-», namely «ta-, ya-, ka-». Thus all these are on the basis of «ēvā, evām > ēvvaṁ». The form «ab-ē, ab» would seem to be merely a weakening of «ēbai, ēbē».

Western Apabhraṁśa as in Hēma-candra actually has forms which would presuppose the new formations «\*tēva, \*yēva, \*kēva» on the model of «ēva»: and these forms show MIA. nasalisation of «-v-»: «emva = ēwa; temva = tēwa, tiwa»; jemva = jēwa, jiwa; kemva = kēwa, kiwa» (cf. Pischel, 'Grammatik der Pkt.-Sprachen,' § 261). NIA. representatives of these adverbs of manner are now found (see *infra*, p. 860). Locative forms of these occurred as adverbs of time in Western Apabhraṁśa: Hēma-candra actually cites «ēwahī=idāntīm» (Pischel, § 261). This «ēwahī» of course cannot give the Bengali «ēbē > ēbē», or the Maithili «abē», and Western Hindī «abaj»; but a parallel MIA. formation «\*ēvva- > ēbba-, ēbbahī» alone can.

[V] Adverbs of Time in খন «khāṇḍ».

603. These are তখন, এখন, যখন, কখন «tā-khāṇḍ, ē-khāṇḍ, jā-khāṇḍ, kā-khāṇḍ» = *then, now, when, when?*, besides an অখন < ওখন «ā-khāṇḍ < ō-khāṇḍ» *then, at that time* which is used as a sort of indefinite addition after future verbs (e.g., দেবোঅখন দেবো-খন, দেবে-খুন «dēbō-ākḥāṇḍ, dēbō-khāṇḍ, dēbō-khunḍ» *I shall give at some future time*, দেবে-অখন, দেবে-খন, দেবে-খুন «dēbē-ākḥāṇḍ, dēbē-khāṇḍ, dēbē-khunḍ» *he will give*: this influenced the past formations in the Standard Colloquial like দিলুম-খুন «dilumḍ-khunḍ» = *I gave then, and I gave*: see *infra*, Verb, 'Pleonastic Affixes'). The «khāṇḍ» is from the OIA. «kṣaṇa», which occurs in Bengali as a *sfx.* ক্ষণ «[kṣæ:n, (k)khon]»: «tat-kṣaṇam > takkḥaṇa, tākhāṇḍ» etc., with irregular absence of lengthening. This form of temporal adverb occurs in all the Magadhan languages. Cf. 'Prākṛta Pāṇḍala' (Bib. Ind. ed.), p. 304, «jakkḥaṇa vīra Hamira calē» *when Hamīr the warrior marches*; p. 318, «Kāsi-rāa jakkḥaṇa calē» *when the king of Kāśī marches*.



[VI] Adverbs of Place in *তা* «-thā».

604. We have *তথ* ( *সেথা* ), *হেথা*, *হোথা*, *বেথা* ( *যথা* ), *কোথা* «-tāthā (sēthā); hēthā; hōthā; jēthā (jāthā); kōthā», which have also locative forms *তথায়* ( *সেথায়* ), *হেথায়*, *হোথায়*, *বেথায়* ( *যথায়* ), *কোথায়* «-tāthāy (sēthāy), hēthāy, hōthāy, jēthāy (jāthāy), kōthāy». The Bengali *সেথা* «-sēthā» is a new formation with a generalised «-thā» base added to the nominative form «-sē», and «-hēthā, hōthā» are for «-ēthā, ōthā» with prothetic «-h-» (see *ante*, p. 556). OB. gives «-ēthu», a form influenced by W. Apabhraṃśa, in *Caryā* 15.

These «-thā» forms are based on MIA. «-taṭtha, ēttha (\*ōttha), yattha > jattha, kuttha (\*kōttha)» which already occur in Pali, and thus date from the First MIA. period. The corresponding OIA. forms are «-ta-tra, \*i-tra = a-tra, \*ava-tra, ya-tra, ku-tra». The aspiration in the MIA. forms presents a difficulty. This may be due to the «-r-» (see *supra*, p. 438). Pischel refers «-ōttha» to the Vedic «-itthā» (in Skt. «-ittham») = *thus* ('Grammatik der Pkt.-Sprachen,' § 107), and the rest apparently would follow analogically. But W. Geiger derives these from the «-tra» forms ('Pali Litteratur und Sprache,' §§ 9, 62), and cites cases from Pali where we have «-tth- < -tr-», like «-sōtthiya, sōtthiya = śrōtriya», and «-ubhayattha = ubhaya-tra». Can it be that we have the OIA. «-√sthā» here, in original forms like «-tat-stha, \*yat-stha» etc.?

Old locatives of these «-tha» forms like *তথি* «-tāthi», *যথি* «-jāthi» are used as oblique bases for their corresponding pronouns : see *supra*.

The MIA. forms were strengthened with the definitive «-ā» in OB. The «-thā» forms do not occur in Assamese and in Oṛiyā : the latter has «-sēthi, ēthi, jēthi, kēthi»; and corresponding «-th-» forms occur also in the Bihārī dialects (see *infra*, § 607).

Assamese has as adverbs of place «-tāt (tātē), jāt (jātē), kāt (kātē)», which correspond to the Maithilī «-tatay (tatē), jatay (jatē), katay (katē)», besides «-ētay (ētē)» and «-ōtay (ōtē)»; and W. Hindī (Brajbhāṣhā) has «-tita, kita (kata), jita» and «-ita, itai, Itai» and

« uta ». The Maithili forms occur in Brajabuli also. They are connected with the Western Ap. locatives like « tēttahē, ēttahē (tēttahi, ēttahi) » etc., noted by Hēma-candra : « tētta, ētta » etc. are apparently the OIA. « tatra, \*itra = atra » etc., altered in MIA. in some Western dialect, without the aspiration which we find preserved in Pali « tattha » etc. and Bengali হেথা « hēthā » etc.

[VII] Adverbs of Place in খানে « khānē », etc.

605. Like সেখানে, এখানে « sē-khānē, ē-khānē » etc. These are late formations, being compoundings of « sē, ē, ō, jē, kōṇḍ » and the noun খান « khāṇḍ » *place* ( < « khaṇḍa », see *supra*, pp. 365, 779 : there seems to have occurred some contamination with the Skt. « sthāna » as well as Pers. « xānah », both meaning *place* ).

606. There are similar compounds with ধার, ধারে « -dhārḍ, -dhārē » = *side, edge, bank, limit, line* (e.g., এদ্বারে « ē-dhārē », ওদ্বারে « ō-dhārē »), agreeing with the Hindōstānī « i-dhar, u-dhar » etc., and with Bhōjpuriyā « ihar, uhar » with weakening of « -dh- » to « -h- ». (Hoernle derives these latter differently : cf. p. 315 of 'Gauḍian Grammar'). The Maithili « em-har, jem-har » etc. are connected.

607. Dialectal Bengali (W. Raḍha) shows ইহে, উহে « indhē, undhē » *here, there*, etc. which agree with the Bihārī (Maithili) « indē » undē » or « inda, unda » etc. They seem to be connected with the Hindōstānī « yahā, wahā » etc., which are old MIA. ablatives, from Western Apabhraṇśa « \*cāhā, \*ōhā » < Second MIA. « \*cāmhā, \*ōamhā » < OIA. « ētaśmāt, \*avaśmāt » etc. From Māgadhi Apabhraṇśa forms similar to those of Western Apabhraṇśa, the new Magadhan dialects could easily have « ihā, uhā, inha, unba » and then « indha, undha », locative « indhē, undhē » etc.

608. Dialectal Bengali preserves also some locative forms in « ṭhi, -ṭi », e.g., সেটি, এটি, জেটি « sēṭhi, ēṭhi, jēṭhi » as in South-West Bengali ; ইটি, সেটি « iṭi, sēṭi » in North Bengali. This « ṭhi » seems to come from an OIA. « sthāman » *place* (see *supra*, under টাই « ṭhāi », p. 762).



Oṛiyā also has it, both as «*ṭhi*» and as an extended «*ṭhā-ra*» with the genitive affix.

609. The New Bengali correlatives যাই—তাই «*jāi, tāi*» *when—then*, *as soon as—immediately* are from the OIA. «*yadā-hi, tadā-hi*».

610. OB. as in the Caryās shows some adverbs of manner in «*-ma*», unquestionably pronounced «*-ṃa*»: *e.g.*, *jima*» (Caryās 13, 19, 29, 30, 31, 41, 43) and «*tima*» (Caryās 9, 43), and also probably «*kima*» (Caryā 39). These are Western Apabhraṃśa forms borrowed in OB. Cognate forms in other NIA. speeches are—Eastern Hindi «*jimi, ṭimi*» etc.; Western Hindi «*jyaū, tyāū; jyō, tyō; jyā, tyā; jū, ṭū*» etc.; Gujarāṭī «*jēm, tem*» etc. These are derived from Western Apabhraṃśa «*jeṃva, teṃva, keṃva = jēṃa, tēṃa, kēṃa*» etc., which are nasalised modifications of OIA. «*\*yēva, \*tēva, \*kēva*», formed on the analogy of «*ēva*» (see *supra*, p. 857. Cf. Pischel, 'Grammatik der Pkt.-Sprachen,' § 261; Tessitori, 'Grammar of OWR.', § 98 [3]).

## CHAPTER V

### THE VERB

[A] CONJUGATION OF THE VERB IN INDO-EUROPEAN, IN OIA., AND IN NIA.


611. The elaborate conjugation of the verb such as we find in Vedic and in Greek did not obtain in Primitive Indo-European. The conjugational system was exceedingly simple in the oldest period. There was no distinction of tenses as such, and the subjunctive and optative moods were just evolving out of the indicative. The verb root (in simple, extended, or reduplicated form), in the active voice, took up certain personal affixes, either added direct to the root, or with certain *themes*, or syllables like «-o-, \*-nu-, \*-so-, \*-to-, \*-sko-, \*-dho-» etc. which were added as links joining the root and the personal termination; and sometimes there was a nasal infix, «-ne-, -n-» which came in and modified the form of the root. The force of the affixed themes was to indicate the *aspect* or nature of the action, whether it was progressive or transitory, iterative or intensive, or indefinite. To express a state attained, as the result of a completed or perfected action, the verb root underwent a special modification in itself and further took up certain other personal terminations, slightly different and curtailed forms of the ones mentioned above. The conjugation of the verb in Primitive Indo-European thus fell into two parts, taking in view the kind of action (whether it was completed or not) and the kind of pronominal affixes it adopted accordingly. The paradigm of a root thus falls into two divisions—or *systems*—which have been named (i) the *Present-Aorist*, and (ii) the *Perfect*. These systems did not indicate time relation, but only the action in the present time, incomplete or perfected. If past time were to be emphasised, an adverbial particle «é», called the *augment*, which was always stressed, was placed before the verb form. In course of time this particle became loosely attached to the verb, and the combined




« \*é » (> Indo-Aryan = « á ») and verb form resulted in the imperfect and aorist (as well as the 'plu-perfect') tenses of Vedic and Sanskrit.

The themes or affixes which were added in between the root and the personal terminations (e.g., Skt. « kar-ō-ti, krī-ṇā-ti, div-ya-ti, sah-a-tē, ga-ccha-ti < IE. \*g<sup>w</sup>m-sko-ti », etc.) had in Prim. IE. each its special meaning or force, but in the later phase of IE., the earlier *nuances* were to a great extent lost, and in several cases they took up distinct and well-defined values not known before. Thus the « -s- » theme came to denote the past tense in Italic, Celtic and Slav, and developed into the aorist tense of Greek and Sanskrit; the « -so- » and « -syo- » themes developed into the future tense respectively in Greek and in Sanskrit and Baltic. The *Perfect System* gradually evolved into the perfect tense in most IE. languages: thus IE. « \*√dṛk » to see, with a strong grade (\*dórk), reduplicated (\*de-dórk) and with the personal affix « -a », gave a form « \*de-dórk-a », which was a present form, = *I am after completing the act of seeing*, form which easily developed the perfect or past sense of *I saw*, and the form became the perfect tense, as in Sanskrit (dadārśa) and in Greek (dédorka). The tense and mood forms of OIA. were developed in this way out of the simple *aspects* of IE. The tables below give the relation borne by OIA. tenses to the Prim. IE. forms :

(i) Indo-European Present-Aorist System.



(ii) Indo-European Perfect System



Originally in IE. there were two moods, the indicative and the imperative. From the indicative developed the conjunctive and the optative. The thematic vowels « \*-ē-, \*-ē-, \*-ō-, \*-ō- » which at first denoted some particular aspect of the action in the indicative, came to acquire the sense of a special mode, that of the conjunctive or subjunctive : and in some of the IE. languages they became well-established as modal affixes, deviating from their original aspect-indicating function. Similarly the affixes « \*-yē-, \*-yē-, \*-ī-, \*-oi- » came to be associated with the optative mood : originally (like the « \*-ē-, \*-ē-, \*-ō-, \*-ō- » above, and the « -s- » of what later became the aorist, as well as « \*-syē-, \*-syē- » of what was later changed to the future ), « \*-yē-, \*-yē- » etc. indicated some aspect of the action, as much as « -nu-, -nā- » and the other *themes* which have not become specialised for a mood or tense and of which the proper force is no longer understood. And themes of the groups « \*-yé-, \*-yó- » and « \*-éye-, \*-éyo- » became respectively the affixes of the denominative and causative forms. The germs of these later modal and other developments in all cases existed in these aspect-indicating themes of Primitive IE.

612. Below is given a conspectus of all the conjugational forms of Vedic, from its own stand-point, and not in historical relationship to Prim. IE. :—the development and systematisation of the former from the latter has been of an intricate character.

This will indicate the extent of the losses sustained by Bengali, which is typical for all NIA.

A CONSPECTUS OF OIA. (VEDIC) VERB-FORMS.

Root: « car », or « cal » to move, to walk. (Finite forms given are of the 3rd person singular, unless otherwise stated).



## I. The Present System.

## A. Indicative Mood :

## (i) With Primary Personal Affixes = Present Tense :

(a) Active Voice . *cár-a-ti* ( *cár-a-si*, *cár-ā-mi*, etc).(b) Middle Voice : (1) Reflexive : *cár-a-tē* ; (2) Passive : *car-yá-tē*.

## (ii) With Secondary Personal Affixes, preceded by the Augment = Imperfect Tense :

(a) Active : *á-car-a-t*.(b) Middle : (1) Reflexive : *á-car-a-ta* ; (2) Passive : cf. *á-hū-ya-ta*.

## (iii) With Secondary Personal Affixes, without Augment = Injunctive :

(a) Active : *cár-a-t*.(b) Middle : (1) Reflexive : *cár-a-ta* ; (2) Passive : cf. *sū-yá-ta*.

## B. Subjunctive Mood :

## With Primary Personal Affixes = Present Subjunctive :

(a) Active : *cár-ā-ti*, *cár-ā-t*.(b) Middle : (1) Reflexive : *cár-ā-tāi*, *cár-ā-tē* ; (2) Passive : cf. *bhri-y-ā-tē*, *uh-y-ā-tē*.

## C. Optative Mood :

## With Secondary Personal Affixes = Present Optative :

(a) Active : *cár-ē-t*.(b) Middle or Reflexive : *cár-i-ta*.

## D. Imperative Mood :

(a) Active : 2 sg. *cár-a*, 2 pl. *cár-a-ta*.(b) Middle : (1) Reflexive : 2 sg., *cár-a-sva* ; (2) Passive : cf. 2 sg., *hū-yá-sva*.

## E. Participles of the Present System :

(a) Active : *cár-ant-*.(b) Middle : (1) Reflexive : *cár-a-māṇa* ; (2) Passive : *car-yá-māṇa*.

II. The Aorist System, in Simple or Non-Sigmatic, Sigmatic (with « -s-, -sa-, -iṣ-, -siṣ- »), and Reduplicating forms of Roots.

A. Indicative Mood :

(i) With Secondary Personal Affixes *plus* Augment = Aorist (past).

(a) Active: á-cār-ṣ-I-t, á-cār-I-t, á-ci-car-a-t; cf. á-ruk-ṣa-t, á-vid-a-t.

(b) Middle: á-cār-ṣiṣ-a-ta, á-cār-a-ta, á-ci-car-a-ta; cf. á-vid-a-ta, á-bud-dha, á-stō-ṣ-ṭa, á-sthi-ta;  
Passive: 3 sg. only: á-cār-i.

(ii) With Secondary Personal Endings, without Augment = Injunctive Aorist.

(a) Active: cār-I-t; cf. dvik-ṣá-t, kār-ṣ-I-t, bhū-t, di-dhar-a-t, etc.

(b) Middle: cār-ṣiṣ-a-ta, cār-a-ta, ci-car-a-ta: cf. 1 sg. sthē-ṣ-am; páv-iṣ-ṭa; 3 pl. hā-siṣ-ur; vid-á-ta; vṛ-ta, 3 pl. si-ṣap-a-nta etc.

B. Subjunctive Mood :

Subjunctive Endings added to Aorist Base, without Augment = Subjunctive Aorist.

(a) Active: cf. stō-ṣ-a-ti, stō-ṣ-a-t; kār-iṣ-a-t; yá-siṣ-a-t; vid-á-ti, vid-á-t; kār-a-ti; si-ṣadh-ā-ti.

(b) Middle: cf. stō-ṣ-a-tē; 3 pl. sán-iṣ-a-ntē; vid-á-tē; kār-a-tē.

C. Optative Mood :

(i) Optative Endings added to Aorist Base = Optative Aorist.

(a) Active: cf. vid-é-t; bhū-yá-t; vōc-é-t.

(b) Middle: cf. bhak-ṣ-I-ta, mam-siṣ-ṭa; jan-i-siṣ-ṭá; ar-I-tá.

(ii) Aorist « -s- » added after Optative Base « -yā-, -I- » = Benedictive or Precative :

(a) Active: car-yá-s: cf. gam-yá-s, bhū-yá-s.

(b) Middle: car-I-ṣ-ṭa: cf. pad-I-ṣ-ṭa.



## D. Imperative Mood :

- (a) Active : cf. 2 dual, mṛk-ṣá-tam ; 2 sg. nē-ṣ-a, av-iḍ-ḍhi, sad-á, kṛ-dhí, bōdh-í.  
 (b) Middle : 2 sg. dhuk-ṣá-ṣva ; 2 sg. sák-ṣva ; 2 dual, yā-ṣiṣ-ṭám ; 2 pl. sad-a-dhvam ; 2 sg. kṛ-ṣvá, yuk-ṣvá.

## E. Participles of the Aorist System :

- (a) Active : cár-ṣ-ant- ; cf. sák-ṣ-ant-, śuc-ánt-, gm-ánt-, kr-ánt-, sth-ánt-, etc.  
 (b) Middle : cf. śuc-á-māna, kr-āṇá, budh-āná, yam-a-s-āná, mand-a-s-āná, etc.

## III. The Future System.

## A. Indicative Mood.

- (i) With Future «-syá-» Base and Primary Personal Endings = Future Tense.  
 (a) Active : car-i-ṣyá-ti.  
 (b) Middle : car-i-ṣyá-tē.  
 (ii) Augment Preterit of the Future, with Secondary Personal Endings = Conditional.  
 (a) Active : á-car-i-ṣya-t ; cf. á-bhar-i-ṣya-t.  
 (b) Middle : á-car-i-ṣya-ta.

## E. Participles of the Future System :

- (a) Active : car-i-ṣyá-nt-  
 (b) Middle : car-i-ṣyá-māna : cf. stav-i-ṣyá-māna.

## IV. The Perfect System.

## A. Indicative Mood :

- (i) Primitive Indo-European Present of the Perfect System = Perfect in Sanskrit.  
 (a) Active : ca-cār-a.  
 (b) Middle : cār-é, cf. tēp-é, da-dh-é,

(ii) Augmented Perfect=Imperfect of the Perfect System=Vedic Pluperfect:

- (a) Active: cf. á-ca-cakṣ-a-t.
- (b) Middle: cf. 3 pl. á-ca-kri-ran.

(iii) Injunctive Perfect, without Augment:

- (a) Active: cf. ta-stambh-a-t.
- (b) Middle: cf. di-diṣ-ṭa.

B. Subjunctive Mood:

Subjunctive Inflexions added to Perfect Base=Subjunc. Perfect.

- (a) Active: cf. mú-mōc-a-ti, mu-muc-a-t.
- (b) Middle: cf. ta-táp-a-tē, jú-jōṣ-a-tē.

C. Optative Mood:

- (a) Active: cf. ja-gam-yá-t.
- (b) Middle: cf. va-vṛt-t-tá.

D. Imperative Mood:

- (a) Active: cf. ci-kid-dhí.
- (b) Middle: cf. va-vṛt-svá.

E. Participles of the Perfect System:

- (a) Active: cf. ca-kṛ-vāms, ja-gm-i-vāms.
- (b) Middle: cf. tēp-āná, ja-gm-āná.

#### V. Participles.

A. Active and Middle, as under the various Tense Systems above.

B. Past or Passive Participle: car-i-tá; cf. li-ná, kṛ-tá.

C. Perfect Participle: car-itá-vant (a late formation).

D. Future Passive Participles and Adjectives: cár-ya, car-áyya, car-éṇya, \*cár-tva, car-tavyà, car-i-tavyà, car-aṇ-íya.

E. Indeclinable Participle or Conjunctive: car-i-tvā, car-i-tvī; -cár-ya; cf. kṛ-tvā, kṛ'-tya.

#### VI. Verbal Nouns and Infinitives:

cáras, car-āsē; cár-i-tu-m, car-i-tav-āi, cár-i-tav-ē, cár-i-tō-s; car-í, car-áy-ē; car-i-ty-āi; car-ádhy-āi; cár-am; -cár-a-m; car-aṇ-i; car-í-tra; car-á-ṭha; cf. also bhár-maṇ-ē, dā-vān-ē, dhúr-van-ē, sã-táy-ē.



## VII. Periphrastic Forms.

A. Perfect Active : car-ay-ām + āsa, -babbhūva, -cakāra.

B. Future : caritā, 1 sg. caritāsmi.

## VIII. Secondary Conjugations.

A. Passive : car-yá-tē (Present), á-cār-i (Aorist 3 sg.).

B. Causative : inflected forms like cār-āya-ti, cār-āya-tē, á-cār-āya-t, cār-ay-iṣyá-ti, cār-áy-ē-t, cār-āya-tu, á-cār-ay-i-ṣy-a-t, cār-yá-tē; etc.; Active Present Participle cār-áy-ant-, Passive cār-yá-māṇa, etc.

C. Denominative : cār-āyá-tē, cār-āyá-tē, etc.

D. Desiderative : cí-car-iṣ-a-ti, cí-car-ṣ-a-ti; á-ci-car-ṣ-it; ci-car-i-ṣyá-ti; Causative-Desiderative—ci-car-iṣ-āya-ti; etc.

E. Intensive : Indicative cār-car-i-ti; also Optative, Imperative, Imperfect Indicative, etc. Present Active Participle, cār-i-car-ant-; Passive Participle—cār-car-āṇa (cf. kán-i-krad-ant-, jár-bhur-āṇa), car-cūr-yá-māṇa.

613. Compared with the above elaborate system, that of the NIA. speeches shows a very great simplification. And Bengali (with Assamese) is perhaps more simplified than any of its sisters and cousins—the distinction in number for verb forms, which obtains in almost all NIA. speeches, the inflected passive, the « karmaṇi » and « bhāvē prayōgas » of W. Hindī, Panjābī, Rājasthānī etc., the negative conjugation of Khaskurā, etc., are all absent. The curtailment of the OIA. system has been carried out along the lines indicated below, to give that of Bengali :

I. The Present System : the OIA. *themes* have been in a few instances retained in the root in NB.

A. Indicative Mood :

(i) The forms for the Present Tense alone have been retained :

OIA. calati > NB. cālē :	OIA. calanti > NB. cālēṇā ;
calasi > cālī-s :	calatha > cālā, cālō.
calāmi > cālī :	(calāmaḥ > cālō).

## D. Imperative Mood :

3 pers. calatu > cālāu > cālu, cālu-kṣ; calantu > cālunṣ;

2 pers. cala > cālṣ; calata > cālā, cālō.

## E. Participles :

(a) Active : calant- > calanta > cālāntā, cālīt- (=the base of the Conditional or Habitual Past).

(b) Passive or Middle : calamāna > cālānā (with Causative influence).

## II. The Aorist System : entirely lost.

## III. The Future System :

A. The Indicative future in « -gyā- » was inherited in OB., but NB. retains only the forms for the 2 person as a Future Precative, or Imperative with Future implication : « calisyasi > cālīs, calisyatha > cālīhā > cālō > cōlō ».

## IV. The Perfect System : entirely lost.

## V. Participles :

The Past Passive Participle in « -tā, -itā », fortified in Late MIA. by the pleonastic « -illa » affix, gave the Past as well as Adjectival Base of Bengali, in « -ila », and also the Conditional Gerund in « -il-ē »; without the « -ila », this OIA. « -(i)tā » participle in the source of the Bengali Verbal Voun in « -ā ».

The Future Passive Participle in « -(i)tavya » was altered into the Bengali Future Base in « -ibā », and of the Verbal Noun in « -ibā ».

The Conjunctive Participle affix « -ya » of OIA. lives in the Bengali Conjunctive affix « -i-yā ».

## VI. Verbal Nouns :

Some have been preserved : « cālṣ, cālṣ, cāl-ānṣ » etc.

## VII. Periphrastic Forms—not preserved.

## VIII. Secondary Conjugations :

The Causative, in the MIA. form of « -āpa- », and the Denominative, are partially represented in the Bengali affix « -ā- ». The original ablaut grade of the Causative has occasionally been maintained.



The above are thus the comparatively few forms inherited by Bengali as a NIA. language. In MB. and OB. a few other relics of OIA. forms are found which are already tending to become obsolete. The losses have been to a great extent made good by newer formations (*e.g.*, by the development of compounded verbs, and the use of particles and help-words). The syntax too has altered, to help in fixing the language in its new and altered environment.

### [B] BENGALI VERB-ROOTS.

#### [I] HISTORICAL CLASSIFICATION.

**614.** The number of Sanskrit verb-roots, according to the grammarians, comes up to some 2,000 (1961, according to N. L. Westergaard's lists in O. Böhtlingk's 'Pāṇini,' Leipzig, 1887, pp. 62\*-84\*). Of these, only slightly over 800 have been found in literature (Vēdas, Brāhmaṇas, the Epics, and Early Sanskrit works), employed their conjugated forms. Of this number, again, some 200 belong to the Vēdas and the Brāhmaṇas alone, about 500 occur in both Vedic and Sanskrit, and less than 150 are found in the later literature alone (W. D. Whitney. 'The Roots, Verb-forms and Primary Derivatives of the Sanskrit Language,' German ed., Leipzig, 1886, p. 244). OIA. as in the Vēdas and the Brāhmaṇas has consequently registered less than 700 roots which were in living use as verbs, apart from those occurring only in nominal and other derivatives. This number, 700, can by no means be said to exhaust all the verb-roots in the speech of the OIA. period, but considering the extent of the Vedic and Brāhmaṇic literature, and fact that this literature touches upon almost all the aspects of the life of the times, the number of roots not represented cannot be very many.

Many of the 800 roots actually used in OIA. literature (Vedic and Early Sanskrit) are merely extensions of primitive roots, and in some cases, as we advance into the MIA. stage, are but Prakritic modifications of OIA. roots. The number of primitive roots inherited from IE. by OIA. will necessarily be rather small. Be it as it may, the absence of some 200 Vedic roots in Sanskrit shows that this inheritance was not retained

intact by the Aryan speech in India. Old roots changed their meaning, and went out of fashion; and the losses were made good by building up anew with the old materials, and in a few rare instances by possible borrowings from the non-Aryan speeches. The MIA. vernaculars employed a large number of derived forms as new roots. The spoken language reacted on the literary speech, Sanskrit, and numerous MIA. forms were adopted into Sanskrit in a slightly altered form, and were gradually accepted by the Sanskrit grammarians, and given an equal place with the primitives. There could be no rule to guide the caprice why some Prakrit roots were taken up and others rejected by Sanskrit: thus « brud < budḍa, hinḍ, hikk, khēl, kaṭṭ, lag, piṭṭ » and a number of others have found a place in both the « dhātu-kōṣa » and the literature of Sanskrit, but other equally good Prakrit roots like « kaḍḍha < kṛṣṭa, lukka, cukka, phiṭṭa, cagh, bhar < smṛ, ghūl < ghūrṇa » were rejected. The grammarians of later ages (from the Second MIA. period) seem to have encouraged this practice to some extent. Sanskrit the language the Gods and the *Rishis* was the mother of all language, and this was apparent from the vernaculars of Northern India; consequently, vernacular words and roots must necessarily originate from those of Sanskrit: when the grammarians were agreed on this principle, at a time when the historic development of forms by phonetic and other changes was not fully understood, the Sanskrit « dhātu-kōṣa » began to grow in extent by the accession of new roots foisted on it by grammarians. Of the roots in the current « dhātu-kōṣas » a small number may even have been the creations of grammarians to explain words of doubtful etymology; but the bulk of them may legitimately be regarded as having been in actual use in IA., though not in its oldest period. Thus in addition to the aristocratic roots of direct IE. origin like « as, bhū, sthā, gam, yā, ad, mṛ, dṛś, dram, cal, pat, dhā, div, mṛj, snih, duh » etc., the « dhātu-kōṣas » give as good Sanskrit humbler roots of late and obscure origin, like « 'gu(n)li' vēṣṭanē, cūrṇikaraṇē'pi; 'dīpa' kṣēpē; 'bha(n)ḍi' parihāsē; 'kha(n)ḍi' manthē; 'capa' kalkanē; 'juḍa' prēraṇē; 'caha' pari-kalkanē; 'khiṭa' uttrāsanē; 'lōḍṛ' unmādanē; 'jimu' adanē; 'huḍṛ, hōḍṛ' gatāu; 'dīṇa' vibhāyasa-gāmanē; 'muṭa'



sarīcūrṇanē; 'dhakka' nāśanē; 'bukka' bhāṣanē; 'kaṇa' nimīlanē; 'kaḍḍa' kārkkāśyē; 'laḍa' vilāsē; 'aḍḍa' abhiyōgē; 'aḍa' udyamē; 'ṭuṭa' alpa-bhāvē, etc., etc., which have in almost all cases NIA. equivalents, and can in the majority of cases be explained easily as secondary formations from words derived from primitive Aryan roots; the origin of quite a number of them, however, remains obscure.

615. The number of verb-roots in Bengali is 1,056, according to the excellent grammar of Paṇḍit Nakuleśwar Vidyābhūṣaṇa (4th ed., Calcutta, Bengali year 1315). This includes original or primitive roots, causatives, and a number of denominatives used chiefly in literature, and excludes onomatopoeics. A Bengali « dhātu-kōṣa » of about 1,500 roots has been easily compiled by me on the basis of Jñānēndra-Mōhan Dās's dictionary (see *supra*, p. 218): this includes onomatopoeics, and a number of obsolete roots not used in NB., beside a large number of Sanskrit denominatives used in high literature. The number will be much larger if proper *tbh.* roots in early Bengali literature and in the present-day dialects are all brought together.

Roots in Bengali, as in other cognate IA. speeches, can be classified on the lines indicated below, taking into consideration their origin, and partly also their function :

- |                    |   |  |  |
|--------------------|---|--|--|
| 1. Primary Roots   | — | Primary Roots inherited from OIA. ( <i>tbh.</i> ) :                          |  |
|                    |   | (a) Simple Roots, (b) Prefixed Roots.  |  |
|                    |   | — Primary Roots from Causatives in OIA.                                      |  |
|                    |   | — Primary Roots re-introduced from Sanskrit ( <i>tsa.</i> and <i>stas.</i> ) |  |
|                    |   | — Primary Roots of doubtful origin ( <i>dēśī</i> ?)                          |  |
| 2. Secondary Roots | — | Causatives in « -ā- ».   |  |
|                    |   | Denominatives  | Native ( <i>tbh.</i> ) — (a) Early (inherited) |
|                    |   |  | — (b) MB. and NB. (coined)                     |
|                    |   |  | — <i>Tatsama.</i>                              |
|                    |   | — Foreign.   |  |
|                    |   | — Compounded and Suffixed ( <i>tbh.</i> )                                    |  |
|                    |   | — Onomatopoeic.  |  |
|                    |   | — Doubtful.  |  |

(1) Primary Roots.

616. Primary Roots in Bengali, at a rough computation, number about 300. Strictly speaking, denominatives derived from MIA., which number about 100, may be classed under primary roots, since they have been inherited as roots by Bengali and behave exactly like primitive roots derived from OIA. (e.g., a root like কাড় *\*kār* *\*snatch away* < *\*kaddha = kṛṣṭa*); these might have been denominatives in MIA., but the nouns or adjectives which were their sources are in many cases obsolete in Bengali.

617. There are a little less than 200 roots in Bengali which can mostly be traced right up to primary roots of OIA. (Vedic and Sanskrit, and in some cases only to the early Prakrits). Examples are, of unprefixd roots: *\*আছ āch* (MIA. *acchati*, IE. *\*es-sko-ti*); *ইছ ich* (*icchati*); *কষ kās* *tighten* (*kṛṣ*); *কর kār* (*kṛ*); *কাঁদ kād* *weep* (*krand*); *কাঁপ kāp* (*kamp*); *কাট kāt* (*kṛt*); *কিন kin* (*krināti*); *কুঁদ kūd* (*kūrdati*); *খন khān* (*khan*); *খা khā* (*khād*); *খুঁজ khūj* *seek* (? *kṣudyatē*); *খেল khēl* (*khēlati*); *গণ, গুন gān, guṇ* (*gaṇ*); *গিল gil* (*gil, gir*); *চর cār* *graze* (*car*); *চল cāl* (*cal*); *চি ei* *awaken* (*cit*, cf. *cāyati*); *চু eu* (*cyav*); *চুন* (*cinōti*); *চুম cum* (*cumb*); *ছা chā* (*chād*); *ছাড় chār* (*chard*); *ছিঁড় chīṛ* (*chīṇḍ, chindati*); *ছেঁচ chēc* (*sic, siñc*); *জপ jāp* *persuade* (*jalp*); *জাগ jāg* (*jāgr*); *জি ji* (*jiv*); *জিন jin* (*jīnāti*); *জল jwāl* = *জল jāl* (*jval*); *টান tān* (*tan*); *টুট tūt* (*truṭ*); *ঢাঁহ ḍāh* (*dah*); *ঢাক ḍhāk* (MIA. *ḍhakk*); *তর tār* (*ṭṛ*); *তার tāj* (*tarj*); *তুল tul* (*tul*); *ঢ়শ ḍāś* (*darś*); *দল dāl* (*dal*); *দুল dul* (cf. *dōla*); *দুহ duh* (*duh*); *দুষ duṣ* (*duṣ*); *দে dē* (*dā*); *দেখ dēkh* (MIA. *dekkh* < *dṛks*); *ধর dhār* (*dhṛ*); *ধ্বর dhwās* = *ধস dhās* (*dhvas*); *ধা dhā* (*dhāv*); *ধো dhō* (*dhāv*); *ধুন dhun* (*dhvan*); *নাহ nāh* (*snā*); *নে nē* (*ni*); *নু, নো nu, no* (*nam*); *পচ pāc* *to get rotten* (*pac*); *পি pi* (*pibati*); *পিঁজ piṅ* (*piñj*); *পুছ puch* (*prechati*); *পুঁজ pūj* (*pūj*); *ফাটি phāt* *split* (OIA. *sphāt* < *\*sphlt*); *ফুট phut* (*ibid*); *বন্ট bāt* *distribute* (*vaṇṭ*); *বট bāt* *remain, be* (*vṛt*); *বর bār* (*vṛṣ* ?); *বাঁচ bāc* *live* (*vañc*); *বোল bōl* (*brū*); *বস bās* (*vas*); *বহ bāh* (*vah*); *বাঁধ bādh* (*bandh*); *বিঁধ biḍh* (*vyadh*); *বুঁজ bujh* (*budh*); *বুল bul* *wander about* (*val*); *ভজ bhāj* (*bhaj*); *ভর bhār* (*bhṛ*); *ভাজ bhāj* *fry, roast* (*bhṛj*); *ভাঁজ bhāj* *fold*



(bhañj); ভূষ bhūṣ (bhūṣ); মহ mäh *churn* (math); মজ maj *sink, get juicy* (majj); মিশ mis (miśr); মিল mil (mil); মাড় māṛ (mṛd, mard); মাখ mākḥ (mrakṣ); মল māl (mard); যা jā (yā); যাচ jāc (yāc); যুজ kujh (yudh); রাখ rākḥ (rakṣ); লহ lāh (labh); লখ lākḥ (lakṣ); লাগ lāg (lag); লাজāj (lajj); লাল lāl (lal); লুঠ luṭṭh (luṭṭh); শুষ śuṣ (śuṣ); শুন śun (śṛṇōti); শুক śūk (śuggh); শো, সো śō, *lie down* sō (svap); সহ sah (sah); সর sār (sr); †সি si (siv); সিঁধ sijh *be boiled* (sidh); শোহ, সোহ sōh (śubh); হের hēr *scrutinise, gaze* (cf. ākheṭa *hunting*) >, etc., etc.

Of prefixed roots, examples are « আ ā (ā-yā); আস, আইস ās, āis (ā-viś); আঙল āoj *make half-shut* (ā-vṛj); আঁচা ācā (ā-cam); আন ān (ā-ni); আছাড় « āchār » *dash, throw down with force* (ā-chard); উছল uchāl *overflow* (ut-śal); উঠ uṭṭh (ut-sthā); উত্তর utār *reach* (ut-tṛ); উপেক্ষ upēkh (ut-pra-ikṣ); †উই ui *rise, as the sun* (ud-i); উজা ujā *flow up, as a river* (ud-yā); উপচ upāc *flow over* (ut-patyatā); উপজ upāj (ut-padyatā); উলহ, উল, উর ulāh, ul, ur *descend* (ut-labḥ); নিবা, নিভা nib(h)ā (nir-vā); নিখর nirākḥ (nir-ikṣ); নিসর nisār (niḥ-sr); নিহাল, নিহার nihāl, nihār (ni-bhāl); †নিবড় nibār *finish* (nir-vṛt); †নেউট nēuṭ *return* (ni-vṛt); পাখাল pākḥāl (pra-kṣāl); পরখ pārākḥ (pari-ikṣ); †পরশ pārāś *serve food* (pari-viś + sparśa); পর < পহির pār < pāhir (pari-dhā); পরিহর pārihār (pari-hṛ); পস, পইস pās, pāis (pra-viś); পোছ pōch *wipe* (pra-uñeh); পোহা pohā *dawn* (pra-bhā); বস, বইস bās, bāis (upa-viś); ভিজ bhij *get wet* (abhi-añj); বিক bik *sell* (vi-kri); †সাঁতর sātār *swim* (sam-tṛ); সামাল sāmāl *gather up, save* (sam-bhāl); সাঁপ sāp, sōp (sam-arp) >; etc., etc.

618. The primary roots have all come to Bengali through the MIA., and as such they bear the stamp of the phonetic modifications of the various periods. The ten classes (gaṇas) into which the Sanskrit grammarians have arranged OIA. verb-roots, taking into consideration their *themes*, became levelled down to one in Apabhraṇśa, and all original thematic affixes which were added to the root in the present system were lost in MIA., being either dropped or incorporated with the root. In some instances, however, a characteristic theme could not be dropped; and the presence of the « -ya- » theme is indicated by the result of its assimilation with the consonant of the root. Bengal

primary roots inherited from OIA. have preserved only a few traces of these themes : thus—

1. « -ya- » theme : *e.g.*, « সিধে sijhē (sidh-ya-ti) ; নাচে nācē (naccāi, nrt-ya-ti) ; যুদ্ধে jujhē (yudh-ya-ti) ; শুধে śuṣṭhē (śuṣ-ya-ti) ; বুধে bujhē (budh-ya-ti) ; সমুদ্রে samujhē (sam + budh-ya-ti) ; টুটে ṭuṭē (truṭ-ya-ti) ; মানে mānē honours (man-ya-tē) » ; etc.

2. « -nō- » theme : « চুনে cune *culls, selects* (ci-nō-ti) ; শুনে śunē (śr-ṇō-ti) ; ধুনে dhunē (dhu-nō-ti) » ;

3. « -nā- » theme : « কিনে kinē (kri-ṇā-ti) ; জিনে jinē (ji-nā-ti) » ; (cf. জানে jānē = jānāti) ;

4. The « -ech- » theme (= IE. \*-sko-), not recognised by Sanskrit grammarians, occurs in the roots « আছে āchē (acchati, \*es-sko-ti) ; ইচ্ছে icchē (icchati) ; পুছে puchē (pṛcchati) ; পহুছে pāhūchē (pahuñcaī, pahucchaī, \*prabhucchati, \*pro-bheu-sko-ti) ».

Original Passive forms, with « -yā- » affix of the Passive, *e.g.*, « উপজর upācāy overflows (utpatyātē) ; উপজয় upājāy (utpadyātē) ; OB. দীসাই (dīś-yā-tē) ; রোচে, রুচে rōcē, rucē is pleasing (rucyātē) », etc., may be noted here.

The « -n- » infix of OIA. remains as a nasalisation of the root vowel in Bengali forms like « চিড়ে chīrē (chiṇḍ-a-ti, chi-n-d-a-ti) ; ভাঁজে bhājē (bha-ñ-j-a-ti) », etc. Cf. « বাঁধে bādhē (\*bandh-a-ti) ; রাঁধে rādhē (randh-aya-ti) ».

619. Apart from phonetic modification and decay, and the analogical tendency which brought about a general uniformity in the stem seeking to marshal the roots under one head, primary roots underwent certain modifications in MIA which would appear erratic and inexplicable. These have been described by Hoernle in his paper on Hindī Roots (JASB., 1880, Part I, p. 35ff.). Phonetic changes which altered « samarpayati » to « sāpē », « vismarati » to « bichurē », « upaviśati » to « bāsē », « svapiti » to « śōy », « abhyaajyātē » to « bhijē », « prōñchati » to « pōchē, mōchē » are sufficiently clear : and the analogical tendency levelling down the diversities in the forms of roots is plain enough. The striking thing is that in MIA., the bases





« pârē » *causes to fall, fells, gets a thing down* ; whence new formations in  
 « -ā- » — পড়ায় « pârāy » *causes to fall*, and পাড়ায় « pârāy » *causes to  
 fell, causes to get something down from high*. The root পাড় « pâr » has become,  
 so far as NB. is concerned, an independent form, with the sense of  
*taking down a thing*. Examples of these causative formations :  
 †উধারে « ughārē » (*udghāṭayati*) ; †উপাড়, উপড় « upārē » > upārāy »  
 (*utpāṭayati*) ; গালে « gālē » *strains, causes to flow off* (*gālayati*),  
 beside গলে « galē » *melts, slips through like water* (*galati*) ; MB. গোড়া  
 « gōṛā » *passes time* (*gramayati*) ; চাবায়, চিবায় « cābāy, eibāy » *chews*  
 (*carvayati*) ; চালে « cālē » *causes to move* (*cālayati*), beside চলে « calē »  
*walks* (*calati*) ; ছোড়ে « chōṛē » *casts, throws from a distance as a ball*,  
 beside ছুটে « chuṭē » *runs* (*Dhātupāṭha* = √chuṭ—chōṭayati *splits, cuts*) ;  
 টানে « ṭānē » *pulls* (caus. < √tan) ; তারে « tāre » *saves* (*tārayati*),  
 beside তরে « tārē » *crosses, is saved* (*tarati*) ; †তাঁও, তাঁওয়ে « tāō, tāōwē »  
 (*tāpayati*) ; ধারে « dhārē » from earlier উধারে « udhārē » *borrow, remains*  
*a debtor* (*uddhārayati*), besides ধরে « dhārē » *holds* ; থায় « thōy » *places*  
 (*sthāpayati*) ; MB. নোড়ে « nōḍē », NB. নোয় « nōy » *bends* (« nāmayati »,  
 confused with « namati ») ; পায় « pāy » (« prāpayati », in the sense  
 of « prāpnōti ») ; পসারে « pāsārē » *extends, spreads out* (*prasārayati*) ;  
 পারে « pārē » *is able, succeeds* (*pārayati*) ; পূরে « pūrē » (*pūrayati*) ; কাড়ে  
 « phārē » *splits* (*sphāṭayati*) ; বাহে, বায় « bāhē, bāy » (*vāhayati*) ; বাটে  
 « bāṭē » *pounds (spices) with a stone roller* (*vartayati*) ; বারে « bārē » *shields,*  
*stops* (*vārayati*) ; MB. ভারে « bhāṛē » *appears* (*bhāvayati*), beside MB.  
 হোএ « hōē » (*bhavati*) ; মারে « mārē » *kills, strikes* (*mārayati*), beside  
 মরে « mārē » (\*marati = mriyatē) ; মাপে « māpē » *measures* (old sts. =  
 \*māppēi < māpayati : cf. Hindi māpe *measures* = nāppēi = jāṇpyatē) ;  
 মোহে « mōhē » (*mōhayati*) ; রাধে « rādhē » *cooks* (*randhayati*) ; টালে  
 « ṭālē » (*tālayati*), beside টলে « ṭalē » (*ṭalati*) ; সারে « sārē » *repairs* (*sārayati*  
*arranges, nourishes*) besides সরে « sārē » *moves, goes to* (*sarati*) ; হারে « hārē »  
*is defeated* (*hārayati*) beside হরে « hārē » *takes away, steals* (*harati*) ;  
 cf. দাঁচাল « ḍhālē » *pours* beside ঢলে « ḍhalē » *reels* ; etc., etc.

621. A number of roots, which do not at all look like  
 secondary formations, cannot be traced to any OIA. (Sanskrit) form ;



although it is extremely likely that they are in most cases *lōhs*. Analogous forms occur in the «dhātu-kōṣas» in some cases, but that is no help in determining the origin. A few resemble Dravidian roots of similar meaning, and these may be of Dravidian origin: e.g., এড় «ēṛ = ēḍ» *give up*; নড় «nāṛ = naḍ» *move, walk* (< OIA. *nṛt dance* > MIA. *naṭ, naḍ* ?); কুদ «kud» *leap* (cf. Skt. *kūrd*); বড় «mur = muḍ» *fold, wrap*; dialectal শাপড় «śāpṛ = śāpaḍ» *eat, gobble up, finish* (e.g., ভাত শাপড়ান «bhāṭṣ śāpṛāṇā» *finishing one's meal of rice*): roots exactly similar in form and meaning to all of the above are found in Tamil. Roots that would come under this group of obscure etymology would be, among others—

আঁচ āc *guess*; আঁট āt *tighten*; কাচ kāc MB. *dress*, NB. *wash clothes*; কুঁড় kūṛ *pound*; কুঁদ kūḍ *carve*; খস khās *slip off*; খাট khāṭ *work, labour, put money on a trade, or lend at interest* (in the last sense a late Skt. «√khaṭṭ» has been found: see Jñānendra Mōhan Dās's Dictionary, under খাটান); খুঁট khūṭ *scratch, rub, rub gently with the finger-tips or nails, peck with the beak*; খুল khul *loosen, open, open bolt*; গাদ gād *ram in*; ঘির ghir *surround*; ঘুচ ghuc *come at an end, be finished*, cf. Assamese গুচ gus *enter*; চট cāṭ *be angry, get ruffled or cracked*; চাহ cāh *look at, ask* (OIA. «caks» ?; cf. Asōkan «caghati» = *strives, wants* < OIA. «\*cagh» = IE. root ?); চাঁচ cāc *scrape*; চাট cāṭ *lick* (OIA. caṣṭa. √caks ?); চাপ cāp *press*; চাঁক chāk *strain*; চাঁট chāṭ *clip off*; ছাপ chāp *print, press*; ছিপ chip *hide*; ছুট chuṭ *run*; জোখ jōkh *measure*; জুট juṭ, জুল jul *meet together*; জল, জুল jhāl, jhul *hang*; জুক jhūk *lean out*; জাঁপ jhāp *plunge*; জাল jhāl *mend a metal pot, clean a well*; জুঁজ jhūj *ooze*; টস ṭās *drip* (onomat. ?); টাঁস ṭās *be finished, die*; টাঁক ṭāk, টেঁক ṭēk, টিক ṭik *endure, repair*; টাক ṭāk *taste* (cf. টাকরা ṭākṛā *palate*); টিপ ṭip *pinch with the fingers*; ঠেল ṭhēl *push*; ডাক ḍāk *call, shout*; ডুব, বড় ḍub, বুঁক ḍuk *drown*; তাড় tāṛ *hustle, pursue*; থুড়, থুর thur, thur *mince* (cf. Skt. √puṭ); পট paṭ *be in agreement*; পিঁজ piṭ *card cotton*; পুড় pur *burn* (cf. Skt. √puṭ); পুত put, পুঁত pūṭ *bury*; ফির phir *turn*; বাঁচ bāc *live* (Skt. *vañe*); বাছ bāch *select, choose*; বিহা, বিহা bi(h)ā *give birth to*; ভাস bhās *float* (< Skt. *bhās shine*

> *appear* ?); রহ *rāh* remain (? arh); রটে *rāt* spread (as a rumour); রড় *rār* run; লড় *lār* fight; লুস, লুখ *lus, luṣ* gorge oneself; সঁটি *sāṭi* ibid, also tighten; হাঁট *hāṭi* walk (cf. Skt. *hiṇḍ*, Gujarātī *hēḍ-vū*); etc.

622. MIA. borrowings from Sanskrit may be included under the inherited or the proper *lôh.* element of Bengali. After Bengali emerged from Māgadhī Ap., as a distinct speech, and literature began to be produced in it, the habit of borrowing from Sanskrit obtained a greater impetus. A practice grew up in Bengali literature from very early times of adopting Sanskrit roots bodily into the language, like the adoption of *ts.* nouns and participles. This practice received a fresh support during the age of Vaiṣṇava renaissance in the 16th century, and again in the 19th century, in the hands of modern poets like Madhusūdan Datta. This use of Skt. forms, even when their *lôh.* counterparts were in actual use, is not peculiar to Bengali alone: we find it in the mediæval vernacular poetry of all Aryan India. It was the inevitable effect of a revival of classical studies—in grammar, literature, law, theology and philosophy, the results of which were brought to bear upon the vernaculars. The revival of Brahmanic studies strengthened the position of Sanskrit, which had throughout retained a living touch with the vernaculars as their natural feeder. We thus find from Middle Bengali times *ts.* roots or bases like • আহ্বা *āhwa*, কীর্ত্তি *kīrtta*, গর্জ্জ *garja*, চুম্বা *cumba*, তিষ্ঠ *tiṣṭha*, ত্যজ *tyaja*, দ্যা *dhyā*, ধ্বন *dhwan*, নম *nam*, নির্মা *nirmā* (*sts.*, নিরমা *nirāmā*), নির্বি *nirvi*, নিশ্চি *niścī*, প্রণম *pranam*, বদ *bad* (*vad*), বন্দ *banda* (*vand*), বর্জ *barja* (*varj*), বর্ত *barta* (*vart*), ভজ *bhañja*, ভবস *bhartsa*, ভিদ *bhid*, বর্দ *marda*, যজ *yaj*, রাজ *rāj* (the last two may be *lôhs.*), শোভ *śōbh*, সেব *sēb* (*sēva*), স্মর *smar*, হিংস *hiṇsa* > etc., etc. to be in common use, side by side with *lôh.* equivalents in many cases. These *ts.* roots, although understood by most people, figure mainly in literature, and only a few have been adopted in the colloquial, like তিষ্ঠ • *tiṣṭha* > (cf. তিষ্ঠাইতে দেওয়া *tiṣṭhāitē dēwā* > Standard Coll. তিষ্ঠুতে দেওয়া *tiṣṭhutē dēwā* = *let one remain at peace*), বর্ত • *barta* > (cf. বাচিয়া বর্তিয়া > বেচে-ব'র্তে থাকা *bāciyā-bārtiyā* > *bēcē-bōrtē thākā* to remain alive and well, বর্তিয়া > ব'র্তে যাওয়া *bārtiyā* > *bōrtē jāwā* to feel saved, to get a new existence). The number of such common *ts.* roots comes up to some 100; but it is often difficult to determine



whether they are *ts.* roots, or denominatives, as frequently the base in Bengali shows « guṇa » of the Skt. root characteristic of noun forms.

## (2) Secondary or Derivative Roots.

623. The Causatives are the most characteristic of this class. They have the affix « -ā- » which comes from the Second MIA. « -āva- » = First MIA. « -āpa- », which is only a generalisation of the « -pa- » affix found in the causative of some OIA. roots ending in « -ā », *e.g.*, √dā > dā-pa-ya-, hā > hā-pa-ya-, mā > mā-pa-ya-, yā > yā-pa-ya-, sthā > sthā-pa-ya-, snā > snā-pa-ya-, etc. Their verbal nouns as well as infinitives and passive participles have the affix অনি, আনো « -ānā. -ānō ». Almost every primary root and denominative which is not already a causative in form can have its causative in « -ā- ». A number of denominatives (especially in the case of bases in three syllables, ending in ড় « -ṛ- », original or affixed) have become obsolete, their places being taken by causative formations which are used without causative meaning: *e.g.*, আঁকাড় « ākāṛḥ » *embrace, hold with both hands* (aṅka-ḍa : cf. aṅka-pālikā *embrace*), proper verb form আঁকাড়ে « ākāṛē », causative extension \* আঁকাড়া > আঁকাড়ায় « ākāṛāḥ > ākāṛāy »; উখাড় « ukhāṛḥ », উখাড়ে « ukhāṛē » > \*উখাড়া, উখড়ায়, উখড়োয় « \*ukhāṛāḥ > ukhāṛāy, ukhāṛōy » *roots out*; উজাড় « ujāṛḥ » *desolate*, উজাড়ে « ujāṛē » > \*উজাড়া > \*ujāṛāḥ, উজড়ায়, উজড়োয় « ujāṛāy, ujāṛōy » *makes desolate, ransacks*; উগার « ugāṛḥ » > উগারে « ugāṛē », \*উগাড়া > \*ugāṛāḥ > উগড়ায় « ugāṛāy, ugāṛōy » *vomits*; তাকে « tākē » *gazes* (tarkayati) > তাকায় « tākāy »; হাঁকাড়ে « hākāṛē » *shouts, hits* > \*হাঁকাড়ায় « \*hākāṛāḥ > হাঁকাড়ায়, « hākāṛāy, beside হাঁকরায় « hākarāy » *belabours*; etc., etc. The causatives present a numerous class in Bengali, the proper « -ā- » causatives numbering some 400.

624. Denominatives are made up from nouns and participle adjectives, these nouns and participles being treated exactly like roots. A vowel ending the noun or participle base is dropped. IA. developed early this habit of making roots out of nouns and adjectives, without adding the denominative-forming affix « -āya- ». According to the Skt. grammarians (who doubtless were guided by vernacular Prakrit usage in

this respect), any noun-stem could be used as a verb-stem. With the decay of inflected past forms, the past participles became, after the present base, the most important. In some cases there was a very great difference in form between these two outstanding parts of the verb. The levelling tendency in MIA. simplified matters by making the passive participle the basis of a new present formation, which in course of time ousted the old present: since in Late MIA., the latter often appeared (from point of view of MIA.) irregular and peculiar. Equally frequently the reverse process took place. Thus, OIA. « upaviśati » and « upaviṣṭa- » gave MIA. « uvaśai » and « uvaṣṭha », but « uvaṣṭha » assumed the function of the present, so that in NIA. (Hindōstānī) we have present « baiṭhē » (rather than « baiśē »), and pass. participle « baiṭhā »; and in the OIA. group « śṇōti, śruta » > MIA. « suṇai, sudō > suṇ », « suṇai » made « suṇō » obsolete by bringing about the creation of a new form « suṇiō », so that in Hindōstānī we have present « sunē » and pass. part. « sunā ». The simple « -a » verbal noun, as presenting the root in a very intelligible form, also often supplied a basis for the new conjugation.

The Kōl and Dravidian speeches might have been responsible for the wide development in IA. of the practice of forming denominatives. Anyhow, it was a late MIA. characteristic which has come down to Bengali. Denominatives in « -ā- » are now freely formed, even from foreign nouns and adjectives.

625. As for the *tbh* (and *dēṣi*) denominatives of Bengali, absence of literary records does not allow us to fix with certainty when they were first employed as verbs—whether in the pre-Bengali period, or in later times. The forms without « -ā- » seem to be earlier. Examples are: « উগে ugē rises (uggaa, udgata); উজাড়ো ujārō clears (\*ujjhāda, \*ud-jhāta with trees cut down); MB. উনাএ unāē gets hot (uṇha, uṣṇa); উভে, উবে ub(h)ē is volatile (ubbha, ūrdhva; ubbhaa, udbbhṛta); MB. উমাএ umāē steams (umha, nṣma); কহে, কয় kâhē, kây (kahēi, kathayati); কাড়ে kārē snatches away, robs (kaḍḍha, kṛṣṭa); কামায় kāmāy earns, shaves (« kamma, karma »: Second MIA. « kammai » cuts; connexion with Pali « kappēti » trims, as suggested by R. Morris, 'Pali, Sanskrit and Prakrit



Etymology,' Transactions of the 9th International Congress of Orientalists, London, 1893, Vol. I, pp. 494-495, not likely); কালার *kālaya gets black, blackens* (kāla); কুড়ার *kuṛāy gathers* (kūḍa, kūṭa); খোয়ার *khōwāy gets lost* (\*khawa, khaa, kṣaya); গাড়ে *gārē buries* (dēśi gaḍḍa: ? < garta); গাবার *gābāy vaunts* (gabba, garva); গাহে, গায় *gāhē, gāy sings* (gāhēi, gāthayati < gāthā); গুছায় *guchāy arranges* (guccha); ঘোলে *ghōlē mixes thoroughly as liquids* (ghōlla = ghūrṇa); ঘামে *ghāmē sweats* (gharma); চিনে *cinē recognises* (cihna); চোরায় *cōrāy steals* (cāura); চেতায় *cētāy comes to senses* (cittāvēi, citta-); চিরে *cirē slits, pie cees* (clara, clvara); হাঁদে *chādē grips, holds tight, binds* (chanda); চিনে *chinē snatches away* (chinna); জিতে *jitē wins* (jitta < jita); ছিটায় *chiṭāy sprinkles* (chiṭṭa-,? kṣipta); জুতে, জোতে *jutē, jōtē hitches ox or horse to vehicle* (jutta, yukta); টকে *ṭakē gets sour* (ṭakka=takra); ঠাটায় *ṭhāṭāy stiffens* (ṭhaḍḍha < \*ṭhaṭṭha: stabdha?); দাঁড়ায় *dāṛāy stands* (daṇḍāyātē); তাকে *tākē gazes* (takkēi, tarkayati); তাতে *tātē gets hot* (tatta, tapta); তিতে *titē gets wet* (tinta, √tim); থামে *thāmē comes to a standstill, stops* (thambba, stambha); থিরায় *thirāy* (sthira) *থিতায়* *thitāy subsides as a residue* (sts. ? < sthitā); দুখার *dukhāy pains* (dukkha, duḥkha); ধূয়ার, ধোয়ার *dhūāy, dhōāy smokes* (dhūwa, dhūma); পাকে *pākē ripens* (pakva); MB. পতিয়াএ, পইত্যার *pātiyāē, pāitāy believes* (sts. < pratyaya); পইঠে *pāiṭhē enters* (pāiṭṭha, praviṣṭa); পিটে *piṭē beats* (piṭṭa, piṣṭa); বাকে *bākē* (baṅka = vakra); বাখানে *bākhānē explains, praises* (bakkhāṇa, vyyākhāṇa); বাজে *bājē is played, as music* (vajja, vādyā); মাগে, মাগে *mā(ṅ)gē begs* (maggaī, maggēi, mārgati, mārgayati); মাত্তে *mātē becomes intoxicated* (matta); মূতে *mūtē* (mūtra); মুদে *mudē closes, as eyes* (mudrā seal); রুটে *ruṭhē angers* (ruṭṭha, ruṣṭa); রুধে *rudhē prevents, forbids* (ruddha); শুখায় *sukhāy dries* (suṣka); সৈত্যার *sētāy gets wet* (\*sinta, sitta < sikta), etc., etc. *Tadbhava* derivatives of NIA. origin in Bengali can be exemplified by forms like « আঁধারা *ādhārā* (andhakāra); আঁউলা, আঁলা, এলা *āulā, āllā, ēlā make dishevelled* (ākula); আলগা *ālāgā loosens* (ālaggera, ālagna); আঁতকা *āṭkā be seized with a sudden fright* (āṭaṅka); ইটা *iṭā stone, hit with pellets* (iṣṭaka); উঁচা *ūcā raise, level as a weapon* (ucca-); আগুয়া, আগুয়া, আগা, এগো *āguā, ālgā > ēgō advance* (agra+uka); কষা *kaṣā tighten* (karṣa); কাঁধা *kādhā to shoulder* (skandha); কিলা *kilā*

give blows with the fist (kilā fisticuff); খেড়্‌রা khēṛā strike with a broom;  
 খেপা khēpā become mad; গালা gālā abuse (gālī=garhikā); চাপড়া cāpṛḍā  
 pat (cāpṛḍā patting with the flat of the palm); ঘনা ghānā deepen (ghana);  
 ঘুমা ghumā sleep (ghumā sleep: see p. 482 supra); ঘোঁজা gōjā tuck inside (cf.  
 gōjā a peg); চড়া cārā slap (cārḍā a slap); ছোঁচা chōcā wash after evacuation  
 (śāuca); জুতা jutā strike with the shoe (jutā shoe); জাঁটা jhāṭā strike with  
 a broom; ঢেউয়া ḍhēuā dash water in a tank or stream (ḍhēu wave); তলা tālā  
 sink deep (tala); তাসা tāsā play cards (slang: tāsḍā playing cards); তেওড়া tēorā  
 make deformed (tri-vṛta); দাঁতা dāṭā gnash teeth, show teeth (danta);  
 MB. নিন্দা nindā sleep (nidrā); পাদা pādā break wind (parda); পাছুয়া > পেছো  
 pāchuā > pēchō fall back (puścāt); বিয়া biyā fester as a wound (viṣa);  
 ভাঙ্গা bhāṅ(g)ā break (bhaṅga); রাঙ্গা rāṅ(g)ā redder (raṅga); লাঠা lāṭhā  
 belabour with sticks (lāṭhi < yaṣṭi? < \*lak-ṭhi=\*lak-, \*lag- [cf. lak-uṭa,  
 lag-uḍā + yaṣṭi); শাঁগা śāṅā whet (śāṅa); হাতা hātā receive in hand to one's  
 advantage (basta); MB. হুমা humā (hōma) », etc., etc., The noun base not  
 infrequently ends in «-u»: thus অগুয়া > এগো «āg-u-ā > ēgō » advance,  
 পাছুয়া > পেছো «pāch-u-ā > pēchō » recede, পারুয়া > পেরো «pār-u-ā  
 > pērō » cross, etc.

The *tbb.* derivatives convey mainly an instrumental or acquisitive sense.

Common *tbb.* roots of this class number some 200 in Bengali.

626. Sanskrit denominatives, in *ts.* or *sts.* forms, like Skt. roots and participial forms, occur from the oldest Bengali onwards. Almost any Sanskrit noun, preferably in «-a», which is not the name of a concrete object, can be used as a root in the language of Bengali poetry. About 100 denominatives of this class are in common use in the Bengali. A few of this have developed characteristic vernacular or *sts.* forms from MB. onwards, e.g., তেয়গ «tēyāgā» < «tyāga», বরণ «bārāṇā» < «varṇa», দরশ «dārāśā» < «darśa», পরশ «pārāśā» < «sparśa» etc.

Examples of *ts.* demonstratives: «agrasara, ādara, ādēsa, ākula, āghāta, ānanda, ālāpa, āśīṣa, ucehēda, uttāpa, uddhāra, unmōca, ulāṅga citra, trasta, dvēṣa, dvandva, dāna, dīpa, nūda, nīrava, nīscaya, niṣphala,



nistāra, parihāra, pradāna, praṇāma, pramōda, prasāra, prasāda, prasāma (ts. root, pra + √sam?), puraskāra, bhāti, bhāva, vikāsa, vighōṣa, vināśa, vistāra, vēṣṭa, rūga, yōga, lēpa, sakhāra, santōṣa, stuti > etc., etc. . we have even a word like «prati-vidhitsā» turned into a denominative root, প্রতিবিধিত্স «prāti-bidhitsā», in poetry (e.g., in Madhusūdan Datta and in Girīś Chandra Ghōṣh).

627. Foreign denominatives number barely 20. They are almost all from the Persian (or Perso-Arabic): e.g., অর্শ «ārsā» *be entailed as property* (\*arsah); কবলা «kāblā» *make agree or accept* (slang: < qabūl); কুলুপা «kulupā» *lock up* (qufl = *lock*); খতা «khātā» *cast accounts, estimate* (xatt); খামচা, খিমচা «khāmṇcā, khimṇcā» *pinch* (Ar. xams = *five*: *pinch with the five fingers*?); গুতা «gūtā» *butt with horns* (gutah *plunge*); গুজরা «gujṇrā» *pass time* (guṇār); জম «jām» *gather*, জমা «jāmā» *collect* (jam\*); MB. তপাস «tāpās» *seek* (tafahhus: see *supra*, p. 218, footnote 2); তোরা «tōā» *flatter* (? tawājah); দাগ, দাগ «dāg, dāgā» *mark* (dāg); নরমা «nārāmā» *be soft* (narm); গরমা «gārāmā» *be hot* (garm); ফাসকা «phāṣkā» *slip from hold* (fasx); বদলা «bādālā» *change* (badl); MB. মানা «mānā» *forbid* (man\*); সাবাসা «sābāsā» *cry bravo* (sābās < sād-bās) > etc., etc.

There are no denominatives proper from the other foreign sources, Portuguese and English. English verbs like *edit, manage, quote, note, agree*, etc., as well as nouns and adjectives, are freely compounded with Bengali roots like «kār, dē» to form verbs, in the familiar speech of persons educated in English, but such words by themselves are not used as verb roots, with or without the «-ā-», as in the case of Persian words. Slang is responsible, however, for one or two genuine denominatives, e.g., in student slang in Calcutta one can hear পাসানো, পেসুনো < পাসহানো «pās-ānō, pēsunō < pās-u-ā-nā» *to pass* < English *pass*.

#### 628. Compounded and Suffixed Roots.

There are over 125 roots which are derivative, being made up of either two roots combined, or a root preceded by a noun or adverb, or in the majority of cases, of a root (primary or denominative)

modified by a suffix. Instances of the first type (two roots combined) can be easily analysed. The second root which is suffixed is commonly *আসা*, *আইসা* « ā(i)sā » *come*. Thus, we have *দেখসে*, *দেখসা* « dēkhā-sē, dēkhā-sā » *come and see* found from early MB. times, = *দেখ* + *আইস* « dēkh + āis » *see and come*, and *স্কক চড়া* « cārāsā » *come and mount* ( $\sqrt{\text{cār}} + \sqrt{\text{āis}}$ ). We have also occasionally a similar combination with *গা* from *গিয়া* « gā < giyā » (*করগা*, *খাওগা* « kārā-gā, khāo-gā » *go and see, go and eat*). We have beside a combination of *রহ* «  $\sqrt{\text{rāh}}$  » *to remain* and *সহ* «  $\sqrt{\text{sāh}}$  » *to endure*, in the imperative only—contemptuous *র'স্* « rōsā », ordinary *রোসো* « rōsō » < « rāhā sāhā » *wait*, in the Standard Colloquial. The above forms strictly speaking are not roots,—they are merely compounded forms, contracted and stereotyped. Besides, they do not occur in all persons and tenses, but only in the imperative. Of the second type (noun or adverb and root) are found some instances, also from eMB., like *আগুছা* « āguchā (< \*āgusā, āgu +  $\sqrt{\text{āis}}$ ) » *advance*, *রাঁকাড়া* > *রাকড়া* « rā-kārā > rākārā » *shout, raise a shout*, and the negative forms *নার* « nār < nā + pār » *fail, not succeed*, *নহ* « nāh < na +  $\sqrt{\text{ab}}$ , hā » *not be*.

The periphrastic forms composed of a noun (*tāh.*, *ts.* or foreign) and a root like « kār » *do*, like *দর্শন করা* « dārsānā kārā » *to see*, *গমন করা* « gāmānā kārā » *to go*, do not come under this.

629. The bulk of these secondary compounded roots are suffixed. We have these suffixes: (i) ক « -k- », (ii) ট « -ṭ- », (iii) ড় « -ṛ- », (iv) র, ল « -r-, -l- », and (v) স, চ « -s-, -c- » (cf. G. A. Grierson, 'On the Irregular Causals in the Indo-Aryan Vernaculars,' JASB., 1896, Part I). These modified the meaning of the original root or denominative base in various ways,—as an intensive or continuative, frequentative or approximative affix. Corresponding forms occur in the other NIA. speeches. These roots may again be described as denominatives from nouns ending in « -k-, -ṭ-, -ḍ- (-ṛ-), -r-, -l-, -ś-, -c- ».

630. Of these affixes, (i) ক « -k- » in Bengali indicates, generally, the suddenness of the action, or its continuity: it is thus an intensive. Its origin has been discussed before (see *supra*, pp. 679 ff.). Examples in Bengali: *চুক* « cuk » *be at an end* (\*cyut-kṛ); *কৌচক* « kōcāḥkā »



*wrinkle* (kuñe); খিঁচকা *khicāka* *pull, nag* (cf. খেঁচ *khēc pull* : ? *krakṣyati* < √krṣ, whence MIA. *kaecchāi, kañcāi*, vowel influenced by *ā-krakṣati* > *\*ākacechāi* > *āyañcāi* > NIA. *aicai*); ঢলকা *calāka* *spill, as water from a vessel full to the brim* (cal); চুলকা *culāka* *scratch* (√cal? cf. চুলবুল *cul-bul wander*); চানকা *cānāka* *glance, make eyes, draw the eyes as in a picture*; (? *\*cayapa-kka, cētana-*); চুমকা *cumukā* *sip, touch vessel with lips* (cumb); ছিটকা *chitāka* *sprinkle* (chitā = drop, sprinkling); so চমকা *cāmāka* *be bright, dazzle, be startled as at a sudden flash or noise*; জমকা *jāmāka* *be showy*; টপকা *ṭapāka* *jump over*; টসকা *ṭasāka* *drip, run out*; ঠমকা *ṭhāmāka* *caper, walk with a dancing gait*; ঢুলকা *ḍhulāka* *wave a fly-flap*; তড়কা *tāṭāka* *be in fits*; থমকা *thāmāka* *be at stand-still*; থকা *thākā* *ibid*; থাককা *thākā* *remain*; দমকা *dāmāka* *come as a gust of wind*; ধমকা *dhāmāka* *rebuke*; নড়কা *nāṭāka* *move about*; বখা < বহকা *bākhā* < *bāhāka* *be borne away* > *go astray*; ভড়কা *bhāṭāka* *be confused, fear* (bhraṣṭa); মচকা *mācāka* *break with a noise, sprain*; মুচকা *mucāka* *smile, wrinkle*; লটকা *lāṭāka* *hang*; লটুকা < লড়কা *sāṭāka* < *saṭāka* *slink away* (sṛta); হড়কা *hāṭāka* *slip one's foot, be slippery*; হেঁচকা *hēcāka* *drag*; etc.

A few words of other origin have come in line with these *-k-* denominatives: e.g., আঁতকা *āṭāka* *be filled with sudden fear* (sts., < *ātāṅka, ā-√tañc*); উসকা *usāka* < *ukṣā* *trim a lamp, incite* (? *utkarṣa*); কড়কা *kāṭāka* *rebuke* (cf. *kaṭakkha- = kaṭākṣa-*, whence NIA. [Hindī etc.] *kaṭākhā* *war-song* < *challenge* < *glance of contempt*: confusion with, or influence of কড়া *kārā* *stiff* likely); ফসকা *phāsāka* *slip, from the Persian* (see p. 884); চটুকা *cāṭāka* *rinse* by metathesis from কচটা, কছটা *kāc(h)ṭā* (next para.); etc.

631. The affix (ii) ট *-ṭ-* is the *-ṭāṭ-* affix (No. 41), noted at pp. 684 ff. *supra*. It indicates continuity of the action. Examples: কছটা, কষটা *kācṭā, kṣṭā* *rinse* (karṣa-varta-); ঘষটা *ghāṣṭā* *rub along* (gharṣa-varta-); চিপটা *cipṭā* *press down*; so জাপটা *jāpṭā* *embrace, hold with both arms*; জাপটা *jhāpṭā* *struggle* (MIA. *\*jhappa, jhampa*); দাপটা *dāpṭā* *be aggressive* (darpa); পাশটা *pāṣṭā* *pass by* (pārśva-

varta-); রপটী < rāpṭā > *gad about*; লপটী or লিপটী < lāpṭā, lipṭā > *stick on*, etc. Cf. MB. নেউটী < nēuṭā > *return* (nivartt-) which is of different origin.

632. (iii) The ড < -r- > affix is the pleonastic ড < -r- >, discussed before as Formative Affix No 46 (pp. 689 ff.) The sense is sometimes intensive, but generally it is merely pleonastic. In some instances the sense is continuative or approximative, and then the ড < -r- > would seem to be connected with < √vrt >, either as a phonetic modification of < -ṭ- < vaṭṭa, vṛtta > above, or it is the same ড < -r- > as Formative Affix No. 44 (pp. 687-688 *supra*): thus ঘেঁষড়া < ghēṣṣṛā, ghāṣṣṛā >, দাবড়া < dābṣṛā > *beside* ঘষটা < ghāṣṣṭā >, দাপটা < dāpṣṭā > *above*; হেঁচড়া < hēcṣṛā > *pull*, see *supra*, p. 878; in আওড়া < āorā > *repeat*, তেওড়া তোবড়া < tēorā, tōbṣṛā > *disfigure*, and MB. নিবড়া < nibārā > *finish*, we have the OIA. < √vrt >. Examples of < -r- >: আঁকড়া < āṅkṣṛā > *embrace* (see *supra*, p. 880); আঁচড়া < ācṣṛā > *scratch*, (? √añc *wander, bend, curl* + -ḍa-); কঁকড়া, কৌকড়া, কুঁচড়া, কৌচড়া < kṁkṣṛā, kōcṣṛā, kūc-, kōc- > *crumple, wrinkle, be curly* (kuñc); খেঁদড়া < khēdṣṛā > *hustle* (cf. খেদা < khēdā > *drive away*, Hindi and Bengali noun < khēdā > 'kheddah,' *enclosure to which wild elephants are driven and caught*: sts., < √khid > *torment*?); খিঁচড়া < khīcṣṛā > *feel tense or annoyed* (see < khīcṣkā >, *supra*, p. 886); ঘাবড়া < ghābṣṛā > *be frightened* (connected with বাপটা < ghāpṣṭā > etc., p. 685); চাপড়া < cāpṣṛā > *slap, pat* (carpaṭa); চিমড়া < cimṣṛā > *dry up, reduce to skin and bone* (√cip > \*civ > \*ciw, cim); চুমড়া < cumṣṛā > *flatter* (cumb), also চুমরা < cumṣṛā >; জোবড়া, জাবড়া < jōbṣṛā, jābṣṛā > *blotch* (cf. জবজবে < jābṣjābē >, *onomatopoetic to denote the idea of stickiness and moisture*); তাঁড়া, তামড়া < tāṅṣṛā, tāṁṣṛā > *save up, store up* (Yōgeś Chandra Vidyānidhi, Bengali Dictionary, VSPd., gives a late Sanskrit < 'tryaṅgaṭa-' śikya-bhēdē >, = Marāṭhī < tāgaḍ > *bind the feet*: Monier Williams, < tri-anggaṭa > *three strings suspended to either end of a pole for carrying 'urdens*); থাবড়া < thābṣṛā > *slap* (cf. থাবা < thābā > *paw*); থুবড়া < thubṣṛā > *give a blow, fall down on the face* (Dhātu-kōṣa √thurv *kill*: cf. থুড়া < thurā > *pound, cut into small bits*); দাঁদড়া < dāḍṣṛā > *be aggressive* (dvandva + ṭa), also দাঁদলা < dāḍṣlā >; ডুমড়া < dumṣṛā > *bend, crumple* (< ?); দৌড়া < dāurā > *run* (drava + -ḍa); নিষড়া < niṅṣṛā < niṅṣṛā > *wring wet clothes* (niñj); নেংড়া < nēṅṣṛā > *limp* (cf. লেঙ্গ < lēṅ[ṅ]ṣ > *foot, kick*); নেবড়া < nēbṣṛā



*smear* (sts. < lēpa); পাকড়, MB. পাকড় < pākārḍ, -khārḍ > *seize* (? parka + -ḍa : √pṛe mix, unite); পাছুড়া < pāch(u)ṛḍ > *dash, toss, clean corn* (< ?); মুচড়া < mucḍrā > *wring* (cf. macḍkā, mucḍkā : onomatopoeitic); মুশড়া < muṣḍrā > *be dispirited* (cf. muṣ steal, rob : cf. the expression < hanta muṣitāḥ vayam > *alas, we are done for*!); রগড়া < rāgḍrā > *rub* (< beat? cf. late Sanskrit < drakaṭa, dragaḍa > *drum*; Yoges Chandra Vidyānidhi, Beng. Dictionary); হাঁকড়া < hāḱḍrā > *drive* (MIA. bakka shout); হাতড়া < hātḍrā > *feel with the hand* (hasta); হুমড়া < humḍrā > *push through eagerness, fall face forwards* (connected with হামা < hāmā > *crawl*); etc., etc. It would be seen that the < -ṛ- > roots are mostly very obscure, and these suffixed forms or roots, a most characteristic element inherited by NIA. from MIA., constitute a problem of prime etymological importance. From these roots with the ড < -ṛ- > affix are to be distinguished roots like আছাড় < āchār > *dash, throw down with force* (ā-chṛḍ); উজাড় < ujār > (see page 881, *supra*, with a variant আজাড় < ājār > *empty a vessel*); উপাড় < upār > (utpāṭayati); etc. : but উখাড় < ukhār > may represent < utkhāta + -ḍa >.

633. (iv) The affixes র, ল < -r-, -l- > represent the OIA. adjectival and pleonastic affix occurring both as < -ra-, -la- > (see *supra*, pp. 697-698). In compounded denominatives, the force is that of approximation or resemblance, or connexion. The < -r- > form in some instances may be a modification of ড < -ṛ- > above; and in other cases it may be for < -ārḍ formative < -ākāra >, implying resemblance (Affix No. 18, *supra*, pp. 668-669). Similarly the < -l- > form may represent the adjectival < -ālḍ > (No. 19, p. 669). Examples : আগলা < āgḍlā > *watch* (arga-la-); উঁচলা, ওঁচলা < ōcḍlā, ōchḍlā > *sift* (uñch); খোসলা < khōsḍlā > *peel* (khōsā skin of fruit); চোমরা, চুমরা < cōmḍrā, cumḍrā > *flatter* (cumb); চোবলা < cōbḍlā >, ছোবলা < chōbḍlā > *bite as a snake* (cf. চোপ < cōpḍ > *blow* : see p. 482 *supra*); ঝাঁকরা < jhāḱḍrā > *shake* (see p. 479 *supra*); ঝামরা < jhāmḍrā > *be pale, dry up* (p. 480); ঠাণ্ডরা, ঠাংরা < ṭhāḱorā, ṭhāḱhārā > *look over, scrutinise, examine a thing that is standing still* (ṭhāḱa, ṭhāwa < √sthā); ডুকরা < ḍukḍrā > *shout, lament loudly* (cf. ḍāḱḍ shout); খেঁতলা < thēṭḍlā > *pound, batter* (cf. খেঁত thēṭā pounded); নাগলা < nāgḍlā > *reach* (lāga + -lā-); দাঁদলা < dāḱḍlā > *swagger* (dvandva); পিকলা < pikḍlā > *spit, squirt out*

(onomatopoetic); फुसला *phusālā* > *wheddle, lead astray by whispering in the ear* (onomatopoetic); फुकरा *phukārā* > *shout out, lament loudly* (onomatopoetic: *phukka* > *puffing, blowing*, cf. Hindi *pukār* > *shout*); बाँसला *bāolā* > *fan, winnow (vāta)*; हाँकरा, हाँकारा *hāṅkārā, hāṅkāṛā* > *shout, give a blow* (MIA. *hakkāra shout*); हामला *hāmālā* > *be eager, fall down on all fours in eagerness* (cf. *hammati crawls*); etc., etc. This affixed *-r-, -l-* of course is not to be confused with original *-r-, -l-* in forms like आङ्गला *āṅgālā* > *to use fingers (aṅguli)*; उतारा *ubhārā* > *bring down, pour* (*udbhārayati*); निकला *nikālā* > *get out* (*niḥ + kr*); बातला *bātālā* > *explain* (from Hindōstānī, a causative in *-lā-*); etc.

634. (v) The affix न, ङ *-s-, -c-* is the affix of resemblance (No. 55, p. 699). Examples with it are कपटा *kāpṭcā* > *chatter like a bird* (*kṛp*); गुमसा *gumṣā* > *be stuffy* (< *grīṣma*? : cf. गुमटे *gumātṭ* > *stuffy weather*); so चकसा *cākṣā* > *become clear, as sky* (see p. 699); चूपसा *cūpṣā* > *be lean, be hollow* (p. 699); बलसा *jhālṣā* > *roast* (see p. 479); लेंदसा *lēṅṣā* > *नेदसा* *nēṅṣā* > *limp* (see p. 699); धामसा *dhāmṣā* > *rummage as a bed* (cf. MB. धामालि *dhāmāli* > *horseplay, sport*); बालसा *bālṣā* > *get fever as a baby* (*bāla*); भापसा *bhāpṣā* > *smell fatid* (*bāṣpa*); बेदसा, भादसा *bhēṅṣā, bhāṅṣā* > *make faces* (*bhaṅga*); etc., etc.

635. Onomatopoeics also fall under denominatives. These can be classed under two heads—Onomatopoeics Proper, and Roots Reduplicated or Repeated, which produce a jingle. Onomatopoeics Proper can also be either simple or reduplicated.

It is evident that in the early stages of IA., onomatopoeics were not so common. Compared with the Vedic, the MIA. dialects are specially rich in onomatopoeics.

Vedic has registered about a dozen onomatopoeics formed by repeating a root to produce a jingle, or by compounding an imitative word with a root of action or existence (cf. Whitney, *Sanskrit Grammar*, § 1091; see also *supra*, pp. 175, 200). Onomatopoeics were included in the category of *dēśī* words by Prakrit grammarians, as they cannot show counterparts in Vedic or Sanskrit. We have onomatopoeics



of two types in the speech of Ancient India (Vedic, Skt., and the Pkts.): *simple*, like the Sanskrit nouns « jhaṇ-kāra, guṇj-ana, kūj-ana », Pkt. verbs « jhaṅkārei, \*guṇjai, kūjai »; and *reduplicated*, like Late Skt. « khaṭ-khaṭāyamāna, maḍamaḍāyitā, pharpharāyatē », etc., Pali « halahala, kinikiṇāyati, capucapu », etc., and Prakrit « caḍapaḍanta, cubūcubū, tharahara- », etc. It would be seen that in Sanskrit the onomatopoeics are treated as denominatives in « -āya- », but in MIA., we have the direct use of the stem as root.

Onomatopoeics of the reduplicating type are found in abundance in all NIA. languages. In Bengali, onomatopoeic reduplications are ordinarily used as adverbs, absolutely i.e., without any affix, and modify a verb of action: e.g., ঢক্‌ঢক্‌ করে « cākṣ-cākṣ kārē » *glitters*; or they are employed as gerundives in « -iyā », also standing in adverbial relation to the verb of action, e.g., কনকনাইয়া < কনকনিয়া উঠে » « kāṅṣ-kāṅāiyā > kāṅṣkōṇiṣ uṭhē » *gives a throbbing pain*. A group consisting of a reduplicated or simple onomatopoeic and a verb like কর « kār » *to do* may be regarded as a compound verb formation.

There are over 125 common onomatopoeics in Bengali which are used as verb-roots. The list of onomatopoeics given in Rabīndra-nāth Tagore's 'Śabda-tattwa' comes up to 651, which includes words of all kinds that would come under this head. By change of the vowel, the same consonant group can be made to take numerous forms, which are slightly differentiated in meaning. Thus টক্‌টক্‌ « tākṣ-tākṣ » *tick of a clock*, টিক্‌টিক্‌ « ṭikṣ-ṭikṣ » *tick of a watch, nagging in a mild way*, টুক্‌টুক্‌ « ṭukṣ-ṭukṣ » *gentle battering with a tiny hammer*, ট্যাট্‌ট্যাট্‌ « tyākṣ-tyākṣ » [tæktækt] *jangle, unpleasant remarks*, টিক্‌টাক্‌, টুক্‌টাক্‌ « ṭikṣ-tākṣ, ṭukṣ-tākṣ » *gentle blows with alternation of sound*, টক্‌টক্‌ « tākṣtākṣ » *quick one after another*, etc. The proper significance and use of the onomatopoeic forms in the psychology and art of Bengali speech has been discussed by Rabīndra-nāth Tagore in 'Śabda-tattwa' and by Rāmēndra-sundara Trivēḍī in 'Śabda-kathā.'

Examples of Onomatopoeic Verbs in Bengali.

A. Onomatopoeics Proper :

(i) Simple : চিলা *cillā* > *shout*; চুঁয়া *cūā* > *scorch in cooking, be fried black*; টুপা, টুসা *ṭupā, ṭusā* > *drip*; ফুক *phuk* > *whiff, smoke, puff*; ফোঁসা *phōsā* > *hiss*; হাঁক *hāk* > *shout* (MIA. *hakka*); হাঁচ *hāc* > *sneeze* (cf. OB. *bhāñjī* > as in *Sarvānanda*); etc.

(ii) Duplicated : কটকটা *kāṭṭ-kāṭā* > *sense of biting or breaking pain*; কটমটো *kāṭṭ-māṭā* > *look with glaring eyes*; কড়মড়া *kārṭṭ-mārā* > *gnash one's teeth*; কুড়মুড়া *kurṭṭ-murā* > *chew something crisp*; ক্যাচক্যাচো *kyācṭṭ-kyācā* > *creak*; খটখটো *khāṭṭ-khāṭā* > *rattle, knock*; গড়গড়া *gārṭṭ-gārā* > *roll*; গেঁগো *gēṅgā*, গেঙো *gēṅgā* > *groan, have a dried-up throat or choked voice in speaking*; চড়চড়া > চচ্চড়া *cārṭṭ-cārā, cāccārā* > *striking with a cane, sense of whipping pain*; ঝলমলো *jhālṭṭ-mālā* > *dangle, be bright*; ঝমঝমো *jhāmṭṭ-jhāmā* > *make a hollow ringing noise, tinkle as anklets, patter as heavy rain*; ঠকঠকো *ṭhākṭṭ-ṭhākā* > *knocking sound*; তড়তড়ো *tārṭṭ-bārā* > *clatter as galloping horses, chatter*; থিকথিকো *thikṭṭ-thikā* > *sense of teeming as with maggots*; পিলপিলো *pilṭṭ-pilā* > *sense of being over-crowded*; কদফরো *phārṭṭ-phārā* > *flutter*; বজবজো *bājṭṭ-bājā* > *sense of being moist and rotten*; বিড়বিড়ো *birṭṭ-birā* > *mutter*; মচমচো *mācṭṭ-mācā* > *crackle in the mouth*; সপসপো *sāpṭṭ-sāpā* > *sense of being wet and uncomfortable*; হড়হড়ো *hārṭṭ-hārā* > *sense of being slippery and uncanny*; etc., etc.

#### B. Roots Repeated.

(i) Complete repetition : জলজলো *jāl-jālā* > *be brilliant* (*jval*); টনটনো *ṭān-ṭānā* > *sense of binding pain* (*ṭan* = *ṭān*); টলটলো *ṭāl-ṭālā* > *be clear and ready to run off, as water* (*ṭal*); ধুকধুকো *dhuk-dhukā* > *pant* (cf. *dhūk pant, gasp*); সড়সড়ো *sār-sārā* > *feel creepy, as with an insect crawling over the body* (*sāṭ* < *sṛta*); গলগলো *gāl-gālā* > *ooze or flow out, as blood* (*gal*); গনগনো *gān-gānā* > *burn brightly* (< *gan* < *agni*? cf. *Pali gini*); etc.

(ii) Modified repetition, where another root of similar sense and assonance echoes the preceding one : চুলবুলো, চিলবিলা *cul-bulā, cil-bilā* > *be fidgety, be eager to move away* (*cāl, bul* : cf. *চলাবুলো* *cālā-bulā* > *wander about, move and walk*); টলবলো *ṭāl-bālā* > *be shaky and moving* (*ṭal, bāl* = *bul* < *Skt. val*); দলমলো *dāl-mālā* > *shake and pat* (*dāl, māl* : cf. *দলাইমলাই* *dālāi-mālāi* > *currying a horse*); etc., etc.



636. In addition to roots which easily affiliate themselves to one or the other of the above classes, there are a few roots of which the origin has not been found out, and which from their look are secondary formations: e.g., কাঁচা < kãcã > *bring to a failure, make 'cutcha'*; গজা < gãjã > *sprout*; MB. গাহা < gãhã > *causer*; গুটা, গুড়া < guṭã, guṛã > *gather up, as a net or line*; গুঁড়া < gũṛã > *pound*; জিরা < jirã > *cool one self, rest*; টাঙ্গা < ṭãṅ(g)ã > *hang on high*; বিলা < bilã > *distribute*; হেলা < hẽdã > *pine away*; লেলা < lẽlã > *set a dog on a person*; etc. In some cases they appear to be *dẽsĩ*.

In a number of *dẽsĩ* and *tbh.* roots, we find a wide range of vowel change: চিপসা and চুপসা < cipãsã, cupãsã > *get shrivelled*; জাবড়া, জোবড়া < jãbãṛã, jõbãṛã > *smudge, blotch*; etc. This, as well as other variations, like nasalisation or the absence of it, and interchange of consonants, etc., have been noticed under *Phonology*. The dislocation of the MIA. tradition in Bengali spelling from the very beginning, through Sanskrit influence, has been responsible for the state of chaos which exists in the spelling of verb-roots (as of other forms) in Middle and New Bengali. Dialectal modifications are not properly discriminated and kept in their proper place. The result is that we have the same root spelt differently, e.g., গোঙা and গোরা < gõṅã, gõyã > (= gãṅã) *pass* (gam-aya-), শু and সূ < šu, su > *sleep, lie down* (svap), নেউটা and লেউটা < nẽuṭã, lẽuṭã > *return* (ni-vṛt), আইশ, আইস, আস < âis, âis, âs > *come* (ã-viś), etc., etc.

## [II] FORMAL CLASSIFICATION OF ROOTS.

637. The proper classification of roots in Bengali, viewed from the formal aspect, is not with regard to their affixes (because they are always the same—the Bengali verb presents only *one* conjugation, and apparent irregularities are only the result of recent phonetic changes), but with regard to the modifications of the root-vowels and also of the affix-vowel in the case of the causatives and denominatives. These modifications are the result of Epenthesis-cum-Umlaut and Vocalic Harmony (*supra*, pp. 376 ff.). Roots have [i, e, u, o] when the following affix has a high vowel, [i, u]; and these are lowered respectively

to [e, æ, o, ɔ] in the case of a low vowel [e, o, a, ɔ] following; and [æ, ɔ] are changed to [e, o] through the influence of a following [i, u].

The principal parts of a Bengali verb, judging from these vowel modifications, can be taken to be (i) Inferior Imperative, which is identical with the Root; (ii) 3rd pers. Present; (iii) 3rd pers. Past; or 3rd pers. Future; (iv) Present Participle, and (v) Conjunctive in «-iyā». All the variations a root can undergo are found in the above forms. To classify formally the Bengali verb, it is best to take the Standard Colloquial in which the phonetic advance has been the greatest. The «sādhū-bhāṣā» spelling does not consider the present-day vowel changes and contractions, and conjugation in the «sādhū-bhāṣā» means only a rigid and regular adding of a series of affixes.

Below are given in phonetic transcript the groups into which the Standard Colloquial verbs would range themselves: the spelling in Bengali is not uniform, as has been noted before.

Class I (a): Roots in «-ā-» [ɔ] closed by a consonant:

- (i) [kər] *do*; (ii) [kore]; (iii) [korle, kolle < \*kōrile; korbe < \*kōribe]; (iv) [korte, kotte]; (v) [kore];
- (i) [bəl] *say*; (ii) [bole]; (iii) [bolle; bolbe]; (iv) [bolte]; (v) [bole].

Class I (b): Roots ending in «-ā-» [ɔ], originally in «-āh-» [əfi]:

- (i) [rə < rəfi] *remain*; (ii) [rəḥ]; (iii) [roilo; roibe, rōbe]; (iv) [roite]; (v) [roe];
- (i) [ʃə < ʃəfi] *suffer*; (ii) [ʃəḥ]; (iii) [ʃoile; ʃoibe, ʃōbe]; (iv) [ʃoite]; (v) [ʃoe]. Similarly [də, bə < dəfi, bəfi] *burn, bear*; etc.
- (i) [fiə < \*əfi] *be*; (ii) [fiəḥ]; (iii) [fiolo; fiōbe]; (iv) [fiote]; (v) [fiōe].

Class II (a): Roots ending in «-ā-» [a]:

- (i) [kha] *eat*; (ii) [khaḥ]; (iii) [khele, khelo; khabe]; (iv) [khete]; (v) [kheḥe];

Class II (b): Roots in «-ā-» [a] ending in a consonant:

- (i) [mar] *beat*; (ii) [mare]; (iii) [marle, malle, marlo, mallo; marbe]; (iv) [marte, matte]; (v) [mere].



Class II (c) : Roots in « -ā » originally closed by « -h » [aŋ > a] :

- (i) [ga < gaŋ] *sing* ; (ii) [gaš] ; (iii) [gaile ; gaibe] ; (iv) [gaite] ;  
(v) [geše < \*gaŋša, gaŋša].

Class III (a) : Roots in « -i » (rare, archaic) :

- (i) [ʃi] *live* ; (ii) [ʃie] ; (iii) [ʃilo ; ʃibe] ; (iv) [ʃite] ; (v) [ʃie].  
So [pi] *drink*, etc.

Class III (b) : Roots in « -i- », ending in a consonant :

- (i) [mil] *unite, be found* ; (ii) [mele] ; (iii) [millo ; milbe] ; (iv)  
[milte] ; (v) [mile].

Class IV (a) : Roots in « -e » (irregular) :

- (i) [de] *give* ; (ii) [dæš] ; (iii) [dile ; debe] ; (iv) [dite] ; (v) [die] ;  
(i) [ne] *take* ; (ii) [næš] ; (iii) [nile ; nebe] ; (iv) [nite] ; (v) [nie].

Class IV (b) : Roots in « -e- » ending in a consonant :

- (i) [khe] *play*, inferior imperative [khæl < \*khelə] ; (ii) [khæle] ; (iii)  
[khelle ; khelbe] ; (iv) [khelte] ; (v) [khele].

Class V : Roots in « -u- » ending in a consonant :

- (i) [ʃun > ʃon] *hear* ; (ii) [ʃone] ; (iii) [ʃuale ; ʃunbe] ; (iv) [ʃunte] ;  
(v) [ʃune] ;  
(i) [khūʃ > kbōʃ] *search* ; (ii) [kbōʃe] ; (iii) [khūʃle ; khūʃbe] ;  
(iv) [khūʃte] ; (v) [khūʃe].

Class VI : Roots in « -o » :

- (i) [ʃo] *lie down* ; (ii) [ʃoš] ; (iii) [ʃulo ; ʃobe] ; (iv) [ʃute] ;  
(v) [ʃue] ;  
(i) [do] *milk* ; (ii) [doš] ; (iii) [duile ; duibe, dobe] ; (iv) [dute, duite] ;  
(v) [due] ; (irregular ; « -o < -uh »).

Class VII : Causatives and Denominatives in « -ā » (see also *supra*,  
under *Phonology*, 'Umlaut') :

- (i) [kora] *cause to do* ; (ii) [koraš] ; (iii) [koraile ; korabe] ; (iv)  
[korate] ; (v) [korie] ;  
(i) [ʃāda] *cause to go* ; (ii) [ʃādaš] ; (iii) [ʃādale ; ʃādabe] ; (iv)  
[ʃādate] ; (v) [ʃāie].

- (i) [c̣ina > c̣ena] *cause to recognise* ; (ii) [c̣inaṣ > c̣enaṣ] ; (iii) [c̣enale ; c̣enabe] ; (iv) [c̣enate] ; (v) [c̣enie].  
 (i) [dækha] *show* ; (ii) [dækhaṣ] ; (iii) [dækhole ; dækhole] ; (iv) [dækhole] ; (v) [dekhe] ;  
 (i) [ṣona] *cause to hear* ; (ii) [ṣonaṣ] ; (iii) [ṣonale ; ṣonabe] ; (iv) [ṣonate] ; (v) [ṣunie].

[III] ROOTS AND VERBAL NOUNS IN BENGALI.

638. Although roots are essentially the creations of grammarians, conceived as the foundation of a number of words, there is always present, even among the uneducated speakers of an inflexional language, what may be called *root-consciousness*. Often the barest form, identical with the grammarian's root, is found to be in use in speech, even in highly inflected languages. Thus in Sanskrit, we see that « dṛś » means *a seeing, a seer* ; so « bhuj, bhū, pṛcch » are used as nouns ; and similarly « vṛt » is *that which turns*, and « vid » occurs as a noun in the sense of *knower*. The nominal inflexions were of course added in Sanskrit, although, as a result of phonetic decay, it would so seem that in the nominative singular the bare root itself without any formative affix added was the word. And in the modern IE. languages like English, French, Persian, Hindi, Bengali, what was originally a combination of root+affix has commonly been reduced to the bare root through phonetic decay. As a consequence in NIA. what at first sight looks like the root unmodified by any inflexion, features as a verbal noun, and also as the inferior imperative. Historical grammar will tell us that originally such forms ended in an affix, « -i » or « -a », which is now lost. In Dravidian, the simple root is used for the imperative singular : in modern Hindi and Bengali, we have the same thing resulting as the *finale* of a long history ; although it looks like an approximation to the Dravidian usage. Instances of such phonetically decayed *Root-Nouns*, as they may be called, are fairly common in Bengali. These occur either singly, or with another root-word of similar meaning, and are in the accusative or nominative relation to the verb with which they are employed : e.g., *সাজ* « sāj » as



in সাজ করা *« sājā kārā » array*; কাট *« phātā » crack as in কাট ধরেছে « phātā dhōrēchē » it has got a crack*; পচ *« pācā » rottenness*; চির, চিড় *« cirā, cirā » mark or line of a crack*; পাক ধরা *« pākā dhārā » become ripe, tend to ripen*; ডুব *« ḍubā » a dipping*; তাক লাগা *« tākā-lāgā » gaze, be struck with wonder*; খাখা করা *« khā-khā kārā » be eager to eat (but cf. খাউ খাউ করা « khāu-khāu kārā », supra, pp. 678-679)*; চল *« cālā » circulation*; রহ-সহ or রহ-ঠহ করা *« rā(hā)-sā(hā), rā(hā)-ṭhā(hā) kārā » to wait and watch*; ভাঙ্গচুর *« bhāṅ(g)ā-curā » breaking and pulverising*; ভুলচুক *« bhulā-cukā » mistakes and omissions*; তোলপাড় *« tōlā-pārā » raising and felling = turning upside down, agitating*; মারধর *« mārā-dhārā » striking and seizing*; ধর-পাকড় *« dhārā-pākāṛā » seizing and catching*; মারকাট *« mārā-kātā » striking and cutting down*; ভাঙ্গ-গড় *« bhāṅ(g)ā-gārā » destroying and building*; দেখ-মার *« dēkhā-mārā » seeing and striking, attacking at sight (cf. in a daily paper—জার্মানী দেখ-মার নীতি অবলম্বন করিল « Jārmānī dēkhā-mārā nīti ābalām-bānā kārila » Germany has adopted the policy of 'hit at sight')*; so উঠ-বস *« uṭhā-bāsā » rising and sitting*; হার-জিত *« hārā-jitā » lose and win*; চল-বুল *« cālā-bulā » walk and wander*; হাঁক-ডাক *« hākā-ḍākā » shout and yell*; কাট-ছাঁট *« kāṭā-cbātā » cut and trim (as of garments)*; কাট-ফুট *« phātā-phuṭā » crack and split*; etc., etc. These Root-Nouns also form compounds with other nouns: e.g., ছাড়-পত্র *« chārā-pātrā » passport*. See also under 'Verbal Nouns,' *infra*. For Root Imperatives, see under 'Moods,' below.

#### [C] KINDS OF VERBS: INTRANSITIVE AND TRANSITIVE.

639. Verbs in Bengali are either intransitive or transitive. In their outward form, however, there is no distinction between the two classes. Intransitive roots are chiefly primary ones, although those of secondary origin also occur. *E.g.*, *« āch, kād, kās, khēl, gāl, cāl, cu, jwār = jār, jwāl = jāl, ji, jā, jujh, jhār, ṭuṭ, ṭal, mil, hil »* etc. Also old denominatives like *« pāk, ruṭh, tāṭ, bāk, māt, phās, thām »* etc.; and new denominatives *« kulā, ghumā, dāṛā, bāhirā, śukhā, sētā »* etc. All primary intransitive roots can be made transitive by adding the causative *« -ā »*.

640. The initial stress of Bengali has in most cases obliterated the means of differentiating between the intransitive and transitive

(causative) forms of roots by making long the quantity of the root-vowel of the latter, and keeping short the quantity of that of the former. This means still obtains in the Bihārī dialects, and in Eastern as well as Western Hindī: *e.g.*, Bihārī « kṛṭab » *get cut*, causative « kṛṭab »; « diṣab » *be seen*, « diṣab » *show*; « gṛṭab » *be interred*, « gṛṭab » *inter*; Hind. « pālṇā » *be reared*, « pālṇā » *rear*; « nikālṇā » *get out*, « nikālṇā » *cast out*; etc. These intransitives with a short vowel are frequently new forms in NIA., built out of the old causatives with a proper long vowel (cf. R. L. Turner, 'The Loss of Vowel-Alternation in Indo-Aryan,' in the 'Proceedings and Transactions of the 2nd Oriental Conference,' Calcutta, 1922, p. 492). But the «-ā-» affix is indispensable in Bengali for the causative, or transitive form of an intransitive root, and quantity of the root-vowel does not count.

641. The transitive verb depends largely on its object. In Bengali, as in other NIA. languages, only inanimate nouns can properly be said to have an accusative case,—i.e., only these do not take a dative affix like «-kē, -kō» etc.: *e.g.*, জল আনো « jalā ānō » *bring water*, ভাত খায় « bhātā khāy » *eats rice*, কাঠ কাটে « kṛṭhā kṛṭē » *cuts wood*, etc. Animate nouns when really in the accusative case take the dative affix «-kē, -rē» in NB. when they are personal and definite: but they do not take the dative affix, and thus behave like inanimate nouns, when the object signified is general, vague or indefinite: গোরু চরায় « gōru cārāy » *grazes cattle*, but গোরুটাকে বাঁধো « gōru-ṭā-kē bādhō » *tie the cow*. The accusative apparently governed by an intransitive verb in Bengali is properly a dative, or a locative: *e.g.*, বাড়ী চলো « bārī cālō » *come home*; জলকে চল « jalā-kē cālā » *come to the water (=river, tank)*; বরকে গেল « ghārā-kē gēlā » *went home*, etc.

The extension of dative the post-position to the accusative is a NIA. development. The NIA. « bhāvē prayōga » or neuter construction of the transitive verb, in the past tense, as in Hindī « us-nē ghōṛī-kō dēkhā » *by-him with-reference-to-the-mare it-was-seen* (as opposed to the « karmanī » or passive construction, « us-nē ghōṛī dēkhī » *by-him mare she-was-seen*), was not a characteristic thing in MIA.: it could be established only when the dative post-position came to be attached to the accusative for precision, as the inflexion of the latter was lost. Bengali সে মানুষকে দেখিল « sē mānuṣā-kē dēkhlilā » *he*



*with-reference-to-the-man saw* and সে মানুষ দেখিল • *sē mānuṣḍ dekhilā* • *he man saw* are in their formation analogous respectively to the • *bhāvē* • and • *karmaṇi* • constructions of Hindi, etc., only the Bengali development has been to make them both active (with the proper nominative rather than instrumental), and definite in case of the post-positional form. The loss of OIA. affixes brought in the employment of post-positions for clearness and definiteness. The accusative did not possess any remarkable inflection—the OIA. • *-am* • had dwindled away to zero in Bengali and other NIA. When the dative post-position was taken up by the accusative, it was to supply this want of an affix; and it brought in greater definiteness. In Apabhraṃśa and in Avahatṭha we have the accusative (for the animate noun) without post-position, *e.g.*, in the 'Prākṛta-Pāṅgala,'—• *girivara-saṇaṇaṃ ṇamaḥa Haraṃ* • *salute ye Hara dwelling in the noble mountain* (p. 313, Bib. Ind. edition); • *gōla (= gōḍa)-rāa jīṇi* • *having conquered the King of Gauḍa* (p. 423); • *Bali chali* • *having cheated Bali* (p. 586); etc.: but • *rajja Suggivaha dija* • *gave the kingdom to Sugrīva* (p. 576), where we have the dative-genitive. In the OB. of the Cāryās, we have the same thing: • *guru pucchia jāṇa* • *ask the guru and know* (2); • *sadguru pucchi* • *asking the good master* (4); etc. In MB. and NB., in some cases the old accusative survives: *e.g.*, বন্দো মাতা সুরধনী • *bāṇḍō mātā surādhānī* • *I worship mother S.*; রাম ভজো মন • *rāmḍ bhājō mānḍ* • *adore R., O mind*. But already in the ŚKK., we find the NB. characteristic of using the dative affix for the accusative established. Bengali in this respect came in line with the other NIA. languages which developed largely the neuter construction: thus রাধাক দেখিল • *Rādhā-kā dekhilā* • *seeing R.*, পুছিল রাধাকে • *puchilā Rādhā-kē* • *asked R.* (p. 135); বড়ারিক ছাড়ি কেহে হৈবো একাকিনী • *bāṛāyī-kā chārī kēhē hāibō ēkākinī* • *why should I be alone, leaving the old woman?* (p. 147); etc.

642. One intransitive verb, compounded with a noun or adjective, behaves like a transitive in NB.: the verb বাস • *bās* •. Originally it meant *to feel, to like, to regard, to hold*. The source of it seems to be the common OIA. root • *vas* • *to dwell*, with the long, or causative grade • *vās, vās-aya* • used as

active; but there seems to have merged in it also the other OIA. roots  
 « vaś » *desire, wish for*, and « vas » *love*, as well as « vās » *put on garment*.  
 In NB., the words ভালো, বাসা « bhālō, bāsā » = *well and like* have formed  
 a compound verb-root, transitive, = ভালবাসা, ভালোবাসা « bhālā-bāsā, bhālō-  
 bāsā » *to love*. The compound মন্দ-বাস « mândā-bāsā » *dislike* also is heard in  
 NB. But in MB., বাস « √bās » was an ordinary root, which was used with  
 other nouns, or was used impersonally: e.g., ভয় বাসি, ভয় বাসি মনে « bhāyāḥ bāsi,  
 dāyāḥ bāsi mānē » *I am afraid in my mind*; শরীরে বাসি বল « śārīrē bāsi balaḥ »  
*I feel strong in body*; কোতুক বাস কি « kūtukā bāsā ki » *do you think it as*  
*queer?*; অদ্ভুত হেন বাসি « ādbhutaḥ hēnā bāsi » *strange as it were it appears to*  
*me*; না দেব কড়ি তোমার মনে বাসে « nā dēbaḥ kārī, tōmārāḥ mānē bāsē » *it*  
*strikes you as if I shall not pay the money*; লাজ বাসে « lājaḥ bāsē » *feels shy*;  
 কোপে না কহিলা মোর মনে বাসে « kōpē nā kāhilā, mōrāḥ mānē bāsē » *appears*  
*in my mind that he spoke not in anger*; বাসি ভাত ব্যঞ্জে হিহ্বায় রস বাসে  
 « bāsi bhātāḥ byāñjānē jihvāy rāsaḥ bāsē » *the tongue feels moist (with relish)*  
*with cold rice and curry*; আমার আগেতে নৃত্য করিতে বাস যুগা « āmarāḥ āgē-tē nṛtyā  
*kāritē bāsā ghaṇā » holdest in scorn to dance before me*; ঘন হেন বাসে  
 « dhāndaḥ hēnā bāsē » *it seems as if it were a maze*; হাটিতে না পারে চান্দ  
 পাএ বাসে বান্দা « hāṭitē nā pāre Cānda, pāē bāsē bāndhā » *C. cannot walk,*  
*feels as if fastened by the feet*; etc., etc. (the examples given above are  
 from the 'Padmā-purāṇa' of Vijaya-gupta, but instances abound in all  
 MB. writers). The nouns in apparent accusative relation with « √bās »  
 like ভালো, মন্দ, ভয়, ভয়, বল, কোতুক etc. above, are properly adverbial in  
 nature, rather than true accusatives.

[D] MOODS: OPTATIVE, SUBJUNCTIVE, IMPERATIVE.

643. NB. possesses but two moods, Indicative and Imperative. The Imperative occurs in the second and third persons only, and in the present tense. It is sometimes quite properly called the 'Imperative Tense.' An old future for the second person is used as a Precative or Future Imperative. For the Infinitive, there are some verbal nouns. The other moods of OIA.—Subjunctive or Conjunctive, Optative, Injunctive, and Precative, are entirely lost in Bengali.



**644.** In the well-known « āryā » or distich giving rules for working land-measures, attributed to the mathematician Śubhaṅkara (under whose name the old Indian system of arithmetic and square and cubic measures as practised in the village schools in Bengal passes), we have an optative or precative form লিজে « lijje » : কুড়ু বা কুড়ু বা কুড়ু বা লিজে, কাঠায় কুড়ু বা কাঠা লিজে « kuṛubā kuṛubā, kuṛubā lijje : kāṭhāy kuṛubā, kāṭhā lijje » *kuṛubā* (= kuḍava, 'bighā' measure =  $\frac{1}{4}$  acre)  $\times$  *kuṛubā*, take (the result) as *kuṛubā*; *kāṭhā* (=  $\frac{1}{30}$ th of a bighā, 'cottah')  $\times$  *kuṛubā*, take as *kāṭhā*. Here « lijje » take, is properly an optative or precative = *let one take*, representing a Late MIA. « \*lahijjaī, lahējjaī », which is made up of the optative form for the 3rd singular, « lahejja, lahijja » (= OIA. « \*labh-yā-t, \*labh-iyā-t » for « labh-ī-ta »), plus the affix for the indicative 3rd present « -i » (< OIA. -ti). The OIA. « -yā- » optative or precative became « -ḍyya » in First MIA., which gave later MIA. « -ḍjja, -ijja », and assumed the personal terminations « -mi, -si- (also -hi), -ti > -i » etc. of the indicative, and sometimes « -tu > -u » of the 3rd person imperative (e.g., 'Prākṛta-Pāṅgala,' p. 427—« sō tuha Saṅkara dijjau mōkkhā » *may he, Śaṅkara, grant you liberation*, where « dijjau » = « dḍjja, dijja [< dadyāt] » + « -u [< tu] » of the imperative. Cf. Grierson, JRAS., 1910, pp. 162-163); and as a distinct tense form—the 'Optative Tense'—it existed in Late MIA. This optative in « -j- » is preserved as a respectful imperative in the Midland and Western NIA. languages—e.g., Hindōstānī « kījīyē » *please do*, Gujarātī « marjē, mārjō », etc.; but it is not found in the Eastern languages, being conspicuous by its absence in the Caryās, and in MB. in general. লিজে « lijje » of Śubhaṅkara is only a stray form which has found a place in a technical verse. It is not unlikely however, that the « -ijja- » optative existed in Māgadhī Apabhraṁśa. The 'Prākṛta-Pāṅgala' verses with the « -ijj- » forms (see *supra*, p. 124) could from that assumption be connected with the East. There is a NIA. inflected passive in « -ij-, -ī-, -ij-, -i- », which is quite a different thing, being derived from the OIA. passive affix « -yā- ». A connexion between the MIA. inflected passive in « -ijja- < -yā- » and the MIA. « -ij-, -j- » imperative was suggested by Hoernle, but Tessitori has shown how this MIA. form is

only the old optative ('Comp. Grammar of the Gaudian Languages, §§ 480, 481, 499; 'Notes on the Grammar of OWR.,' §120).

645. In MB. the optative sense is expressed by the indicative with the pronominal adverb *বেন* « *jēnā* » used as a conjunction = *so that* (see *supra*, p. 853); and sometimes the instrumental of the pronoun *বা* « *jā* » *that*, *বাতে* « *jātē* » *so that*, is also similarly employed: *e.g.*, *আমি বেন দেখি* « *āmi jēnā dēkhi* » *so that I may see, may I see*; *সে বাতে করে* « *sē jātē kārē* » *so that he may do, may he do*. There is also a periphrastic form with the root *পা* « *pā* » *obtain* or *পার* « *pār* » *be able*: *e.g.*, *বেন আমি দেখতে পাই, or পারি* « *jēnā āmi dēkhtē pāi, pāri* » *may I see*. The conjunctives *বেন*, *বাতে* « *jēnā, jātē* » have no fixed place in the sentence. This idiom is found as early as the ŚKK.: *e.g.*, p. 168, *সে বেহু আন্ধাক বাহাএ দধিভার* « *sē jēnhā āmhā-kā bāhāē dādhi-bhārā* » *may she make me carry the load of curds*; p. 186, *দাবধানে লম বেহু না ছাড়িএ ঘোল* « *sābādhānē lām jēnhā nā chāḍiē ghōlā* » *take it carefully, that the whey may not scatter*; p. 211, *কেহো কাহাকো বেহু না করে উপহাস* « *kēhō kāhākō jēnhā nā kārē upāhāsā* » *may no one laugh another*. In other MB. works also this construction figures: *e.g.*, 'Caitanya-Bhāgavata,' p. 204 (ed. Atul Krishna Goswāmī), *মোর কাম—বেন দেখা পাই* « *mōṛā kāmā, jēnā dēkhā pāi* » *my desired object—may I get a sight*; etc., etc. The conjunctive or adverbial participle in *ইলে* « *-ilē* » implies a condition, and it can be used with an optative force: *e.g.*, *গেলে দেখা হয়* « *gēlē dēkhā hāy* » *an interview might take place if one went*. In this idiom, however, the optative sense is not always implied: *e.g.* OB. Caryā 2, « *rāti bhaīlē Kāmara jāi* » *she goes to Kāmarūpa (would go, may go) when it becomes night*; ŚKK., p. 397, *বে বুধি করিলে বহে আন্ধার জীবন* « *jē budhi kārīlē rahē āmhārā jībānā* » *by doing such contrivance with which my life may endure (or will endure), etc.*

646. The Subjunctive Mood, which was of so great importance in Vedic, was dropped in Classical Sanskrit, although it lingered on in Early MIA. (cf. E. Müller, 'Pali Grammar,' p. 108). Bengali in common with other NIA. (except Assamese) possesses a Present Participle form which is used for the Past Subjunctive or Conditional, as well as Past Habitual: *e.g.*, *(বদি) করিতাম (করিতে, করিত)* « *(jādi) karitām (kārītē, kārītā)* », *Oṛiyā*



« mu kārānti (tu kārāntu, sē kārāntā) » *if I (you, he) did, etc.*; so Maithili « ham karitahu, sē karitai », Western Hindi « mai kartā, ham kartē » etc.

The subjunctive is formed in Bengali with the help of the conjunction যদি « yadi, jādi » *if, a ts.* which has ousted the OB. *lbh.* « jāi ». Occasionally in early Bengali (as in early 19th century prose), the conjunction যে « jē » *that* is used. A similar use of « jāi » or « yadi » occurs in OB.: *e.g.*, Caryā 5, « jāi tumhē, lōa hē, hoiba pāragāmi » *if ye, O men, will be goes across*; 41, « jāi tō mūdhā acchasi, bhānti pucchā-tu sadguru-pāva » *if thou art ignorant, ask thou about thy mistakes at the foot of the good master*; in eM., ŚKK., p. 137, যদি মোরে পুছে আইহনে « jādi mōrē puchē Āihānē » *if Ā. were to ask me*; p. 244, তোকা দেখি যদি মোর বিচলিল মনে « tōmhā dekhi jādi mōrā bicālilā mānē » *if by seeing you my mind is moved*; p. 289, আনল শরণ কিবা করিবে যদি না দিবে বচনে « ānālā śārāṇa kibā kārībē jādi nā dibē bācānē » *if you do not give word, I seek not I shall seek refuge in fire*; p. 351, যদি কাহ্নাকি কর পার, হএ মোর তবেসি নিস্তার « jādi Kāhñāki kārā pāra, hāē mōrā tābēsi nistārā » *if you get me across, O Kṛṣṇa, then indeed may come my salvation*; etc.

This use of « yadi, jāi » is common in the Apabhraṃśa and Avahatṭha: cf. 'Prākṛta-Paṇḍala,' p. 211, « sēra ōkka jāi pāvau ghittā » *if I could get a seer of ghee*; p. 465, « jāi ētthi digantara jāihi kantā » *if the beloved one were to go to a foreign land even now*; p. 430, « jāi jaḍḍā rūsaī, cittā hāsaī pētē aggi thappiā » *if cold rages, the heart contracts, and fire is put on the stomach*; etc., etc.

647. The Imperative Mood, or 'Imperative Tense,' has the following affixes:

New Bengali :

First Person: Same as those for the Indicative Present.

Second person: Inferior (=Original Singular) has a form identical with the bare root: *e.g.*, কর্ « kār-ḥ », চল্ « cāl-ḥ »; Ordinary, used with inferiors and equals (= Original Plural) has root + « -ā » or « -ō »: কর, করো « kār-ā, kār-ō », চল, চলো « cāl-ā, cāl-ō ».

Honorific (= Originally 3 plural) = root + উন্ < -unḡ > :

করুন, চলুন < kâr-unḡ, cāl-unḡ >.

Third Person : Singular, now also Plural : root + উক্ < -u-kḡ > : করুক,  
চলুক < kâr-u-kḡ, cāl-u-kḡ >.

Honorific (= Original Plural) : root + উন্ < -unḡ > ; করুন

চলুন < kâr-unḡ, cāl-unḡ >.

### Early Middle Bengali :

First Person : Same as for Indicative Present.

Second Person : Singular and Plural অ, < -ā > ; অহ, হ < -āhā, -hā >, and  
হা < -hā > : *e.g.*, কহ < kâh-ā >, লঅ < lā-ā >, স্তত < sut-ā >  
(= *sleep* !), দে, নে < দেঅ, নেঅ < dē, nē < \*dēā, \*nēā >;  
করহ < kâr-āhā >, চিত্তহ < cint-āhā >, জাহ, বাহ < jā-hā >,  
দেহ < dē-hā >, খাহ < khā-hā >, নিষদহ < niṣādḥ-āhā >, থোহ  
< thō-hā > ; খাহা < khā-hā >, বাহা < jā-hā >.

Third Person : Singular and Plural : উ, অউ < -u, -āu > with or without  
pleonastic ক < -kā > (উক, অউক < -u-kā, -āu-kā > : rarely,  
honorific অন্ত < antā > : *e.g.*, জীউ < jī-u >, পসু < pāsu = pāś-u >,  
< dē-u >, ধর < dhār-u >, খণ্ডউ < khāṇḍ-āu >, তেজুক < tēj-u-kā  
< \*tēj-āu-kā >), থাকু < thāku (< \*thā-u-kā >); দেন্ত  
< dē-ntā > (only instance in the ŚKK.). (Also forms in ইউ  
< -iū >, for which see *infra*.)

### Old Bengali :

- Second Person : (i) < -a > : < jān-a (Caryās 1, 44); sun-a (2); cāl-a (3);  
phāl-a (4); bāha-a (13); bāh-a (14); mār-a (21); kar-a  
(28, 41); bindh-a (28); pēkh-a (30, 46); bhōl-a (37);  
dhar-a (38); pasar-a, bas-a (39); bhaṇ-a (40, 42);  
phuḍ-a (47); hēr-a, chāḍ-a (50); accha = āch-a (37) >;  
(ii) < -a-tu > : < pucch-a-tu (5); bāh-a-tu (8); bujh-a-tu  
(33) >;  
(iii) < -aha, -ha > : < bindh-aha (28); bhul-aha (15);  
chēv-aha (45); (bāhaa, Caryā 13 = bāh-aha ?) >;



- (iv) « -hu, -u » : « lā-hu (1); hō-hu (6); lē-hu, jā-hu, lō-u = lēhu, lē-u ? (32); dhahu = dhara-hu ? (38); jā-u (38); chāḍ-u (50) »;

- (v) « -hī » : « hō-hī, jā-hī » (5).

Third Person : « -au » : « kar-au » (22);

Passive Third Person : « -iu », as in « ghōl-iu (12), marāḍ-iu ? (12), saṁkēl-iu, jā-iu, (15); caṭār-iu ? (26) ».

648. OIA. employed the corresponding subjunctive forms for the imperative 1st person : singular « -āni », dual « -āva », plural « -āma ». These have not survived in MIA. and NIA. The OIA. imperative 2 sg. had « -a » as well as « -hi ». This « -a » was continued through MIA. and OB. down to eMB., after which it fell off from pronunciation : OIA. « cal-a » > NIA. « cal-a » > OB. « cal-a » > eMB. « cāl-ā » > lMB., NB. « cāl-ā ». This old singular is now used as the inferior imperative, both singular and plural : তুই, তোরা চল « tui, tōrā cālā ». This « -a » affix was fairly common for the ordinary imperative, and in the general confusion of numbers, it seems to have been extended to the plural as well from the OB. period. The « -a » certainly assimilated with the root vowel, when the root ended in a vowel, before the eMB. stage : witness ŚKK. দে, নে = NB. দে, নে « dē, nē », < « \*dēā, \*nēā », inferior forms beside the ordinary NB. দেও or দাও « dēo, dāo » and নেও, নাও « nēo, nāo » < eMB. « dēā, nēā < dēha, nēhā ». <sup>1</sup>

The affix « -hi » of OIA. seems to have been continued down to OB. in the strengthened form « -hī », as in the Caryā « hō-hī, jā-hī » : and possibly in a form like করী « kārī » in the ŚKK., as in প্রভু হইয়া হেন নাহি করী « prābhu hāyia hēnā nāhī kārī » *do not do so, being the lord* (p. 236),

<sup>1</sup> This loss of inflexional vowels occurring immediately after the root ending in a vowel seems to have taken place in Old Bengali, and possibly earlier still. Thus, for example, Tibetan tradition gives as an Old Bengali (or Old Magahi ?) sentence of the 11th century 'bhālā hoo (= hōn ?), nāth(a) Atīā, bhāt onā, bhāt onā (= bhāta anā < apāa < MIA. \*ānāpayā! = Skt. ānāyān) 'may it be well, Master Atīā, get (them) bring rice, with which a beggar-boy accosted Dīpaṅkara Śrījñāna Atīā distributing alms and food at Vikramaśīlā. (Śarat Chandra Dās, 'Indian Pandits in the Land of Snow,' Calcutta, 1893, p. 60.)

we have traces of «-hi», or of its influence (but see *infra*, under 'Inflected Passive'). But this «-hi» is lost to NB. The «-hi (-hī)» affix for the imperative seems to have been foreign to the eastern speech, which preferred «-a». In MB. we have one or two instances of this «-hi (-āhi)» affix for the imperative, as a relic from MIA.: *e.g.*, Kṛttivāsa (VSP., I, p. 497)—  
 আপনি ধার্মিক তুমি ধর্ম বুঝাহি আনে «āpāni dhārmikṣ, tumi dhārmā bujbāhi ānē» *you yourself are a righteous person, you explain the dharma to another.*

The OB. forms in «-tu», like «pucch-a-tu», are cases of pure agglutination arising out of an emphatic employ of the pronoun «tu (< tvam)». As a stereotyped form it was extended to the plural or honorific also (*e.g.*, Caryā 5, «jaī tumbhē, lōa hē, hōiba pāragāmi, pucch-a-tu Cāṭila anuttara-sāmi», translated at p. 262 *supra*).

The OIA. affix for 2 sg. *ātmanē-pada* was «-sva». This gave a vocalised «-ssu» in First MIA. (Pali), which was used even with *parasmāi-pada* roots (E. Müller 'Pali Grammar,' p. 107; W. Geiger, 'Pali-sprache,' in the Grundriss, § 126). From «-ssu» came the Second MIA. «-su». Pischel, however, holds that the Second MIA. «-su» arose by analogy: the Indicative had in MIA. the singular forms «-mi, -si, -ti > -di, -i», plural «mō, -tha > -dha > -ha, -nti», and by the juxtaposition of the 3rd personal forms, Indicative «-ti > -i, -nti» beside Imperative «-tu > -u, -ntu», the 1st and 2nd person singular also came to have in the Imperative «-mu, -su» beside the Indicative «-mi, -si» (cf. 'Gramm. der Pkt.-sprachen,' § 467).

The OB. forms in «-hu, -u» were used both for the singular and the plural, but probably they were singular at first, and it seems not unlikely that the «-hu, -u» affix originated from the «-su» form, in the pre-Bengali stage: «\*cala-sva > cala-ssu > cala-su» might have given «cala-hu» in OB., with the obscure change of «-s-» to «-h-» remaining unexplained. Or a blend of *ātmanē-pada* «cala-su», plus «calāhi, calabi» (with *parasmāi-pada* «-hi» affix) may have given «calahu», and «calasu» + «cala» similarly may have resulted in «calu».

The forms «calahu, jāhu, hōhu» etc. may equally be the original plural, with the «-ahu» affix, as in Śaurasēni Apabhraṇṣa, originating as follows: OIA. Indicative 2 plural «calatha» > MIA. Imperative «calaha, calahu»,



the «-a» changing to «-u» in MIA. probably through analogy of the 3rd plural «-ntu».

This «-u» affix was also extended to the 2nd person of the other tenses—to the past in «-il-» and the future in «-ib-» in dialectal Bengali, and to the singular 2nd person of the present, simple past, habitual past, and future in Oṛiyā.

The «-u» imperative is quite common in Apabbraṃśa, e.g., 'Prākṛta-Pāṅgala,' p. 463, «ē atthirā dōkkbu sarirā gharu jāā» *see, all this is unstable,—the body, house, wife.*

The Imperative 2nd plural affix in OIA. was «-ata». This fell together with the Indicative 2nd plural «-atha» as early as the First MIA. period, and «-atha» became in Second and Late MIA. «-adha, -aha». OB. inherited this as «-aha», and this অহ «-āhā» continued down to eMB., and is even now used in NB. as an archaic, literary form (e.g., আপন পাঠেতে মন করহ নিবেশ «āpanḍ pāṭhē-tē mānḍ kārāhā nibēśḍ» *direct your mind to your own studies*; পশ্চাৎ দেকহ «pāścādbhāḡḍ dēkhāhā» *see back*, as in Calcutta tramway tickets a few years ago). The contraction of «-āhā» to «-ā, -ā» however, took place in the spoken language as early as eMB., and this «-aha < -ā» did not coalesce with the root when it ended in a vowel, unlike the «-ā» of the original singular. Final «-ā» > -ā also occurs as «-ō» in NB., and is as a matter of fact written ও «-ō» after vowels: জাহ, জাহ > জাও «jāhā, jāā > jāō» *go!*; খাহ, খাহ > খাও «khāhā, khāā > khāō» *eat!*; নেহ, নেহ > (নেও) নাও > নাও «nēhā, nēā > nēō [neo] > nāō» *take!*; হো হো > হাও «hāō» *be!*; জীহ, জীহ > জীও «jīhā, jīhā, jīā > jīō» *live*, which even occurs as জীউ «jīu» through the influence of the preceding high vowel (cf. 'Māṇik Candra Rājar Gān,' জীউ জীউ রাইসত ধর্ম দেউক বর «jīu jīu rāiātā, dhārmā dēukḍ bārḍ» *live, ye farmers, may Dharma grant this boon*: the «-u» here, however, can equally be the other imperative affix «-hu, -u»). With roots ending in consonants the affix «-āhā» becomes also «-ō», and it is written either অ or ও: কর, চল or করে, চলে,—the pronunciation is generally [o] although the old tradition makes it অ in writing.

MIA. also changed «-aha» to «-ahu»: this has been noted before.

Early MB. «-hā» is only the «-ha» affix affected by the «-ā» of the root, as in «khā-hā, jā-hā».

649. The OIA. affix «-tu» for 3 pers. sg. gave «-u» in OB. From eMB. times, the pleonastic क «-kā» came to be added to this form (see *infra*, 'Pleonastic Affixes'). Oṛiyā and Bihārī do not employ this «-kā». In MB., forms with «-kā» are almost as common as those without; in NB., the «-kṣ» is universal, and after the loss of the «-u», this consonant has become the distinctive affix for this form: *e.g.*, बाक्, बाक्, निक्, दिक् «jāk, khāk, nik, dik», etc. The group «-u-kṣ» modified its spelling in accordance with the epenthesis of «-i-, -u-», *e.g.*, MB. जाकु, पाकु, हकु, देकु = जाउक, पाउक, हउक, देउक «jāukṣ, pāukṣ, hāukṣ, dēukṣ» etc. (see *supra*, p. 383).

The plural form of the imperative 3 pers. in OIA., «-ntu», seems to have continued down to OB. The normal development in MB. and NB. ought to have been «-tu, -ūt, -t», but we actually find उन «-unṣ». The expected «-nt- > -t-» has been ousted by «-n-» which is certainly the nominal plural affix extended to the verb (see *supra*, pp. 725-726).

OB. and eMB. have as a living form a passive imperative in «-iu, -iū», which is discussed below (under 'Passive in Bengali').

650. Forms for the Imperative in the other Magadhan speeches may be compared:

Assamese	Oṛiyā	Maithilī
1. kārō;	1. kārē—karū;	1. dēkhiaj, dēkhū;
2. kār, <i>honorific</i> kārā;	2. kārṣ—kārā;	2. dēkb, dēkhahū;
3. kārōk.	3. kārū—kāruntu.	3. dēkhan, dēkhathū.

The Assamese «kārā» represents «karaha, karāhā»; and «kārōk» = «karau+ka». The Oṛiyā and Assamese 1st person is borrowed from the indicative. Oṛiyā 2 plural «kārā» is from «karaha». The Maithilī «dēkhiaj» is extended from the indicative, and the other form «dēkhū» seems to have the «-ū» from «-mu, -mō», the Apabhraṃśa imperative 1 sg. and pl. forms. The plural «-ntu» is represented by «-thū», like the indicative «-nti > -thī».



651. NB. «sādhu-bhāṣā» has for the second person a future imperative, precative, and prohibitive in ইয়ে «-i(y)ō» which is found from the earliest period. In OB. and eMB. the form was ইহ «-ihā, -ihā». It is a relic of the old inflected or sigmatic future of OIA. : singular «caliṣyasi» > «\*calibasi, calihisi» > Bengali চলিস «cāliṣ», plural «caliṣyatha» > «calihaha» > চলিহ «cālihā» > চলিঅ, চলিয় «cāliā, cāliya» > চলিয়ো, চলিও, চল্যো, চলৌ «cāli(y)ō, cāliyō, cā'lō=[ç̣olo]». NB. Standard Colloquial has this «-iya, -iyō» affected by Umlaut. The «-iṣya» > -ih-» future was current in OB. and in eMB. (along with the «-itavya» > -ib-» future) in the three persons, but only the second person has survived in NB. (see *infra*, under 'Future Tense'). In the Caryās, as instances of the «-ih-» future imperative, we have «hōhisi, māribasi» (Caryā 23). It is exceedingly common in the ŚKK. and other MB. works: *e.g.*, «আসিহ āsihā, চাহিহ cāhihā, করিহ kārīhā, ছাড়িহ chārihā, তোষিহ tōṣihā, দিহ dihā, ধরিহ dhārihā, নিবেদিহ nibēdihā, পুছিহ puchiḥā, রাখিহ rākhiḥā» etc. In latter MB., epenthesis is noticeable, as usual: *e.g.*, রাখিহ, রাখিঅ «rākhi(h)ā» becomes রাইখ, রাখ্য «rāikhā, rākhyā = rāikhā»; so দাড়াইহ «dāṛḍāihā» as দাড়াইয় «dāṛḍāiā» > dāṛḍāiyyā», etc., etc.

The same future imperative occurs in Maithilī and other Bihārī dialects, *e.g.*, Maithilī «dēkhihāh < dēkhihahu», Bhōjpuriyā sg. «dēkhihē» plural «dēkhihā, dēkhihau». In the Bihārī dialects, the ordinary future in «-b-» can be similarly employed, as much as in Bengali. A similar imperative use of the sigmatic future does not seem to occur in Assamese and Oṛiyā.

A future imperative for the second person only can be noted, in Old Western Rājasthānī, in Western Apabhraṁśa and in Second MIA. and in all these it occurs generally with the negative particle «mā» (L. P. Tessitori, 'Grammar of OWR.', § 121).

652. The verbal form গা, গে «gā, gē» added to the imperative is found from the MB. period onwards to express the imperative in the immediate future, with a slight precative sense: *e.g.*,

1. আমি, আমরা করিগা, করিগে «āmi, āmarā kārī-gā, kārī-gē»;
2. তুই, তোরা কর্গা, কর্গে «tui, tōrā kārā-gā, kōr-gē», করিস্গা, করিস্গে «kārīsā-gā, -gē»;

তুমি, তোমরা করণা, করণে < tumi, tōmārā kārā-gā, kārā-gē >;

3. সে, তারা করণা, করণে < sē, tārā kārūṅ-gā, -gē >;

তিনি, তাঁরা, করণা, -গে < tini, tārā kārūṅ-gā, gē > (also second person honorific with আপনি, আপনারা < āpani, āpanārā >).

Cf. MB., Kṛttivāsa, ‘Ayōdhyā-kāṇḍa,’ p. 17: সীতারে কহিল—‘কল করণা ভক্ষণ’ < Sītā-rē kāhila—phāṣṣ kārā-gā bhākṣāṇḍ > said to Sītā, ‘go eat this fruit’; ‘Uttara-kāṇḍa,’ p. 20: সেই শস্তের ফল তুমি খাওগা আপনি < sēi śāstyērṣ phāṣṣ tumi khāō-gā āpani > you yourself go and eat the fruit of that grain; etc. Carey in his ‘Bengali Dialogues’ (Calcutta, 1818) translates forms in < -gā > as a simple future in the 1st person, and as an imperative in the 2nd and 3rd; e.g., উনিও সামগ্রী আরোজন করণা, আমিও করিগা < uni-ō sāmāgrī āyōjāṇṣ kārūṅ-gā, āmi-ō kārī-gā > let him get things ready, and I will do the same (p. 42). We can compare this affix of Bengali with the future suffix < -gau, -gō, -gā, -gi, -gē, -gi > of the Western Hindi and Panjābī dialects.

The Western < -gā, -gē, -gi > etc., are from the passive participle < gata > gaa >. For the Bengali < -gā, -gē >, the source may equally be the same < gata >, but the indeclinable participle গিয়া < giyā > having gone, certainly had something to do with it: the change of the root-vowel in the contemptuous second person করণে [koraṅ] can be explained only as being from করগিয়া [kōr giā]. We can compare the use of গে < gē > < গিয়া < giyā > (not গা < gā >) with the simple past and the future tenses in the Standard Colloquial, with the force of *though, nevertheless, however, even now, immediately*: e.g., সে করলে গে [śe korle ge] and then he did, তুমি করবে গে [tumi korbe ge] and you will do.

#### [E] VOICE : THE PASSIVE IN BENGALI.

#### [I] THE INFLECTED PASSIVE IN BENGALI.

##### [1] Passive Indicative.

653. Primitive Indo-European does not seem to have possessed a passive conjugation. In the Aryan (Indo-Iranian) period the passive developed out of the middle or reflexive, but it was confined to the present stem



and to the third person singular of the aorist only. The distinctive affix of this inflected passive was «-yá-» in the present stem, and the personal terminations of the middle voice were employed. Old Indo-Aryan (Vedic and Sanskrit) has preserved this passive. In Middle Indo-Aryan, the conjugational system underwent the greatest decay imaginable, but the passive was retained, being found in the present indicative and optative imperative; and a few forms like passive aorist and future were built up in Second MIA.

The «-yá-» affix occurs as «-ya-, -iya-, -iyya-, -lya-» in First MIA. and as «-ijja-» or as «-ia-» in Second and Third MIA., or is assimilated with a preceding consonant. The middle inflections of course are changed for those of the active; and the passive is extended to a number of neuter roots, forming deponents. The NIA. languages inherited the «-ijja- > -ija-» or «-ia-, -ia-» passive from Apabhraṃśa, but it is not preserved in all of them. Early in the history of NIA., the analytical mode of expressing the passive came into being, and in most of them the old inflected passive fell into desuetude. The languages of the West have preserved it, but those of the Midland, the South and the East have either entirely lost it or have only retained it as an obsolete or archaic form. Western Panjābī, Sindhi and Rājasthānī, for instance, employ «-Ij-» or «-I-, -i-» to form the passive; e.g., W. Panjābī «mārdā < mārānda-» *striking*, «mārindā» *being struck*; «cāhdā» *wanting*, «cāhidā» *being wanted*; «paṛhē» *reads*, «paṛhī» *is read*; Sindhi «karījē» *is done*, «paṛhījē» *is read*; Mārwāṛī «karaṇō» *doing*, «karījaṇō» *being done*. 'Modern Gujarātī has *ē* only in -*ē*, a 3rd sing. present passive form which is used in a reflexive sense as a substitute for the 1st plur. active [*i.e.*, «hū karū» *I do* < «aḥam karōmi», but «amē karīē» *we do* < «asmābhiḥ kriyātē» instead of from «vayam kurmaḥ»], and in all other cases substitutes the potential passive in *ā*.' (L. P. Tessitori, 'Notes on the Grammar of OWR.' § 136: R. L. Turner suggests another explanation of the Gujarātī «-īē», as being from «-imaḥ», through «-imō > -imu > -ī > -i», + «ē» of the 3 pl. [-anti > -ahim- >

-ē], to distinguish it from the absolutive in «-i» < earlier «-ia» [JRAS., 1916, p. 227, foot-note]).

654. The western languages are thus more conservative in the matter of preservation of this inherited form. The Midland language has curtailed the old passive, but relics do occur in it: e.g., Braj-bhākhā «māraj» *strikes*, «māriyai» *is struck*. Bhandarkar and Tessitori have given instances from the Early Awadhī of Tulast-dāsa. (R. G. Bhandarkar, 'Wilson Philological Lectures,' Bombay, 1914, p. 227; Tessitori, 'Grammatical Forms in Old Baiswari,' JRAS., 1914.) The modern Hindī respectful imperative or precative forms like «kijiyē» *please do* have in all likelihood been influenced by the passive, if they are not of passive origin (cf. Hoernle, 'Gauḍian Grammar,' § 480, 481, 499). An expression like Hind. «kaprā cāhiyē» *cloth to sell* is a passive one, where «cāhiyē» = *is wanted*. Compare the Bengali চাই in কি চাই «ki cāi» *what do you want?* (literally, *what is-wanted?*), তোমার আসা চাই «tōmār āsā cāi» *you must come* (literally, *your coming is-wanted*): Bengali «cāi», Hindī «cāhiyē» are from a Middle Indo-Aryan passive from «\*cāhiā(ḍ)i» = Old Indo-Aryan «\*ca(g)hyātē»: compare these with কি চাও «ki cāō» *what do you want* and তুমি আসিতে চাও «tumi āsītē cāō» *you must come*, where «cāō» = চাহ «cāhā», 2nd pers. (plural), present and imperative, = «cāhaha» (= Skt. «-atba» and «-ata»). The «-i-, -i-» or «-ijja-, ija-» affix for the passive is quite common in the dialects of the 'Prākṛta-Pāṇḍala,' which represent the stage immediately before Modern Hindī: and the loss of this affix is quite a remarkable feature in Western Hindī when compared with the neighbouring Rājasthānī and Panjābī. The «-ij-, -ij-» passive was also quite frequent in Early Marāṭhī, as Bhandarkar has noticed it (R. G. Bhandarkar, 'Wilson Philological Lectures,' pp. 226-227); but it seems to have died out in Modern Marāṭhī.

655. It would be interesting to see how far the inflected passive is preserved in Old and Middle Bengali, and in other Magadhan languages.

The language of the 'Dōhā-kōṣas' (see *supra*, p. 112) shows some cases of the «-i-» or «-ijja-, -ija-», as well as the assimilated passive:



e.g., 'Bauddha Gān Ō Dōhā,' p. 89, « purāṇē vakkhānijjāi » *it is described by the Purāṇa*; p. 103, « sō ē māi kabiājē » *that has been declared by me*; *ibid.*, « sō paramēsuru kāsū kahijjāi » *for whom is that supreme lord (to be) described?*; p. 105, « visaya ramanta ṇa visaa vilippāi (=vilippāi) » *enjoying the world, yet the world is not attached to him*; p. 106, « dēva pi (=vi) jjaī (=jaī) lakṣa (=lakkha) vi dīsaī, apyaṇu (=appaṇu) mārii sa [ki] kariai » ? *if the deity is seen face to face, self becomes dead: he (=by him) what can be done?*; p. 107, « jāva ṇa disāi » *until it is seen*; p. 109, « kāsū kahijjāi » *to whom is it (to be) declared?*; p. 129, « aīsō sō nibbāṇa bhaṇijjāi, jahi mana mānasa kiṭṭh pi na kijjāi » *Nirvāṇa is described to be such that there nothing is done of the mind or of the qualities of the mind*; p. 130, « jāi pavana-gamana-duārē [diḍḍha] tālā vi bhijjāi, jāi tasu ghōrāṇḍhārē mana diva hō kijjāi » *if the strong lock at the door for the passage of the wind is shut* (« bhijjāi », cf. Bengali root *বন্ধ* « bhēj » *to shut*=? Skt. « abhy-ajyatē »), *if in that, in the deep gloom, the mind is made as a lamp*: etc.

In this Western Apabhraṃśa dialect, the « -ijja- » affix is more common than the « -ia- », and it is in full force as a passive form. The Old Bengali of the Caryā-padas has a number of instances of the inflected passive, but the affix is « -i(a)- », not « -ijja- » or « -ija- »; besides there are a few of the assimilated « -yā- » forms: e.g., Caryā 1, « saala sa[mā]hia kāhi kariai » *what is attained by all samādhi?*; 6, « hariṇā hariṇira nilaa na jāṇi » *the abode of the stag and of the doe is not known*; *ibid.*, « hariṇāra khura na dīsaā (=disai) » *the stag's hoof is not seen*; 26, « pāviai » *is obtained*; « bhāviai » *is thought of*; 32, « dubiē » *is milked*; 46, « echijai » (=chidyatē) *is cut*; etc.

The analytical passive with root *জা, যা* « √jā < yā » *to go* following the verbal noun in « -ana » has already become established in the language of the Caryās; and the analytical « √jā » passive in NIA. seems to have been influenced by, if not actually developed out of, the older inflexional « -ij- » form.

It would seem that in Māgadbī Apabhraṃśa, the two forms \* -ia- > and \* -ijja- > occurred side by side: and \* -ia- > seems to be the genuine Magadhan affix, and \* -ijja- > borrowed through the influence of the Western speeches, and not native in the East. The \* -ia- > was preserved in OB. and in MB., although as an obsolete form in the latter, and its real nature seems to have been lost to the speakers quite early.

The examples of the \* -ia- > passive in the 47 Caryās are not so few, there numbering some twenty. In Middle Bengali literature we find similar relics of the inflected passive—a linguistic survival which seems not to have been noticed before. The affix loses prominence as the language progresses, and is ultimately merged into the 1st and 3rd personal affix; and in this way the passive verb is transformed into the active one.

There are numerous cases of the passive in \* -i(a)- > in the ŚKK. : for instance—

p. 19, বত নানা ফুল পান করপুর সব পেলাইল পাঁএ ।

উঠিআ বড়ায়ি রাধাক বুইল—হেন কাম না করিএ ॥

\* jāta nānā phulā pānā karāpurā sabbā pelāila pāē :

uṭhiā Bārayi Rādhā-kā buila—'hēnā kāmā nā kariē' •

*All the various flowers, betel-leaves and camphor and all she threw away with her foot. The Old Lady got up and said to Rādhā, 'you should not do so' (lit. such a deed should not be done : \* kariē >);*

p. 57, আইহন বীর তিন লোকে ভালে জাণি ॥

\* Āihānā bīrā, tinā lōkē bhālē jāṇi •

*That Ā. is a hero is known (jāṇi) well in the three worlds ;*

p. 59, দান সাধিএ রতিপতিআশে ।

\* dānā sādhiē rāti-pātiāśē •

*The toll is demanded (sādhiē) with the expectation of dalliance (with thee) ;*



- p. 118, ভুখিল হয়িলে কাহ্নাকি জুই হাথে না খাইএ ।  
 • bhukhilā hayilē, Kāhñāki, duī hāthē nā khāiē •  
*When one is hungry, O Kāhñā, one should not eat (• khāiē •, lit. it should not be eaten) with both hands ;*
- p. 137, আপণা রাখিয়ে আপণে ।  
 • āpāṇā rākhiyē āpāṇē • (=ātmā rakṣyātē ātmanā)  
*Self is (to be) preserved by self ;*
- p. 145, নাএর আন্তরে গেলো চন্দ্রাবলী রাহী ।  
 তার পাছে আর যত গোআলিনী সহী ॥  
 কথো দূরে গিয়া দেখিএ একখানি নাএ ।  
 দ্বর হয়আ রাহী তার পাস বাএ ॥  
 • nāērā āntārē gēli cāndrāvalī Rāhī,  
 tārā pāchē ārā jātā gōālinī sāhī.  
 kāthō dūrē giā dēkhiē ēkā-khāni nāē :  
 sātwarā hāyiā Rāhī tārā pāsā jāē •  
*In search of a boat went Candrāvalī Rādhikā ;  
 After her, all her milk-maid friends ;  
 Having gone some distance, a boat is seen (dēkhiē).  
 Quickly Rādhikā goes to its side ;*
- p. 184, বোলৈ চালৈ না পাইএ পরার রমণী ।  
 • bōlē cālē nā pāiē pārārā ramaṇī •  
*Another's wife is not won (pāiē) by talk and (gallant) ways ;*
- p. 185, গোপত কাজত কাহ্নাকি ছয় আখি বারী ।  
 • gōpātā kūjā-tā, Kāhñāki, chāyā ākhi bārī •  
*In a secret deed, O Kāhñā, six eyes are barred (bārī) ;*
- p. 236, ত্রিভুবন নাথ তোমহে হরি । প্রভু হয়আ হেন নাহি করী ॥  
 • tribhubānā-nāthā tōmhē Hāri, prābhū hāyiā hēnā nāhī kārī •  
*You are Hari, the Lord of the three worlds ; being the Master,  
 you should not do so (lit. it should not be done : • kārī •) ;*
- p. 289, পুনমীর চান্দ তোমার বদন ঘুদিএ অগতজনে ল ।  
 • punāmīrā cāndā tōmhārā bādānā ghusiē jāgātā-jānē, lā •.  
*O, your face is proclaimed (ghusiē) by the people of the world  
 to be the moon of the full-moon night ;*

p. 367, সোণা ভাঙ্গিলে আছে উপাএ জুড়িএ আগুন তাপে ।

পুরুষ নেহা ভাঙ্গিলে জুড়িএ কাহার বাপে ॥

• sōṇā bhāṅgilē āchē ūpāē, juṛiē āgunā-tāpē :

puruṣā-nēhā bhāṅgilē, juṛiē kāhārā bāpē ? •

*If gold is broken, there is a way—it is joined (juṛiē) by the heat of the fire ; but if a man's love is shattered, by whose father (=by what man) can it be joined ?*

There are numerous other instances of a similar type in the ŚKK. The general tendency will be to explain the forms in ইএ «-iē» as being in the ই «-i» of the first person, and the এ «-ē» only as a final lengthening for reasons of metre. But পাইএ, করিএ «pāiē, kariē» etc., are true inflected passives, and it will be seen that in the instances quoted above, the passive construction gives the correct explanation of the passages rather than the active first person : পাইএ, করিএ etc., thus represent the Caryā forms like «pāviai, kariai», =Sanskrit «prāpyātē, kriyātē». The passive was already dying out in Old Bengali; and in Middle Bengali it would be easily confused with the active first person from similarity in form. We may recall as a parallel instance the Gujarāṭi use of the passive third person singular as the first person plural active, as in «amē utārīē, amē cālīē», etc., which have been explained as being really passive forms (see *supra*, p. 910). The same thing seems to have happened in Central Magadha, in the «-iai» forms for the 1st person of the verb. The passive in its origin is connected with the reflexive, and the transition to the active is always easy. More so in the early periods of Bengali, when there was a confusion between the instrumental and the nominative, from which the language even now is not wholly free.

The transition from the decaying passive, which was less and less properly understood, to the active was quite a matter of course : from after the ŚKK. onwards, we find frequent use of «-iē» in active forms, for the 1st person generally.

The passive use of the neuter verb is also common in Old and Middle Bengali: e.g., ŚKK., p. 364, পুণ্য কইলো স্বৰ্গগ জাইএ, নানা উপভোগ পাইএ  
• puṇyā kailē swāggā jāiē, nānā upābhōgā pāiē • (=gamyatē, prāpyatē)  
*practising virtue, heaven is attained, and many enjoyments are obtained.*



Examples of the inflected passive are frequent in Middle Bengali literature. A few are given below :

From poems by Caṇḍidāsa (VSP., II, pp. 968 ff.): নীল মুকুতার হার মনোহর শোভিত দেখিএ গলে • *nila mukutāra hāra mānohāra śōbhita dēkhiē gālē* • a charming necklet of blue pearls is seen beautifully in her neck; অবলা পরাণে এত কি সহিএ • *ābalā parāṇē ēta ki sahiē* • can so much be endured in the life of a weak woman?; কুরের উপর রাধার বসতি, নড়িতে কাটিএ দে • *kṣurēra upāra Rādhāra bāsati, nāritē kāṭiē dē* • Rādhā's abode is on (the edge of) a razor, her body is cut at the (slightest) movement; মানুষে এমন প্রেম কোথা না শুনিএ • *mānuṣē ēmaṇa prēmā kōthā nā śuniē* • such love in man has nowhere been heard of; from the 'Caitanya-caritāmṛta' of Kṛṣṇa-dāsa Kavirāja (VSP., II, p. 1223): সনাতন কৈল গ্রন্থ ভাগবতামৃতে। ভক্তি-ভক্ত-কৃষ্ণ-তত্ত্ব জানি বাহা হইতে ॥ হরিভক্তিবিলাস গ্রন্থ কৈল বৈকব আচার। বৈকবের কর্তব্য বাহা পাইয়ে পার ॥ • *Sanātana kaila grānthā Bhāgavatāmṛtē, bhakti-bhaktā-Kṛṣṇa-tattwa jāni jāhā hāitē: Hari-bhakti-bilāsa grānthā kaila baiṣṇava-ācāra, baiṣṇava kārṭtabya jāhā pāiyē pāra* • Sanātana made the book Bhāgavatāmṛta, from which are known the doctrines of bhakti and bhakta, and the nature of Kṛṣṇa; he made the book Hari-bhakti-vilāsa, on Vaiṣṇava ritual, in which the duties of a Vaiṣṇava are made to cross over, as it were (i.e. described in detail); from 'Bhāgavata,' by Daivaki-nandana Siṁha. (VSP., II, p. 844): যে অঙ্গে দেখিএ সেই অঙ্গে অলঙ্কার • *jē āṅgē dēkhiē sēi āṅgē ālāṅkāra* • jewels on every limb that is viewed; বিনি না পুছিলে কারো না জানিএ জাতি • *bini nā puchilē kāro nā jāniē jāti* • no one's family is known without asking.

656. Instances like the above are fairly common in Early Bengali literature, and further quotations are not necessary. Maithili and Oriyā, too, show similar forms, and some instances may be given :

Maithili : Vidyāpati (VSPd. edition), p. 6, • *lakhaī na pāria, jēṭha kanēṭha* • cannot be distinguished, (whether) old (or) young; p. 9, • *jata dēkhala, tata kahabi na pāria* • all that was seen cannot be described; p. 19, • *paṛhabī na pāria ākhara-pāṭi* • the rows of letters cannot be read; p. 21, • *sē nahi dēkhala jē diya upāmā* • that has not been seen with which a

comparison can be made; p. 80, « saba taha sunia nisana bēwahārā » *that such is the usage is heard from all*; p. 89, « Madhu-ripa sama nahi dēkhia sohāwana, jē dia tanhika upāma rē » *nothing handsome like the Fox of Madhu is seen, with which his comparison can be made*; p. 44, « na jāniya kiya karu mōhana cōra » *what this charming scamp may do is not known*; p. 499, « kajjala-rūpa tua Kālī kabiaō...Gangā kahiē pānt...Bramhā-ghara Bramhānt kahiē, Hara-ghara kahiē Gaurī » *in favour like lamp-black, thou art called Kālī; she is called Gangā when in watery form; in the home of Brahmā, is called Brahmānt; is called Gaurī in the home of Hara*; etc.

Oriyā : Jagannātha-dāsa's 'Dhruva-caritra' (Contai edition): p. 5, « kāmpii (=kampyatē) tāhārā nijā dēhi » *her own body trembles*; p. 83, « dēhā-mānā diśāi, khājurā-bṛkṣā-prāyā » *his body's measure is seen, like a date-palm*; p. 11, « dāśā-diśi āndhākārā, kichi hi nā diśi » *the ten quarters are dark, nothing is seen*.

Thus the older literatures of Maithilī and Oriyā also demonstrate the presence of the inflected passive in these speeches.

657. The inflected passive is also preserved in a curious idiomatic usage in Modern Bengali, in which both its form and nature are disguised. We have expressions like এ কাজ করে না « ē kājṛ kārē nā » *shouldn't do this*, রবিবার দিন মাছ খায় না « rābi-bāṛṣ-dinṣ māchṣ khāy nā » *shouldn't eat fish on Sundays*, অর হ'লে নায় না « jwārṣ hōlē nāy nā » *shouldn't bathe when there is fever*, etc., etc., where the forms করে, খায়, নায় etc., are used with or without the negative particle, and are apparently 3rd person indicative present, the subject, however, being left understood; and such expressions have a general prohibitive or imperative force. The fuller form is presented in dialectal Bengali: in Birbhum, for instance, there is an imperative or optative in «-jīyē», e.g., in sentences like হোথা জেয়ে না « hōthā jēyē (< jāiyē) nā » *one shouldn't go there*, ভাইকে না দিয়ে খেয়ে না « bhāi-kē nā diyē khēyē (< khāiyē) nā » *shouldn't eat without sharing with one's brother*, আগুনে হাত দিয়ে না « āgunē hātṣ diyē nā » *shouldn't put one's hand in fire*, তোর দাদা যেনে না এসে « tōṛṣ dādā jēnē nā ēsē (=ēsiyē?) » *may your brother not come*, যে আমাকে এত কষ্ট দিলে তার কষ্টব্যাধি হ'লে, সে যেনে



হুটী চোখ খেয়ে • jē āmākē ētā kāṣṭhā dilē tārṣ kuṣṭhā-byādhi hōyē, sē jēnē duṭi cōkhṣ khēyē • *may he get leprosy, may he eat his two eyes, that caused me so much pain* (Basanta Kumār Chatterji in the VSPdP., 1926, p. 266): in these, খেয়ে, দিয়ে are passives, and খেয়ে, এসে, হ'য়ে are equally passives of neuter verbs (such as are found in the ŚKK.) in which the archaic aspect, which cannot be confused with the indicative active present, is retained. In MB. there are instances of this construction: cf. ŚKK., p. 333, প্রভু হুগিঅঁ হেন না করী • prābhu hūyīḥ hēnā nā kārī • *shouldn't do so, being the Master*; p. 185, লোভ হুগিলে কাহাঞি আরতি না করী • lōbhā hūyilē Kāhāñi ārati nā kārī • *O Kāṇha, shouldn't yearn (too much) although there is desire*; p. 257, কেহ তার না কহিএ মরণে • kēhā tārā nā kāhiē mārāṇē • *none should speak of his death, etc.*; etc. The MB. forms in • -i-, -ī- • indicate that this construction is properly a passive one; এ কাজ করে না, • ē kājṣ kārē nā • is • ētat kāryam na kriyatē •: • kriyatē • would be • kariaī, kārīē, kārī • in MIA. and OB. and MB. As in the other cases, the passive nature of the verb was forgotten, and the active form came in. The influence of a similar imperative use of the optative (active and middle) and of the passive, as in Sanskrit, is likely here.

General statements, in which the subject is not definite or important, may be in the third person, active. But it is just likely in such popular expressions like জামায়ের জন্য মারে হাঁস। গুষ্ঠী-শুদ্ধ খায় মাস ॥ • jāmayērṣ jānyā mārē hāṣṣ, guṣṭhī-śuddhā khāy māṣṣ • *they kill the goose for the son-in-law, and eat the meat with the whole family (= the goose is killed, the meat is eaten)*; and এক দেয় বর দেখে। আর দেয় বর দেখে ॥ • ēkṣ dēy [dæṣ] bārṣ dēkhē, ārṣ dēy [dæṣ] ghārṣ dēkhē • *they give (in marriage), first by looking at the bridegroom, again by looking at the house = (the daughter) is given (in marriage), taking into note either the bridegroom or his family*; and in similar proverbial couplets and phrases, we have the passive.

It seems we have also the passive in a rare polite imperative in some North Bengali dialects, e.g., জাখেক, রাখেক • dyākhē-kṣ, rākhē-kṣ • *please see, please keep* (= • dēkhiē, rākhiē + -kā •: see below, 'Pleonastic Affixes: Affix • kā •').

## (2) BENGALI ' KARMA-KARṬṚ-VĀCYA.'

658. The so-called middle-voice (*karma-karṭṛ-vācyā*) of Bengali, which we find in impersonal constructions, seems originally to have been this inflected *-yā-* passive: e.g. কলসী ভরে *•kālāsī bhārē • the jar becomes full*; কাপড় ছেঁড়ে *•kāpāṛṣ chēṛē • the cloth gets torn*; বই কাটে *•bāi kātē • the book cuts > sells*; বাঁশ ভাঙ্গে *•bāśṣ bhāṅgē • the bamboo breaks*; শাঁখ বাজে *•śākhṣ bājē • the conch-shell is sounded*; etc. Here ভরে, ছেঁড়ে, কাটে, ভাঙ্গে, বাজে, etc., are to be explained as passive forms, derived from earlier, fuller *\*bharīāi > \*ভরিএ •bhārīē*, *\*chiṇḍīāi > \*ছিড়িএ •chiṇḍīē*, *\*kaṭṭīāi, \*kaṭīāi > কাটিএ •kāṭīē*, *\*bhañjīāi* or *\*bhaṅgiāi > \*ভাঞ্জিএ •\*bhāṅgiē*, *\*bājīāi > \*বাজিএ •\*bājīē* etc., of OB. and eMB. A similar use of the passive is known also in Sanskrit (cf. Speyer, ' Vedische und Sanskrit-Syntax,' § 169).

## (3) OB. AND MB. PASSIVE IMPERATIVE.

659. In the ŚKK. there is a form in ইউ *•iū •* which is illustrated by the following examples :

p. 140, নান্ন বান্ধিতে গিঅঁ করিউ যতনে *•nāṣ bāndhitē giā kārīū jātānē • let us make an attempt to build (lit. bind) the boat*; p. 141, আনহঁ সকল সখিজন মেলা করিউ যুগতি *•ānāhā śākālā śakhi-jānā, mēlī kārīū jugāti • bring all girl friends, let us hold a consultation together*; p. 141, পসার সাজিউ দধি দুধে, সেসি জীবর উপাএ *•pāsārā sājiū dādhi dudhē, sē-si jībārā upāē • let us arrange our milk and curds for sale, that indeed is the means of livelihood*; p. 204, নানা ফুল ফুটিলছে মাঝ বৃন্দাবনে । তাক পিন্ধি মথুরাক করিউ গমনে ॥ *•nānā phulā phuṭilā-chē mājhā Bṛndābanē, tākā pindhi Māthurā-kā kārīū gāmanē • flowers of many kinds have blossomed in the middle of Vṛndāvana, wearing these, let us go to Mathurā*; p. 253, বদুনাক যাইউ রাধা লয়ি আঁ সখীগণে *•Jāmunā-kā jāiū Rādhā, layiā śakhi-gaṇē • let us, O Rādhā, go to Yamunā, taking (our) girl-friends*; p. 270, দধি বিকঁ জাইউ মথুরা *•dādhi bikē jāiū Māthurā • let us go to Mathurā to sell curds*; p. 292, নব্বরে রাখা লইকাঁ জাইউ ঘর *•sātwarē Rādhā lāiā jāiū ghārā • let me take Rādhā quick to her home*; p. 310, বাঁশী চোরায়িতঁ করিউ যতনে *•bāśī cōrāyitē kārīū jātānē •*



*let us make an effort to steal the flute*; p. 354, বারতা পুছিউ রাখা সব জন ধানে « *bārātā puchiū Rādhā sabbā jānā thānē* » *let us ask for news, O Rādhā, from everybody*; p. 347. কদমতলাক জাইউ চিত্তের হরিষে « *kādamā-tālā-kā jāiū cittērā hāriṣē* » *let us go to the foot of the Kadamba tree, with joy in mind*.

This ইউ « *-iū* » form is certainly the passive imperative: in force it is generally optative or imperative. In an example like হাশী চোরারিতে করিউ যতনে, করিউ যতনে « *kāriū jātānē* » = Skt. « *kriyatām yatnaḥ* »; so জাইউ « *jāiū* » = « *gamyatām* », বারতা পুছিউ « *bārātā puchiū* » *let us ask for news*, lit. *let news be asked for* = « *vārttā pṛcehyatām* ». The ইউ « *-iū* » affix is the Second MIA. imperative passive 3rd pers. singular affix « *-ladu* », as in Śaurasenī (and Māgadhi) « *kadhīadu, kariadu (kaltadu), suñīadu (śuñīadu)* » = « *kathyatām, kriyatām, śrūyatām* », « *-ladu* » giving the later form « *-laū* » and « *\*-lu* ».

In eMB., the spelling with long উ « *ū* » has no special point, unless the lengthening had a historical reason analogous to that for the final « *-ī* » in the same period (see *supra*, p. 309). This 3 pers. imperative in « *-iū, -iū* » soon became confused with the 1 pers. indicative present in « *-ō, -ō* » (for which see *infra*, 'Radical Tense'). This « *-iū* » passive is also found in Old Bengali (see *supra*, pp. 904, 907): e.g., Caryā 15 « *bāṭa jāiū* » *go the way* (= *vartma, vartmani gamyatām*).

## [II] ANALYTICAL FORMATION OF THE PASSIVE IN BENGALI.

660. The inflected passive is a fossil in Bengali: the living method is analytical and periphrastic. The following are the ways in which the passive is formed in Bengali:

*I am seen* = (1) আমি দেখা বাই « *āmi dēkhā jāi* »; (2) আমাকে (আমার, আমারে) দেখা যায় « *āmākē (āmāy, āmārē) dēkhā jāy* »; (3) আমাকে (আমার, আমারে) দেখন যায় « *āmāḱē (āmāy, āmārē) dēkhāṇē jāy* »; (4) আমি দেখা পড়ি « *āmi dēkhā pāri* »; (5) আমাকে (আমার, আমারে) দেখা হয় « *āmākē (āmāy, āmārē) dēkhā hāy* »; and (6) আমি দৃষ্ট হই « *āmi dr̥ṣṭā hāi* ».

Of these (1), (4) and (6) are true passives (*karma-vācya*), and these agree with the passive forms of English, French and other modern

Indo-European languages. The other forms, (2), (3) and (5) are instances of the neuter construction (*bhāva-vācya*) in Bengali. All the above forms are used in Bengali, but there are slight shades of difference in their meaning.

661. (1) আমি দেখা যাই • *āmi dēkhā jāi* • *I am seen* is best explained as being composed of the passive participle (adjective) in *আ* • *ā* • and *যা* • *√jā* • *to go*, and which assumes the function of the substantive verb. But this form, though allowable, would not ordinarily be regarded as very idiomatic or natural in Bengali: the passive proper, with the object in the nominative, would hardly be considered as natural to the language, especially when the nominative is a definite person. But general statement, where only the action is definite, and is the more important thing, can be easily made with an impersonal construction in the passive: *e.g.*, দেখা যায় • *dēkhā jāy* • *it is seen* (subject ইহা • *ihā* • *this, it* understood); যদি বলা যায় • *yādi bālā jāy* • *if it is said*; শোনা যাইতেছে or যাচ্ছে • *śōnā jāitēchē, jācchē* • *it is being heard*. In the passive construction, the mind of the speaker is loth to forget that what is the grammatical nominative is the real object, and hence the feeling of the native speaker has this preference for the neuter construction, with the nominative-object in the dative, *e.g.*, আমাকে দেখা যায় or আমাকে দেখা হয় • *āmākē dēkhā jāy, hāy* •. The conscious use of the passive would bring in a certain amount of emphasis; and to make a statement emphatic or definite, the dative with *কে* • *-kē* • is preferred to the accusative or nominative without any inflexion, when we are speaking of a sentient or animate being (see *supra*, pp. 897, 898). So আমাকে (আমারে, আমার) দেখা যায় • *āmākē (āmārē, āmāy) dēkhā-jāy* • would be preferred, as the idea is definite so far as the object of sight is concerned, to আমি দেখা যাই • *āmi dēkhā jāi* • where আমি • *āmi* •, although formally nominative, is in sense really the oblique or accusative. আমি দেখা যাই • *āmi dēkhā jāi* •, however, would seem to be the older form, and আমাকে দেখা যায় • *āmākē dēkhā jāy* • a later one. আমি করা যাই • *āmi kārā jāi* • *I am done* would be bad Bengali, because here the first personal pronoun would preferably have the *কে* • *-kē* • and be put in the dative as it is very



definite, and করা যাওয়া « kārā jāōā » is rather vague: the construction would be regarded as clumsy. But আমি ধরা গাই « āmi dhārā jāi » *I am caught* would be quite allowable, as ধরা « dhārā » refers to a definite action.

Names of inanimate objects as a rule do not take কে « -kē » when they are in the objective or dative; hence ঘর দেখা যায় « ghārāḍ dēkhā jāy » *the house is seen* (not ঘরকে « ghārāḍ-kē »), where ঘর « ghārāḍ » can be easily parsed as being the subject of the passive sentence.

662. (২) আমাকে (or আমারে, আমার) দেখা যায় « āmakē (āmārē, āmay) dēkhā jāy » *I am seen* or, with a slight potentiality implied, *I may be seen* (= *they can see me*). There is a difficulty in explaining দেখা « dēkhā » here. Generally it is looked upon as a verbal noun in আ « -ā », derived ultimately from the passive participle in « -tā » of Indo-Aryan, the nominal use of which is also quite common in Sanskrit. It would thus be explained as meaning *with-regard-to-me, a-seeing goes-on* (or *takes-place*). The occurrence of (৩) আমাকে দেখন যায় « āmakē dēkhāṇḍ jāy » *with-regard-to-me a-seeing takes-place* would lend countenance to the above explanation. But it would seem that in an expression like আমাকে দেখা যায়, দেখা is really a passive participle adjective, and the whole construction is in the impersonal, which is so characteristic of the Western and Southern Indo-Aryan languages: আমাকে দেখা-যায় would be best explained as being literally, *with-regard-to-me, it-is-seen*.

If we had evidence from Old and Middle Bengali remains on this point, we might expect a solution of the difficulty. But the passive with the past participle in আ « -ā » was not at all a popular form, and its occurrence is rather rare in the plain direct narration of Middle Bengali verse. Stray instances in the ŚKK. like তোমরা জাইবে মার « tōmhā jāibē mārā » (= মারিঅ, মারঅ OIA. « mārā » > mārā, mār-ā » = Modern মারা « mār-ā », i.e., মারিঅ+আ « mārā » + pleonastic affix « -ā ») *you will get killed* (p. 33), বান্ধিল জাই « bāndhilā jāi » *becomes tied up, is put in bonds*, (p. 71: here we have the old passive participle adjective in ইল « -il- », for which see *infra*, under 'Past Tense') indicate that the passive participle is the form associated with this construction. The transition was from the real passive made up of the participle and the verb (and with the

object proper in the nominative) to the impersonal neuter construction (with the nominative-object in the dative and the passive participle); and such a state of things has its parallel in the other cognate languages.

663. The origin of this জা or যা «jā» passive has undoubtedly been influenced, as Beames had suggested ('Comparative Grammar of the Indo-Aryan Languages,' Vol. III, 1879, pp. 73-74), by the old «-ijja-» passive of Apabhraṃśa. We have the «-ijja-» forms in Prakrit and Apabhraṃśa on the one hand, and the «jā» forms in the modern languages on the other: the middle is blank, and linking these two in all likelihood there was a transitional stage, not represented in linguistic remains, when the «-ijja-» was slowly assuming a new rôle as a root—when it was merging into the «jā» root, as it were. It would seem that the neuter passives (deponents) like «marijjaī=mriyātē» *dies* first took up an analytical form: because «marijjaī» is equivalent in meaning to «marai» or «marē» (=māraṭi, māratē), the «-jjaī» would seem to have been regarded as a form of «jāī» from «√jā», giving rise to the analysis «mari jāī» *having-died, goes or passes away* (=MB. মরিয়া যায় «māriyā jāy»). The occurrence of the compound verb in the speech would help such an analysis. Once this analysis was established, there would not be any bar in forming other tenses and verb forms from «√jā». In Early Middle Bengali, analysed forms of the above type (the conjunctive in ই «-i» or ইয়া «-iyā» + √যা «jā», mostly with neuter verbs) are very common; e.g., in the SKK. চলি জাইহ «cālī jāihā» *depart*; পড়ি গেল দিঠী «pāṛi gēla diṭhī» *the night was cast*; ভাঙ্গি জাএ «bhāṅgi jāē» *gets broken*; মোর মজি গেল মনে «mōrā māji gēla mōnē» *my mind became attached*; পড়িয়া যাইবৈ «pāṛiyā jāībē» *you will fall*; মরিয়া যাইবি «māriyā jāibi» *will die*; etc., etc. An Old Bengali instance would seem to be «avasari jāī» (<«\*avasarijjaī», deponent of «ava» + «√sṛ» *more*) in Caryā ১২. The modern passive or neuter with the জা «-jā» participle would seem to be of later origin. The potential sense which one can attach to the passive in যা «√jā», and which is never present in the passive with হ «√hā», seems to point



at the «-ijja-» origin of the former. The old potential or optative had «-ĕjja-» in Prakrit, and the confusion between the passive and the optative, already noted, might just be continued in the newly risen analytical form.

As has been noted above, the «-ijja-» form seems to have been foreign to Māgadhī Prakrit and Māgadhī Apabhraṃśa, the source of Bengali; since no «-ijja-» forms are found in the relics of the inflected passive preserved in Bengali and other Magadhan languages, only «-i-» forms. The formation of the analytical passive with «jā» may thus have been brought about in Old Bengali through contact with and influence of Western dialects having «-ijja- > -ij, -ij-».

664. (3) আমাকে দেখন যায় «āmākē dēkhāṇā jāy» *I am seen, I may be seen*, lit. *with-regard-to-me, a-seeing goes-on (or takes-place)*. This form of passive is one of the oldest constructions in Bengali. It occurs in the Caryās, and it is quite plentiful in Middle Bengali; e.g., (Caryā 2) «dharaṇa na jāi» *cannot be held*, (35) «kahaṇa na jāi» *cannot be described*, (4) «lēpana jāi» ? *is entangled or smeared*; ŚKK., p. 38, ললাট লিখিত বস্তুন না জাএ «lālātā-likhitā khaṇḍāṇā nā jāē» *that which is written on the forehead cannot be averted*; p. 58, প্রাণ ধরন না জাএ «prāṇā dhāraṇā nā jāē» *life cannot be endured*, etc. Middle Bengali instances are fairly common. In Modern Standard Bengali, this construction is falling into disuse, but it is fully preserved in the East Bengal dialects. The employment of this অন «-āṇā» + যা «-jā» passive is impersonal, and it is on the lines of (2).

It would seem to have originated from an unconscious analysis of the verbal adjectives, passive, in «-anīya(ka)». The line of development was probably as follows: «karaṇīya-ka > karaṇijja(y)a» > করণি জাএ «\*karaṇi jāē», করণ জাএ «kārāṇā jāē»; so «paṭhanīya-ka > paṭhanijja(y)a», পড়ণি জাএ, পড়ন (পড়ন) জাএ, «\*paṭhaṇi jāē, pāṭ(h)āṇā jāē»; etc. The intermediate form in this process of analysis, as in করণি জাএ, পড়ণি জাএ, is not preserved in Bengali, but it seems to be represented in Early Baiswārī forms like «barani jāya, kahani jāi» etc., as in Tulast-dāsa. We may note that an expression like না জায় কহনে «nā jāyā kāhānē» would be quite

natural in Middle Bengali, and the locative-instrumental in এ •-ē• in কহনে •kāhān-ē• might be a reminiscence of the older form in ই •-i• which could be regarded as a locative. The analysis into a noun in অন+√বা •-ana• + •√jā• took place before the Old Bengali period: and once this analysis became accepted, transposition of the noun and the verb, and the insertion of the negative particle না between the noun and the verb, which is so frequent in negative constructions of this type in Middle Bengali, would result: thus সহন না যায় •sāhānā nā jāy•, না যায় সহন •nā jāy sāhānā• *it cannot be borne* (but curiously enough, না সহন যায় is not found, although সহন যায় না is commonly met with in modern speech: the reason being probably that না •nā• which qualifies the verb in this analysed form must not be separated from it by the noun).

In Middle Bengali we have a few cases where there is apparently a verbal noun in অ •-ā•: e.g., নিবার না যায় রে •nibārā nā jāy rē• *cannot be prevented* (VSP., p. 981); so বোল না যায় •bōlā nā jāy• *cannot be described*. There is no form in Modern Bengali corresponding to it: the absence of the -ন (ণ) •-nā (-ṇā)• in such cases is in all likelihood due to hapology.

665. (4) আমি দেখা পড়ি •āmi dēkhā pāri• *I am seen, I happen to be seen*, lit. *I fall seen*. This construction, apparently an old one, is essentially idiomatic, and strictly speaking it should come under the consideration of the characteristic 'Compound Verbs' of Modern Indo-Aryan. The use of the পড় •√pār• is restricted to a few verbs only, and as Beames has fully noticed it, it indicates accident as well as finality more than anything else. The দেখা •dēkhā• etc., are best explained as passive participle adjectives. The modern Dravidian employment of a root •paḍ• to form the passive has been noted by Beames and others, but it would seem that it is a matter of coincidence. The old Dravidian speech did not possess a passive form, but the employment of obviously the same root in the two groups of Indian speeches, Aryan and Dravidian, is interesting; and it is only one of numerous points of similarity which demonstrate a fundamental agreement between the speakers of the languages of the two groups in their habits of



thought. The impersonal construction with পড়  $\sqrt{\text{pār}}$  (e.g., আমাকে দেখা পড়ে  $\text{āmākē dēkhā pārē}$ ) is unknown.

666. (5) আমাকে দেখা হয়  $\text{āmākē dēkhā hāy}$  *I am seen* (i.e., *they see me*); lit. *with-regard-to-me, a-seeing takes-place* (or *a-seeing there-is*). Here we have a verbal noun in  $\text{-ā}$ : we never say আমি দেখা হই  $\text{āmi dēkhā hāi}$  where  $\text{āmi}$  would be the nominative. Note that মারা যায়  $\text{mārā jāy}$  or মারা পড়ে  $\text{mārā pārē}$  *gets struck or killed, dies*, but মারা হয়  $\text{mārā hāy}$  *the striking or killing takes-place*; দেখা গেল  $\text{dēkhā gēlā}$  *seen went, came in sight*, but দেখা হইল  $\text{dēkhā hāilā}$  *a-seeing took-place*. The root হ  $\text{hā}$  here is non-committal and merely states the fact. This construction seems to be a modern one.

667. (6) আমি দৃষ্ট হই  $\text{āmi dṛṣṭā hāi}$  *I am seen* is a learned form and a modern one, and it is found in high-flown speech and in the  $\text{-sādhu-bhāṣā}$  only. This construction seems to have received a new impetus from the English passive: the Sanskrit passive participle avoids any ambiguity that might result if the native passive participle in আ  $\text{-ā}$  were used. But it undoubtedly originated in Middle Bengali, as Sanskrit passive participles have been largely introduced into the language since its birth.

668. The root আছ  $\sqrt{\text{āch}}$  is used with the past participle to form a sort of passive perfect, mostly in connexion with inanimate nouns or nouns that are names of lower animals, which are subjects of the predicate; e.g., এ বই আমার পড়া আছে  $\text{ē bāi āmārā pārā āchē}$  *this book has been read by me*, where আমার  $\text{āmārā}$  governs পড়া  $\text{pārā}$  which predicates বই  $\text{bāi}$  the subject of আছে  $\text{āchē}$ ; মাছ ধরা আছে  $\text{māchā dhārā āchā}$  *fish have been caught* (or *fish that have been caught are*); এ কথা সকলের জানা আছে  $\text{ē kāthā śakālērā jānā āchē}$  *this is known to everybody*; এ বই তো পড়া ছিল  $\text{ē bāi tō pārā chilā}$  *this book indeed was read before, etc., etc.* This construction seems to be recent.

669. Two other idiomatic forms of the passive may be noted. চল  $\sqrt{\text{cāl}}$  *to go*, to express the idea of possibility or continuance, occurs with the verbal noun in আ  $\text{-ā}$ , which governs the personal object

in the dative with কে «-kē», and the inanimate object or object which is the name of a lower animal in the accusative. The construction is impersonal: e.g., খাওয়া চলে «khāṓā calē» *can be eaten*, দেখা চলল «dekhā callā» *the seeing went on*. বা «√khā» *eat* in the sense of *suffer* is used with the verbal noun মার «mārā» *a beating*, and is conjugated actively, to denote *to be beaten*. This last idiom occurs in other Indo-Aryan languages, as well as in Dravidian.

670. The impersonal and indefinite use of the passive is a noticeable feature in Modern Bengali. When one is not sure whether to use the honorific forms in speaking to an individual, recourse is taken to the passive impersonal to avoid any chance of giving offence by using the ordinary non-honorific: e.g., কি করা হয় «ki kārā hāy» *what do you do?* literally, *what is done (by you)?* instead of the direct forms, the honorific আপনি কি করেন «āpani ki kārēṣ» or the inferior তুমি কি কর «tumi ki kārā». So কোথা থাকে হয় «kōthā thākā hāy» *where do you live?* etc. Cf. also the indefinite expressions ব'রে নেওয়া যাবে «dhōrē nēṓā jāk» *let it be granted*; যদি বলা হয় or যায় «yādi bālā hāy, jāy» *if it is said that*; এখান দিয়ে যাওয়া যায় না «ēkhāṇā diyē jāṓā jāy nā» *one cannot go by this way* (where যাওয়া যায় «jāṓā jāy» is probably from «\*jāijjāi», passive with «-ijj-»: cf. এখান দিয়ে যায় না «ēkhāṇā diyē jāy nā» *one does not, one should not go by this way*, where যায় «jāy» = «\*jāiaī», passive in «-ia-»).

### [III] THE PASSIVE IN «-ā-».

671. In MB. and NB. occurs a passive with a distinctive «-ā-» affix, which is illustrated below. This passive may have a potential implication.

Middle Bengali: SKK., p. 89, দেখি এহা পথে মাহাদানী বোলাও «sēhi ēhā pāthē māhādānī bōlāē» *he is called the chief toll-collector in this highway*; p. 186, ঘেহ না ছাড়াও ঘোল «jēnhā nā chārāē ghōlā» *so that the butter-milk is not scattered*; also cf. পঞ্চানন হুলো কয়, তেজীয়া ন দোষায় «Pañcānāṇ Nulō kāy, tējīyā nā dōṣāy» *says Pañcānana, the one with defective arm: 'a man of spirit is not censured'* (Nagen-dranātha Vasu, 'Banger Jātiya Itihās,' Brāhmaṇa-kāṇḍa, I, i, p. 224);



Modern Bengali instances : বেশ মানায় • *bēś mānāy* • *fits nicely, looks well* ; কথাটা ভাল উনায় না • *kāthā-ṭā bhālā ūnāy nā* • *the story does not hear nice (=it is not to be regarded as welcome)* ; কথাটা চারাইয়াছে • *kāthā-ṭā cārāiyāche* • *the news has been spread* ; সে ভাল মানুষ কহায় বটে, কিন্তু দোষ খণ্ডায় না • *sē bhālā-mānuṣṣ kāhāy baṭe, kintu lokaṣ subidhārṣ nāy* • *he is spoken of as an honest man, but he is not of the good sort* ; এতে কিন্তু দোষ খণ্ডায় না • *ē-te kintu dōṣṣ khaṇḍāy nā* • *but the evil is not averted by this* ; যত পরখায় তত দোষ বা'র হয় • *jātā pārākhāy tāta dōṣṣ bārṣ hāy* • *the more it is tested the larger the tale of faults that come out* ; ছল পরবার জন্য কান বেধায় • *dulṣ pārābhārṣ jānyā kāṇṣ bēdhāy* • *the ear is pierced to put on earrings* ; এটা তত খারাপ দেখাবে না • *ēṭā tāta khārāpṣ dēkbābē nā* • *this will not show so bad* ; etc., etc. : the sense in most instances, as above, is impersonal.

It occurs in Oriyā : 'Dhruva-caritra' of Jagannātha-dāsa (Contai edition), p. 8, • *sē bōlāi pātārāni* • *she is called the chief queen* ; p. 48, • *dēbā gāṇḍa-mādhyē tu bōlāu sunāsirā* • *thou art called Sunāsira (=Indra) among the gods* ; p. 16, • *dwādaśā ākṣārā māntrā-rājā ē bōlāi* • *of twelve syllables, this is called the prince of charms*.

This •-ā-• passive is found in other NIA. languages : in the Magadban Maithilī and Bhōjpuriyā ; in Eastern Hindi, in Western Hindi, though rather rarely in these (e.g., Kabīr, Kṣiti-Mōhan Sēn's Selections, IV, p. 63 • *sabahi piyāsa pūrana hōta hai, tana-ki tapana bujhāy* • *all thirst is fulfilled, and the burning of the body is relieved* ; Guru Nānak, 'Sukhamanī,' ed. in Bengali characters by Jñānēndra Mōhan Datta, Calcutta, 1916, p. 80, • *jīwana-mukata sōu kahāwai* • *he is called 'emancipated in life,'* beside the proper passive in • *uha purukha kahiyai jīwana-mukata* •) ; in Rājasthānī (dialectally), and in Gujarātī, in which the •-ā-• passive is the common method. It occurs also in Marāṭhī, where the affix is •-āv- -av-, -vav-, -avav-• (cf. Rāmebandra Bhikājī Jōshī, 'Prauḍha-bōdh Marāṭhī Vyākaraṇ,' Poona, 1917, p. 215).

The •-ā-• passive has been explained as a Causative or Potential form, 'originating from the causative affix •-ā-, -āv-• < OIA. •-ā-pa-ya-• (Hoernle, 'Gauḍian Grammar,' § 484 ; Tessitori, 'Grammar of OWR.,' § 140).

But another and a more reasonable derivation of the «-ā-» passive has been suggested by Sir George Grierson (in a private communication). He derives potential the passive affix «-ā-» from the denominative «-āya-» of OIA. The Bihārī dialects offer a clue to the source of this «-ā-» passive. In Maithilī, Magahī as well as Bhōjpuriyā, there is clear indication that the affix for this passive was originally «-āya-», distinct from that of the causative which was, and still is in many forms, «-āwa-» (< -āpaya-). Thus, the causative base in Maithilī is «dēkhāb (< dēkhāw < \*dēkkh-āva-)> to show, and the potential passive base is «dēkhā» to be seen: in the 3 pres., the causative is «dēkhābē (dēkhāwē), dēkhābathī», the passive is «dēkhāē, dēkhāthī»; so in the future, causative «dēkhāot» (= MIA. \*dēkkhāvanta-), passive «dēkhāit» (= MIA. \*dēkkhāyanta-); and the past participle forms are, causative «dēkhāol» (< -āwa-la), passive «dēkhāel» (< -āya-la) (Grierson, 'Introduction to the Maithilī Dialect,' Calcutta, 1909, pp. 214 ff., esp. tables on pp. 219 ff.). But even in Bihārī itself, the separate identity of the two affixes is to some extent confused, owing to interchange of «-w-» and «-y-» as intervocal glides. In the other NIA. speeches, the distinction has been entirely levelled down, both «-āya-» and «-āwa-» being reduced to «-ā-», or to «-āw-». We see that from Early MIA. times the causative affix «-āpaya-» has encroached into the domain of the denominative (see *infra*, under 'Denominatives').

The «-ā-» passive is thus an extension of the denominative «-āya-» of OIA. The NIA. intransitives in «-ā-» are similar OIA. denominatives in «-āya-», and this can be well seen from cases like *देवदार, छत्रादेवदह, परदार, वरदार* etc. at p 928, which certainly are based on nouns. Compare W. Hindi «Hari-simarana kari bhagata pragatāy» a saint is made manifest (< prakāṣa) by thinking on God (Nānak, 'Sukhamaṇī'). NIA. thus has preserved the denominative way of forming the potential passive, despite its being obscured by the causative.

672. The Passive Construction (*karmaṇi-prayōga*) in the past and future tenses is discussed below (under 'Participial Tenses' and 'Personal Affixes').





3. «-ē, -y >; «-ēṇṇ, -ṇṇ >: «sē, tārā cāl-ē; tini, tārā cāl-ēṇṇ >.  
(āṇṇi, āṇṇārā cāl-ēṇṇ = 2nd person honorific).

The distinction in number in the 1st person was dropped from the earliest times in Bengali. In the 2nd and 3rd persons, this distinction was retained to some extent, in that the plural forms became honorific: in the 2nd person, the old singular became the familiar, inferior or contemptuous (both in the singular and the plural), and the old plural, for some period honorific no doubt, followed suit, although it is slightly more respectful and formal than the singular form. The 3rd person plural became the respectful or honorific, both plural and singular.

675. Typical forms occurring in the OB. of the Caryās are:

First Person :

« jivami, pīvami (Caryā 4); acchahu (6); puchami, mārāmi, lēmi (10); dēhū, lēhū (8); bāhāma (20: = cāhāma); jāṇahū (22); acchama (29); āvēṣi (33); pēkhāmi (35); birahūi =? biharaī (39: Comm. = vibaraṇam karōmi); ācchuhū (44); siṇcahū, jānami (49) ».

Second Person :

« aisasi, jāsi (10); bujhasi, pucchasi, bāsasi (15); gilēsi (39); bujhaṣi, acchasi (41) ».

Third Person :

« Lui bhaṇai (1); jāi, khāa = khāi, jāga = jāgai, jāa = jāi (2); sāndhaa = sāndhai, bhamanti Birūā (3); taraī, gaṭai = gaṭhai (5); chāḍai, chupai, pivaī, bōlaa = bōlai (6); bājaē, biharaē, lavaē (11); gājai, bhājai, dhāvaī, ghōlai (16); bājai, bilasai, nācanti Bājila, gānti dēvi, hōi (17); bhanathi Kaukkuripā, jō bujhaē = bujhai (20); bhakhaa = bhakhai, karaa = karai (21); jē bhamanti tē bōnti; Saraha bhanati = bhananti (22); paīsaa = paīsai; bōlathi Sānti (26); basai, hiṇḍai, khāi, pōhāi (28); lāgē (29); jujhaa = jujhai (33); bhuṇjai (34); ujāa = ujai, bhanaī; pamāē = \*sāmāi (38); Saraha bhaṇanti (39); » etc., etc.



676. Below are given specimens of forms occurring in MB. :

First Person :

\* (mui, mu, mō, mōē, mōē, mōña, āmhi, āmhē, āmi, āmhārā, āmārā, āmi-sābā, āmārā-sābā etc.) চলি, চলী cālī, cālī; চলৌ, চলৌ cālō, cālō; চলহ্, চলহ্ চলউ, চলু cālāhū, cālā(h)u, cālu; (চলিএ cālīē) \*.

Cf. VSP., p. 30, কঙ kāṭ; p. 31, বলৌ bālō; 34, খাঙ khāṭ; 57, যাঙ yāṭ=jāṭ; 65, দেঙ deṭ; 67, জানৌ jānō, থোয়ৌ thōyō; 68, দেঙ deṭ = deṭ; 276, বটি bāṭi; 732, রাখৌ rākḥō muñi = rākḥō; 733, পড়হ্ pāṭāhū, মুঞি জাঙ muñi jāṅ = jāṅ; 853, থাকিয়ে thākīē, করিয়ে kārīē; 855 কান্দিএ kāndīē; 861, মোরা আছৌ mōrā āchō; 974, জানিএ jāniē, বাসিএ bāsiē; 1204, মাগৌ māgō; 1211, পারৌ pārō; etc., etc.; 'Padmā-purāṇa' of Vanśī-dāsa: p. 4, বন্দম bāndāmā (= bāndāwā, bāndō); p. 11, প্রণমহ্ prāṇāmāhū (বনৌ, বনৌ \* bāndō, bāndō, and প্রণমহৌ \* prāṇāmāhō are quite common in MB.); Kṛttivāsa, 'Uttara-kāṇḍa,' p. 28, বিস্তারিয়া কহ মুনি শুনিউ কথন bistāriyā kāḥā muñi, śuniū kāṭhāṇḍ (narrate in detail, O Sage, I [shall] hear the tale) \*; etc.

Cf. Oṛiyā: Modern Oṛiyā, singular \*dēkhō, dēkhi\*, plural \*dēkhū\*: Jagannātha-dāsa's 'Dhruva-caritra' (Contai edition), p. 12, \*śśīrbādā kāṭā mōtē, sādhai jēmāntē\* give me blessing, so that I (may) succeed; p. 13, \*muhi jībāi\* I live. Also, Maithilī \*dēkhi, calī, dēkhiai; chī, chiahū; thikahū; rahī, rahiahū\*; Early Maithilī, as in Vidyāpati (VSPd. edition, Pada 30), \*kahañō = kahañō\*; Magahī, \*dēkhi, dēkhī\*; Bhōjpuriyā, singular \*dēkhō\*, plural \*dēkhī, dēkhyī\*.

Second Person :

\* (tui, tuñi, tāi, tō, tōē, tōrā etc.) চলসি, চলসি, চলসি cālasi, cālasi, cālasi; (tumhi, tumhē, tumi, tōmhārā, tōmārā, tumi-sālā, tōmārā-sābā etc.) চলহ, চল, চলৌ, চলু cālāhā, cālā, cālō, cālu \*.

The \* -asi, -is(i) \* and \* -āhā, -ā, -ō \* forms are exceedingly common in MB.; the \* -u \* form is rather rare.

## Third Person :

« (sē, tāhā, tāhārā, tāhārā-sābā etc.) চলই, চলে, চলএ cālāi, cālē, cālāē ; (tāhō, tāhārā etc.) চলন্তি, চলন্ত, চলন্ত, চলেন, চলাইন, চলাই, চলঞি cālānti, cālāntā, cālēntā, cālēntā, cālāin, cālāi, cālāni » .

Cf. VSP., p. 357, « যাওন্তি যুগল yāonti śrgāla=jāwānti, jānti » ; Kṛttivāsa, 'Uttara,' p. 179, « কুকুর বলেন kukkurā bālenā, কুকুর জানেন kukkurā jānenā » ; *ibid*, p. 7, গঙ্গা শিরে ধরিয়া হাসন্ত শূলপাণি « gaṅgā śire dhāriyā hāsēntā Śūlapāṇi » the One with the trident in hand (Śiva) laughs, bearing Gaṅgā on his head ; p. 10, গুরুজন্য বাসেন লাজ « guru-janā bāsēntā lāja » the revered ones feel shame.

The « -ānti, -āntā, -ēntā » forms are very common in the ŚKK., in Chuṭi-Khān's (Śrīkara Nandi's) 'Mahābhārata,' in Vijaya Paṇḍita's 'Mahābhārata,' and in other older works. In Vanḍi-dāsa's 'Padmā-purāṇa' (Maimansing District, 17th century), a large number of « -āni, -āi » forms occur, beside « -nti » ones : the former, it should be noted, occur more frequently with the past and future bases than with the present : e.g., « p. 3, স্মরন্তি বিধাতা smārānti bidhātā ; p. 44, নারদে কহন্তি Nārādē kāhānti ; p. 260, মহল গাহন্তি māṅgālā gāhānti ; pp. 262, 318, 362, 489, 496, নারীগণে দেহন্তি (দেয়ন্তি) জেঁকার nārīgāṇē dēhānti (dēyānti) jōkārā the women give shouts of triumph ; p. 417, মহল গায়ন্তি সুখবতী māṅgālā gāyānti su-jubāti » ; besides p. 631, কারাঁনি = kārānti ; p. 622, যাঁনি = jānti ; p. 643, পূজাঁনি = pūjānti » ; etc., etc.

In addition, through Sanskrit influence, a few *ts.* or *sts.* forms occur in MB. in the 3rd person : e.g., বসতি « bāsāti » *dwells* for বসে « bāsē » (vasati) ; বদতি « bādāti » *speaks* for বলে « bālē » (vadati), etc.

The forms in the sister speeches are : Oṛiyā sg. « cālāi », pl. « cālānti » ; Maithilī, original sg. « dēkhai », pl. « dēkhathī », also in Magahī, besides forms with affixed object pronouns ; Bhōjpuriyā sg. « dēkhē », pl. « dēkhan », besides other forms.

## 677. Origin of the Forms for the Radical Tense.

The different « gaṇas » of OIA. were practically levelled to one —with the theme « -a- ». The OIA. causative « -aya- » > MIA. « -ē- » lost its force, and « -ē- » was also found in the indicative present form :



OIA. « karōti » thus figured as « karaī, karēi » in Apabhraṃśa. NIA. forms are based on these Apabhraṃśa simplified ones, both in form and use.

### First Person.

From OB. and MB., we see that the following were the old affixes : « -ami (= aṃi, aī), -mi (= -ṃi -ī), -ī, -i ; -ama (= -aṃa), -ō, -ō ; -a-hū, -a-hu, -hō, -au, -ū, -u ». The « -iyē, -iē » form in MB., as has been explained before (p. 915, *supra*), is really a passive form.

The old sense of number had died out in Bengali from the OB. period : it has continued in Oṛiyā to the present day. The affixes « -a-hū, -a-hu, -ahō, -aū, -u » form one group: here the « -hū » seems to be the first personal pronoun « \*haū » *I* (see p. 807, *supra*), agglutinated to a basic form of the root in « -a ». Cf. « -tu » for the 2nd person imperative (*supra*, p. 905). This « -hū, -ū, -u » form seems to have merged into the « -ō » form in MB. A form like *সুনিউ* « *śuniū* » (*supra*, p. 932) seems to be first person in « -i », « *śuni* » + « *hū* »; or is it a blend of the passive in « -iu- » (*supra*, pp. 919-920) + « -hū », or « -ō »? The « -hū > -hu » is found in Maithili also.

The form « -ō » is the affix for the first person now obtaining in Assamese and in North Bengali. This is apparently the same as « -ama » of OB., doubtless pronounced « -aṃa ». Influence of the agglutinated « -hū » here is likely in post-OB. times. Cf. Oṛiyā first person pl. affix « -ū », which is doubtless based on « -ama ». The « -ō » occurs also in Central Magadhan.

The MB. and NB. « -ī, -i » is the OIA. and MIA. « -mi » affix of the singular. The OB. « *āvēśī* » (Caryā 33) would go to show that it was already evolved in the OB. period; but at that time the nasalisation in all likelihood existed; and it seems to be generally indicated by retaining the « -m- », pronounced as « *ṃ* » or nasalised « *y* ». But in a case like « *āvēśī* », it could not be so indicated *metri causā*, but seems to have been merely left unnoted (\**āvēśī* = \**āvēśī* = \**āvēśīṃ* = \**āvēśīmī*: MB. *āśī*). The Modern Oṛiyā first person sg. form in « -ē » (< Early Oṛiyā « -āī »), given above (p. 932), *e.g.*, « *dēkhē, sādhaī, jibāi* », preserves the old nasalisation. The nasalisation is lost in Bengali and in Central Magadhan

and partially also in Oṛiyā, *e.g.*, in its «-i» form. It seems that in Māgadhi Apabhraṇśa, an OIA. form like «calāmi» had resulted in «\*calāmi» as well as «\*calimi», the former having given the Oṛiyā «cālāi, cālō», the latter the Bengali, Oṛiyā, and Maithili-Magahi «-i, -i» forms.

OIA. : «aham calāmi——vayam (Late OIA. asmē) calāmaḥ » ;

MIA. : «abakaṁ, abakē calāmi——mayam, ambhē calāmō, \*calāmē ;  
hakaṁ, hake (\*hagaṁ, hage) calāmi, calāmi——ambhē  
calāmō, \*calāmē, \*calāmō, \*calāmē » ;

Māg. Ap. : «haū, \*haī \*calami, \*calimi——amhi \*calamu, \*calami  
\*calama, \*calāma (m = ō) » ;

NIA. OB. : «haū (maī) \*calaī, \*caliī, \*calī, calī—āmhi (āmhē) calaṭṭa, calō » ;

MB. : «(māī, mui, āmhi, āmi, āmhārā, āmi-sābā etc.) calī, cālī, cālō. » ;

NB. (Standard Speech) : «(āmi, āmārā) cālī » ; † «(mui, āmi,  
āmārā) cālō » ;

Assamese : «(māī, āmi) cālō » ;

Oṛiyā : «(mū) cālō, cālī », plural «(āmbhē, āmbhē-mānē) cālū » ;

Maithili : «calī, calī » (for both numbers) ;

Magahi : «calī, calī, calī » (for both numbers) ;

Bhōjpuriyā : «calō », plural «calī, calyī » (the singular «calō » probably  
influenced by Western speeches).

In the indiscriminate use of singular and plural forms, it is not unlikely that the singular «\*calami, calimi» in Māgadhi Apabhraṇśa became confused with an expected, and possible Māg. Ap. plural form «\*calāmi, \*calami» < Magādhī Prakrit «\*calāmē» < OIA. «calāmaḥ», with the change of final «-aḥ» to «-ē» and then to «-i».

## 678.

### Second Person.

The history of the forms seems to have been as follows :

OIA. : «tvam calasi—yūyam (Late OIA. \*yuṣmē, \*tuṣmē) calatha » ;

MIA. : «tumaṁ, tūṁ calasi—tumbhē calatha, caladha ; tūṁ calasi  
—tumbhē calaha » ;

Māg. Ap. : «tū, tō calasi, \*calisi, \*calahi ; \*calasu, \*calahu, \*calaū  
(from the Imperative)——tumhi calaha » ;



- NIA. OB. : \* tū, tō, tai calasi, calisi—tumhi, tumbhē calaba, \* calaa >;  
 MB. : \* (tō, tō, tōē, tai, tui, tōrā) cālāsi, cālisi, cālāis, cālīs—  
 (tumhi, tumi, tōmhārā, tōmārā etc.) cālāhā, cālā, cālā, cālō >;  
 NB. : \* (tui, torā) cālīs, † cālās (as in East Bengali), † cālū  
 (as in S.W. Bengali : cf. Oriyā)—(tumi, tōmārā) cālā, cālō >;  
 Assamese : \* t̃ai cālā ——— tumi cālā (tomālokē cālā, cālāhāk) >;  
 Oriyā : \* tū cālū ——— tumbhē (-mānē) cālā >;  
 Maithilī : \* tō calahi, calah ——— tōh, tōh-sabb calahu >;  
 Magahi : \* tū, tō cal ——— tōhani calah(in) >;  
 Bhōjpuriyā : \* tū, tē cal (calas, calasi, calis)—tōhanikā calah > .

## 679.

## Third Person.

- OIA. : \* sa(h) calati ——— tē calanti >;  
 MIA. (Māgadhi) : \* sē calati ——— tē calanti >;  
 \* sē caladi, calai ——— \*tē calanti >;  
 Māgadhi Ap. : \* sē, \*si calai ——— \*ti, tē calanti >;  
 NIA. OB. : \* sē \*calai (calanti *honorific*)—\*tē, \*tēhi, \*tēhi \*tēha,  
 calanti, \*calēnti >;  
 MB. : \* sē cālāi, cālāē, cālē ; tēhā, tēhārā cālanti, cālēntā,  
 cālāntā, cālēnā, cālāni, cālāni, cālāni, cālāin >;  
 NB. : \* (sē, tārā) cālē—(tini, tārā) cālēnē († cālāin) >;  
 Assamese : \* (si, sihātē) cālē (Early Assamese si-hātē cālāntā,  
 cālēntā) >;  
 Oriyā : \* sē cālāi—sē-mānē cālanti >;  
 Maithilī : \* sē (sē-sabb) calai, calathi > (the latter honorific only);  
 Magahi : \* sē calai, calē (calas < Bhōjpuriyā)—taun calin,  
 calī, calathi >;  
 Bhōjpuriyā : \* sē calē, cala (calasi, calasu < Awadhī)—taun  
 calan, calin > .

The plural form in Bengali is now used as an honorific. The change of OIA. <-nt> normally is to <-t-> in Bengali, not to <-n-> : \*cālēnā > therefore does not represent OIA. <calanti>. The form has obtained its <-n-> (further reduced to a mere nasalisation in dialectal Bengali) ultimately from the plural <-na> of the noun (see *supra*, pp. 725-726). It seems that this

«-na» was added to the plural-honorific forms for the verb in the past and the future tenses, which as participial forms did not have any affix originally, and therefore could take up both the plural «-na» of the oblique noun and the «-anti» of the radical tense: MB. ordinary «gēl-ā, gēl-ā», honorific «gēl-ēnṣ, gēl-ānti». Thus «-na» and «-anti» became identical; and in the place of «calanti, cālēnta», and a possible «\*cālēti, \*cālētā» (cf. ŚKK. दैति «dēti» *they give* = «dēnti»), the form «cālē-nṣ» came in. Doubtless the use of the present participle in «-itē» (cālītē-cālītē), the infinitive in «-itē», and the past habitual base «cālīt-», all the three with «-it-», helped the establishment of «-ēnṣ» in the other verb forms as the plural honorific affix. Oṛiyā alone among Magadhan languages has preserved the «-nti». In other Magadhan, in E. and W. Hindi, and in other NIA., the «-nti» has similarly given place to a mere nasalisation or to «-n»: except in Marāṭhi, where the «-nti» is altered to the normal NIA. development, «-t» (Jules Bloch, 'Langue Marathe,' § 235).

The Maithili and Magahi «calathi» is peculiar, showing «-thi» for OIA. «-nti»; probably it is a case of emphatic «hi»: «calanti hi > calat(i) hi > calathi». In the Caryās, «-thi» for honorific «-nti» occurs in a couple of instances: «bhaṇathi Kukkuriṇṣ» (20), «bōlathi Sānti» (26). These seem to have been due to the mistake of the Nēwāri scribe of the MS., familiar as he was more with Maithili than with Old Bengali.

The «-s-» forms for the 3rd person in Magahi and Bhōjpuriyā seem to be ultimately from Awadhī, and the «-s-» seems to be the pronoun «sē» *he*, agglutinated with the verb-base (like «hū, tu» for the 1st and 2nd persons in OB.).

## [II] THE TENSES ORIGINATING FROM OIA. PARTICIPLES.

### (1) THE PAST BASE.

680. The inflected past tenses of OIA.—the imperfect, aorist and perfect—were continued in MIA., but their employment grew more and more rare. In Early MIA. (as in Pali) the imperfect and aorist



coalesced, and formed practically one past form (cf. Geiger, 'Pali Grammatik,' § 158 ff.), although Pali grammarians sought to indicate a theoretical difference between them by calling the forms derived from the old imperfect and the strong or root aorist (with the 3rd person singular ending in « -a, -ā ») the « *hiyattanī* » or *yesterday past*, and the forms derived from original sigmatic aorist (with the 3rd person singular ending in « -i, -si ») as the « *ajjatanī* » or *to-day past*. The perfect became very much restricted. In Second NIA., the perfect all but disappeared, being found only in a few stereotyped forms; and the same thing happened with the imperfect-aorist tense, which could be found with a number of roots, or had resulted, as in Ardha-Māgadhī, into a couple of affixes—a singular « -itthā, -ṭthā » and a plural « -īṃsu », originating from the OIA. *ātmanā-pada* (medial) aorist forms (Pischel, 'Gramm. der Pkt.-Sprachen,' §§ 515-517; Geiger, *op. cit.*, § 159).

This gradual decay or disuse of the old moods and forms of the old inflected past is a notable thing in the history of Indo-Aryan (cf. Jules Bloch, 'La Phrase nominale en Sanskrit,' *Mémoires de la Société de Linguistique*, Vol. XIV). In this connexion Dravidian influence has been suggested, and indeed is probable (see *supra*, pp. 38, 174). As the old past forms fell into desuetude, their place was taken up more and more by the passive participle adjective which had the ending « -ta, -i-ta » or « -na » in OIA. In this extension of the verbal adjective to assume the function of the finite verb, going hand in hand with the decay of the latter, Dravidian influence, again, is likely. But the germs of this use we find within OIA. itself. In Vedic, the past or passive participle in « -ta » is quite frequently used as a finite verb, when the copula or the substantive verb « *as* » or « *bhū* » is omitted (cf. A.A. Macdonell, 'Vedic Grammar for Students,' § 208; B. Delbrück, 'Altindische Syntax,' Halle, 1888, §§ 215, 219). This construction, periphrastic in nature, with the substantive verb present or understood, seems to have come in first with intransitive verbs (meaning *going, sitting, standing*, etc.), or in impersonal statements. But as yet the passive participle has not invaded the domain of the transitive verb, in a passive construction with the true nominative in the instrumental,—

a construction which is perfectly normal in Second MIA., and which is continued down into NIA. : «sa yātaḥ, sa jātaḥ, sa ārūḍhaḥ» might be used instead of «sa jagāma (iyāya, agacchat, agamat, ayūt), sa ajāyata (ajani), sa arubhat (arukṣat, ruṛōha)» etc. ; but «tēna kṛtaḥ (kṛtā, kṛtam), tēna dṛṣṭaḥ (dṛṣṭā, dṛṣṭam)» are not yet well-established in the place of «sa cakāra (akārṣīt, akarōt), sa dadarśa (apaśyat, adrākṣīt)», etc. But from Early MIA., the extension of the passive participle to transitive verbs also came in. In Pali, however, the OIA. condition obtains, and there is plentiful use of the past tense or aorist, the «-ta» forms occurring with intransitive verbs mainly : but the traditions of Pali as a literary speech go back to the oldest MIA., or latest OIA. period, and Pali syntax is not wholly based on that of the spoken vernaculars of the centuries immediately before Christ. But the language of Aśōkan and other early inscriptions sufficiently demonstrate what an important place the passive participle in «-ta» had already obtained for itself in the popular dialects, considerably restricting the inflected past tenses. Thus, to give a few examples : Aśōkan Rock Edict I (Girnar), «iyam dhammalipi dēvaṇaṃ priyēna priyadasinā rāṇā lēkhāpitā» ; II (Girnar) «dvē cikicchā katā ; ōsuḍḍhāni...sarvatra hārāpitāni ca rōpāpitāni ca» ; V (Girnar) «ta mayā bahu kalāṇaṃ kataṃ» ; Pillar, Rummindei, «piyadasina lājina atana āgāca mahiyitē ; silā vigaḍabbhicā kālāpita, silāthabbhē ca usapāpitē, Lūhminīgāmē ca ubalikē kaṭṭē» ; Nigliwa, «lājina thubē dutiyaṃ vaḍḍhitē» ; Khāravela Inscription, «mahārājēna...kiḍḍitā kumāra-kiḍḍikā : yōvarajaṃ pasāsitaṃ» ; Bharhut Inscription on gateway, «...Dhanabhūtiṇa kāritaṃ tōraṇaṃ (= tōraṇaṃ), silā kammaṃtō ca upaṇṇa» ; Sanchi, Stupa I, «Vēdisakēhi daṃṭa-kārēhi rūpa-kammaṃ kataṃ» ; Besnagar Inscription of Heliodoros, «garuḍa-dhvajē ayaṃ kārītō Hēliōdōrēṇa» ; Mathurā Āyāgapatṭa Inscription, «...gaṇikāyē Vasu(yē)...silāpaṭṭo pratisthāpitō» ; etc., etc.

Illustrations can be multiplied. These show that the passive participle construction, the verb being an adjective qualifying the nominative when it was intransitive and the object when transitive, became the common idiomatic way of expressing the past in MIA. By the time when the Apabhraṃśa Stage came in, the old inflected past forms, which still



lingered in Second MIA., were clean swept away, and only this participial past remained in IA. ; and the NIA. past tense was formed out of this.

The IA. speeches outside India show similarly the passive participle as the base for the preterit : Sinhalese (Geiger, 'Litteratur und Sprache der Sinhalesen,' pp. 71-72), and the Gipsy speeches of Europe (F. Miklosich, 'Ueber die Mundarten und die Wanderungen der Zigeuner Europas,' XI, p. 44).

681. The affix « -ta, -ita » was by this time reduced to « -a, -ia », except where it was assimilated to a preceding consonant (*e.g.*, « dṛṣṭa- », = Panjābī « dīṭhā », beside « \*dṛkṣita- » > dēkhhia- » = Hindi « dēkhyā, dēkhā », Bengali দেখি « dēkh-il- » ; « sūpta » > sutta » Early Beng. সূতিল sut-il- » ; « matta » Beng. মাতিল māt-il- » ; etc.). A pleonastic « -ka », which was reduced to « -a » in Prakrit and Apabhraṃśa, was sometimes added. But the need for some distinctive affix for this important form, the only one to indicate the past tense, was felt in some parts of the country. The « -la » affix of OIA., in extended forms « -i-la, -a-la », which became very popular as an adjective affix (or a merely pleonastic one) from the early centuries of the Christian era, and probably even earlier, was frequently added. In the Second and Third MIA. periods « -i-la, -a-la » apparently became « -illa (-ōlla), -alla ». In any case, in North-Eastern India the « -ll- » was specially popular from the Apabhraṃśa period (it may be earlier still) in connexion with the passive participle in « -a < -ta, -ia < -ita ». We have no specimens of this North-Eastern or Māgadhī Apabhraṃśa, but from the evidence of the Magadhan languages we have to surmise all that. In the Ardha-māgadhī area, and in the Midland, the « -ila, -ala » > -illa (-ōlla), -alla » affix was rather sparingly used ; also in the North-West : the source-dialects Eastern Hindi, Western Hindi, and Western and Eastern Panjābī apparently never used it with the passive participle, whether attributive or predicative. In the South-West, its use was more common than in the Midland, but not so common as in the East : it was used, as we can infer from Gujarātī and Rājasthānī and Sindhī, when the passive participle was a plu-perfect, or an attributive form, and not a predicate in the simple past, performing the function of a verb. In the

South, it was fairly common, and shortly after the formation of the Marāṭhī language, it became more and more popular as an affix in connexion with the passive participle > past tense.

The remnants of Second MIA, (especially in the Jaina dialects as written in the South-West) have preserved for us examples of this «-illa (-ēlla)» and «-ulla, -alla» affix with nouns and adjectives, like «kaṇṭailla, chailla, mā(y)illa, lōhilla, sōhilla, ṇēurilla, thalailla, niyaḍilla, kasilla, sāsilla, kalaṇkilla, gaṇṭhilla, muttāhalilla, kandalilla, lacchilla, kivāilla, gōilla, chailla, gāmilla, bāhirilla, paḍhamilla, uvarilla, dāhiṇilla, majjhimilla, puvvilla» etc., etc.; and stray forms like Ardha-māgadhi «āṇilliyā» (āṇia = āṇita + illa: Pischel, 'Grammartik der Pkt.-Sprachen,' § 595), and «āgaḷliyā (āgata-), varēlliya (varia-, vṛta-), chaḍḍiḷlayaṁ (chardita-), laddhilliyatū (labdha-)» (Tessitori, 'Grammar of OWR.,' § 126) etc. confirm the surmise made chiefly from the modern languages that «-illa (-ēlla), -alla» added to the passive participle in «-a, -ia < -ta, -ita» is the source of the NIA. «-l-» in this case. When the «-illa» in this way strengthened the passive participle, the latter retained fully its original adjectival nature, and «-illa» would change its ending according to the gender of the noun qualified.

682. Thus the past base in «-il-» in Bengali, Assamese and Oṛiyā, in «-al-» in the Bihārī speeches, and in «-il-, -al» in Marāṭhī, and similar «-l-» forms in the other NIA. speeches, originated from the OIA. «-ta, -ita» plus the OIA. diminutive or adjectival affix «-la-» in the extended forms «-ila, -a-la, > -illa (-ēlla), -alla». This explanation, first suggested by Sir Charles Lyall in his article on Hindōstānī in the 'Encyclopædia Britannica,' 9th edition (1879: reprinted as 'A Sketch of the Hindustani Language,' Edinburgh, 1880: pp. 41-42) and by Sir Ramkrishna Gopal Bhandarkar in his 'Wilson Philological Lectures' (1877, Lecture V, first published Bombay, 1914, pp. 223-224), has finally been accepted as the only possible explanation, after Sten Konow showed how this «-l-» of Marāṭhī (and other NIA. speeches) phonologically must rest on a MIA. «-ll-» (in his 'Note on the Past Tense in Marāṭhī,' JRAS., 1902, pp. 417 ff. Cf. Tessitori, 'Grammar of OWR.,' § 126; Jules Bloch, 'Langue Marathe,' § 256),



683. Lassen and Hoernle, whose views, now disproved and abandoned, still obtain some following in India, traced this «-l-» to the «-ta, -ita» affix of OIA. direct: either along this line: «-ta, -ita» > «-da, -ida» > «-ḍa, -iḍa» > «-la, -ila»; or along this: «-ta, -ita» > «-da, -ida» > «-la, -ila» (cf. Hoernle, 'Gauḍian Grammar,' § 306). But neither of the above lines of change are known to have taken place on any large scale in IA.; and although there are cases of 'spontaneous cerebralisation' (*supra*, p. 487), and although there are a few cases where NIA. «-l-» (< earlier «-l-») corresponds to Skt. «-ḍ-» (*supra*, p. 543), a wholesale change of MIA. «-d-, -ḍ-» to «-l-» is not attested. Under influence of preceding «r, ṛ», a dental «-ta» became a «-ṭa» in 'Old Māgadhī,' and the normal change of it in Second MIA. Māgadhī would of course be «-ḍa»; in fact, Vararuci notes two cases, «kaḍa, maḍa < kaṭa, maṭa < kṛta, mṛta» and a third «gaḍa (< gata)» by analogy apparently ('Prākṛta-prakāśa,' XI, 15); and many more can be attested from MIA., from Sanskrit, and from the NIA. speeches (like «\*saḍakka > saṛikṣ» *street* from «sṛta», «\*dhaḍa > dhaṛṣ» *torso* from «dhṛta», «\*bhaḍa > bhaṛṣ» = surname in Bengali = *servant* from «bhṛta, bhata»). In all these cases we find «-ṛ-» in NIA. (< «-ḍ- < «-ṭ- < «-ṛt-»), and never «-l-». The equivalent of «kaḍa, maḍa» should be «kaṛṣ, maṛṣ» or «kaṛā, maṛā» in NIA., and not «kaila, maila» as in Early Bengali or in the Bihārī dialects. In fact, the «-ṛ-» form, मार *mārā* < «maḍa», has continued apart in Bengali, in the sense of *dead body, corpse*, and this is quite distinct from the verb মার *māila* = \*maa-illa = mṛta + illa.<sup>1</sup>

The adjectival accented «-lá» (Whitney, 'Skt. Grammar,' §§ 1189, 1227) became «-lla» in Second MIA. (Pischel, 'Grammatik der

<sup>1</sup> As has been noted before, the genuine, inherited Māgadhī forms in «-r,» = «-ḍ-» < «-ṭ-» < «-ṛt-, -rt-» were largely ousted from or restricted in the eastern dialects, probably during the Second and Third MIA. periods, by new formations which did not show cerebralisation, but simple elision of the «-t-»: see *supra*, p. 487. This was either due to the analogy of the larger number of «-ta-» participles in which there was no scope for cerebralisation and the «-t-» was duly lost in Second MIA.; or it may be that here there was strong influence from the Western speeches due to the continuous immigration of Westerners into the East—Bihar and Bengal—during the formative period of the Eastern languages.

Pkt.-Sprachen,' § 194). It is just possible that the doubling was due to the fact that it was a *ts.* (or *sts.*) affix introduced in Transitional MIA., at a time when original *tšk.* or inherited intervocal *\*-l-* tended to become cerebralised to *\*-l̥-*, and that its *ts.* character as an intervocal *dental* or *alveolar* sound was sought to be preserved by this doubling. Another explanation, quite possible, would derive the MIA. *\*-lla-* from the OIA. *\*-la-*, strengthened by *\*-ya-* (also an adjectival affix): *\*-l-ya > -lla-* (Jules Bloch, 'Langue Marathe,' p. 256). In any case, the fact remains that in Second MIA. it became *\*-ll-*. In NIA., in those speeches where the cerebral *\*-l̥-* is preserved, this *\*-l̥-* stands on a MIA. single intervocal dental or alveolar *\*-l-*; and where in NIA. it is a dental *\*-l̥-*, the MIA. source of it is double *\*-ll-*, and not single *\*-l-*. This has been shown for Marāṭhī (Sten Konow, JRAS., 1902, as cited above; cf. Jules Bloch, 'Langue Marathe,' §§ 144 ff.), and for Gujarātī by Turner (JRAS., 1921, pp. 527-528, 535, 537, 538). It is also the case with Ōṛiyā: e.g., Ōṛiyā *\*kālā > black*, *\*kālī > ink* (< *kāla-*), *\*bēlā > (< vēlā)*, *\*dēulā > (< dēvakula)*, *\*tālā > (< tila)*, *ts. \*tālīlā > (< tāila)*, with *\*-l̥-*, but *\*kālī > (kallīm, kalya-)*, *\*bēla > (bēlla, bilva)*, *\*tēla > (tēlla, tēilā)*, etc. (see *supra*, p. 538): and for the past tense and pass. part. adj., Ōṛiyā has *\*-l-*, not *\*-l̥-*, which thus must rest on a MIA. *\*-ll-*. The same seems also to be the case with Panjābī. So that Apabhraṃśa (Eastern, Western, Southern) *\*kaa-illa-*, *\*kaya-illa-*, *\*kaa-alla-*; *\*gaa-illa*, *\*gaya-illa*, *\*gaa-alla*; *\*calia-illa > \*calilla*, *\*callēlla* *\*calla-illa (= \*calya- + -ita- + -la)* etc. can alone be the sources of Early Bengali *\*kāla*, Bihārī *\*kail*, Ōṛiyā *\*kālā*, Marāṭhī *\*kālā*, gēlā, Gujarātī *\*karēlo* (= *\*karia-illa*), Sindhī *\*kayalū*, *\*kītalū* (the last = *\*kitta-alla-*); and Bengali *\*gēlā*, *\*cālilā*, Ōṛiya *\*gālā*, *\*cālilā*, Bihārī *\*gail*, *\*calal-*, beside Ōṛiyā *\*cālilā*, Gujarātī *\*cālēlō*, etc.

684. Another view about the origin of the NIA. *\*-l-* is that it is an independent affix occurring in Indo-European itself, preserved in NIA., but ignored or left unnoticed in OIA. S. H. Kellogg first suggested this in his Hindi Grammar (cf. p. 340, second edition), and Beames connected this *\*-l-* with the *\*-l-* affix indicating the past tense in the Slav languages, and compared Slav (Russian) preterit



forms in «-l-» with those of the Marāṭhi as a typical Indian language with the «-l-» past ('Comp. Grammar,' III, pp. 135-136). But this connexion is not proper. We have seen that the MIA. form of the suffix was «-ll-» < OIA. «-l-» and that it is adjectival (diminutive or pleonastic) in its nature, whereas the «-l-» affix that we find in Slav is entirely different. The latter is a participle affix, forming *nomina agentis*, with an active present participle sense, and in Slav it is used to form periphrastic tenses with the substantive verb: and this «-l-» or «-lo-» affix has been found, in addition to the Slav, in Latin, Greek, Armenian and Tokharian among Indo-European speeches (A. Meillet, 'Le Slav Commun,' Paris, 1924, § 281; French trans. of Brugmann's Short Comparative Grammar, Paris, 1905, p. 351; S. Lévi and A. Meillet, 'Remarques sur les Formes grammaticales de quelques Textes en Tokharien B.: I: Formes verbales,' Extrait de Mémoires de la Société de Linguistique, Vol. XVIII, Paris, 1912, p. 22).

685. The «-l-» affix is established for the past tense in Bengali and other Magadhan speeches, so that its use in the Māgadhi Apabhraṃśa can reasonably be presumed. The «-l-» affix is absent for the past tense in Eastern Hindi, Western Hindi, Panjābī, Rājasthānī, Gujarātī, Sindhī: in the source Apabhraṃśas of these, therefore, it would be reasonable to think that it was not present there, or in any case it could not have been so prominent. But the «-ll-» form did not entirely supplant the simple passive participle in «-(i)a» in the East: from Old and Middle Bengali and from Early Oṛiyā and Early Maithilī, we can see that the passive participle in «-ita > -ia» without the strengthening «-illa, -alla» was actually used predicatively for the past base. Examples are given below. The non-l form of the passive participle has given the Bengali passive participle in «-ā»: «calita- > calia- + -ā > cālā». This non-l form occurs also in Eastern Hindi as well as in Western Hindi: but in NB. it is attributive, and not predicative. All this would show that the «-ll-» and the non-l forms were used side by side in Māgadhi Apabhraṃśa, but the NIA. Magadhan speeches decided for the «-ll-» form for the past base as well as for the

adjectival participle base : in Modern Bengali, in the standard language however, the non-l form is employed as the adjective, and the «-l-» form has been restricted to the predicate.

686. The following tables recapitulate the position in the NIA. languages :

[a] Non-l Forms in NIA.

(i) OIA. « calita- » > Second MIA. « calia- ; (nominative) caliō, caliē » > Apabhraṇśa « calia- ; caliu, \*caliī » ;

(ii) OIA. « calita-ka- » > Second MIA. « caliaa- ; (nominative) caliaō, caliaē » > Apabhraṇśa « caliaa- ; caliaū, \*caliaī ».

From MIA. passive participles of the above type are derived :—

Western Hindī (Braj-bhākhā) passive participle adjective and past base

« calyau » ;

„ (Kanauij) „

« calō » ;

„ (Hindōstānī) „

« calā » ;

Eastern Panjābī „

« calliā, caliā » ;

Western Panjābī „

« callēā » (with

personal terminations added optionally to form the verb past) ;

Sindhī pass. part. adjective and past base

« haliō » (with

personal terminations added in the intransitive) ;

Gujarātī pass. part. adjective and past base

« cālyō » ;

Rājasthānī „ „

« calyō » ;

Pahārī (Khaskurā) „ „

« cālyō » ;

Eastern Hindī „ „

« calā » (with

personal terminations added to form the past tense) ;

Early Maithilī past form

« calia, cali, calu » ;

Early Oṛiyā past form

« cālī » ;

Oṛiyā past participle

« cālā » ;

Old Bengali past participle and past form

« calia, cali, caliā,  
calā (caliō, caliu, calu) » ;

Middle Bengali past form

« cālī (cālē ?) » ;

New Bengali passive participle

« cālā (cāliyā ?) » ;

New Bengali and Assamese verbal noun

« cālā ».



[b] Forms with adjectival or pleonastic « -l- » in NIA.

OIA. « calita- » > MIA. « calia- » + « -illa-, -ëlla-, -alla- » > Ap.  
« \* calilla-, \* calëlla-, \* calialla- ».

From « -ll- » forms of the above types in Apabhraṃśa are derived :—

Sindhī passive past participle	« halyalū » ;
Gujarātī                    „	« cālēl, cālēlō » ;
Marāṭhī                    „	« cālālā » (with personal terminations added to form the past tense), besides a double « -l- » form, « cālālēlā » ;
Marāṭhī verbal noun	« cālālē » ;
Bihārī past base, passive participle adjective, & verbal noun	« calal- » ;
Oriyā past base and passive participle adjective	« cālilā » ;
Bengali past base and passive participle	« cālilā- » ;
Assamese past base	« cālil- ».

687. Examples of non -l and « -l- » forms from OB. and MB. are given below.

#### Old Bengali : non-l forms.

In OB., as in the Caryās, the adjectival nature is still clear in many cases. The form expected in OB. would be « -ia » > « -ī » , or « -ia » + definitive « -ā » = « -iā » ; « -iā » is found, and « -ī » also ; and « -ia » , with the final « -a » retained, is also found as an archaic literary survival (cf. Bengali treatment of final MIA. vowels, *supra*, pp. 301 ff.). Besides, forms in « -iō (-ō) , -iu, -u » due to Western influence also occur (see *supra*, p. 115). This « -iu, -u, -iō (-ō) » is not found in MB. and NB.

Caryā 1 : « paīṭhō » (= pavitṭhō, pavitṭhaō = praviṣṭa-, -ṣṭa-ka-) ;  
« āmhē sāṇē diṭhā » (drṣṭa-) ; « baīṭhā » (cf. বৈঠা মানুষ *bāiṭhā mānuṣā* « *sitting man* in Chittagong Bengali, and বঠিয়া *bāṭhiyā* « *having sat* in 'Māṇik Candra Rājār Gān,' VSP., p. 82—which show that « *bāiṭh-* » was a good OB. form, though now supplanted by the root « *bāis* ») ; Caryā 7, « bhinnā » ; 9, « haria » ; 10, « chāḍi » ; 11, « paīṭha, kiū, bhaīa » ; 13, « kia, māri » ; 16, « paīṭha, paīṭhā, diṭhā » ; 17, « picie = ? cāpiu, kia, biāpiu » ; 18, « bāhia, biṭaliu, ṭāliu » ; 19, « uchaliā, caliā, abāriu, kia » ;

20, « saṅghārā »; 26, « abāriu, caṭāriu »; 27, « bikasāū, unbasiu, cālia, gaū, bujhia »; 28, « khāi?, pōhai? »; 30, « phariā, uittā, bujhjhia »; 31, « ṇaṭhā, paīṭhā, bihariu, ni-āriu »; 34, « bādha (< baddha-), ladhā = lādha (< labdha-) »; 36, « pabārī, ahārī »; 44, « miliā, ūiā, paīṭhā, biṇaṭhā »; 47, « jalia (< jwalita), paṭā (= patita-) »; 49, « bāhiu, luḍiu, ṇaṭhā, paīṭhā, thākiu, laīā ».

Old Bengali : « -l- » forms.

Caryā 2, « cauri nila, cōrē nila, nida gēla »; 3, « āīla, paīṭhēla »; 4, « ubhila »; 6, « beṭila = beḍhila »; 7, « rundhēlā, bhaīla, āīlā, gēlā, bhaīlā = bhaīlā »; 8, « gēlī, mēlīlī, milīla »; 10, « mōē ghalīlī »; 12, « jītēla »; 13, « calīla »; 14, « buḍīlī, bhaīlā, caḍīlā »; 15, « gēlā, bhaīla »; 16, « lāgēlī »; 18, « sutēlī »; 28, « maṇḍīlā, lāgēlī, paḍīlā, chāīlī, pōhāīlī »; 30, « ūjōlī (= udyōtitam) »; 31, « chāḍjīla » (cf. Commentary); 32, « mukala, bhāīlā »; 33, « dubīla (adj.), biśēla »; 35, « hāu acchilē (= āchilē? āchila?), maī bujhīla, dīla, ahārīla, laīlā, ahārā-kaēla »; 36, « nida gēlā, sutēlā, maī dekhīla »; 37, « ṭuṭī-gēlī, acchilēsa »; 39, « nīlēsi, bhāgēla »; 41, « phulīlā »; 44, « āīlēsi, biccharīla »; 47, « lāgēlī āgi, uṭhī-gēla »; 49, « bhaīlī, lēlī »; 50, « phuṭīlā, tāēla = uēlā? bhāēla?, phīṭēlī, phulīā = phulīlā, pākēlā, mātēlā, bhēlā, bhāīlā, (gaḍīlā), hakaēlā, māīlā, bhaīlā, phīṭīlī ».

In OB. the affix is commonly « -il- », as in Bengali, Assamese and Oṛiyā, and at times it occurs as « -ēl- ». Except in « mukala », « -al- », characterising Central and Western Magadhan, is not found. The affixing of personal terminations has started already in OB. (e.g., acch-il-ēsa, n-il-ēsi); but the old adjectival nature is sufficiently present, making the form take up the « -ī (-ī) » affix of the feminine when the subject is feminine for the intransitive verb and when the object is feminine for the transitive.

688. Examples of the Middle Bengali verb in « -ī, -ī < -ia < -ita », without the « -l- » :

SKK. : p. 75. মৌন করিস্না দুই থাকি এক পাশে « māunā kārīś dubē thāki (= thākilā) ēkā pāśē » *keeping silent, the two remained on one side*; p. 217, যেহেন বাহির তেহেন ভিতর সরুপে জাপিলো তোরে : কপট সাগর হৃদয় তোমার



নাহি যোর গোচরে ॥ \* jēhēnā bāhirā tēhēnā bhitārā, sārūpē jānilō tōrē : kápātā sāgarā hṛdayā tōmhārā, nāchi (=nā āchilā) mōrā gōcārē \* *as on the outside, so within : I have known you in your true form ; your heart is an ocean of deceit, this was not known to me ;* p. 325, সরূপে বুঝিলে মো কাহাজি তোরা বানী আন্ধে নাহি পাই \* sārūpē buyilō mō Kānhāñi, tōrā bāñi āmhē nāhi pāi (= pāilā) \* *I have said in sooth, O Kānha, I have not found your flutz* (note: past form with নাহি \* nāhi \* ) ; p. 343, তোকে তব বোলে চন্দ্রাবলী । ঘোড় হাথ করী বনমানী ॥ তাত বড় পাইল আপমান । তেঁসি তোহ্মা ছাড়ী গেল কাহ ॥ \* tōkē iātwā bōlō Cāndrābālī, jōrā hāthā kārī (=kārilā) bānāmālī : tātā barā pāilā āpāmāñā, tēsi tōmhā chārī gēlā Kānhā \* *I tell you the truth, O Cāndrāvalī : the one garlanded with wild flowers (Kṛṣṇa) folded his hands (before you) ; through that he has felt insulted, that is why Kṛṣṇa has left you and gone away ;*

Kṛttivāsa, 'Uttarā Kāṇḍa' (VSPd. ed.) : p. 16, দুই চক্ষু ঢাকিয়া রাণী হেঁট মাথা করি । নারদ মুনি তবে দিল টিটকারী ॥ \* dui cākṣu ḍhākiñā rāñi hēṭṭ māthā kārī (=kārilā), Nārād-muni tabē dila ṭiṭākārī \* *closing both her eyes, the queen (Mēnakā) hung down her head, and then the sage Nārada said words of scorn :* p. 17, হাথে ধরি কজা আনিগ দেব শূল-পাণি ॥ কজা লঞা হর ছায়ামণ্ডপে বসি । চারিদিকে বেষ্টিল সব দেব ঋষি ॥ \* hāthē dhāri kānyā ānilā dēbṣ Śūlāpāñi ; kānyā lāñā Hārā chāyā-māṇḍapē bāsi (=bāsilā), cāri dikē bēṭhilā sābṣ dēbṣ ṛṣi \* *holding her by the hand, the Trident-bearer led the bride (Umā) : Hara (Śiva) then sat in the pavilion with the bride, and all the gods and sages surrounded them on four sides ;* p. 14, পুষ্পকরথ সাজিঞা ত্রকা তাহাকে দিল দান ॥ ত্রকার বরে তুষ্ট হইলা বাপেরে নমস্করি । জত বর পাইল তাহা বাপকে গোচরি ॥ হুহুত বর ত্রকা যোকে দিল দান ॥ \* puṣpākṣ-rāthṣ sājiñā Brāhmā tāhākē dila dāñṣ, Brāhmārṣ bārē tuṣṭā hāñilā, bāpērē nāmāskārī (= -kārilā) ; jāṭā bārṣ pāilā, tāhā bāpākē gōcārī (=gōcārilā) : \* durlābhṣ bārṣ Brāhmā mōkē dila dāñṣ \* \* *Brahmā prepared the (aerial) flower-chariot and gave him as a gift : he was pleased at Brāhmā's boon and saluted his father, and told his father about all the boons he received : ' rare boons has Brāhmā made a gift of to me ' ; etc., etc ;*

Chuṭi Khān's 'Mahābhārata' (VSPd. ed.) : p. 144, এত বলি অনুশাল করএ বিনয়, প্রীত হই আদিদি কৃষ্ণ মহাশয় \* ēṭā buli Anuśālā kārāē bināyṣ, prītā hāi

alingi (=ālingilā) Kṛṣṇa mabhāṣayā > saying all this Anuśālva does courtesy ; being glad, the great-hearted Kṛṣṇa embraced him ;

Mālādhara Vasu's 'Bhāgavata' (VSP., p. 771) : তার দন্ত উপাড়িয়া নিল দুই ভাই । সেই দন্তে, মাহুত মারি বম্বরে পাঠাই ॥ • tāra dāntā upāḍiyā nilā dui bhāi, sei dāntē māhutā māri Jāmā-ghārē pāṭhāi (=pāṭhāilā) > the two brothers pulled out his tusks, and with those tusks killing the elephant-driver sent (him) to the abode of Yama ;

Vijaya-gupta's 'Padmā-purāṇa' (see *supra*, p. 735) : p. 108, গোসাঞি কোন দোষে শাপি • gōsāñi kōṇṣ dōṣē śāpi > through what fault did the lord curse ? p. 109, কলসী ভরিয়া বৃত নাগ সবে ঢালি • kālāsī bhariyā ghṛtā nāgā-sābē ḍhālī > the Nāgas poured ghee in full jars ; p. 214, পদ্মার বচনে বেহলা মনে মনে হাসি • Pādmārā bācānē Bēhulā mānē mānē hāsi > Bēhulā laughed in her heart at Padmā's words ; etc. ;

'Caitanya-caritāmṛta,' Ādi-līlā, Chap. 13 : শ্রীকৃষ্ণ চৈতন্ত নবদ্বীপে অবতরি । অষ্ট চল্লিশ বৎসর প্রকট বিহরি ॥ চৌদশত সাত শকে জন্মের প্রমাণ । চৌদশত পঞ্চাশে হৈলা অন্তর্ধান ॥ • Śrī-kṛṣṇa-caitānyā Nābādwpē ābatāri, ṣṣṭā-cāllisṣ bātsārā prākāṭṣ bihāri ; cāuddā-sātā-sātā śākē jānmērā prāmāṇṣ, cāuddā-sāta-pāñcānnē hāilā āntārdhāṇṣ > Śrī-Kṛṣṇa-Caitanya came down to Navadvīpa ; he sojourned in manifest form for 48 years ; the date of his birth, Śaka 1407 ; he disappeared in 1455 ; also cf. VSP., p. 1222, যে পথে যে গ্রাম নদী শৈল ঘাই হই লীলা । বলভদ্র-ভট্টাচার্য্য-স্থানে সব লিখি নিলা ॥ • jē pāthē jē grāmā nādī śāilā jāhā hāi līlā, Balābhadrā-bhāṭṭācāryyā-sthānē sābṣ likhi nilā > in all the ways, in all villages, rivers and hills, wherever there were any events, he wrote down all from Balabhadra Bhāṭṭācārya ; etc.

The Past use of the Present Tense in Bengali.

689. The •-i> affix in the past is thus found in MB., although it is not so common ; and this can only be expected, considering that in OB. the non-l form is hardly obsolete, although the •-l-> has well-established itself. But in MB. and NB. we meet with a very common use of what is apparently the present tense in the past, in historical narrative generally : e.g., NB. গেল বছর যখন আমি কাশী ঘাই (= গিয়াছিলাম) • gēlā bācārā jakhāṇā āmi Kāśī jāi (=giyāchilām) > when I went to



*Benares last year* ; ভারতে আৰ্য্যদের আগমন কখন হয় জানা যায় না • Bhārātē Āryyādērā āgāmāṇā kākhaṇā hāyā jānā-jāyā nā • *it is not known when the first coming of the Aryans into India happened* ; সম্রাট আকবর প্রায় ৫০ বৎসর রাজত্ব করেন • sāmrat Ākbārā prāyā pāñcāśā bātsārā rājatwā kārēṇā • *Emperor Akbar reigned for nearly 50 years* ; etc., etc. In MB. (and also in NB.), this 'present' is very frequently used side by side with the ordinary • -ilā • past, and is not distinguished from the ordinary present in any way as a present used especially for the past. This usage seems however to point to a continuance in MB. and NB. of the OB. passive participle without • -l- •, used for the past tense. The regular form would be • -ita > -ia > -ī, -i •, which is not uncommon in MB., as in the instances given above ; but it seems that when • -ilā • became established as the characteristic past base in OB. and MB., the • -i • form was not properly understood : in the 1st person it could easily be confused with the 1st person present affix, and in connexion with the 3rd person the final vowel could be changed to • -ē • as in the 3rd person present ; and in this way the old passive participle adjective could formally merge into the present tense, retaining its old past sense. This gave rise to what at first sight looks like a past use of the present. Once this construction was accepted, in Early MB., substitution for the • -i • participle by the 2nd personal affix • -ā • and by the honorific • -ēṇā, -ēṇā • was a matter of course. The use of the present for the historical past is of course a most natural thing, being found in many languages, Sanskrit and the Prakrits and the NIA. languages included. But the presence of the • -i • past for all persons in MB. points to • -ia < -ita • ; and also the use of • -i • and the • -ēṇā, -ā, -ē, -i • forms along with • -ilā • in the same sentence or proposition seems to indicate that the passive participle without • -l- • had something to do with the so-called 'present' tense for the past in MB. and NB.

Examples of this promiscuous employ of • -ilā • with the non -l forms can be found in the passages quoted in § 688, and further instances are given below :

ŠKK., p. 19, এ বোল স্থণিষ্ঠা নাগরী রাধা হাণএ সকলগাএ । যত নানা কুল পান করপুর সব পেলাইল পাঞ ॥ • ē bōlā ṣṇiṣṭhā nāgarī Rādhā hāṇāē sakalā

gāē, jāta nānā phulā pānā kārapurā saba pēlailā pāē > *hearing this talk, winsome Rādhā struck all over her body; all the various flowers, betel leaves and camphor and all she scattered with her feet*; p. 240, হেন বুলী রাধা কালী লক্ষী জাএ গজগড়ি ছান্দে ..... পাইল রাধা কালীদহ-কুল > *hēnā buli Rādhā kālāsi lākṣī jāē gajā-gaṛi chāndē ..... pāila Rādhā Kālīdaha-kūla* > *saying this Rādhā took her jar and went with the gait like that of an elephant, and she reached the shore of Kālī lake*; p. 24, সকল গোআল যুবতী রহিলা যেহু কনক পুতলী ॥ এখো পাঅ কেহো চলিতৈ নারে বুলিতে নারে বচনে । > *sākālā gōālā jubāti rahilā jēhā kānakā-putālī: ēkhō pāā kēhō calitē nārē, bulitē nārē bacānē* > *all the young girls of the cowherds stood still like images of gold, not one of them could walk even one step, nor could utter a word*; etc., etc.;

Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 29, ফলমূল আনি দিল ঠাকুর লক্ষ্মণ ॥ পিণ্ডান করেন রাম রাজীবলোচন । > *phālṣ-mūlṣ āni dilā ṭhākuraṣ Lakṣmaṇṣ, piṇḍā-dānṣ kārēnṣ Rāmṣ rājībā-lōcānṣ* > *worshipful L. brought fruits and roots, and lotus-eyed Rāma offered piṇḍas*; p. 17, সীতারে কহিল, ফল করগা ভক্ষণ । ফল হাতে করি কহে, ধরহ লক্ষ্মণ ॥ > *Sitā-rē kāhilā, 'phālṣ karāgā bhākṣaṇṣ': phālṣ hātē kārī kāhē, 'dhārāhā Lakṣmaṇṣ* > *he said to Sitā, 'eat (these) fruits'; taking the fruits in his hand he said, 'hold, Lakṣmaṇa'*; 'Uttarā-kāṇḍa,' p. 5, মঙ্গল দ্রব্য লঞা আইলা সখীগণ মেলি । কস্তুর অধিবাস করে দিয়া হলাহলী ॥ অধিবাস সঙ্গে হৈল সিদ্ধ সব কাজ । হেমন্তে মেলানি করি চলে মুনীরাজ ॥ > *māṅgālṣ drābyā lāṇā āilā sakhi-gaṇā meli, kānyārṣ ādhibāsṣ kārē diyā hulaḥalī: ādhibāsṣ sāṅgē hāilā siddhā sabṣ kājṣ, Hēmantē melāni kārī calē muni-rājṣ* > *the girl-friends (of Umā) came in company, bringing auspicious articles, with the hulu sound (of joy); the adhibāsa with all the ceremony was complete, and the prince of sages (Nārada) left, taking farewell from Himavanta*; etc., etc.;

Chuṭi Khān's 'Mahābhārata,' p. 54, প্রবীর পড়িল হেন ঘোষে সর্বজন । দূরে থাকি নীলধ্বজ শুনে ততক্ষণ ॥ হা হা পুত্র করি রাজা হৈল বাহির । > 'Prābīrṣ pāṛilā' hēnā ghōṣē sārba-jānṣ, dūrē ṭhāki Nīlā-dhwājṣ śunē tāṭā-kṣaṇṣ: 'hā hā putrā' kārī rājā hāilā bāhirṣ > 'Pravīra has fallen,' so shouted every one: then from a distance Nīladhwaja heard it; the king came out with 'ah, ah, my son!';



Kavikāṅkapa Mukunda-rāma (Vāṅgavāst edition) : p. 14, কোলেতে করিয়া রামা ছেলি করে পার ॥ প্রবেশ করিল ছেলি গহন কানন । • kōlēte kārīyā rāmā chēli kārē pārṣṭṣaḥ : prābēṣṣaḥ kārīlā chēli gāhāṇṣṣaḥ kānāṇṣṣaḥ > the lady took the goats across in her lap : the goats entered the dense forest ; p. 155, হস্ত পরিহাসে দৌহে বসিলা দম্পতী । জিজ্ঞাসে ঘরের বার্তা সাধু ধনপতি ॥ লহনা কহিল, প্রভু তুমি ভাগ্যবান । • hāsyaḥ pāribāsē dōhē bāsīlā dāmpatī ; jījñāsē ghārēṣṣaḥ bārttā sādhu Dhānapāti : Lahanā kāhila, 'prābhu ! tumi bhāgyābān' > the two, husband and wife, sat, in laughter and in jest ; the merchant Dhanapati asked about the news of home : Lahanā said, 'my Lord ! you are fortunate indeed' ; p. 175, তাহার পশ্চাতে আইল দাস নীলম্বর । আদর করিয়া আইসে উজানী নগর ॥ • tāhārṣṣaḥ pāścātē āīlā Dāsṣa Nīlāmbārṣṣaḥ, ādarṣṣaḥ kārīyā āīsē Ujānī-nāgarṣṣaḥ > behind him came Nīlāmbara Dāsa, doing (proper) respect he came to the city of Ujānī ; p. 185, সমুখ দুয়ারে অগ্নি দিলেন খুল্লা ॥ ছয়াবর্তে যায় অগ্নি, সান্তাইল ঘরে । প্রবল হইল অগ্নি জউয়ের উপরে ॥ জউগৃহে বাঢ়ে অগ্নি ক্রোশ পরিমাণ ॥ • sāmukhaḥ duārē āgni dilēṇṣṣaḥ Khullāṇṣṣaḥ : duārētē jāy āgni, sāmbhāīlā ghārē ; prābalṣṣaḥ hāīlā āgni jāū-ērṣṣaḥ upārē, jāū-grhē bārṣṣaḥ āgni krōṣṣa-pārimāṇṣṣaḥ > Khullānā set fire to the front door : the fire came through the door, and entered the house ; upon the lac, the fire became strong, and the fire grew a krōṣa measure within the house of lac ; etc., etc. ;

Vanṣṭi-dāsa, 'Padmā-purāṇa,' (ed. Rām-nāth and Dwārakā-nāth Chakrabarti) : p. 207, আশুবাক্তি ওঝারে আনিল আনিল চন্দ্র ঘরে ॥ পরম গৌরবেতে করিল সম্ভাষণ । ধনন্তরি আগে আনে মড়া ছয়জন ॥ • āgu-bākti ōjharē ānilā Candraḥ ghārē, pāramṣṣaḥ gaurābētē kārīlā sāmbhāṣṣaṇṣṣaḥ ; Dhānwāntari-āgē ānē mārṣṣa chāyṣṣa-jānṣṣaḥ > Candra advanced and brought the snake-doctor home, greeted him with great honour and they brought the six corpses before Dhanvantari ; etc. ;

'Caitanya-caritāmṣṭa,' Madhya-līlā, Chap. 9 : রাজিকালে রায় পুন কৈল আগমন । দুইজনে কৃষ্ণকথায় করে আগরণ ॥ দুইজনে কৃষ্ণকথা হয় রাজিদিনে । পরম আনন্দে গেল পাঁচ সাত দিনে ॥ • rātri-kālē rāyṣṣa punā kārīlā āgāmāṇṣṣaḥ ; dui jānē Kṛṣṇā-kāthāyṣṣa kārē jāgārāṇṣṣaḥ : dui jānē Kṛṣṇā-kāthā hāyṣṣa rātri-dinē, pāramṣṣa ānandē gēlā pācṣṣa sātṣṣa dinē > the king came again at night time ; both of them kept awake discoursing about Kṛṣṇa ; there was

*discourse about Kṛṣṇa between them, night and day; some 5 or 7 days were thus passed in great bliss; Antya-līlā, Chap. 9: এত বলি ঘোড়া আনি রাজদ্বারে ধরি ..... এক রাজপুত্র ঘোড়ার মূল্য ভাল জানে। তারে পাঠাইল রাজা পাত্র-মিত্র সনে ॥ সেই রাজপুত্র মূল্য করে ঘাটাইয়া। গোপীনাথের ক্রোধ হৈল মূল্য শুনিয়া ॥ « ētā bali ghōṛā āni rāja-dwārē dhāri ..... ekṣ rāj-putrā ghōṛārṣ mūlyā bhālā jānē; tāre pāṭhāilā rājā pātrā-mitrā sānē; sei rāj-putrā mūlyā karē ghāṭāiyā, Gōpīnāthērṣ krodhṣ hāilā mūlyā śuniyā » saying this and bringing the horse, they kept before the king's palace-gate: a prince knew well the price of horses; the king sent to him with his courtiers and friends; that prince fixed the prices very low, and hearing that (low) price, Gōpīnātha's anger rose; etc., etc.*

Such cases of indiscriminate use of the « -ila » and the present forms are exceedingly common in MB. Where continuous action is meant, it may be admitted that the form in use can very well be that of the present, since in the syntax of Bengali, action is viewed as happening before our eyes as much as possible. But we have also cases of finite or transitory action, and there the use of a present form would be difficult to justify even from the point of view of Bengali syntax. It is to be noted that with this so-called present past, the negative form which is employed is নাই « nāi », which seems to be itself a past form (see *supra*, p. 555).

In the 'Prākṛta-Pāṅgala' we have a few instances of a form in « -ē » (for the third person), analogous to the Bengali 'present' past: *e.g.*, p. 334 (Bib. Ind. ed.) « jini Kāṁsa viṇāsia kitti paāsia Muṭṭhi Ariṭṭhi viṇāsa karē; Jamalajjuṇa bhañjia paa-bhara ganjia Kālia-kula-saṭhāra karē, jasa bhuaṇa bharē..... »; p. 576, « bappaa ukki sirē jini lijjia, tējja rajja vaṇanta calē.... ». In the above cases, all the commentators are agreed (except in one or two instances) in regarding « viṇāsia, paāsia, bhañjia » etc. as well as the « -ē » forms—« karē, dharē, bharē, calē » as being passive participles in « -ia < -ita », with the instrumental form « jini = yēna » as the subject (cf. *supra*, p. 124). The final « -ē » (instead of « -i ») is due in the 'Prākṛta-Pāṅgala' to reasons of rime or rhythm in some cases, but as the work was finally redacted in the second half of the 14th century, the influence of the present tense third person in altering



the final vowel as in Bengali is also quite conceivable here. With the forms in « -ē » as above, one can compare certain other forms in « -u », genuine Western Apabhraṃśa inheritances, in the 'Prākṛta-Pāṇḍala': e.g., p. 570, « jīṇa vēa dharijjē...dantahi ṭhāu (= sthāpitā) dharā...daba-muḥa kappē (= kartitaḥ) ».

690. The non-l past form is found occasionally in Early Oṛiyā also, where it ends in « -i ». Thus Jagannātha-dāsa, 'Ūṣā-haraṇa' (Contai ed.): p. 6, « pāriḡhā-prāhārē bināsi, simhā yēsāṇē pāsu grāsi: pāriḡhā-ghātā bājṛā-prāyē, jibānā nāsīlā thōkāē: kāhārā bhuja-dāṇḍā chiṇḍi, pālāi gālē bālā chāḍi: dēkhiṇā Aniruddhā-gāti, nāgā-bāndhānē māhārāthi Aniruddhā-ku bēgē bāndhi: tā dēkhi Ūṣā kāndi » *he slew with a blow of his mace, as if a lion devoured a beast: the blow from the mace was as a thunderbolt, it destroyed the lives of some; the hands and arms of some were torn away, they ran away leaving the forces: seeing Aniruddha's devoir, the great warrior quickly bound Aniruddha with snake-bonds: seeing that, Ūṣā wept*; p. 9, « Kṛṣṇa upārē bāṇā bindhi » *the arrow pierced Kṛṣṇa*; p. 10, « sābhāyē dāsā digā cāhi » *looked at the ten quarters in fright*; p. 11, « jūānā pāsīlā nija dēhē: uṭhi sāmbhāji kāḷebārā » *senses came back into his body: getting up, he took care of his person*; ibid, 'Kaṇsa-janma': p. 2, « Kṛṣṇa-bāiri-bhābā icchi » *desired the inimical attitude of Kṛṣṇa*; p. 16, « dēbē pālāi swārgā chāri » *the gods fled, leaving heaven*; 'Rukmiṇi-haraṇa,' p. 15, « jētē āyudhā hāstē dhāri, sābu chēdilē Nārābhāri » *Narahari (Kṛṣṇa) cut to pieces all the weapons that he took in hand*; ibid., « Kṛṣṇā dhāilē Rukmā-śirā: tāṭ-kṣāṇē tālā tāku pāri, pāñcā prākārē kāṭi dāhi: tā dēkhi Rukmiṇi sundāri, Kṛṣṇārā hāstā bēgē dhāri » *K. seized Rukma by the head; at once flinging him down on the ground, cut his beard in five places: seeing that, fair Rukmiṇi quickly took K.'s hand*; etc., etc. Examples are fairly common in Early Oṛiyā.

In Early Maithili also, we have equally the non-l form: but it seems owing to the strong influence exerted by the Western Apabhraṃśa, the remains of Early Maithili literature that we have show the non-l form with the characteristic Western « -u » (as much as in OB.). This « -u » form so far as Maithili is concerned was purely literary, and has no

place in Modern Maithili. Examples: Vidyāpati (VSPd. ed.), Pada 32, « sasana parasa khasu ambara rē, dēkhala dhani-dēha » *with the touch of wind the garment fell off, ho, the damsel's frame was seen*; Pada 40, « saba-jana ēka ēka cuni sañcaru, Śāma-daraśa dhani lēla » *all (her friends) moved about picking (pearls dropped from her necklace) one by one, and the damsel had her view of Śyāma (Kṛṣṇa)*; Pada 50, « ambara bighaṭu akāmika, kāmīni karē kuca jhāpu suchandā » *of a sudden the garment slipped, and the lady with her hands covered her breasts with great grace*; ibid, « sundari rahu sira lāi » *the fair one remained hanging her head*; Pada 52, « candanē caracu payōdhara » *the breasts smeared with sandal-paste*; Pada 60, « takhanē upaju rasa, bhēlihu mōñē parabasa » *sentiment (of love) was born even then, (and) I became another's thrall*; Pada 75, « jakhanē duhu-ka dīṭhi bichūrali, duhu manē dukha lāgu : duhu-ka āśā-dīpa mijhāela, madana-ākura bhāgu.....bāma nayanā jañō bhēla dūtē, ō dāhina rahu lajāi » *when the two were out of (each other's) sight, sorrow afflicted the hearts of both; the lamp of hope of both went out, and the sprout of love was broken; .....the left eye was a messenger, but the right one remained in bashfulness*; Hara-gaurī Pada 9, « pāhuna āela, Bhabānī bhāga-chāla basaiē dia āni » *the guest came and Bhavānī (Umā) brought the tiger-skin to sit upon; etc., etc.*

The non-l adjectival forms in Middle Bengali and New Bengali.

691. The non-l form gave OB. « -l », e.g., « calī »: with the definitive « -ā », Māgadhi Ap. « calia » became « calīā », and then by loss of the « -i- », it became « calā » by Early MB. times. A similar loss of the « -i- » occurs in the Western Hindi: cf. Hindōstānī—« calā », Kanauji « calō », beside Braj-bhākhā « calyau (= caliai) », 'Vernacular Hindōstānī' of Ambala « calīā » (cf. also Bāngarū of Karnal « kahyā » = Hindōstānī « kahā »). The « -i- » seems to be preserved in the perfect tense in Standard Bengali « cāliyā-chē » and dialectal « cālī-chē [tsollse] < cālī-chē », where « cāliyā (cālī) » is in all likelihood the passive participle (see *infra*, under 'Compound or Periphrastic Tenses').

In the ŚKK., the non-l form is rather rare, *its* forms in « -ita » and the « -l- » participle adjective being more common; but instances



do occur : e.g., p. 259, চলি চৈলী চন্দ্রাবলী < calī (= calitā) bhāilī Cāndrābālī > *C. was gone*; p. 381, বাহতে কনক চুড়ী, মুকুতা রতনে জড়ী < bāhutē kāṇākā curī, mukutā rātānē jāṛī > *on her arms gold bracelets, encrusted with pearls and gems*; etc. (these two examples < calī, jāṛī > are feminine). Examples of the < -ā > form are plentiful in other MB. literature: to quote a few random instances, Kṛttivāsa, 'Uttarā-kaṇḍa,' p. 177, পথে স্থা কুকুর < pāthē suā kukur > *a dog lying on the way*; Vijaya-gupta, 'Padmā-purāṇa,' p. 12 তিতা বস্ত্র < titā bāstrā > *wet cloth*, p. 38 টুটা < ṭuṭā > *broken*, p. 55 ভাঙ্গা < bhāṅgā > *broken*, এড়া রুটি < ēṛā ruṭī > *cast-away bread* (= *leavings of a meal*), p. 58 তোলা জল < tōlā jāḷ > *water drawn (from well or tank)*, p. 107 পোড়া কপাল < pōṛā kāpāl > *burnt forehead = bad luck*, p. 69 মরা মানুষ < mārā mānuṣ > *dead man*, p. 132 পাকা মূলা < pākā mūlā > *ripe radish*, p. 158 দন্তগুলি ছোলা < dāntā-guḷi chōlā > *the teeth were well-scraped*, etc.; VSP., p. 386 লেখা < lēkhā > *written*, p. 989 অবোলা < ābōlā > *not uttered*, p. 1057 হারা < hārā > *lost*, etc.; Chuṭī Khān's 'Mahābhārata,' p. 55 বাণ কাটা গেল < bāṇ kṭā gēlā > *the arrow was cut into pieces*; etc., etc.

The < -l- > form in Middle Bengali.

692. Examples need not be adduced for the verb past tense, as < -il- > is the past base of Bengali. Passive participial adjectives in < -il- > were very much in evidence in MB. In the NB. the non-l adjective in < -ā > has practically superseded the earlier, more common < -il- > adjective (except in one or two phrases like গেল বছর < gēlā bāchār > *last year* in the Standard Colloquial: in the dialects it is still living, in forms like জুড়াইল দুধ < juṛāilā dudh > *cooled milk*, সুতিল মানুষ < sutilā mānuṣ > *sleeping man*, করাইল কাম < kāṛāilā kāṁ > *done work*, ভুখিল ছাইল্যা < bhukhilā chāilyā > *hungry child*, etc.). The < -l- > form continues in full vigour in Oṛiyā and in the Bihārī dialects as an attributive adjective.

Examples from OB.: Caryā 6, < bāḍhila hāka > *a tumult that has been surrounded*; 8, < gēlī (= gēlā?) jāma babuḍāi kaisē > (printed text = বহ উই < bahu uī >, but cf. Commentary translation = < vyāghuṭati >) *how can a birth that is past (gēlī = gata-) come back?* 14, < rathē-caḍilā bāha-bāṇa >

? carriage-riding scholars; 33, « duhila dudhu ki bēṇṭē ṣāmāya », see *supra*, p. 263.

From MB.: ŚKK., p. 26, ভাঁগিল নেহা « bhāṅgilā nēhā » *shattered love* (NB. ভাঙ্গা « bhāṅgā »); p. 45, আরতিল কাক « āratilā kākā » *greedy crow* (from *ts.* noun « āratī », or < « āratā = ārakta »); পাকিল বেল « pākilā bēlā » *ripened (ripe) bael-fruit* (= NB. পাকা « pākā »); p. 54, পাইল নিধি « pāilā nidhi » *received wealth* (= NB. পাওয়া « pāwā »); p. 99, ভুখিল বাঘ « bhukhilā bāghā » *hungry tiger* (< *tbh.* noun « bhukha »); p. 163, আউলাইল চিহ্ন « āūlāilā cikurā » *dishevelled hair*; p. 171, ভরিল বমুনা « bhārilā Jāmunā » *full Jamunā*; p. 195, ফুটিল বাকুলী ফুল « phuṭilā bāndhālī-phulā » *blooming bāndhulī flower* (cf. ফুটিত পদ্ম « phuṭitā pādmā » *blooming lotus*, with *ts.* « -ita », in the same page); p. 216, রোষিল রাধা দিল খর বচন « rōṣilī Rādhā dilā khārā bācānā » *angry Rādhā gave (spoke) sharp words*; p. 207, পাকিল দ্রাক্ষা « pākilā drākṣā » *ripe grapes*; p. 246, আসুখিল হইল « āsukhilā hāilā » *became unwell* (from *ts.* noun « asukha »); p. 304, মজিল চিত না জাএ ধরণ « mājilā citā nā jāē dhārāṇā » *heart lost (in love) cannot be retained*; p. 370, দগধিলী রাধা জীএ তোর দরশনে « dāgādhilī Rādhā jīē tōrā dārāśānē » *Rādhā burnt (with love) as it were, will live (only) at thy sight (sts. dagadha < dagdha)*; p. 392, বিষাইল কাণ্ড « biṣāilā kāṇḍā » *poisoned arrow* (from noun « viṣa »); *ibid.*, বজরে গড়িল বুক না জাএ ফুটিয়া « bājarē gaṛhilā bukā nā jāē phuṭiā » *heart built of thunder-bolt does not burst* (NB. = গড়া গুঁড়া); p. 398, কাটিল ঘাঅত লেখু রস « kāṭilā ghāātā lēmbū-rāsā » *lemon-juice in an incised wound*, etc.; from Kṛttivāsa, 'Uttara Kāṇḍa'; p. 272, ভরিল সমাজে « bhārilā sāmājē » *in full assembly*; *ibid.*, 'Ayōdhyā Kāṇḍa'; p. 21, কাটিল কদলী যেন পড়ে ভাল মূলে « kāṭilā kadālī jēnā pāṛē ḍālē mūlē » *like a plantain tree that has been cut down, which falls with its branches and its roots*; Kavi-kaṇkaṇa, p. 118, ভুখিল বাঘিনী « bhukhilā bāghinī » *hungry tigress*; p. 160, রাহর ভুখিল বেলা « Rāhurā bhukhilā bēlā » *at Rāhu's hungry time*; Vaṇśī-dāsa, 'Padmā-purāṇa,' p. 48, কুপিল নন্দী « kupilā Nāndī » *angry N.*; p. 644, হারাইল ধন « hārāilā dhāṇā » *lost wealth*; etc., etc.

The adjectival use of the « -l- » forms in OB. and MB., as well as in Early Maithili (see below) establishes the passive construction as having originally obtained in place of the active one in the eastern languages.



When these «-l-» participles qualify feminine nouns (either subjects, as in the case of intransitive verbs, or objects, as in the case of transitive ones), in OB., in eMB., and in Early Maithili, they take the feminine affix «-l-, -i» (see before, pp. 672 ff.): thus, in OB., «mēlilī kāchi» (Caryā 8); «ghalilī māli» (10); «buḍilī Mātangī» (14); «lāgēlī tāntī» (17); «lāgēlī dālī, sēji chāilī, rāti pōhāilī» (28); «ṭuṭi gēlī kaṅkhā» (37); «lāgēlī āgi» (47); «ghariṇī caṇḍālī lēlī» (49); «phitlī ṣabarālī» (50): eMB. ŚKK., p. 72, কোণ পুরাণে কাহ্ন হেন কণিলী কাহিনী «kōṇa purāṇa Kāṇhā hēṇā ṣaṇilī kāhiṇī» in *what Purāṇa, O Kāṇha, has such a tale been heard* (passive construction lingering in MB., with transitive verb); p. 9, বড়ায়ি চলিলী আন পথে «bāṛāyi calilī āṇā pāthē» *the old dame went by another way*; p. 14, সে কি রাধিকা ভেলি সীতা মতী নারী «sē ki Rādhikā bhāilī Sitā sāti nārī» *is it that R. has become a chaste wife (like) Sitā*; p. 22, রাধা সিঁঝা বসিলি শয়নে «Rādhā siṅhā bāsili śāyānē» *R. having come sat down on the bed*; p. 144, মথুরা লড়িলী বড়ায়ি হইয়া আশুমানী «Māthurā lāṛilī bāṛāyi hāi āṣṇānī» *the old dame moved (towards) Mathurā, being the leader*; p. 145, বলিতে লাগিলী বড়ায়ি «bulitē lāgilī bāṛāyi» *the old dame began to say*; *ibid.*, গেলী রাধী «gēlī Rāhī» *Rādhikā went*; p. 156, হেন শুধী মনত চড়িলী রাধা নাএ «hēṇā ṣuṇī mānā-tā cāṛhili Rādhā nāē» *thus pondering in mind, R. got into the boat*; p. 266, জিলী পদ্মার কৌ «jilī Pādmārā jhī» *Padmā's daughter lived (again)*; etc., etc. In Late MB., and in NB., as the «-l-» form lost its original adjective nature, and became more and more a verb, this affixation of the feminine «-l-, -i» went out of use. The same thing has happened in Maithili, though to a lesser extent.

Instances of the «-l-» adjective from Early Oṛiyā: 'Dhruba-carita,' p. 11, «āpāṇā arjilā karmā āpāṇē bhuñjāi» *one tastes (the results of) one's deeds done by oneself*; p. 73, «Dhrubārā arjilā bibhūti» *merits earned by Dhruba*; 'Rukmiṇī-haraṇa,' p. 11, «ṣṣṭhā pācilā phāḷā bimḃā» *lips (like) ripe (i.e. red) bimba fruit*; etc., etc. It is common also in Modern Oṛiyā.

Instances from Early Maithili: Vidyāpati, (VSPd. ed.) Pada 37, «titalā basana» *wet clothes*; 9, «nahāilī gōrī» *bathing fair woman*;

62, « mūruchali abañō » *am one that has fainted*; 41, « nagara bharalā » *a well-filled city*; 21, « kāmīni kōnē gaṛhalī » *by whom (this) woman was created?* (fem. affix « -i »); Hara-gauri Pada 17, « Śaṅkarē Gōrī karē dhari ānalī maṇḍapa-mājhē » *Gaurī was brought to the middle of the pavilion by Śankara holding her hand*; etc., etc.

Western Hindi shows adjectives in « -l- » which are extended forms from nouns: e.g., « lajilī (lajjā), sawādila (svāda), adōkhila (dōṣa), haṭhīlī (haṭha), rangīlā (raṅga), caṭakīlā (caṭak *splendour*), chaīla (chavi) » etc. occur in Bibārī's ‘Sata-sai’; and similar forms like « lāḍīlī » *petted* (√*laṣ*): > Bengali লাজলী « lāḍāḷī »), « bhīḡīlā » *wet*, « kaṭīlī » *cut*, « rasīlā (rasa) », « ghāyala (ghāta) », « gāīla » *lane* (gata) etc. are fairly common in Braj-bhākhā and other Early Western Hindi literature. The extension of the passive participle form occurs, but that is rare.

## (2) THE PAST CONDITIONAL OR HABITUAL.

693. The Past Habitual or Conditional occurs in most NIA. speeches. Of the Eastern languages, Assamese, however, does not show it. This past base is simply the old Present Participle, the Oṛiyā forms (retaining as they do the full « -nt- »: see next section) are clear on this point: OIA. « -ant-, -ayant- » > MIA. « -anta-, -enta- » > OB. « -anta-, -enta- » > MB. ইত « -it- » (cf. Hoernle, Gaudian Grammar, §§ 298-300, §§ 506 ff.). To denote the conditional or habitual, « -it- » is inflected with the personal endings as an ordinary past form. The conditional or finite use of the present participle occurred in Second MIA. (cf. Tessitori, ‘Grammar of OWR.’ § 123). Both the conditional and habitual uses of the present participle seem to be connected with the sense of *when, while, whilst, when that* etc., which is inseparable from this form when it is not frankly attributive: and this sense of duration implying almost a condition is emphasised in the locative absolute with the present participle, a construction which is found in the language of the Rig-Veda. The conditional and independent use of the present participle could thus normally evolve out of it. Cf. e.g., the Pāli Jātaka formula, « atitē Bārāṇasīyaṃ Brahmaḍattē rajjaṃ karentē », followed invariably by a past verb.



OB. as in the Caryās has the locative absolute with the present participle: e.g., Caryā 42, « muṣhā acchantē lōa na pēkhaī » *people do not see while they are ignorant*; quotation in Commentary to Caryā 48, « ghara acchantē mā jāṅga (= jāha? jāwa?) baṇē » *when there is a home, go not (let us not go?) to the forest*; etc. But an example of the past conditional or habitual tense does not occur in the Caryās. In Early MB., this habitual or conditional past is fully established as a tense; and judging from its occurrence also in Early Oṛiyā and in Bihārī, it may be inferred that this temporal employment goes back to Māgadhi Apabhraṃśa.

Examples from MB.: ŚKK., p. 164, ডুবীয়া মরিতো যবে না থাকিত কাহ্নে • *ḍubiā māritō jābē nā thākitā Kānhē* • *I would have died by drowning if Kṛṣṇa were not (there)*; p. 256, জীবন্ত থাকিত যবে নান্দেৰ নন্দনে । এত থনে আবদই হৈত দরসনে • *jīyāntā thākitā jābē Nāndērā nāndānē, ētā khānē ābāsāī hāitā dārāsānē* • *if the son of Nanda were living, by this time certainly we would have seen him* (lit. *his viewing would have taken place*); p. 223, জানিতো নাসিতো, যাইতো, • *jānitō, nāsitō, jāitō* • *I would know (if I had known), I would not come, I would go*; p. 284, দিতো • *ditō* • *I would give*; p. 307, চাহিত • *cāhitā* • *I would ask*; etc., etc.; Kṛttivāsa, 'Uttarā-kāṇḍa,' p. 103, আমি যদি থাকিতাম • *āmi jādi thākitām* (= *thākitām*) • *if I had remained*; Kavi-kaṇkara, p. 128, প্রতিদিন কিতিনাথ অঙ্গে ব্লাহিত হাত, চন্দনে করিয়া বিভূষিত । স্বৰ্ণ পিঞ্জর পর পুষিতেন নৃপবর • *prāti-dinā kṣiti-nāthā āṅgē bulāitā hāt, cāndānē kāriyā bibhūṣitā: subārṇā-piñjārā-pārā puṣitēnā nṛpā-bārā* • *everyday the lord of earth would rub with his hand on its body, adorning with sandal (paste); the good king would tend it in a cage of gold*; etc., etc. Examples are copious in MB.

#### 694. Forms in the other Magadhan speeches:

##### Oṛiyā

1. cālānt-i—cālānt-u;
2. cālānt-u—cālānt-ā;
3. cālānt-ā—cālānt-ō.

(The affixes are those of the verb simple past.)

##### Maithili

1. dēkhit-i;
2. dēkhit-ab, dēkhit-ē;
3. dēkhaīt, dēkhit-athi.

(Besides a number of forms with pronominal affixes.)

## Magahī

## Bhōjpuriyā

- |                             |  |
|-----------------------------|--|
| 1. dēkhat-I, dēkhait-I, -ñ; | 1. dēkhat-I, (fem.) dēkhat-yñ;         |
| 2. dēkhait-ā, dēkhait-ai;   | 2. dēkhat-ē, -as, -is; <i>pl.</i> -ah; |
| 3. dēkhait, dēkhait-athi-n. | 3. dēkhit, dēkhat—dēkha(i)t-an.        |

(Besides forms with affixed pronouns.) (Besides a few other forms for the third person.)

Assamese expresses the past conditional by affixing the word « -hētē » to the inflected « -il- » past form : « kārīlō-hētē, kārīlō-hāk-hētē » etc. This « hētē » occurs in Early Assamese as « hēntē » (as in « pāilō-hēntē » *I would receive* in 'Ādi-caritra,' p. 67), and it is undoubtedly the present participle of « √ah, ha » *to be*, in the locative absolute, « \*ahantahi » > \*ahēntahi > hēntē », a variant of the other form « hāntā, hātā » (see above, p. 739).

The « -it-, -at- » Future in the Modern Magadhan Speeches.

695. In Maithilī and Magahī, there is the use of the present participle form in « -t- » for the Future. In both these forms of Central Magadhan, the « -t- » future has ousted « -b- » future (for which see *infra*) in the 3rd person: in Maithilī there are also alternative « -t- » forms for the 1st and 2nd persons. Thus—

Maithilī, 1st person : « dēkhat-iai, dēkhit-āhū (dēkhat-iai-nhi) » ;

2nd person : « dēkhat-iai (dēkhat-iai-nhi) » ;

3rd person : « dēkhat (dēkhat-ai) », fem. « dēkhati », besides forms with the pronouns affixed — « dēkhat-ai-nhi, dēkhat-tah, dēkhatu, dēkhatūnhi, dēkhatīnhi », fem. « dēkhatīhi ».

Magahī, 3rd person, only : « dēkhat (dēkhat-ai) », besides « dēkhatābin, dēkhatān, dēkhatathi, dēkhatin, dēkhatathin, dēkhatathin(i) ».

Leaving apart the extended forms, with the pronominal affixes, the simplest form for the 3 person future in both Maithilī and Magahī is « dēkhat » : thus, « sē dēkhat » *he will see*. Here we have the simple participial base apparently : < « sē \*dēkkhanta » = *he seeing*. But in the



past conditional it is « sē dēkhait », which seems to represent an old oblique form, a locative absolute apparently : « tasmin \*dṛkṣati (base \*dṛkṣant-) > \*tabi dēkkbantē, dēkkhanti > sē dēkhati, dēkhait (by epenthesis) ».

In dialectal Bengali, of Eastern Bengal (specially in the East Vanga area), there is also a future use of the « -t- » forms : thus, in East Sylhet Bengali, we have 1 pers. দেখতাম « dēkhtām » *I shall see, also I would see, if I saw*; 2 pers. দেখতায় « dēkhtāy », দেখতে « dēkhtē »; 3 pers. দেখতো « dēkhtō », দেখ্তা « dēkhtā » (LSI., V, I, p. 226). From the future, an imperative use also seems to be found occasionally in East Sylhet : e.g., আপত্তি করলাম, তিল কাটত না « āpatti kā'rlām, tilā kāṭatā nā » *I objected, 'don't cut the sesamum'* (LSI., V, I, p. 232). Similar use is found in Tippera, in Noakhali, and in Chittagong : e.g., দিত না « ditā nā » *he will not give, ক'রতাম ন « kā'rtām nā » I shall not do*. The following peculiar construction is also noticeable, with the « -t- » conditional or future, to denote purpose or desire : আমি যাইতাম চাই « āmi jāitāmṣ cāi » *I want to go* (besides যাইতে, যাইবার « jāitē, jāibārṣ » as in Standard Bengali), তুমি যাইতায় চাও « tumi jāitāy cāo » *you want to go*, হে যাইত চায় « hē jāitā cāy » *he wants to go*, honorific তাইন যাইতা চাইন « tāin jāitā cāin » (as in Eastern Sylhet : LSI., V, I, p. 227). Cf. also দিতাম পাইরতাম না « ditām pāirtām nā » *shall not be able to give, কইরতাম দিতাম ন « kāirtām ditām nā » shall not allow (them) to do* (as in Noakhali), আমি যাইতাম লাগ্গিলাম « āmi jāitām lāggilām » *I began to go*, তুই যাইতা লাগ্গিলা « tui jāitā lāggilā » *you began to go*, হিতে যাইতে লাগ্গিল « hitē jāitē lāggil » *he began to go* (as in Chittagong : cf. Basanta Kumar Chatterji in VSPdP., 1926, p. 114, = Standard Bengali « jāitē lāgil- » for all persons). Here we have simply the present participle adjective inflected as a tense even when it is not a finite verb. Such use is found in South-East Bengali of several centuries ago : thus in the Chittagong poet Ālāol of the 17th century, we have a line like কুবোল সহিতাম নারি « kubōlā sāhitāmṣ nāri (= nā pūri) » *I shall not be able to endure bad words* (VSP., p. 1142). The « -t- » future is also found in Mayang or Bishnupuriyā (LSI., V, I, p. 424), which seems to be an old extension of Sylhet Bengali in the Tibeto-Burman tracts of the east. With the « -r- » affix (see *infra*, 'Pleonastic Affixes'), Sylhet Bengali and

Mayang, again, have some forms with the «-t-» conditional or future to indicate the present or future (LSI., V, I, pp. 226, 423, 424).

This future use of the present participle in the Bengali dialects of the extreme east is not shared by the other forms of the language, and seems only to be a local development. But the point is not clear. It is plain that in Central Magadhan, the future use of the present participle made a start with the third person, and Magahī did not go beyond it. The future use of the third person is found in the 14th century Maithilī of Vidyāpati quite plentifully, but mainly in the third person. It cannot be surmised definitely whether this idiom originated in the Māgadhi Apabhraṃśa period as a form inherited equally by Central and Eastern Magadhan.

Mārkaṇḍēya in his 'Prākṛta-sarvasva,' notes that in Nāgara (i.e., Western) Apabhraṃśa, the present participle is used for all the tenses: thus, «sarvadā śatṛ: 'hontō' = bhavan, babbūva, bhaviṣyati vā» (XVII, 62, Vizagapatam ed., p. 119). This note is interesting: «hontō» is actually the source of the Gujarātī «hatō», Rājasthānī «thō» and Western Hindī «hatau, butau, hatō, thō, thā» (Tessitori, 'Grammar of OWR.,' §§ 113, 123), and of the Gujarātī and Western Hindī (Hindōstānī) present participle «hōtō» and «hōtā» besides; and further, the present participle affix «-ant-» has given the Western Panjābī, and Sindhī affix «-nd-» for the future base. These are all Western languages. But how far the future use of the «śatṛ» of Sanskrit characterised Māgadhi Apabhraṃśa cannot be known.

### (3) THE FUTURE TENSE.

The OIA. Sigmatic or Inflected Future in NIA.

696. The future was formed by adding «-sya-» (with or without the additional vowel «-i-») to the root in OIA. This inflexional or sigmatic future is preserved in many forms of NIA. as «-s-, -ś-, -h-», in W. Panjābī, Rājasthānī (Jaipurī and Mārṇāṭī), Gujarātī and W. Hindī (Braj-bhākhā, Kanaujī, Bundēlī), and partially in E. Hindī (in the 3rd person only in Awadhī and Baghelī, and in all the persons in Chattisgarhī;



the « -b- » future also occurs in the E. Hindi dialects, but never in the 3rd person). Of the Magadhan languages, Bhōjpuriyā preserves it in the 3rd person only, and in 2nd person as future precative; Magahi, 3rd person (beside the « -t- » future), and in the 2nd person as future precative; in Maithili and in NB., it is found in the 2nd person as a future imperative (see *supra*, p. 908); and in Assamese and Oṛiyā, it seems to have been entirely lost.

The sigmatic future at one time was present in the East, and traces of it continued down to eMB. The OIA. sibilant has survived as a sibilant in Gujarātī, in some of the Rājasthānī dialects, in Western Panjābī (the MIA. « -ss- » < OIA. « -sy- » doubtless being retained as a single « -s- » in the latter: cf. *supra*, pp. 549-550, p. 79). Thus: Gujarātī 1. « māṛś (māras)—māṛśū (mārsu) », 2. « māṛsē (mārsē)—māṛsō (mārsō) », 3. « māṛsē (mārsē) » = OIA. « mārayiṣyāmi », etc.; Jaipurī 1. « māṛasyū — māṛasyā »; 2. « māṛasī — māṛasyō »; 3. « māṛasī — māṛasī »; Lahndā 1. « māṛēsā — māṛsāhā, māṛsāh », 2. « māṛēsō — māṛēsō », 3. « māṛēsī — māṛēsī ». In the rest, where the « -sy- » form is preserved, it occurs as « -h- »; and this change of « -s- » to « -h- » is an unexplained problem in MIA. and NIA. phonology (see *supra*, pp. 549-550, p. 783). Thus, Mārwarī 1. « mārahū — mārahā », 2. « mārahi — mārahō », 3. « mārahī — mārahi »; Braj-bhākhā 1. mārihaū — mārihaī », 2. « mārihai — mārihai », 3. « mārihai — mārihai »; Awadhī 3. « mārihai (> māre) — mārihai », Bhōjpuriyā 3. « māri — mārihē, mārihen », etc. The « -h- » is thus further lost intervocally in the Eastern languages: thus, « māriṣyati » > MIA. « mārihai, mārihi » > NIA. « mārihi, māri » (as in Bhōjpuriyā).

In Early MB. we have cases of the sigmatic future for the third person also. A number of instances occur in the ŚKK., and a few could be culled from 15th century Bengali: after which period it died out evidently when the intervocal « -h- » was slurred, and the form became confused with the present indicative (or the passive present, which itself was merging into the present active). No instance of the sigmatic future in the first person has been found, either in OB. or in MB.; and no

case of third person occurs in the Caryās ; only of the second person (see *supra*, p. 908).

SKK., p. 65, ববে তোরে মারিহে পরাণে । তবে তোকে রাখিব কোণ জনে ॥  
 « jābē tōrē mārihē pārāṇē, tābē tōkā rākhibā kōṇa jānē » *when he will strike you in life, then who will protect you ?* ; p. 100, কাঁদিয়া জ্ঞানারিবে কাঁশে । পাছে কাহাকি মোকে না দিহে দোষে ॥ « kādiā jāṇāyibē Kāśe, pāchē Kānbāñi mōkē nā dihē dōṣē » *I shall lament and inform Kañśa, and Kṛṣṇa will not (= should not) blame one after that* ; p. 180, হাথ দিতে লিহে কলিআ « hāthā ditē lihē kaliā » *the black (stain) will smear (itself) on placing the hand* ; p. 251, কেহো ববে বেকত করিহে এহা কাজ । আন্ধার বাঁধার তবে তোকে পাইবে লাজ ॥ « kēhō jābē bekātā karihē ēhā kājā, āmhārā khākhārā tābē tōmhē pāibē lājā » *when someone will make this affair known, then (there will be) blame for me, and you will have shame* ; p. 267, নিষধ রাধাক বতনে ॥ আর বার হেন না করিহে । পুরুষের আখি নিবরিহে ॥ « niṣādhā Rādhakā jātanē : āra bārā hēnā nā karihē, puruṣērā ākhi nibārihē » *carefully forbid Rādhā, that she will not do like this again, she will avoid a man's eyes* ; p. 323, শুণিআ কি বলিহে বলভদ্র ভাই « śuṇiā ki bulihē Bālābhādrā bhāi » *what will brother B. say on hearing (this) ?* ; p. 324, শুণী সব দেব গণে কি বলিহে আন্ধারে « śuṇi sabbā dēbagāṇē ki bulihē āmhārē » *what will all the gods say to me hearing this ?* ; p. 336, ববে কাহ না মিলিহে করমের ফলে । হাথে তুলিআ মো খাইবো গরলে ॥ « jābē Kānbā nā milihē kārāmērā phālē, hātē tuliā mō khāibō garālē » *if, through the fruits of karma, Kṛṣṇa will not be obtained, then I shall eat poison with my own hands* ; cf. Kṛttivāsa, 'Uttarā-kaṇḍa,' p. 59, column 117, আইসুক ভুগুরাম তবে সি প্রাণ জাইহে « āisukḥ Bhṛgurāmḥ, tābē si prāṇḥ jāihē » *let B. come, then indeed life will depart*.

The « -itavya » > -b- » Future in NIA.

697. The characteristic suffix for the future base in Bengali as well as Assamese and Oriyā is « -ib- », = « -ab- » of Bihārī and of Eastern Hindi. About the origin of this affix, there is no difficulty: it comes from the OIA. future passive participle gerundive in « -tava- » or « -itavya », in Second MIA. « -(i)avva-, -(i)abba-, -ēbba » and other



forms (Pischel, 'Gramm. der Pkt.-sprachen,' § 570). This affix does not occur in the Rig-Veda, and it is rare in other Vedic literature: it is a new formation, and replaces the Vedic gerundive «-tua» or «-tva». In MIA. and in Classical Skt. it became much more evident. In Early MIA. it has the force of an imperative: *e.g.* Aśōkan, Rock Edict I Girnar, «na prajuhitavyaṁ na ca samājō katavyō»; Sarnath, «iyāṁ sāsane viṁṇa-payitaviyē», etc., etc. There is here a vague mandatory sense, with an express future implication. The simple future notion evolved gradually; side by side with it, the old notion of an action which is to be done continued, and was modified into simply the notion of an act. In NIA. both the uses of this form occur: as a future passive participle (which finally became the future tense), and as a verbal noun. Thus, Gujarātī has verbal nouns in «-vū», «karvū = kariavvaṁ, \*karitavyakaṁ, kartavya-kam», Rājasthānī (Mārwarī) in «-bō», «mārabō = \*māriabbaṁ, māritavyakam», and Western Hindī (Braj-bhākhā) «māribaṁ, māribau», (Kanaūjī) «māribō»; Marāṭhī has a subjunctive base in «-āv-», *e.g.*, impersonal «myā uṭhāvē» *I should rise*, lit. *it is to be risen by me* (= \*mayā ut-sthātavyam), active «mī uṭhāvā»; and the Eastern languages, Eastern Hindī, Bihārī, and Bengali-Assamese and Oṛiyā, have the verbal noun in «-ab-, -ib-» as well as «-ab-, -ib-» as the base of the future tense, with personal terminations added.

As it has been noted before, the «-(i)tavya- > -iabb- > -ib-» is not a native *tbh.* form in the East (*supra*, pp. 374, 375, 486-487). In the Eastern dialect, whether 'Old Ardha-Māgadhī' or 'Old Magadhī' of the First MIA. stage, as we can see from Aśōka inscriptions, OIA. «-vya-» became «-viya-», not «-vva-» (as for instance at Girnar). This First MIA. «-viya-» could only give «-vī, -i, -i» in the Modern Prācya languages. The change «-(i)tavya > -(i)abba» is a later, post-Transitional MIA. feature in the eastern dialects, and «-iabba» is either a *semi-tatsama* form introduced from Sanskrit in the Transitional period (before the softening and final dropping of the intervocal «-t-» in «-itavya» was carried out), or was an imposition from some Western dialect which normally changed «-vya-» to «-vv-» and then to «-bb-».

The «-(i)tavya» > «-ib-» was originally a verbal adjective, and the construction with a transitive verb was in the passive, the «-ib-» form qualifying the object in that case. This old usage is still in force in OB., as in the examples from Caryā 29 below.

Cases of «-ib-» future in OB.: Caryā 5, «tumbhē hōiba» (= yuṣ-mābhir bhavitavyam); 7, «kariba nivāsa» (= nivāśaḥ kartavyaḥ); 10, «tōē sāma karibē (= ? kariba; ? < kariabbaī = \*kariabbaē = kartavyakāḥ) ma (= maī) sānga» (= tvayā samatṁ kartavyō mayā sangāḥ); 14, «jāiba puṇu jīṇaūra» (= yātavyaṁ puṇaḥ jīṇa-puram); 23, «tumbhē jāibē»; 28, «lōḍiba» (= Comm. «anvēṣayitavyaḥ»); 29, «maī dibi pīricebā» (= mayā dātavyā pīcehā: dibi = \*diabba, + fem. -ī); 36, «kariba»; 39, «thākiba, khāiba maī»; 40, «kahiba» (kathayitavyaṁ); etc.

It will be noted that in the Caryās, the form is «-ib-», and not «-ab-» as in Central and Western Magadhan, showing that the language of the poems belong to the East Magadhan group. Like «-illa-: -alla-», this affix, «\*-iabba, \*-iēbba, \*-ēbba» in Mag. Ap., ranged itself into two groups «-ibba-: -abba-», the Eastern Magadhan speeches adopting the former.

The affix for the 1st person future in many Bengali dialects (both in MB. and NB.) show «-m-», as «mā, -mu», and «-ṇ- = -ṣ-» as «-ṇā, -ṇ», instead of «-bā, -bō, -bū, -bō, -bōhō». This is merely a phonetic change, a softening of «-b-» in connexion with the nasal to «-ṣ-, -m-», which has been discussed before (pp. 531-532). This «-m-» has been wrongly referred to the Sanskrit affix «-maḥ» for the 3 pers. plural indicative present by some Bengali writers on Bengali philology.

#### [G] PERSONAL AFFIXES

##### [I] ACTIVE (KARTARI), PASSIVE (KARMAṆI) AND IMPERSONAL (BHĀVĒ) CONSTRUCTIONS (PRAYŌGA) IN NIA.

698. The personal affixes of the present or radical tense in NIA. are the phonetically decayed forms of those of OIA. Affixation for the participial tenses is a NIA. development. The future in Bengali and other



Magadban languages, and in NIA. generally when it is of participial origin, followed the fortunes of the past. The formation of the past tense in typical NIA. of the first few centuries of the 2nd millennium A.C. agrees in principle with that of MIA. But subsequently, or it may be from the very beginning of the NIA. stage, there were new developments in some of the various groups of IA. The central language, W. Hindī, together with Eastern Panjābī, is most conservative, and has resisted innovations in the formation of the past, keeping true to the MIA. principle. The past tense in these speeches retains its MIA. character as the passive participle adjective qualifying the nominative when it is intransitive, and the object when it is transitive, the subject in the latter case being in the instrumental—the past of the transitive verb being thus a true passive albeit the construction of the phrase in nominal. Besides these active (intransitive) and passive (transitive) constructions for the past (◀ kartari ▶ and ◀ karmaṇi prayōgas ▶), the central speech has preserved (though dialectally) the old neuter or impersonal construction (bhāvē prayōga) for the intransitive verb, and has further extended this neuter construction to the transitive verb (cf. LSI., IX, pp. 50-52). Thus, OIA. ◀ Kṛṣṇaḥ calitaḥ (calitakaḥ) ▶ > MIA. ◀ Kaṇhō caliaō, Kaṇhu caliaū ▶ > NIA. (W. Hindī, Braj-bhākhā) ◀ Kāṇha calyau ▶ (Active Construction); OIA. ◀ Kṛṣṇēna pustikā paṭhitā, \* Kṛṣṇa-karṇēna pustikā paṭhitikā ▶ (= MIA. idiom with instrumental postfix ◀ -karṇa ▶ and feminine in ◀ -ikā ▶) > MIA. ◀ \* Kaṇha-(k)añṇē(ṇa)m pōtthiā paḍhiā (paḍhiā), \* Kaṇha-añṇēm, Kaṇha-añṇahī pōtthia paḍhia ▶ > NIA. (Braj-bhākhā) ◀ Kāṇha-ṇai, -nē pōthī paṛhī ▶ (Passive Construction); OIA. ◀ Kṛṣṇēna (\* Kṛṣṇa-karṇēna) calitam (calitakam) ▶ > MIA. ◀ Kaṇha-(k)añṇē(ṇa)m caliaam, caliaum ▶ > NIA. ◀ \* Kāṇha-nē calyau ▶, not found in Standard Hindōstānī or Braj-bhākhā, but occurring in Vernacular Hindōstānī (Neuter Impersonal Construction); and on the basis of this last, a new formation with transitive verbs (Impersonal Construction with the Transitive Verb) was established in NIA., as in W. Hindī (Braj-bhākhā): e.g., ◀ Kāṇha-nē Rāhī-kaū dēkhyau ▶, of which the OIA. translation, word for word, would be ◀ Kṛṣṇēna Rādhikāyāḥ-kṛtē dṛṣṭam ▶ for ◀ Kṛṣṇēna Rādhikā dṛṣṭā ▶.

This MIA. principle of « karmaṇi, karttari » and « bhāvē » constructions, together with the NIA. extension, is substantially preserved in Rājasthānī, in Gujarātī, in Marāṭhī, in Western Panjābī, and in Sindhī, despite certain innovations. Rājasthānī in general agrees with W. Hindī, but its congener Gujarātī has confused the transitive impersonal construction with the transitive passive one, by making the past participle form qualify the object in the former construction as much as in the latter : e.g., « tēṇē rāṇīnē jōī » *by-him with-reference-to-the-queen she-was-seen*, instead of « jōyū » *it-was-seen*. In this confusion some Rājasthānī dialects agree with Gujarātī.

Marāṭhī despite its affixing « -l- » to the passive participle has on the whole kept true to the MIA. standard : it has the active construction with intransitive verbs, and the passive with transitive ones, besides the impersonal with transitives. Its great innovation is adding personal affixes to the intransitive verbs (and following that, to some transitive verbs also : LSI., VII, p. 26), by which the past intransitive (also transitive in some cases) has become a regular inflected active past form, as much as in the Sanskrit perfect aorist or imperfect, or in the Bengali « -il- » past. Thus, « mī uṭhal-ō » for « mī uṭhalā » *I rose* (i.e. « aham utthita-laḥ + mē, mayā », instead of « aham utthitalaḥ = utthitaḥ », active), « myā rāṇī pāhīlī » (= « mayā rāṇī dṛṣṭā », passive), but « myā rāṇī-s pāhīlē » (= « mayā rāṇī-viṣayē dṛṣṭam », impersonal). The extension of the active construction to the transitive verb in some cases (e.g., « mī bōlalō », or « bōlilō, bōlilā » *I said*, as in the 'Jñānēśvarī,' instead of the passive « myā bōlalā, bōlālī » etc. or impersonal « myā bōlalē ») shows that the old system has not been kept intact.

The Pahārī speeches on the whole agree with W. Hindī, and in some cases with Rājasthānī-Gujarātī in mixing up the impersonal and the passive. The Eastern Pahārī speech, Khaskurā, on the other hand shows a mixing up of the passive and active, by putting the subject in the instrumental, and the passive participle instead of qualifying the object is conjugated like a verb, taking affixes corresponding to the subject : e.g., « mai-lē pāp garō (garyē, garyā = garya- < karia, \* karita, kṛta + mē) »



*I sinned*, lit. *by-me sin done-by-me* or *did-I*). The MIA. principle is thus obscured here. (Cf. LSI., IX, pp. 26, 37, 147, 294, 328, 398-399, 466, 489, 572, 678, 695, 727, 783, etc., etc.)

The languages of the extreme west, W. Panjābī and Sindhī, both maintain the adjectival character of the passive participle, modifying it according to the gender and number of the object. But at the same time W. Panjābī employs pronominal affixes to emphasise the proper subject of the transitive verb (really instrumental), in addition to that of the intransitive; and Sindhī regularly adds these affixes to the intransitive (cf. LSI., VIII, Part I, pp. 270-271, and Trevor Bomford, 'Language spoken in Western Panjab,' JASB., 1895, p. 317, for W. Panjābī; LSI., VIII, Part I, pp. 67-68, for Sindhī). The use of pronominal suffixes in these western speeches is not confined to the passive participle only, but to other forms of verbs, and to nouns as well (LSI., VIII, Part I, pp. 42, 261), and is a special development in these, which is unknown to other cognate NIA., or to MIA. and OIA. The affixed pronoun in the passive participle or verb past base is to some extent necessitated in these speeches to ensure definiteness of the subject, as the instrumental post-position is frequently dropped (as in Panjābī, both Western and Eastern), or is non-existent (as in Sindhī, in which the oblique is employed for the instrumental). The affixation is merely formal, and does not imply any alteration in the old passive conception of the transitive past.<sup>1</sup>

<sup>1</sup> The use of the pronominal affix with nouns (e.g., W. Panjābī 'ghar-am' 'my house, Sindhī 'piu-mē' 'my father'), as well as dative and accusative use of the affixed pronouns (e.g., W. Panjābī 'Sahiban mut-ēi khatt' 'S. has-sent-to-thee a-letter', 'kitu-s mōpā' 'he-made-it fat', 'bukhār hi-s' 'fever is-to-him', etc.) in these western languages, as well as in the extra-Indo-Aryan (Dardic) Kāśmīrī, resembles the Iranian enclitic pronouns which one finds, e.g., in Persian, in Paštō, and in Balōc (cf. Geiger's 'Grundriss der iranischen Philologie': O. Salemann, 'Mittel-persisch,' p. 291; P. Horn, 'Neu-persische Schriftsprache,' p. 118; Geiger, 'Die Sprache der Afghanen,' p. 217; 'Die Sprache der Balutschen,' p. 240). The whole of the Indo-Iranian area from Persia right up to the frontiers of the old Saurasēni (W. Hīndī) area,—including the W. Panjābī (and probably also E. Panjābī in early times) and Sindhī tracts (among areas occupied by the NIA. speeches), the Dardic tracts, and those occupied by the Iranian speeches—seems to have been an area where

699. In the Magadhan languages, as well as in Eastern Hindi, on the other hand, the construction has become purely active, and the old MIA. principle has been completely ignored. The subject of a past sentence is in the nominative now at the present day, whatever might have been its nature originally. Traces of an instrumental affix may be found in the subject (e.g., « -ē » in Assamese and Bengali), but the instrumental idea is now entirely absent. The personal forms, which (as in Sindhī and W. Panjābī) doubtless originally emphasised the instrumental-nominative, have in the Eastern languages lost their enclitic, emphasising character—have become personal inflexions pure and simple. Judging from indications in the earlier as well as later phases of these eastern speeches—OB., MB., NB., Early Maithilī, etc., as well as Early Awadhī and Modern Awadhī, and from comparison with other NIA. speeches and with the habits obtaining in MIA., we can surmise that the personal affixes were not added to the past passive participle (and to the future passive participle) in Māgadhi Apabhraṇśa, and that this affixation was not indispensable in the early stage of the neo-Māgadhan speeches. Thus, Māg. Ap. in all likelihood had « \*haū (? haī), tūm, sē calilla(a) » (= aham, tvam, saḥ calitāḥ) and « \*amhi, tumhi, tē calilla(a), calillahi » (= vayam, yūyam, tē calitāḥ), beside « \*maī, ambahī, taī, tumbahī, tē, tēhī rāa dēkkhilla(a) » (= mayā, asmābhiḥ, tvayā, yuṣmābhiḥ, tēna, tāiḥ rājā dṛṣṭaḥ), and « \*maī, ambahī, taī, tumbahī, tē, tēhī raṇṇī dēkkhillī » (= mayā, asmābhiḥ, tvayā, yuṣmābhiḥ, tēna, tāiḥ rājā dṛṣṭā). Beng. made the first « xui, āmi, tui, tumi, sē, tēhā calila » and « mui etc. rāya, rājā dēkhila (rāṇī dēkhili) » and then by affixation, « mui dēkhil-i, -ā-hō, -ō, -ū, -ām; tui dēkhil-i, -is;

the old Aryan enclitic pronouns were retained as living forms, and were later turned into suffixes: and these suffixes therefore were different in origin from the personal affixes of the Eastern languages (e.g., OIA. 'mayā kṛtam, kṛtam mayā, kṛtam mō' > Lahndā 'kitu-m'; Old Persian 'mana kartam' > Middle Persian [Pahlavi] 'man kart, am kart,' and 'kart-am' > New Persian 'kard-am': [cf. Horn, *op. cit.*, p. 148]: compared with this, Early Bengali মূই কৈলুম 'mui kailum' I did is a different thing, originating in NIA. times from 'maī kailla'; and Hindi 'main-nō kiya' is of course entirely different, showing no kind of personal or pronominal affixation).



tumi dēkhlil-a, -āhā; sē dēkhlil-anti, -enta, -ēn, -āin, -āñi (calil-i, calil-āhō etc.) >. (Besides, the < bhāvē prayōga > with the object in the dative with < -kē > etc. was evolved: see *supra*, pp. 897-898.) Affixation was not fully established in Bengali even in the 15th century, as we can see from MB. literature, where the base form in < -ilā > is frequently used for all persons: and in fact, in some dialects even now the base form is used for the third person (*e.g.*, Standard Bengali < sē dēkhlilā >, Dacca < sē dēkhlā, dēkhlō >, *he saw*, base only, but Calcutta Bengali < sē dēkhl-ē > with < -ē > suffix for the third person; so Dacca < sē kāirbā, kōrbō > *he will do* beside Standard < sē kārib-ē >, Calcutta < sē kōrbē >). Similar affixation has taken place in other Magadhan, and in Eastern Hindi (*e.g.*, Awadhī: 1. < dēkhēū, dēkhiū, *pl.* dēkhlī, dēkhā, dēkhan, dēkhēn >; 2. < dēkhisi, dēkhēs, *pl.* dēkhēn, dēkhā, dēkhlī >; 3. < dēkhisi, dēkhai, *pl.* dēkhin-i, dēkhēn > etc.).

Pronominal affixation apparently was carried on independently in each of the various groups of dialects in the Magadhan area,—in West Magadhan (Bhōjpurīyā), in Central Magadhan, in the various Bengali and Assamese dialect groups, in Oṛiyā. But some common tendencies were shared by all or most of them. The most remarkable development has been in Central Magadhan (Maithilī and Magahī), which display a greater richness and variety in the matter of pronominal affixation than any other NIA. language—by which two or even three pronominal forms can be tagged on to the verb base. Thus we have Bengali মারিলাম্, ‡ মারিলুম্ or ‡ মারিলি < mārīl-ām, ‡ mārīl-um, ‡ mārīl-i > *I, we beat* (past), = Oṛiyā < mārīl-i, mārīl-ū >, Assamese < mārīl-ō >, Bhōjpurīyā < mārāl-i >, Maithilī < mārāl-ahū, mārāl-i >; but also we have Maithilī < mārāl-i-au-k > *I struck you*, or < mārāl-i-ai-nhī > *I struck him or them* (honorific object). We have here practically cases of polysynthesis, of long sentence words resulting from affixation. In this matter there may have been a strong influence of Kōl on Central Magadhan in the formative period of Maithilī and Magahī: with forms like < mār-al-i-au-k > or < mār-al-i-ai-nhī >, we can compare Kōl (Muṇḍārī) < om-ad'-iñ-ae > *he-gave-it-to-me* and < lel-k-iñ-ako > for < \*lel-ked'-iñ-ako > *they-saw-me*. The affixation in Eastern Magadhan is simpler, and approximate rather than of modern Dravidian

(e.g., Bengali. « pāṛ-il-ām » *I read* = Tamil « paṭ-itt-ān », root + tense affix + personal termination: see *supra*, p. 175).

700. Grierson, in two noteworthy papers to the JASB. for 1895 ('Suffixes in the Kāçmīrī Language' and 'Radical and Participial Tenses in the Modern Indo-Aryan Languages') has tabulated the various affixes of NIA. and suggested their etymologies. The Eastern languages have these affixes for the verb past tense, and the future tense; the Western languages have also the pronominal adjuncts; the Southern language Marāṭhī partially employs them. All this is opposed to the Midland language, W. Hindī. In this Grierson finds a point in support of the theory of Inner and Outer Indo-Aryan groups (see *supra*, *Appendix A to Introduction*, pp. 165-166; JASB., 1895, p. 351). But the conjugational system cannot be assumed to prove much, as has been said before. The languages started in the East without the personal terminations, and in later times only they entered into the habit of affixation; whereas it seems likely that in the Western languages the enclitic has persisted from OIA. times (or might have been due to the influence of the contiguous Iranian), and were at once the cause and the effect of the absence or rare use of the instrumental post-position. Grierson derives all the affixes of the past verb in Bengali etc. (equally with those in other languages) from pronouns. But in some cases at least, they were merely extensions of the affixes of the present or radical tense. Bengali, Assamese and Oṛiyā, again, show a development distinct from Maithilī, Magadhī and Bhōjpuriyā within the Magadhan family.

Except in the 3 sg., there is no distinction in Bengali-Assamese in the affixes of the intransitive and transitive verbs past tense. In Oṛiyā, the same affixes, sg. « -ā », pl. « -ē » are found for the verbs of both the kinds.

The affixes may now be discussed.

## [II] AFFIXES FOR THE PAST TENSE.

701. MB. and NB. forms are given below. The affixes are added to the base in ईत् « -il- » of which the « -i- » is dropped in most NB. dialects after influencing the preceding vowel.



*First Person* : অ < -ā > ; ই < -i > ; উম্, উঙ, উঁ (নুন্, নুঁ > হ), ওম্, অম্, ওঁ, ওহোঁ, আহোঁ, ওহো, আহো, ও < -um, -uṅ, -ū ( -lum, -lū > -nu), -ōm, -ām, -ō, -ōhō, -āhō, -ōhō, -āhō, -ō > ; আম্, আঙ, এম্ < -ām, -āṅ, -ēm > ;

*Second Person* : অ < -ā > ; ই < -i > ; ইস্, এসি, এস < -is, -ēsi, -ēs > ; উ < -u > ; আ, আহা < -ā, -āhā > ; এ, এঁ, এহেঁ < -ē, -ēi, -ēhē > ;

*Third Person* : no affix, simply ending in -ইল্ < -il > ; অ (ও) < -ā, (-ō) >, for both transitive and intransitive verbs ; আ < -ā > ; এ < -ē > for transitive verbs only, dialectally ; আক্, ওক্, এক্ < -ā-k >, -ō-k >, -ē-k >, for both transitive and intransitive verbs ; besides অস্তি, আস্তি, অস্ত, আস্ত, এস্ত, এন, আইন, আতি, আই < -ānti, -ānti, -āntā, -āntā, -ēntā, -ēntā, -āinā, -āni, -āi >, honorific.

Standard NB., literary and colloquial, recognises only the following :—

*First Person* : আম্ < -ām >, colloquially also এম্, উম্ < -ēm, -um >, and in poetry occasionally হু < -nu > ;

*Second Person* : non-honorific, ই < -i > ; ordinary, এ < -ē > ; poetical আ < -ā > ; honorific এন < -ēn > (with আপনি < āpāni >) ;

*Third Person* : অ < -ā > ; এক্ < ēk > (rather archaic) ; এ < -ē > dialectally for transitive verbs ; poetical আ < -ā > ; besides honorific এন < -ēn > .

### (1) THE AFFIXES FOR THE FIRST PERSON PAST.

**702.** The affix অ < -ā >. This is the simple base form, and is found in MB. and OB. : আমি চলিল < āmi cālilā > *I went*, আমি, মুই রাখিল < āmi, mui rākhilā > *I kept* ; cf. OB. Caryā 35 < māi bujhilā > *I understood* (see *supra*, p. 808). The source of this ইল < -il > is Māgadhi Ap. < -illāa, -illāwa (< -ila-ka) >, MB. < -ilā, -ilā >, in NB. pronunciation often ইলো < -ilō, -lō >. This simple base is not found in NB., although it is common in eMB., becoming less common in lMB., and found but infrequently in post-17th century MB. As indicated above, the absence of affix means preservation of the OIA. conditions.

In OB., the < -ila > base had a feminine for < -ilī, -ilī >, according as the subject of an intransitive verb or the object of a transitive one was feminine. Early MB. carried on this feminine affixation, but it has died out from eMB. times. Examples have been given above, p. 958.

703. The affix ই «-i». This is now confined to the dialects of West Rāḍha, and to 'S.-W. Bengali,' and in any case is regarded vulgar. It was fairly common in MB. It seems originally to have been a (West) Rāḍha form. Although used for both singular and plural, the evidence of Oṛiyā shows it to have been originally singular: Oṛiyā «mū āsil-i», pl. «āmbhē āsil-ū» *I came, we came*; «mū dēkḥil-i, āmbhē dēkḥil-ū» *I saw, we saw*. The affix seems only to be an extension of the present (singular) «-i» to the past tense (*supra*, pp. 934, 935).

704. The affixes উম্, উঙ, উ (ম্, ন্ > হ্) ওম্, অম্, ওঁ, ওহৌ, আহৌ, ওহো, আহো, ও «-um, -uṅ, -ū, (-lum, -lū > -nu), -ōm, -ām, -ō, -ōhō, -āhō, -ōhō, -ō». These form one group, and in their formation, two affixes seem to have converged: the «-ō» of the present (=OB. -aŵa < MIA. -ama < OIA. -āmaḥ: *supra*, pp. 934-935), and the old first personal pronoun nominative «\*haū, hāu» as in OB. (pp. 807-808 *supra*) agglutinated to the past base (in «-ilā, -ilā»); «\*haū» seems to have been added to the present base (see *supra*, p. 934), and an extension of it to the past was a matter of course. Of the fuller forms, ইলাহৌ «-ilā-hō» occurs in eMB. (as in the ŚKK.), and ইলোহৌ «-ilō-hō» is found in the Early Assamese; and this and \*ইলহৌ «-ilā-hō» seems also to have occurred in MB. and the other forms, with loss of nasalisation, are found in MB. and Early Assamese. As can be expected, «\*haū > hō» as the nominative pronoun should occur with the intransitive verb; and that is what we find from eMB. In the ŚKK., the ইলাহৌ «-(ilā-)hō» form occurs with six verbs, all intransitive: আছিলহৌ «āchilāhō» *I was*, আইলাহৌ, আরিলাহৌ «āilāhō, āyilāhō» *I came*, জিলাহৌ «jilāhō» *I lived*, পড়িলাহৌ «pāṛilāhō» *I fell*, বাঢ়িলাহৌ «bāṛhilāhō» *I increased*, হরিলাহৌ, হৈলাহৌ «hāyilāhō, hāilāhō» *I was* (to which we may add a seventh intransitive form showing «-hō», although in a different tense—মরিতাহৌ «maritāhō» *I would die*): Kṛtti-vāsa similarly has তপ্তা করিল আমি নহিলাহৌ অমর «tāpasyā kārila āmi, nāhilāhō āmarā» *I performed austerities, but did not become immortal* ('Uttarā-kāṇḍa,' p. 29); নিমন্ত্রণে গেলাহৌ «nimāntrāṇḍe gēlāhō» *I went to an invitation* (ibid, p. 15); also হইলাহৌ «hāilāhō» (pp. 26, 30, 36). MB. «jilāhō, pāṛilāhō» etc. would thus agree with Skt. «jivitō'ham, patitō'ham».



The ŠKK. uses «-ḥ̃» (at times «-ḥ̄» by dropping the nasalisation) with both transitive and intransitive verbs. This apparent complay of the full «-h̃» form with intransitives only was not maintained in Assamese: in the Early Assamese of the 15th and 16th centuries, we find it employed with transitive verbs also—e.g., Dēvēndra Nāth Bēz-baruwā, 'Asamiyā Bhāṣā Ārū Sāhityar Burāñji,' Jorhat, Saka 1893, pp. 75, 173, «kārīlōh̃» *I did*, p. 89, «lābhilōh̃, pāṛhilōh̃» *I received, I studied*, p. 138, «cinilōh̃» *I recognised*, p. 169, «bulilōh̃» *I said*. In Early Maithili, the corresponding «bū» form seems to be restricted to the intransitive: e.g., Vidyāpati has «bhēlihu» *I was*, «mōñē cukalihu» *I ceased*, «achalihū» *I was*, «gēlihu» *I went*, etc. (Pada 63); but in later Maithili, «-hū» is found for both the kinds of verbs. It has apparently become «-ñ̄» in Magahi. From the 14th century, the «-h̃» and the «-ḥ̃» forms had merged together, and the former occurs in the ŠKK. as a survival only (e.g., for one «āchilāh̃» there are some six cases of «āchil̃»; «āñl̃» occurs 11 times beside «ā(y)ilāh̃» 9 times, and other intransitive verbs show only the «-ḥ̃» form). The Oriyā «-ñ̄» of the plural seems to represent the «-ḥ̃ (<-āmaḥ)». The OB. «acchil̃» (see *supra*, p. 808) seems to be scribe's error for «āchila», or it might be for «āchil̃»; in the latter case, the affixation for the past in imitation of the present could be said to have begun from OB. times.

The form «-ilāh̃» thus converged into «-il̃», but «-ilāh̃» could also give «-ilāw̃», and these would easily result in the MB. and NB. forms «-ilū, -iluṇ, ilum, -ilōm, -ilām, -inu» etc., since in MB. «m» final and intervocal interchanges with «w̃», written «ṇ»; and MB. forms like «-il̃, -ilū» could develop the off-glide «w̃» (-il̃w̃, -ilūw̃), which would easily resolve into «m».

705. The affixes आमि, आते, एम् «-ām, -āṇ, -ēm». It is not unlikely that «-ām» has partly evolved from «-āh̃» as above («-ilāh̃ > -ilāw̃, -ilāw̃ > ilāṇ, -il-ām»). But this «-ām» should rather be affiliated to आमि «-āmi» *I (we)*, affixed to the past base, for this reason that in all the spoken dialects, where «-ām» occurs, the «-m» is retained intact, and there is no trace of a nasalised form «\*-il̃» or «\*-iñ» such as

we might expect to be present in MB. or NB. if « \* -ilāw < -ilāhō » were the only source.

By Vowel Harmony, « -ilām » gives « -ilēm », which is regarded as a refined form, and is frequently used in literature and formal discourse.

**706.** A plausible etymology for the « -āmi, -ām » affix would be the OIA. substantive verb « asmi »: the use of the passive participle with « asmi » in the active sense is found in MIA. and medieval Skt. (e.g., « viditō'smi, vismṛtō'smi » etc.: cf. E. J. Rapson, 'Specimens of the Kharoṣṭhī Inscriptions discovered by Dr. Stein at Niya in Chinese Turkestan: Tentative Transcriptions and Translations,' British Museum, 1903, p. 7). The Sinhalese past tense is formed on the same plan by affixing forms of « √ as », present tense, to the passive participle (Geiger, 'Litteratur u. Sprache der Sinhalesen,' § 60). The same method seems to occur in the Bengali perfect tenses (see *infra*, 'Compound or Periphrastic Tenses'). But « asmi » does not occur as « āmi » either in Bengali or in other Magadhi: the equivalents of « asmi » in Bengali are « āchi » (\*acchāmi) and « hāī » (\*asāmi). A source like « paṭhita + asmi » is untenable for the NB. « paṭilām », not only because of the non-continuance of OIA. « asti, asi, asmi » in Bengali, but also because of the fact that personal affixation is late in the language, and is either pronominal, or is by analogical extension of affixes from the present.

Hoernle explained the « -ām » affix as being the Skt. « -āmi », present sg. affix: according to him, Bengali has preserved the original present indicative termination « -āmi », in forms like « pāṭ(h)ilām » = Māgadhī « \*paṭhidāmi ». But this derivation is inadmissible: MIA. « -d- » does not become « -l- » in Bengali (see *supra*, p. 433), and « -m- » intervocal of OIA. occurs in NIA. only as the nasalisation of the contiguous vowel.

## (2) THE AFFIXES FOR THE SECOND PERSON, PAST.

**707.** The affix 𑀅 « -ā » is the simple base form without any personal termination, found in MB. for the 2nd person as much as for the other two persons, but is now obsolete.



The affix  $\text{ই}$  «-i» is of obscure origin. It occurs with the past in «-il-» and in the future in «-ib-». It is not found in the radical tense and with the past conditional. Bengali-Assamese alone among Magadhan speeches has it. The fact that it is contemptuous, being used with the familiar «tui (tōrā)» form of the 2nd personal pronoun, shows that it was originally a singular affix. The corresponding affix in Oṛiyā is «-u», e.g., «tu thil-u» *thou wert*, «tu dēkhal-u» *thou didst see*. The Central Magadhan languages have confused the plural and singular; but it seems that the 2 pers. affix «-ē» in Magahī (as in «hal-ē» *thou wert* or *you were*, «dēkhal-ē» *thou didst see* or *you saw*, beside «halē, dēkhal-ē»; Maithilī does not possess the «-ē» form, but the nasalised one only) and in Bhōjpuriyā (as in «dēkhal-ē, dēkhal-as» singular, «dēkhalāh < \*dēkhalahu» plural) is connected with the Bengali «-i», it being exceedingly probable that the «-ē» was formerly «-a-ī» (cf. Maithilī «dēkhalāi» beside «dēkhalē, 2 personal forms).

There is the other singular 2 personal affix «-is, -s» (see p. 979 below) with which the «-i» cannot be connected. In the absence of any other indication as to its source, it can only be referred to the 2 sg. imperative in «-hi, -a-hi» (see *supra*, p. 904), which would give «-i, -ai (-ai, -ē)» by loss of «-h». The Oṛiyā «-u» similarly can be best explained as the 2 sg. imperative in «-hu» (*supra*, p. 906). This «-hi» lost its original function as an imperative affix, and became associated, first, it would seem, with the future base, and then with the past: we should note that «-i» is the only 2 personal contemptuous or singular affix for the future, whereas «-is» may be used for the past; and «-i» is not found with the past habitual («cālib-i, dib-i», but «chil-is» beside commoner «chil-i», and «cālit-is, dit-is»; but we never find «cālib-is, dib-is»): this apparently shows that «-i» became first definitely attached to the future base, and then it was extended to the past; and the use of the future and the imperative should be taken into consideration in this connexion. There is an «-ahi» affix (< OIA. -asi) for the 2 sg. present tense in Western Apabhraṃśa, whence the imperative «-ē, -āi» affix in the Western languages, e.g., Hindōstānī «tū kar-ē» Gujarātī «tū

kar-ē », and Mārwarī « t(h)ā kar-āi » (< tū kar-ahi); but this present « -ahi » apparently did not occur in Māg. Ap., and is not represented in Bengali, which has only « -as, -is » < « -asi ».

708. The affixes ইস, এসি, এস « -is, -ēsi, -ēs » are contemptuous in sense, being used with « tui, tōrā », and were consequently originally singular. They represent the OIA. « -asi » which is preserved in the radical tense. The affix « -asi » has been partly extended to the past base, but the future did not take it up, apparently deciding for the « -hi > -i » from the imperative. The forms « -is » etc. are exceedingly rare with the past tense in NB., the employ of it with the « -il- » past being only occasional. MB. instances also are rare. In NB. it may be used with the past of « √āch » *to be*, as ছিলিস « chil-is » *thou wert*, both by itself as well as in the past progressive and perfect tenses, e.g., যাচ্ছিলিস « jācchilis » *thou wert going*, গিয়েছিলিস « giyēchilis » *thou hadst gone*, দিয়েছিলিস « diyēchilis » *thou hadst given*; but the « chil-i » form would be preferred. We may similarly occasionally hear নিলিস, দিলিস « nil-is, dil-is », but such forms would not be regarded as normal in the Standard Colloquial. It seems that analogy tried to attach « -is » to the past base, but has failed so far, although apparently this analogical use began early. We have thus in Kṛttivāsa ('Uttarā-kāṇḍa,' VSPd. ed., col. 124) ব্রহ্মবধ করিয়া তুমি লুকাইলিস ডরে « brāhmā-bādhaḥ kārīyā tumi lukāilīs dārē » *killling a Brahman, you hid in fear* (here we see the improper use of « tumi », instead of « tui », with an « -is » form). I have not found « -is » with the past in the ŚKK., but apparently there is one case in the Caryās, e.g., Caryā 37, « jāisanē acchilēsa taichana (= taīsana) accha » = ? *as thou wert, so be thou*; in Caryā 39, we have « baṅgē jāā nilēsi parē bhāgēla tōhāra biṇāṇā » *thy science (vijñāna) fled away after thou didst take a wife in Varāṇa*: here « nilē si » may be either an « -ēsi » form, or it is « nilē » (conjunctive in « -ilē ») + « si » emphatic particle, as in Caryā 20—« jāubaṇa mōra bhailē si pūrā » *on my youth being mature*. The « -ēsi » would thus seem to have been attached to the past as early as OB. The vocalism in « -ēsi, -ēsa » seems to be due to a combination of the base form in « -a » + « -isi » (see p. 935): « \*acchilla-isi » > « āchilais(i) » > āchilēs(a) ».



709. Grierson explained the «-i» as an instrumental pronominal enclitic: «mār-il-i» = *struck-by-thee* (karmaṇi prayōga), «cal-il-i» *gone-by-thee* (bhāvē prayōga); and the «-is» was explained by him (as an affix for the past habitual derived from the present participle) as being 'the direct pronominal suffix for the nominative'—«-s» and «-i» being respectively nominative and oblique forms of a second personal pronoun (JRAS., 1895, I, p. 371). There cannot be any question of a 2nd personal pronoun in «-s» from the existing specimens of IA., and Grierson considered this «-s» (as in Bengali «-is» in «mār-it-is» etc.) 'as a termination borrowed either from the first or the third person,' but at the same time the possibility of «-is» being the OIA. «-asi» is admitted by him (*op. cit.*, p. 374). The «-s» form of the first person occurs in Lahndā and Sindhi, and in the Dardic Kāśmīrī: it is a singular form, if derived from OIA. «asmad»; but the whole question is rendered extremely problematical (*op. cit.*, p. 365 for the «-s» for the 1st person). The use of the 3rd person «-s» (<Prakrit «sē» *his*, which is an enclitic: Grierson, *op. cit.*, p. 347) for the 2nd pers. is hardly more satisfactory as an explanation. The well-known «-asi» which has survived in the radical sense should not therefore be ignored. And as for regarding «-i» as an oblique form of the 2nd personal pronoun, and referring it to the MIA. «bhē» or «uyhē» (JASB., 1895, p. 374, p. 346), there is this great difficulty that in Bengali-Assamese, which alone preserves the «-i», the form is contemptuous and as such cannot originally have been a plural suffix, whereas the MIA. «bhē, uyhē» are definitely plural ones.

710. The affix উ «-u» is found dialectally in 'South-West Bengali' and in North Central Bengali, and is distinctly of Oriyā affinity: কৈলু «kailu» *thou didst do*, গালু = গেলু «gyālu = gēl-u» *thou didst go*, etc. It is singular in origin, and can only be referred to the imperative in «-hu, -u» (see above, p. 906). It is found in the present also, e.g., আছ «āchu» *thou art*.

711. The affixes আ, আছ «-ā, -āhā» were originally plural, being used with «tumi (tōmārā)», the old plural of the 2nd person, and never

with «tui». They seem to be the same affix as the «-aha» of the radical 2nd plural (see *supra*, p. 935). The past base to which this 2nd person pl. affix was added (in Bengali-Assamese) apparently was extended by the definitive «-ā»: «calilā + -aha > \*cālilāha, cālilāhā, \*calilāā, cālilā» (cf. «khāhā, jāhā» for the imperatives: *supra*, pp. 903, 907). The «-ā» might, again, be simply the base in definitive «-ā», without the personal termination «-āhā». The «-āhā» form occurs in eMB. (ŠKK.) and in Early Assamese side by side with «-āhā, -ā». Late MB. has only «-ā»; and as a result of Vowel Harmony, through influence of the «-i» of «-il-», this «-ā» can be altered to «-ē» in NB., as in the Standard Colloquial চ'লে «cōllē» < «cālilā» *you went* (*supra*, pp. 400-401). Among ŠKK. forms in «-āhā» may be quoted আছিলাহা «āchilāhā» *you were*, গেলাহা «gēlāhā» *you went*, পড়িলাহা «pārilāhā» *you fell*, হয়িলাহা «hāyilāhā» *you became*; cf. imperative ওলাহা «ōlāhā» beside ওলাহ «ōlāhā» *take down, put down*. In Modern Assamese, the affix is «-ā», honorific; and Oṛiyā has retained it as «-ā (< -āhā)». Cf. Maithili simple form for 2nd person past «dēkhalāh < dēkhalahū», and Bhōjpuriyā «dēkhalahū», where we have the «-ahu» form as in the imperative.

712. The MB. forms এ, এঁ, এহেঁ, «-ē, -ē, -ēhē» make one group. Judging from the ŠKK., the nasalised form «-ē» is the proper one for this affix, and this is only shortened from the older and fuller «-ēhē». In the ŠKK., it is either «-ēhē», or «-ē»: and it is rarely «-ē» without the nasalisation: thus আণিলেঁ, আণিলেহেঁ «āṇilē, āṇilēhē» *you brought*, এড়িলেহেঁ «ēṛilēhē» *you abandoned*, কইলেঁ «kailē» *you did*, কৰায়িলেঁ «kārāyilē» *you caused to make*, গঢ়িলে «gṛhilē» *you built*, নিলেহেঁ «nilēhē» *you took*, সাধিলেহেঁ «sādhilēhē» *you performed*, চাহিলেঁ «cāhilē» *you looked at*, etc. No instance of «-ē, -ēhē» with intransitive verbs occurs in the ŠKK.: originally it was probably used with transitive verbs. «-ēhē» > -ē > -ē is thus its development in NB. (Of course, in NB. the «-ē» can also be from «-ilā» by Vowel Harmony; see preceding paragraph.) This affix is unknown to Assamese and Oṛiyā. But Maithili «-ē, -āi», Magahi «-ē, -ahī» («dēkhalē, dēkhalāi; dēkhalē, dēkhalahī») seem to be the same affix.



The source of this «-ēhē, -ē, -ē» is obscure. The full form being «-ēhē», connexion with the Prakrit enclitic 2nd pers. pl. «-bhē, -uyhē» as suggested by Grierson (JASB., 1895, pp. 374, 346) is not impossible, but «bhē, uyhē» are otherwise unknown. It is a politer form than the «-i, -is» ones, both in MB. and NB. Is it that here we have the instrumental of the respectful or polite form for the pronoun of address «ahā, aha!», which is still current in Maithilī? (see *supra*, pp. 850-852). The fact of «-ēhē, -ē > -ē» not being found with intransitive verbs in the ŚKK. should be recalled: «āṇilēhē» can therefore very well be from MIA. «\*āṇilla-» + «\*ahāhī, \*abēhī» = instrumental pl. of «ahā-» (= OIA. āṇita-la- + āyuṣmadbhiḥ).

### [3] THE AFFIXES FOR THE THIRD PERSON, PAST.

713. The oldest Bengali had three forms for the passive participle as used with the pronoun third person or with the noun: «-ila (< -illa)», the simple base without any affix; «-ilāwa, -ilaa (< -illa-a, i.e., -illa- + -ka)», with an extension by the pleonastic «-ka > -a» (*supra*, pp. 652-653); and «-ilā (< -ila + -ā)», strengthened by the definitive «-ā» (*supra*, pp. 658 ff.). The NB. equivalents of these are respectively, ইল, ইল, (ইলো), ইলা «-ilā, -ilā (-ilō: MB. -ilā), -ilā». All the three are found: «-ilā» is dialectal, occurring in North Bengali and North Central Bengali (with both transitive and intransitive verbs), as well as in Eastern Vanga dialects (Sylhet, Kachar, Mayang, Chittagong and Chakma, where «-ilā» seems to be preferred with intransitive verbs); «-ilā» is also restricted to the intransitive verb in Modern Assamese; «-ilā» is found in the «sādhubhāṣā» and in the East Bengal dialects with both transitives and intransitives, and in the Standard Colloquial with intransitive verbs (see *supra*, p. 974); while «-ilā» is now archaic and poetic for NB., and is found commonly in MB. and in Early Assamese, and in Oṛiyā «-ilā» is the only form in which this affix occurs for the 3rd person singular («-ilā» however, occurs in Eastern Vanga, in Mayang as honorific, i.e. plural).

All these three forms «-ila > -ilā; -ilaa, -ilā > -ilā; -ilā» lack a personal or pronominal termination and this colourless form was accepted for

the third person. Doubtless there were slight shades of difference between the three; ‘-ā’ and ‘-ā̃’ forms were possibly more emphatic. Also the base form without any affix, ‘-ila > -ilā’, retained its old adjectival nature unmodified in connexion with intransitive verbs, and this distinction is largely maintained now. In the Caryās, we find both ‘-ila’ (= ‘-ila’ as well as ‘-ilaa, -ilāwa’) and ‘-ilā’ (see *supra*, p. 947).

714. The affix ‘-ē’: occurs in West Bengali (including the Standard Colloquial), North Bengali and Assamese, with transitive verbs only: e.g., Standard Colloquial সে চলল, সে গেল, [ʃe ʈʰollo, ʃe gælo] *he walked, he went*, North Bengali চলিল, গেল [tsolil, gəl], Assamese ‘si cālil, si gāl’, but for *he gave, he ate*, we have Standard Coll. সে দিলে, খেলে [ʃe dile, khele], North Bengali দিলে, খাইলে, খালে [dile, khaile, khale] besides দিল, খাইল [dil, khail], and Assamese ‘dilē, khālē’. The Bihārī dialects show a similar differentiation (see *supra*, p. 93). No such differentiation between intransitive and transitive verbs is found in the East Bengal dialects, in which typical forms would be [tsolʎlo, tsolʎo; gʎlo] and [dilo, khailo], or as in Chittagongese [tsolil, gəl] and [dilo, khailo].

The restriction of the ‘-ilē’ affix to the transitive verb past tense in a continuous tract embracing Rāḍha, Varēndra and Kāma-rūpa, and excluding Vangā (E. and S.-W.) and Caṭṭala (S.-E. Vangā), is noteworthy: equally noteworthy is the occurrence of the ‘-ila > -ilā’ for the intransitive in Varēndra (partially), in Kāma-rūpa, and in E. Vangā and Caṭṭala. The ‘-ē’ affix occurs in the future 3rd person (-ib-ē) for all verbs, in the both ‘sādhū-bhāṣā’ and in the Standard Colloquial, but not in East Bengal dialects, in Assamese, in Oṛiyā, which use the ‘-ā’ (-ibā, -bā). The usage in the future does not help us here.

The explanation seems to be as follows. The intransitive past is in its origin a verbal adjective qualifying the subject: here no special verbal suffix was necessary, for the adjectival nature remained long with intransitive, right down to eMB. (see *supra*, p. 958,—the feminine adjectival ‘-i’ continued to be used with both the kinds of roots). Hence the simple ‘-ila > -ilā’, or ‘-ilaa > -ilā > -ilā, -ilō’, was enough for it. But the



transitive past was not like that, and its nature developed into that of a proper verb with an object. So too the future form, both transitive and intransitive, partook more of the nature of the verb. In some of the dialects of the Bengali group, an affix gradually came to be attached to these. And that affix we find in NB. as « -ē » for both transitive past, and transitive and intransitive future.

The « -ē » was never a literary favourite in MB., the simple « -ā » or « -ā » base being commonly employed for the past third person. The composite « sādhu-bhāṣā » here followed the MB. preference for « -ā » in the past tense, but not in the future. But nevertheless, the « -ē » is found in MB. works—in the ŚKK., for instance. Thus, as 3 personal forms, we find in the ŚKK., for *he did*, কৈলে, কইলে « kailē, kailē » 4 times, করিলে « karilē » once (= NB. Standard Coll. করলে, ক'লে [korle, kolle]), while কইল, করিল « kâ(y)ilā » occurs 17 times and করিল « kârilā » 6 times (= NB. ক'রল, ক'ল [korlo, kollo]); for *he received*, পাইলে « pailē » (= NB. পেলে [pele]) occurs once, but পাইল « pailā » (= NB. পেল [pelo]) 7 times; for *he sent*, পাঠাইলে, পাঠায়িলে « pāṭhā(y)ilē » (= NB. পাঠালে, [paṭhale]) 3 times, পাঠাইল, পাঠায়িল « pāṭhā(y)ilā » (= NB. পাঠাল [paṭhalo]) 4 times; for *he said*, বুলিলে « bulilē » (cf. NB. ব'লে [bolle]) once, বুলিল, বুলিল « bu(y)ilā » (cf. NB. ব'ল [bollo]) 28 times; for *he gave* দিলে « dilē » once, দিল « dilā » 10 times; for *he took*, নিলে « nilē » 5 times, নিল « nilā » 6 times, and আণিলে « āṇilē » *he brought* is found once. The « -ē » for the 3rd person thus goes back to the 14th century. It is not, however found in the Caryās.

This « -ē » affix I take to be the « -ē » of the radical or present tense, 3rd person, extended to the past transitive base: দেখিল « dēkhilā » *seen*, *he saw* changed to দেখিলে « dēkhil-ē », NB. দেখলে « dēkhl-ē », on the analogy of দেখে « dēkh-ē » *he sees*; but an intransitive form like গেল « gēlā » = *gone*, fem. গেলি « gēli », sufficiently retained its adjectival nature not to require a verbal affix. We should note that the plural affix « -ānti, -āntā, -entā » was similarly extended to the past verb, as an honorific form merely (see *supra*): « -ē » was the characteristic 3rd pers. affix, and the plural as an honorific form was less frequent. This

extension of the « -ē, -ānti » etc. was accomplished possibly during the transition from OB. to eMB.: it was established by the end of the 14th century, and if the ŚKK. does not use it exclusively, it is because the literary speech tends to preserve the older tradition (in keeping to the older, unaffixed « -ā » form).

A partial agreement with Maithilī may be noted. In Maithilī, in the honorific, the transitive past base takes the affix « -thi » (< -anti) of the present honorific (= original plural), because its nature is that of a verb: « dēkhala-thi » *saw*. But the intransitive past base (with its adjectival nature) to denote the honorific takes the affix « -āh(a) » which is found with *nouns* and *adjectives* in Early Maithilī: « sūtal-āh(a) » *slept*. (This « -āha » is very common in the 'Varṇa-ratnākara' MS., see *supra*, pp. 102-103: it seems to be the Māg. Ap. genitive in « -āha » extended to form the plural, like « -rā » of Bengali, « -kā » of Bhōjpuriyā).

In the Standard Colloquial, some intransitive verbs are seen to employ the « -ē » affix, in apparent contradiction to the rule that it is confined to transitives only: thus নাচলে « nāclē » *he danced*, কাঁদলে « kādlē » *he wept*, হাঁটলে « hāṭlē » *he walked*, খাটলে « khāṭlē » *he laboured* (but খাটিল « khāṭilā » *it fitted*). Cases like these can be explained as a phonetic development out of « -ilā » forms of MB. — < « nācilā, kāndilā, hāṭṭilā, khāṭilā » etc. (see *supra*, pp. 400-401): but the proper explanation is that these verbs are really transitives with cognate objects like নাচ, নাচা, নাচন « nācā, nācā, nācānā », কাঁদা, কাঁদা, কাঁদন « kādā, kānnā, kādānā » etc. understood and sometimes expressed. The « -ē » is thus never extended to intransitives in the dialects in which it is employed. On the other hand, through the influence of the « sādhu-bhāṣā » and of East Bengal dialects, the « -ā » form is now being used at times by Standard Colloquial speakers with the transitive also—e.g., পেলা, খেলা, দেখল, দিল « pēlā, khēlā, dēkhlā, dilā » *he obtained, ate, saw, gave*, beside the proper « -ē » forms.

The credit of first noticing the difference between the intransitive and transitive past bases in Bengali as well as of suggesting explanations belongs to Grierson (JASB., 1895, pp. 366, 374, 350; LSI., V, I, 1903, p. 13, foot-note; cf. also 'Prabāsi' for 1329, Pauṣa, pp. 382 ff.). In



the JASB. article, a form like মারিলেক *\*māril-ē-(kṣ)* *he killed* Grierson sought to explain (on the analogy of Maithili forms with affixed object and subject pronouns) as being from *\*māril-ai-ka*, being either *< \*māril-āya-ka = killed-this(object)-by-him*, where *\*āya* was the (Western) Apabhraṃśa equivalent of Skt. *\*idam*, and *\*ka* was a third personal pronoun with instrumental power having affinities in Kāśmīrī; or *< \*māril-ahāi-ka = killed-that(object)-by-him*, where *\*ahāi* was the oblique of *\*aha*, the (Western) Apabhraṃśa equivalent of Skt. *\*adas*. But there is nothing in MB. and OB. to warrant such derivations. We have the *\*-ēka* affix with intransitive verbs from the eMB. period. Grierson formulated another explanation in the LSI.: খালে *\*khālē* *he ate* = *\*khālā* *eaten* + *\*-hi* *by him, by them*. But this *\*-hi* as an enclitic instrumental pronoun cannot be otherwise assumed from MB. and OB.

715. The *\*-kṣ* affix in the forms অক, ওক, এক *\*-ākṣ, -ōkṣ, -ēkṣ* in the past tense is pleonastic: possibly it was polite or honorific in Early Bengali. This is discussed below, under 'Pleonastic Affixes,' pp. 989 ff.

716. The honorific forms —অন্তি, আন্তি, অন্ত, আন্ত, এন্ত, *\*-ānti, -ānti, -āntā, -āntā, -ēntā* and এন, আইন, আঞি, আই, *\*-ēnṣ, -āinṣ, -āñi, -āi* have been extended from the present tense by adding to the past base in *\*-ilā ilā*. As has been explained before, they form two groups—the verbal *\*-anti* and the nominal *\*-āna, -ana, -ān-i, -an-i*, the latter having ousted the former (see *supra*, p. 936). In the eMB. of the ŠKK., we find the verbal *\*-nt-* forms only: কাড়িলান্ত *\*kāṛhilāntā* *took off*, চাহিলান্ত *\*cāhilāntā* *looked at*, গেলান্তি *\*gēlānti* *went*, কহিলান্ত, কহিলেন্ত *\*kāhilāntā, kāhilēntā* *said*, etc.; and there are no *\*-n(i), -ñi* forms, which came in later. Early Assamese has *\*-āntā* — *\*thāilāntā, bbāilāntā* *was (were)*, *\*kāilāntā* *did*, etc. Maithili and Magahi also have *\*-thi (< -anti)* (*supra*, p. 937): but in Maithili *\*-thi* occurs only with transitive verbs (Maithili *\*dēkhalāṭ-thi*, but *\*calal-āḥṣ*, whereas Magahi has both *\*dēkhalāṭ-thi, calalāṭ-thi*).

In later MB., *\*-nt-* and *\*-n-* occur side by side in the texts. *\*-ēntā, -āntā* are the common affixes in Chuṭi Khān's 'Maḥābhārata' (VSPd. ed.): and *\*-ēnṣ* is already well-established in Kṛttivāsa. The

nominal «-n-» form may thus be said to have successfully invaded the domain of the verb in the 15th century. In the 'Padmā-purāṇa of Vaiṣṇī-dāsa (17th century: Maimansing), «-āī (< -āni)» is almost the rule for the past third person honorific: *e.g.*, p. 43, পুলস্ত্য কহিলই «Pulastyā kahilāī» *P. said*; p. 71, কহিলই মেনকাসুন্দরী «kahilāī Mēnakā-sundārī»; p. 98, ব্রহ্ম চলি আইলই «Brāhmā cāli āilāī» *B. came away*; p. 109, ধরিলই «dhārilāī» *caught*; p. 185, দিলই «dilāī» *gave*; p. 194, বলিলই «balilāī» *said*; p. 196, ভাবিলই «bhābilāī» *thought*. The «-āni, -āni, -āī» form is still current for the honorific in E. Vanga.

The nominal «-n-» figures in Bhōjpuriyā (*e.g.* «rahal-an» *was, were* = Bengali রহিলেন «rahil-ēṇṇ», «dekhāl-an, dekhāl-ani» *saw* = Bengali দেখিলেন «dēkhil-ēṇṇ»). In Assamese «dēkhilā-hāk» *you saw*, «dēkhilō-hāk» *we saw*, the affix «-hāk» is found with the 2nd and 1st person to form the plural, and this also is undoubtedly the nominal «-na, -nha» with pleonastic «-ka». In Maithili and Magahī, the nominal «-nh-» is added to the verb, but commonly with a dative-accusative (and not nominative-instrumental, or simple plural) force: *e.g.*, Maithili «dēkhathi» *he* (honorific) *sees* (< *they see*), but «dēkhathi-nhi» (honorific) *he sees* (< *they see*) *them* (i.e. a respected person), and «dēkhiai-nhi» *sees them* > *sees a respected person*: and so with the past tense—«dēkhalṭ-thi» beside «dēkhalṭ-nhi» (here active «-nhi» as an equivalent of «-thi»), «dēkhalṭ-k-ai» (object), «dēkhalṭ-thi-nhi» (object). In the intransitive, «-nhi» is used for the indirect object only. So Magahī «dēkhalṭ-thi», «dēkhalṭ-thi-n» (object «-n-»). Oṛiyā too adds the plural affix (found with the noun) to the past and future bases of the verb, but it is not «-n-» of the genitive, but «-ē» < «-ahi» of the instrumental (see *supra*, p. 724): *e.g.*, sg. «dēkhilā», pl. «dēkhil-ē» *saw*; sg. «hōilā», pl. «hōil-ē» *were*.

### [III] THE AFFIXES FOR THE FUTURE TENSE.

These are exactly on the lines of the past, and detailed treatment is not necessary.

717. The forms for the First Person in MB. and NB. are: অ (ʔ), ওহৌ, ও, (বৌ, ব় > ব, য, ড), আম «-ā (-ō), -ōhō, -ō (-b-ō, -b-ū > -mu, -m,



-ŋ = ৳), -ām >. The base in <-ā> —ইব <-ib-ā> —occurs in OB. and MB. (including the ŚKK.), and has been adopted as the <sādhū-bhāṣā> form, without any personal affix. In the ŚKK., <-ō> is the affix for the first person, and <-āhō, -ōhō> do not occur there; but the <-hō> forms may be attested for eMB. from Early Assamese < hāibō-hō, dibō-hō > beside < hāibō, dibō > (= New Assamese < hām, dim >) *I shall be, I shall give*. The eMB. <-ō> may have been also the result of <-aŋa, -ama>. In any case, it would seem to have extended from the past; and in the past, already in the 14th century, <-ilā-hō, -ilō-hō> had given <-il-ō>. The Early MB. <-ō> lost its nasalisation through confusion with the base in <-ā>, and the Standard Colloquial <-ō> (-bō), is commonly written ব <-bā> following the <sādhū-bhāṣā> spelling. The <-m-, -ŋ-> forms have been noted before (p. 967). The affix <-ām> is found in Maimansing, and is evidently the same form as in the past (see *supra*, pp. 976-977).

718. The affixes for the Second Person are (in addition to the base form অ <-ā> in MB. and OB.): ই <-i> contemptuous or familiar; উ <-u> contemptuous and familiar, in MB.; এ, এ, এহে <-ē, -ē, -ēhē> polite, of which the shortened form <-ē> alone occurs in NB.; and আ, আহা <-ā, -āhā> polite and ordinary (besides এন্ <-ēn> with আপনি <āpani> honorific, from 3rd person).

Of these, <-i> and <-u> are the same as in the past tense (pp. 978-980). <-ēhē> is found in the ŚKK., e.g., উঠিবেহে <uṭhibēhē> *you will rise*, কৰিবেহে <kāribēhē> *you will do*, কৰিবেহে <ruṣibēhē> *you will be angry*, etc.; also the contracted <-ē> and the denasalised <-ē> are found there; and in the same work <-ibēhē> occurs as a contracted <-ibhē> in বহিহে <bāhibhē> *you will carry* (p. 175). This <-ēhē, -ē, -ē> has also apparently been extended from the past. So, too, <-ā, -āhā>, also polite forms. <-ā> is found in MB.—চলিবা, কৰিবা <cālibā, kāribā>; and this <-ā> might by Vowel Harmony give the Standard Colloquial চ'লবে, ক'ৰবে [ṣolbe, korbe]. These last two forms (-ā, -āhā) are not found in the ŚKK., but the <-āhā> can be attested from Early Assamese: e.g., <kāribāhā> (as in p. 852 *supra*). The <-ā> affix is now quite common in East Bengal dialects: the Standard Colloquial prefers <-ē>.

719. The affixes for the Third Person are : অ «-ā» (< -aa, -ā) the base, in OB. and MB. (found at the present day in East Bengali and in Modern Assamese); এ «-ē», in the «sādhū-bhāṣā» and in the Standard Coll. (= same as the «-ē» of the 3rd person past : some influence of the «-ē» in the 3rd person sigmatic future of eMB.— «-hē» —described before at p. 965 —is very likely here : «-ibē» is found in the ŚKK., in both transitive and intransitive verbs, and also in Early Assamese); and the honorific অঙ্ক, এঙ্ক, এন, আঞ্জি, অঞ্জি etc. «-āntā, -ēntā, -ēnḍ, -āñi, -āñi», as in the past tense. Besides, there is the affix এক «-ēkḥ» with pleonastic «-ka», found in the ŚKK. and in Early Assamese, and also in the NB. «sādhū-bhāṣā» and in West Rāḍha dialects : this is discussed below.

[IV] THE AFFIXES FOR THE CONDITIONAL OR HABITUAL PAST.

720. They also agree with those for the other two participial tenses. There are some restrictions : for the 1st person, ই «-i» does not occur; for the 2nd person contemptuous (= old singular), ইন্ «-is» is used, and never (or rarely in some dialects) ই «-i» or উ «-u»; and for the 3rd person, similarly, এ «-ē» is not found.

[H] PLEONASTIC AFFIXES.

[I] THE PLEONASTIC AFFIX «-KA».

721. The pleonastic affixes added to the tense forms are noteworthy in Bengali as in the other Magadhan languages. The most common of these affixes is «-ka».

In NB., the forms for the 1st person are free from the pleonastic affix, at least it is not added directly to the verb; but it is added to the 2nd person past and future (ordinary, with «tumi»), and to non-honorific 3rd person past and future (and in some dialects to the 3rd person past habitual), as well as 3rd person imperative, and but rarely to the 2nd person imperative : e.g., তুমি দিলেক, দিলাক, দিবেক, চল্বেক «tumi dil-ēkḥ, dil-ākḥ, dibē-kḥ, cā'lbē-kḥ» (never, however, «tui dibi-kḥ, cā'lbī-kḥ»); সে দিলেক, চল্বেক, দিবেক, চল্বেক «sē dilē-kḥ, cā'llē-kḥ, dibē-kḥ, cā'lbē-kḥ»; সে দিক্, চলুক «sē di-kḥ (< diu-kḥ), cālu-kḥ». Except in the case of 3rd person



imperative, the use of « *kā* » is regarded as archaic in the « *sādhū-bhāṣā* » and is to a great extent dialectal in Bengali.

Of the present-day dialects, that of West Rāḍha has a marked preference for the « *-ka* », commonly in the third person : and it is found also in North Bengali (which has a special employ with the 2nd person polite imperative = original passive? : *e.g.*, *আবেক* « *dyākhēkā* » < *dēkhē-ka* » = ? \* *dēkhiai + ka* », p. 130, LSI., V, I; so *রাবেক* « *rākhēkā* » < ? \* *rākhiai + ka* », p. 179, *ibid*; also *cf.* p. 216, in Haijong dialect : see *supra*, p. 918), in Mayang (where it seems to occur as « *-gā* »), and in Chittagong (in the Chakma dialect, rather rarely). It is found pretty frequently in MB., from the ŚKK. downwards, generally with the third person, occasionally with the second, and very rarely with the first. Already in the ŚKK. we have forms like *ধরিলেক* « *dhārilēkā* » *caught*, *চাহিলেক* « *cāhilēkā* » *looked*, *হিপিলেক* « *hiphilēkā* » *cast*, *নাহিবেক* « *nāhibēkā* » *will not be*, *করিবেক* « *kāribēkā* » *will do*, *লৈবেক* « *lāibēkā* » *will take*, etc. In the ŚKK., it is noteworthy that the « *-ka* » has also been found with the 1st person future and with the 3rd person present—this sort of use with the first and third person is not noticed ordinarily : thus ŚKK. *নিবৌক* « *nibō-kā* » *I shall take* (p. 287), and *পোড়েক* « *pōṛē-kā* » *burns* (p. 110). In the NB. Standard Colloquial, however « *-ka* » may be used with negatives in all persons and tenses as a detached word, without any special force, unless it be of some sort of finality : *e.g.*, *দেবো না ক'* « *dēbō-nā-kā* » *I shan't give*, *সে দিলে না ক'*, *সেই নি ক'* « *sē dilē-nā-kā*, *dēy-ni-kā* » *he didn't give*, *তুমি দিও না ক'* « *tumi diō nā kā* » *you won't give*, *নাইক'* = *নাহি-ক'* « *nāi kā* » < *nāhi-kā* » *is not, are not*; in cases like the above, the negative phrase may be taken as one group-word to which the affix is added.

The « *-ka* » for the 3rd person imperative is already well-established in the ŚKK., although the older form without the affix is still equally common (see *supra*, pp. 903, 907).

The « *-ka* » is absent in the Caryās as a verbal affix.

722. Of the other Magadhan Languages, Bhōjpuriyā alone seems not to employ it with the past and future bases. It is fairly common in Early Oṛiyā, specially with the past in the 3rd person (sg. « *-ilā-kā* »,

pl. and sg. honorific «-ilê-kâ»): but Oṛiyā never used it with the 3rd person imperative. The «-ka» affix for the verb, however, has fallen into disuse in Modern Oṛiyā. So, too, Early Assamese shows as much preference for the «-ka» as Bengali; e.g., 'Ādi-caritra,' p. 3, «bhāilēkâ» beside «bhāilā» *was*; p. 7, «bōlāntōkâ» *they say*, «thākāntōkâ» *they are*; p. 9, «thākibekâ» *they will be*, «bulibekâ» *they will say*; p. 20, «nā-hi-k-āntâ» *they are not*; p. 28, «nā-hi-k-ay» *is not*; p. 36, «thāilēkâ» *was*; p. 43 «yōgāilēkâ» *supplied*, etc., and elsewhere «nu-hi-k-ō» *I am not* (cf. Standard Coll. Bengali নহে ক' = নহি' «nā(h)i-kâ» *I am not*, নাই ক' «nā(h)i-kâ» *he is not*). All this usage is curtailed in Modern Assamese, where we find the «-ka» only with the 3rd person imperative, as in Bengali: e.g., «kār-ō-kâ» *let him do*. The unstableness of the «-ka» in Oṛiyā and Assamese is, remarkable: and it is almost equally unstable in MB. and NB., being commonly attached to the imperative only.

The «-ka» features also in Central Magadhan. Its use in Magahī is rather restricted, it being found only in the 3rd person past both transitive and intransitive. The root «√ha» *to be* in Magahī also occurs as «√ha-k», for all the three persons. But in Maithilī «-ka» has a greater importance. It is added to the 3rd person of the simple past tense of the transitive verb («dēkhala-k» beside poetic or earlier «dēkhala» *he saw*), where it apparently refers to the subject; but in the 1st, 2nd and 3rd persons, it can be added pleonastically where the verb-form takes the pronominal affixes referring to the non-honorific object: e.g., 1st person: «dēkhal-i, dēkhalā-bū, dēkhalā» *I saw* (simple form), «dēkhal-i-ai, dēkhal-i-a(h)u; dēkhal-ai, dēkhal-a(h)u» *saw* (with affixed «-ai, ahu» referring to the object in the 3rd and 2nd persons); and optionally, the latter group can have «-ka», as «dēkhal-i-ai-k, dēkhal-i-au-k; dēkhal-ai-k, dēkhal-au-k»; so 2nd person «dēkhal-āh» beside «dēkhal-āh-k»; and 3rd person «dēkhala-k» *he saw* (simple), «dēkhal-k-ai, dēkhal-k-au» (with object pronoun «-ai, -au»), beside optionally «dēkhalā-k-ai-k, dēkhal-k-au-k» (in which two «-k-» affixes occur: the first «ka» refers apparently to the 3rd person subject, and the second «ka» is simply pleonastic). Early Maithilī as in literature does not show these curious extensions



the form for the 3rd person was simply in «-ala»—«dēkhala», and not «\*dēkhala-ka», as in Modern Maithili. This we find in the old poetry, in Vidyāpati, in the 'Varṇa-ratnākara.' The affixation of the pleonastic «-ka» etc. thus developed along independent lines in Maithili.

723. The usage in MB. and NB. and in Maithili shows that the «-ka» is not restricted to a single person: it is found with all the three. We have a very popular pleonastic «-ka» affix in Bengali with other parts of speech also: we find it with nouns (*e.g.*, plural affixes গুলক *gula-kṣ* beside গুল *gula*), আদিক > দিক *ādi-kṣ* > *-di-gṣ* beside আদি > দি *ādi* > *-di*), একটুক *ēkṣ-tu-kṣ* a little beside একটু *ēkṣ-tu*; etc.), and dialectally it is found with conjunctions (*e.g.*, কিন্তুক for কিন্ত *kintu-kṣ* = *kintu* in North Bengali). This «-ka» is always handy to give a point, a supposed elegance to a form in the speech of the uneducated classes in many dialectal areas: we see that in the case of learned Sanskrit words. The pleonastic «-ka» with verb forms appears to be the same affix noted under 'Formative Affixes,' No. 36 (pp. 682-683). It came specially to be associated with the 3rd person past and future in Bengali because there was no prominent affix for these finite verb forms—nothing comparable with the «-āhō, -ō, -ām» etc. of the first person, or with «-is, -āhā, -ēhē» of the second. Sometimes it was thought to be quite a polite form too. The same apparently was the reason for the other Magadban speeches: and if Maithili restricted it to the transitive past 3rd person (*e.g.*, «dēkhalak» beside «calak»), it was because the past intransitive still retained a great deal of the original adjectival nature.

The link vowel of the pleonastic «-ka» in the 3rd person already occurs as «-ē» (and not «-ā» or «-ṁ») in the ŚKK. In the future, the 3 pers. affix was «-ē», and «-kṣ» was simply added to it. In the past, it was apparently the transitive verbs in «-ē» in the 3rd person that first took up the «-ka» (we should compare with the state of things in Maithili in this matter): in the few instances of «-il-ē-ka» that we find in the ŚKK., there is no case of an intransitive verb. From the transitive it was apparently extended, as «-ē-ka», to the intransitive forms from the 15th century onwards.

724. Grierson, basing his observations on the modern Maithili use of « -ka » for the 3rd person past of the transitive verb, explained this « -ka » both as an instrumental pronoun referring to the subject (*e.g.*, « dëkhal-k-ai » = *seen + by him* [k] + *object* [ai]), and as a nominative pronoun (*e.g.*, « dëkhal-i-au-k » = *seen + by me* [i] + *for you* [au] + *he* [k]: JASB., 1895, p. 350). But an *ensemble* view of the whole question would certainly connect other facts with what we see in Maithili, and make the simple explanation of the « ka » as the pleonastic affix as the more likely one, rather than regarding it as a problematic 3rd personal pronoun « -ka ». Grierson found support in postulating the 3rd personal pronoun « -k » from the Assamese forms « bōpāi » *my father*, « bāpā » *your father*, and « bāp-ē-k » *his father*: but another explanation may be suggested for these forms: « -āi (bōp-āi) » may be compared with the affix of endearment found in Bengali personal names (for which see *supra*, 'Formative Affixes,' No. 9, p. 662); « -ā (bāp-ā) » for the 2nd person is an affix of respect, such as we find in the Assamese 2nd personal forms of the verb; and « -k (bāp-ē-k) » is just the pleonastic affix, perhaps originally added as a polite form, to the naked word « bāp ».

Among other NIA. speeches, the Jaipurī form of Rājasthānī has a fondness for this pleonastic « -ka » which can be compared with the Magadha usage (LSI., IX, II, p. 35).

725. The « -ka » affix has had a very important place among the affixes of IA. Already in OIA., from post-Vedic times, this affix was employed with a variety of forces (*cf.* Franklin Edgerton, 'The *k*-suffixes of Indo-Iranian,' Part I, Leipzig, 1911). It seems to have been re-introduced in MIA., evidently through the influence of a large percentage of the Skt. *tsa.* and *sta.* which showed it. The pleonastic use of it has been exhaustively noted by Pāṇini. We find that the « -ka » could be used in Skt. pleonastically, or with a sense of contempt, pity, littleness, or unfamiliarity, in connexion with all sorts of forms—inflected pronouns and inflected verbs (mainly 3rd pers. sg.), as well as indeclinables, in addition to noun bases (*cf.* Pāṇini, V, iii, 71-78, 85, 86): *e.g.*, the instances given by the grammarians,



\*uccaiḥ : uccakaiḥ; śanaiḥ : śanakaiḥ; tvayā : tvayakā; yuvayōḥ : yuvakayōḥ; yuṣmāsu : yuṣmakāsu; jalpati : jalpataki; pacati : pacataki; pāti : pātaki; svapiti : svapitaki; ēhi : ēhaki > ; etc. It is not unlikely that a revived \* -ka, -kka > should develop in MIA. and NIA. a similar employ as a pleonastic.

[II] THE PLEONASTIC AFFIX \* -ra > .

726. An affix \* -ra > occurs in dialectal NB. and in MB. In NB. this is found in West Rāṇḍha (e.g., in the Sarākī dialect of Ranehi) in connexion with the conjunctive in \* -i(y)ā > : e.g., বাইআর \* jāiār > = jāiā-rā > *having gone*, খাইআর \* khāiār > = khāiā-rā > *having eaten*, উঠিয়ার \* uṭhiyār > = uṭhiyā-rā > *having risen* (LSI., V, I, pp. 88, 89); it is found also in the dialects of East Vanga—in Sylhet, Kachar and Mayang dialects, in Tipperah, Noakhali and Chittagong. The usage in East Vanga is more extensive : the \* -ra > occurs not only with the conjunctive, e.g., Chittagong দিয়ারে, করিয়ারে, আইয়ারে \* diyār-r-ē, kāriyār-r-ē, āiyār-r-ē > *on having given, on having done, on having come*, Mayang \* ēilā-rā > *on having come*, but also with the present (radical) and the past conditional (< present participle) tenses, to indicate continuous or progressive action : e.g., E. Sylhet বাইয়ার, বাইজাম, বাইরাম \* jāiyār-rā, jāit-r-ām, jāi-r-ām > *I go, I am going* (beside বাইতেছি \* jāitēchi > as in Standard Bengali); করি \* kārāt-r-ā > *is or are doing*; বাইজায় \* jāit-rā-y > *you are going* (beside বাইতেছ \* jāitēchā >); হয়র \* hāyār-rā > *is happening*; and Mayang \* pait-rā > *are getting*, \* jā-r-gā > *he goes*, \* tumi-te āho-r-ai (= āiśa-r-āy) > *you are coming*, \* sōre dākāite hin kōrtā-r-ā > *thieves and robbers are making destitute*, \* āmi kākuti kōriyār-r > *we pray*, \* bāpōk gum jā-r > *the father sleeps*, \* tā huōr rākhe-r > *he tends swine*, \* bōk paiyā mōring-kōrau-r-i > *I am dying of hunger*, etc., etc. (LSI., V, I, pp. 419 ff.); Chittagong করি beside করি \* kāri-rā, kāri > *I (we) do*, করর beside করর \* kārā-rā, kārā > *you do*, করের beside করে \* kārē-rā, kārē > *he does, they do*, খাইর, খাই \* khāi-rā, khāi > *I eat*, খাওর \* khāo-rā > *you eat*, খায়ের, খার \* khāyērā, khār > *he eats*, আই উরাসে মরির \* āi uāsē mārī-rā > *I am dying through starvation*, আই তৌয়ার খেজমৎ করিয়ার \* āi tōārā khēzmāt kāriyērā > *I am doing service for you*, etc.; and Chakma \* mārāṅ-ārā > *I am dying*, \* gārāṅ-ārā > *I am doing*, \* bhābē-rā > *he is thinking*, etc.

The MB. examples are all found in the ŚKK., and the <-ra> there occurs, not with the conjunctive, but with the finite tense forms—present, past and future, as well as imperative: thus: p. 39, আছের <āchē-rā> is; p. 195, শোভের <śōbhē-rā> is beautiful; p. 69, বাজের <bājē-rā> sounds; p. 152, গেলির <gēli-rā> it went (=gēlā-rā?); p. 2, চিত্তির <cinti-rā> he deliberated (non-l past in <-i>: *supra*, p. 947); p. 50, বেড়িলের <bēṛhilē-rā> it surrounded; pp. 50, 193, 279, দিবোর <dibō-rā> I shall give; p. 84, হৈবের <hāibē-rā> it will be; p. 334, কহিয়ারো <kāhiā-r-ō> let me narrate; p. 11, কহিয়ার <kāhiā-r-ā> do tell; p. 72, খায়ার <khāā-r-ā> do eat; pp. 16, 115, 319, 336, 394 দিয়ার <diā-rā> do give; p. 38, দিয়ার <diā-r-u> let him give. In the imperative forms, the base seems to be the non-l passive participle in <-iā>, to which <-rā> is added, and the whole is treated as a base to which the personal suffixes are attached. Cf. the Sylhet and Mayang forms, and the Chittagong idiom তুই দিয়ারে মুই দিয়া <toi diyā-r-ē mui diyā> on your giving, I would give, or if you have given, then I have given also (VSPdP., 1326, p. 251).

727. The fact of this <-ra> occurring in the two extreme dialect areas of Bengali—in Early West Bengali, in modern dialectal West Bengali, and in modern extreme Eastern and South-Eastern Bengali—would suggest that it was a common Bengali affix, but its development has been localised in certain tracts. It seems to occur sporadically in other dialects also in MB.: e.g., Vijaya-gupta's 'Padmā-purāṇa' (Barisal), ধূপের ঝোঁয়া দিয়ারে বাসিত করে কেশ <dhūpērā dhōā diyārē bāsita kārē kēśā> perfumes hair with incense smoke (VSP., p. 186).

The <-ra> affix apparently occurs in other NIA., outside Bengal and the Magadhan area. We find it in Rājasthānī (e.g., Mār-wārī <hūya-r, whē-r> having become beside <hūy-naī, hō, hō-kar, whētō-kānaī>, <māra-r> having struck beside <mār-kar, mār-naī, mārī-naī>; Central Rājasthānī, Jaipurī etc., <whai-r, hō-r> having become, <māra-r> having struck; Mēwātī <hō-r, mār-ar>), where the affix <-ra> is added to the conjunctive participle; we find it in Pahārī, e.g., Khas-kurā <gārē-ra> having done, <bhayē-ra> having been (where the <-ra> has been explained as a conjunction meaning *and*, which is added to the oblique form of the passive



participle), beside the «-i» conjunctive «gari, bhai» *having done, having been* (LSI., IX, IV, p. 36); Sirmauri «khāy-rō» *having eaten* (where «-rō» seems to be a post-position: LSI., *ibid.*, p. 465); also «-rō» in other Pahārī dialects (LSI., *ibid.*, pp. 570, 602).

The etymology of the Bengali «-ra» is puzzling, and probably the source is not one, but many. In the NB. conjunctives, whether of West Rāḍha or of S.-E. Vangā, it can very well be post-positional in origin, from «pārḍ, pār-ē» *after*, used in an adverbial sense. We have Modern Bengali instances like W. Rāḍha বারে বাদে «jāyē bādē» *after having gone* (where «bādē» *after* is the Perso-Arabic «ba'd») = Standard Colloquial গিয়ে পর «giyē pārḍ»: Cf. Haijong dialect (Maimansing) উঠিয়ামি «uṭhiyā-mi» *after getting up*, দেখিয়ামি «dēkhiyā-mi» *on seeing* where «-mi» is the locative affix (see *supra*, p. 751); we can also compare Marāṭhī «uṭhilyā-var» *on having risen*, «sōḍilyā-var» *on having left*, where «var=par». The «-ra» in Khas-kurā, explained by Grierson as meaning *and* (< apara), can similarly be a postpositional form. In the present forms, in Bengali, the «-ra» can very well be the conjunction «āra, āara, aara < apara» *and*: «karē-rḍ» *does and=does, continues to do, is doing*. So, too, in the MB. past and future. But the addition of it to a verbal base, and then tagging on personal suffixes to it (as in the MB. imperative 1. «kāhiā-r-ō», 2. «kāhiā-r-ā», 3. «diā-r-u» and in NB. of E. Sylhet 1. «jāit-r-ām, jāi-r-ām» 2. «jāit-r-āy», 3. «jāit-r-ā», and Mayang 2. «āho-r-ai», 3. «kōrtā-r-ā») is a unique phenomenon. I would suggest that here the «-r-» is the contracted form of «√kār», and the affix is simply the verbal auxiliary added on to the root: «kāhiārō < \*kahiā + karō» = «kathitañ karōmi» *I make it described*, for «kathayāmi» *I describe it*; «diāru < \*diyā + karu» = «dattañ karōtu» for «dadātu»: «jāit-rām = \*jāita + karō, \*karām» (Bengali «√kār + affix «-āmi») = *going I do = I go on, I am going*; and a form like «jāi-rām» or «āhō-r-ai» shows a combination of a regular conjugation in the present + the «-r- < √kār» and personal affixes combined. The genitive affix «kara > -ārḍ» implying connexion may also have something to do with it.

## [III] THE PLEONASTIC AFFIX «-LI» OF MB.

728. The affix लि «-li» occurs in the ŠKK. less than half a dozen times with the future or precative imperative: *e.g.*, करिहलि «kārīhāli» *you will do*; दिहलि «dihāli» *you will give*; गाअ गड़ाहलि «gāā gārāhāli» *you will roll (your) body*; चलिहलि «cālihāli» *you will go*. An equivalent of this affix has not been found in any NB. dialect Bhōjpuriyā among Magadhan speeches has an «-l-» form which is added to the old present (or radical) tense to form a present definite or future (LSI., V, II, p. 52). In some of the Rājasthāni dialects, in Marāṭhi, in Khas-kurā, and in Garhwāli and Kumāūni (Central Pahāri), the future is also expressed by an «-l-» form.

The MB. «-li», occurring as it does with an original future form to strengthen its force, seems to be equally a future-indicating suffix, as in the other NIA. speeches, and to be identical with that. Various derivations of this «-l-» suffix have been suggested (cf. Beames, 'Comp. Gramm.,' II, p. 163; Bhāṇḍārkar, 'Wilson Lectures,' p. 272; Hoernle, 'Gaudian Grammar,' §§ 501, 509; Bloch, 'Langue Marathe,' p. 241). The derivation suggested by Bloch for this suffix seems to be the most likely one: it is the passive participle of a Prakrit root «lē» *to take* (corresponding to the Skt. «√lā»: cf. similar alternation between Prakrit and NIA. «√dē» and Skt. «√dā»), such as we find, for instance, in Hindōstāni «li-ā», in Brajbhāṣā «li-nau», in dialectal Bengali লিলে «li-l-ē» (=in Standard Bengali নিলে «ni-lē» with merging of নী «√ni» and লহ «√lāh < √labh» in it). This «\*li(a) > li» would seem to be added pleonastically, and in MB. it is used in both genders. Cf. similar future use of «gā, gau (< gata)» in Western Hindi (and in Maithili).

## [IV] THE PLEONASTIC AFFIX «KHAN» OR «KHUN».

729. The colloquial of Calcutta and the surrounding districts uses the word খন «-khāṇḍ» or খুন «-khunḍ», or অখন, অখুন «-ākhāṇḍ, -ākhunḍ» after vowels, pleonastically with all persons in the past and future tenses: *e.g.*, যাবো-(অ)খুন, দিন্ম-খুন, হবে-(অ)খুন «jābō-(ā)khunḍ,



dilum-khunṣ, bābē-(ā)khunṣ > *I shall go, I (we) gave, it will be*. There is just a suggestion of the finality or instantaneous completion of the action : here the force of the OIA. < kṣaṇa > *instant*, its source, is preserved. Its origin has been given *supra*, p. 857, under 'Adverbs of Time in খন < khāṇ >.' It seems to occur also in Magahi, in forms like < kailṣkai-khan > *did*, < kahālṣkai-khan > *said*, < chōṛālṣkai-khan > *gave up*, < chōṛaulṣkai-khan > *caused to give up*, < ailai-khan > *came*, besides < kariai-khan > *I do, I shall do*, etc. (as in the 'Gospel of St. Mark, in Magadhi,' Calcutta, 1890 : a form which does not occur in Grierson).

In dialectal Bengali (Khulna, Jessore, etc.), this form has been reduced to < nē > ( < ānē < āānē < āhānē [oxone], = ākhānē ) with the future only : দেবোনে < dēbō-nē > *I shall give*, যাবোনে < jābā-nē > [ zabane ] *you will go*, etc.

#### [V] THE PLEONASTIC AFFIX '-TĀ.'

730. The Mayang dialect apparently uses a pleonastic affix < tā > : thus, < eil-tā > *he came* < eilā-tā > *they have come*, < peilāṅ-tā > *I got*, < korauri-tā > *I am making* < ose-tā, āse-tā > *is*, beside < eil > *he came*, < dekhilo > *he saw*, < nā-peil-gā > *did not get*, < korauri > *I do*, < āse > *is*, etc. This < -tā > is found with nouns and pronouns also (LSI., V, I, pp. 419 ff.).

Mayang does not distinguish between cerebrals and dentals, as much Assamese, and this < -tā > can well represent a cerebral < -ṭā >. This < -ṭā > apparently is the 'Enclitic Definitive' noted at pp. 780-781, and at p. 686. Its use with verbs is not noticed elsewhere in Bengali, but it seems to be present in Oriyā as < -ṭi >, especially in Early Oriyā : e.g., < tu jibu-ṭi > *will you go ?* (cf. LSI., V, II, p. 381, Expletive Additions) : Early Oriyā, 'Dhruva-caritra' (Contai ed., p. 16) < pāibā-ṭi kāhi > *where will one get it ?*; 'Bhāgavata, Vāstra-haraṇa' p. 8, < nārākē pāribā-ṭi jāi > *will fall in hell*; 'Rukmiṇī-haraṇa,' p. 3, < sē dhārmē bāñcā-ṭi-ki sukhē > *live happily in that dharma* (cf. Oriyā < ṭikē > = Bengali একটুক, টুক < ekṭ-ṭu, -ṭu-kṣ >, p. 780); 'Rāsa-līlā,' p. 8, < āmbhārā pūrilā-ṭi kāla > *my time is over*; etc.

## [VI] THE PLEONASTIC AFFIX «-ḍA».

731. In the OB., the two forms «gāi-ḍa» *sang* and «sanāiḍa» *signified* occur (Caryā 2). They represent OIA. causative passive participles «gāpitam» and «samjñāpitam» + the pleonastic affix «-ṭa > -ḍa» = «-ṛa» in NIA. (=Formative Affix No. 46, pp. 689 ff., *supra*). Use of this pleonastic affix for verb-forms is known in other NIA., although this figures no longer in that connexion in Bengali (of Rājasthānī dialects, LSI., IX, II, pp. 30, 59).

## [I] THE PARTICIPLES.

## [I] THE PRESENT PARTICIPLE.

732. The present participle occurs in Bengali in two forms: in the base-form in অন্ত «-āntā», and in the locative in ইতে «-itē». It represents the OIA. active present participle in «-ant-» (the «śatṛ» of the Indian grammarians). These have been discussed under 'Formative Affixes,' Nos. 3 and 28. Other instances of the «-āntā» form may be given: পড়ন্ত «pār-āntā» *falling*, নিবন্ত «nib-āntā» *dying out (as a flame)*, উঠন্ত «uṭh-āntā» *rising*, জ্বলন্ত «jwal-āntā» *burning*, সাজন্ত «sāj-āntā» *fitting*, ফুটন্ত «phuṭ-āntā» *blossoming, boiling (bubbling)*, অকুরন্ত «ā-phur-āntā» *unending*, etc. The affix «-āntā» is an archaic survival (doubtless a literary one) for Bengali, with the «-n-» fully retained: it ought to have been \*জৈ «-āt-»: we actually find «-āt-» in some rare instances in MB.: e.g., VSP., p., 658, জীয়াত «jīyātā» *living*. The participle as an attribute of the subject of a sentence, e.g., as in Hindōstānī (cf. Platts, 'Hindustānī Grammar,' p. 332), is not found in Bengali. The Assamese equivalent is «-ōt-»: «kār-ōt-ā» *doer*, «cāl-ōt-ā» *walker*, «di-ōt-ā» *giver*, etc. Oriyā has a form in «-u, -ū» as in «kāru, kārū» (which is different in origin from the «-āntā» participle,) as the present participle absolute (see *supra*, p. 678). In Maithilī, the affix occurs as «-ait», fem. «-ait-i», in Magahī as «-ait, -at, -it» (feminine with «-ī» added); and in Bhōjpuriyā the same forms as those of Magahī occur.

The absolute or attributive use of the «-āntā» participle is found only with one root in the Caryās: thus in 18, we have «jīvantē maālē



(=mañlē) nāhi bisēsō > *there is no difference between the living and the dead*, where it is instrumental ; also in 49, < jivantē mañlē nāhi bisēṣa > ; and in 23, < jivantē bhelā bihaṇi maēla > *died without having been a living one*, where it is apparently nominative. The form is also restricted in use in eMB., but a few instances are found : thus ŚKK., p. 256, জীবন্ত < jiyāntā > *living*, p. 276, মারন্তা < mārāntā > *one who strikes*.

733. The present participle in ইতে < -itē > represents the proper Bengali transformation of the MIA. < -anta > to < -ita >—the native line of development in the language, represented in the Past Conditional or Habitual also. It is an inflected form—a locative absolute, and it indicates the condition under which an act is done. In dialectal Bengali, the uninflected form occurs either in forming the progressive tense (*e.g.*, কর্তাছে [kortase] < করিত্ + আছে > < kârit + āchē > in Maimansing Bengali), or to indicate either the simple participle, or when repeated a condition (*e.g.*, আসিং আসিং < āsit āsit > *while coming* in Manbhum, Khārīā-ṭhār dialect: LSI., V, I, pp. 93, 94). A locative of the present participle in < -it > with the common postpositional affix for the locative case, *viz.*, ত < -tā >, seems to feature in the progressive tense in dialectal North Bengali: see *infra*, under ‘Compound or Periphrastic Tenses.’ By repeating the < -itē > form, continuity of the conditional or concurrent event is indicated: thus, আমি বাইতে সে আসিল < āmi jāitē sē āsilā > *on my going* (lit. *I going*), *he came*; আমি বাইতে যাইতে সে আসিল < āmi jāitē jāitē sē āsilā > *while I was going*, *he came*; আমি খাইতে খাইতে বলিব < āmi khāitē khāitē balibā > *I shall narrate while eating*; তার এমন ভাই থাকতে সে কষ্ট পায় < tāra ēmāṇṇ bhāi thāktē sē kaṣṭa pāy > *with such a brother living*, *he suffers*; সে নাচিতে নাচিতে আসে < sē nācitē nācitē āsē > *he comes dancing*; গান গাইতে গাইতে সূতা কাটে < gāṇṇ gāitē gāitē sutā kātē > *spins while singing*, etc. The < -itē > form practically is in adverbial relation to the finite verb. This adverbial employ with an oblique form of the present participle is found in other NIA. speeches: *e.g.*, Early Assamese < -āntā > (fairly common); Oṛiyā < āntē >, *e.g.*, (< kārāntē > *whilst doing*, also *on doing*, *about to do*: cf. < cālāntē mōdinī kāmṇāi > *the earth trembles while he walks*, as in Jagannāthadāsa); Maithilī < -itāī >, (*e.g.*, < dekhitāī > *on seeing*); Hindōstānī

« -tē » (see Platts, 'Hindustānī Grammar,' pp. 333, 335), e.g., « sārī rāt talaphtē kaṭī » *the whole night passed in restlessness* (lit. *I being agitated*), « ḍartē ḍartē mai pās giyā » *I approached (it) in great fear (fearing much)*, « ham gātē gātē sītī haī » *we (fem.) keep singing while we stitch*: in all the above, the oblique form is a locative; but in Old Western Rājasthānī, the source of Gujarātī and Mārwarī, where also this adverbial participle occurs, and in Marāṭhī similarly, the oblique form seems to be an absolute plural genitive (Tessitori, 'Grammar of OWR.,' § 124: but Jules Bloch and V.K. Rājawādē suggest the MIA. absolutive in « -tvā-nam, -ttāgaṇ » as in Pali and Ardha-māgadhi as the source of the Marāṭhī as well as Gujarātī « -tā »: 'Langue Marathe,' p. 260).

In the Caryās, the locative or adverbial participle occurs in a number of instances: e.g., « (15) jāntē, jāantē *while going*; (16) buḍantē *while sinking*; (20) biārantē *while discussing*, (23) paśantē *while entering*; (30) suṇantē *on hearing*; (31) cāhantē cāhantē *while seeing*; (39) amiā ācchantē bisa gilēsi *while there is nectar thou swallowest poison*; (42) mūḍhā acchantē lōa na pēkhaī *while he remains a fool a man does not see*; dudha majhē laḍa ṇacchantē dēkhaī =? dūdhā mājhē laḍa āchantē na dēkhaī *he does not see the butter (fat) while it is the midst of the milk*; (44) aṇa cāhantē āṇa biṇaṭhā *while asking for the one, the other is destroyed*; (50) jāgantē *while keeping awake*; cf. also (6) « taraṅgantē = ? turam̐ gantē » *going quickly*; and « ghara acchantē mā jāṅga baṇē », *supra*, p. 960.

MB. instances: ŚKK., p. 11, পাছে পাছে জাইতে পথ হারাইল আন্দি « pāchē pāchē jāitē pāthā hārāilā āmhi » *I lost the way while going after (her)*; p. 15, বাহুত বলরা শোভে পাঁওত নুপূর। চলিতে চলিতে তোর কণ্ঠনু বাজে ॥ « bāhu-tā bālāyā śōbhē, pāē-tā nupūrā: cālitē cālitē tōrā kuṇṇu-jhaṇu bājē » *armlets grace (your) arms, on (your) feet anklets: while walking, these your (trinkets) tinkle*; p. 27, তাক সোঁঅরিতে মোর মনে বাঢ়ে তাপ « tākā sōāritē mōrā mānē bāṇhē tāpā » *sadness grows in my mind while I remember it all*; p. 355, যেবা কিছু হুখ দিলে। পার হৈতে নাঞ « jēbā kiehu dukhā dilē pārā haitē nāē » *all the trouble I gave (thee) while crossing in the boat*;



ibid, না শুনিবে। তোর বোল লক্ষ। জাইতে পাই। « nā śunilē tōrā bōla lāṣ jāitē pāi » *I did not listen to thy words while fetching water* ; p. 376, চাহিতে চাহিতে পাইল আচম্বিত। « cāhitē cāhitē pāila ācāmbitā » *while seeking (looking for), found of a sudden* ; etc., etc. ; Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 24, কান্দিতে কান্দিতে যান ভরত শত্রুঘন। « kānditē kānditē jāṇḍa Bhārataḥ Śātrughanaḥ » *Bharata and Śatrughna go weeping* ; VSP., p. 709, নকুলক দেখন্তে সকল যায় মরি। « Nākula-kā dēkhāntē sākālā jāyā māri » *all go dead while seeing N.* ; ibid, p. 182, দুই চক্ষু থাকিতে। « dui cākṣu thākitē » *while the two eyes exist* ; etc., etc.

This adverbial or locative absolute present participle goes back to OIA., and occurs throughout the history of IA. : cf. Rig-Veda, I, 184, « uccāntyaṃ uśāsi » *at Dawn as it shines forth > when Dawn shines forth* (Macdonell, 'Vedic Grammar for Students,' § 205) ; see also *supra*, p. 959.

From MB. times, the adverbial present participle in « -itē » has been confused with the infinitive in « -itā », for which see *infra*, under 'Verbal Nouns and Infinitives.'

## [II] THE PAST (PASSIVE) PARTICIPLE.

734. The Bengali Passive Participle comes from the OIA. « -(i)ta », fortified either by « -ā » or by « -il-, -il-ā ». We have thus two types, the « -ā » type, and the « -l- » type, of which the latter is obsolete in the Standard Colloquial. They have been fully discussed under the 'Past Tense,' *supra*, pp. 940-959. In NB., the perfect tenses are made with a verb form in ইয়া « -iyā » + the auxiliary substantive verb « āch » (and « thāk ») : করিয়াছি « kārīyā-chi » *I have done*, করিয়াছিলাম « kārīyā-chilām » *I had done*, করিয়া থাকিব « kārīyā thākiba » *I shall have done*. In Early Bengali, this « -iyā » occurs as ই « -i », and also as ইয়া, ইয়া, ইয়া « -iā, -iyā, -iñā » etc.,—and the nasalised forms are still in use in West Bengali dialects.

This « -iyā » form is commonly explained as the conjunctive form = *having done*, but in the periphrastic combination of the tense, it is likely that it is the passive participle rather than the conjunctive indeclinable (see *infra*, under 'Compound or Periphrastic Tenses').

That the «-iyā, -i» form represents the Passive Participle also (in addition to the conjunctive) is seen from its adjectival or adverbial employ which has occasionally a present participial force : thus, মাঝে লক্ষ্মীর মূর্তি, দুই পাশে দুই হাতী ওঁড় উচু করিয়া দাঁড়াইয়া «mājhē Lakṣmīr mūrtti, dui pāśē dui hātī sūṛṣ ōu kārīyā dāṛāiyā» in the middle the figure of Lakṣmī, on two sides two elephants standing with trunks raised high ; শিব নাচি নাচি যায় «Śibā nāci nāci jāy» Śiva goes dancing ; Kṛttivāsa, 'Ayodhyā-kāṇḍa,' p. 20, কান্দিয়া কান্দিয়া রাণী আইল বাহির «kāndiyā kāndiyā rāṇī āilā bāhirā» the queen came out weeping : cf. কান্দিতে কান্দিতে বান ভরত শত্রঘন at p. 1002. The transition in significance from the passive participle adjective to the active present participle can easily happen through intransitive verbs.

Causative and Denominative verbs form their passive participle in আন, আনো «-ānā, -ānō», which is discussed below under those verbs.

### [ J ] THE CONJUNCTIVES.

735. There are two Indeclinable Conjunctives, or Gerunds, in Bengali, one ending in ইয়া «-iyā» (> Standard Coll. এ «-ē» with mutation of preceding vowel), the other in ইলে «-ilē» (> Standard Coll. লে «-lē», with accompanying mutation through influence of the «-i-»). Both mean *having done*, or *having finished* : but «-iyā» indicates merely a *succession of actions or events* done by or with reference to the *same* subject, while «-ilē» implies a *condition or precedence in a succession of acts* performed by the same subject or by different subjects : e.g., আমি আসিয়া দেখিলাম «āmi āsiyā dēkhilām» *having come, I saw = I came and saw* ; সে আসিলে (এলে) পরে আমি দেখিলাম «sē āsilē (ēlē) pārē āmi dēkhilām» *I saw after he came* ; আমি সময় মত ফিরিলে যেতে পারি «āmi sāmāyā-mātā phirilē jētē pāri» = *I may go if I return in time* ; খেয়ে নাও, খেলে পর হাঁটতে পারবে «khāyē nāḍ, khēlē pārā hāṭtē pārbē» *eat (your fill), you will be able to walk if you eat (enough)* ; আমি গেলে তুমি যেও «āmi gēlē tumi jēḍ» *you will go if I go (after I have gone)* ; দিলে দেয় «dilē dēy» *gives when one gives him*, পেলে দেয় «pēlē dēy» *gives if he gets beside* পেয়ে (পাইয়া) দেয় «pēyē=pāiyā dēy» *gives after he gets, etc., etc.* There are other points of difference in the idiomatic use of these two forms (cf. Milne, 'Bengali Grammar,' pp. 180-189), but



the outstanding fact is that «-ilē» is conditional with reference to the same subject or different subjects, and «-iyā» is sequential with the same subject.

[ I ] THE CONJUNCTIVE OR ABSOLUTIVE IN ইলে «-ilē».

736. The conjunctive in ইলে «-ilē» is based on the passive participle in «-il-», and it is occasionally an adjective and occasionally a noun, like the «-(i)ta-» participle in Sanskrit and also like its cognate «-al-» form in Bihārī. It is adjectival in character when it occurs absolutely with a noun or pronoun : e.g., রামে মারলেও ম'রবে, রাবণে মারলেও ম'রবে «Rāmē mārle-ō mōrbē, Rābāṇē mārle-ō mōrbē» *he (Kālanāmi) will die, whether Rāma kills him or Rāvaṇa*; আমি তাকে দিলে তবে সে বাচে «āmi tākē dilē tābē sē bācē» *he would live only if I give him*; and it is a verbal noun where it occurs with the genitive, e.g., আমার না দিলে কিছু আসে যায় না, কিন্তু তোমার দেওয়া চাই «āmārā nā dilē kichu āsē jāy nā, kintu tomārā dēwā cāi» *it doesn't matter (lit. nothing comes or goes) through my not giving, but you should give (lit. your giving is wanted)*; or where it forms an absolute clause word : e.g., দিলে হয় «dilē hāy» *it would be well to give, it won't be bad to give, lit. if there were a giving, it may be (good)*; cf. Standard Colloquial (dialectal) আমার আদেখলার = «আদেখিলাএ «āmārā ādēkhlāy < «ā-dēkhlā-ā-ē» *me not seeing, during my not seeing.*

«-il-ē» is a locative form, and as a locative it has an absolute or conditional force. It can be compounded with other verbs in «-itē» and in «-iyā», to express, in the former case, a subjunctive or purposive gerund (e.g., করিতে গেলে «kāritē gēlē» *if one is to do, when one is to do, খাইতে দিলে «khāitē dilē» when one gives to eat, if one is given to eat*), and, in the latter case, to denote a past conditional (e.g., খাইয়া গেলে «khāiyā gēlē», *after one has eaten or after one has started to eat on, or, after one has finished eating, দেখিয়া নিলে «dēkhiyā nilē» after one has finished seeing, etc.*). Unlike the conjunctive in «-iyā», it cannot be repeated to indicate repetition or continuity : e.g., করিয়া করিয়া, ক'রে ক'রে «kāriyā-kāriyā, kōrē-kōrē» *having done again and again, but not «kārilē-kārilē»*, the reason apparently being that as a past base «-ilē» is already perfective and final, and continuous or imperfect action cannot be well expressed by it. This

doubling of the «-iyā» or «-i» conjunctive is found OB., and also its equivalent form in MIA. and OIA. (e.g., saṁsmṛtya saṁsmṛtya, pītvā pītvā, etc.)

Instances of the conjunctive in «-ilē» from OB. and MB. : (Caryā 2) «rāti bhaile» *when it is night*; (5) «sāṅkama-ta caṣṣilē» *after getting upon the bridge*; (20) «-jaubana mōra bhaile si pūrā» ? *as soon as my youth was mature*; ŚKK., p. 84, নান্দ গোপ ভনিলে হৈবের কোণ গতি «Nanda-gōpā ṣuṇilē hāibērā kōṇā gāti» *what will be the fate (then), when the cowherd Nanda hears?*; p. 98, তপত দুধ নালে ন পীরে, জুড়াইলে দোআদ তার «tāpātā dudhā nālē nā piē, juṛāilē sōādā tāra» *hot milk is not drunk through a straw, its taste (comes) when it is cooled*; p. 107, বল কইলে জানাবিবে রাজা «bālā kāilē jāṇāyibō rājā» *shall make the king know if you use force*; p. 297, যে বুধি করিলে রহে আশ্রয় জীবন «jē budhi kārilē rāhē āshraya jīvanā» *by doing such contrivance by which my life can endure*; p. 299, হেন কাম করিলে নাসিবে তোর পাশে «hēnā kāmā kārilē nāsibō tōra pāśe» *shan't come near you if you do such a thing*; etc. etc.

The conjunctive use of the locative form of the «-il-» base is found in other Eastern Magadhan : e.g., Oṛiyā «dēkhilē» *if one had seen, when one has seen*; Assamese «hāl-ē, hāl-āt» (= Bengali «hāilē, \*hāilē-tē»). In Maithili, Magahī and Bhōjpuriyā, the ablative of the verbal noun in «-al-» is used : e.g., Maithili «carī nahī bhēṭṭālā-sā» *through not getting fodder*, «ghumalā-sā ki lābh ahī» *what profit is there from wandering about* (Grierson, 'Maithili, Grammar,' p. 48 : the adjectival «-al-» is rather restricted in Maithili, see Grierson, pp. 113-114, and hence the locative absolute use of it is not found in Maithili, corresponding to Bengali সে এলে «sē ēlē» *on his coming*, etc.); Bhōjpuriyā «paṛhalē, paṛhalē-sē» (Hoernle, 'Gaudian Grammar,' § 488). With the locative use of the «-il-» participle in Bengali we may compare the Hindūstānī oblique use of the past participle to denote a condition or sequence (see Platts, 'Hindustānī Grammar,' pp. 337-338 : e. g., kyū itnī rāt gayē tum āyē «*why have you come at this late hour of the night, lit. when so much of the night is gone* : = কেন এত রাত গেলে তুমি এলে «kēnā ētā rātā gēlē tumi ēlē»), «pahar din carhē, mai utrā» *when the sun had risen to one watch, I came down* = বেলা এক পহর হ'লে «bēlā



ekā pāhārā hōlē » ). Compare also Marāṭhī « cālalyā-s », dative of the perfect participle in « -l- », = *having walked*.

The use of the passive participle locative, absolutely, with a noun or pronoun in the locative, to indicate the conjunctive, is found in OIA. and MIA. : e.g., « dr̥ṣṭē sūryē, punar api bhavān vāhayēd adhya-śēṣam » (Mēgha-dūta) : « alē, lāa-śālāē haggē ; gōṇā maḷē (=maḍē), aṇṇē kiṇiśśam ; pavahaṇē bhaggē, avalam̐ ghaḷiśśam ; tumaṇ maḷē (=maḍē), avalē pavahaṇa-vāhakē huviśśadi » *I say, I am the king's brother-in-law ; if the oxen are killed, I shall buy others ; if the carriage is broken, I shall have another built ; if you die, then there will be another carriage-driver* (Mṛcchakaṭṭika) ; etc., etc.

[II] THE CONJUNCTIVE IN *ই* « -i », *ইয়া* « -iyā », *ইয়ী* « -iyā̃ ».

737. In the « sādhu-bhāṣā », the gerund or conjunctive is formed by adding « -iyā » to the root : চলিয়া « cāl-iyā » *having gone*, রাখিয়া « rākh-iyā » *having kept* : in the Standard Colloquial, this « -iyā » is contracted to « -ē », and there is mutation of the preceding vowel : চলৈ [c̣ōlē, রেখে [rekhe]. In MB., especially in West Bengal texts, « -iyā » also occurs in a nasalised form, side by side with the non-nasalised one, and this is written *ইয়ী*, *ইয়ী*, *ইয়ী*, *ইয়ী* « -iyā̃, -iñā, -ñā, -iñā̃ » etc. This nasalised form was a living one in some forms of West Bengali, and at the present day it occurs as (*ইয়ে*, *ইয়ী*) « -(i)yē, -iyyā̃ » [iṣ] in the West Rājha dialects. In addition to this « -iyā, -iyā̃ », MB. (and the NB. language of poetry) has another form—in « -i » ; e.g., চলি, রাখি « cāl-i, rākh-i ». The Caryās show all the three, as « -iā, -iā̃, -i (-i) » : thus, « -i, -i » : (1) পাণ্ডি *having spread* ; (2) দুধি *having milked*, চুরি *having stolen*, থিরা কৰি *making steady* ; (4) কাঁপি *having pruned*, কুম্ভি *having kissed* (6) চাড়া *giving up* ; (7) দেখি *having seen*, গাই *having gone* ; (9) পাই *having entered* ; (15) চাড়া ; (16) সুনী *having heard* ; (21) উঠি *having got up* ; (22) রচি রচি *building again and again* ; (26) ধুনি ধুনি *carding (cotton) again again* », etc., etc. ; « -ia » : (1) দিঠা (=diḍha) *karia making firm*, পুচ্ছিয়া *questioning* ; (5) প্ৰা(দ) *splitting* ; (10) ভাঙিয়া *breaking* ; (15) বুজিয়া *having closed* ; (39) নাসিয়া *destroying* », etc. ; « -iā » : (2) দেখিয়া = ? *dekhia having seen*, বাহিয়া

walking (< bearing) ; (11) *māriā* having killed ; (12) *tōjiā* destroying, *kariā* having done ; (35) *bhaṇiā* having spoken ; (50) *laīā* having taken > ; and < -iā > : < (26) *laīā* having taken, (50) *diā* having given (= instrumental postposition) > ; etc.

In South-East Bengali (Chittagong and Chakma dialects) there is an affix *নে* < -nē > (-iā-nē), or *নৈ* < nāi > (-i-nāi) which figures in connexion with the < -iyā-i > conjunctives : e.g., *আইয়ানে* < āiyā-nē > having come, on coming (Chittagong : LSI., V, I, p. 313), and < *jēi-nāi* > having gone, < *ēi-nāi* > having come (= *āisi-nāi*), < *jāgi-nāi* > having kept awake, < *hāi-nāi* > having become, < *di-nāi* > having given, < *dēi-nāi* > having seen (= *dēkhi-nāi*), < *bēi-nāi* > having sat down (< *bahi-nāi*, *basi-nāi*), etc. (LSI., V, I, pp. 324 ff.). This < -n- > affix seems to be connected with the < -ā, -nā, -yā > of OB., MB. and dialectal NB. (W. Bengali). We can compare the Early Oṛiyā conjunctive affix < -iṇā >, found plentifully in literature (e.g., Jagannātha-dāsa's 'Bhāgavata, Kaṇṇa-janma' : < *emāntē śuṇi Śukā yāti, hāṣiṇa rājā-ku kṣāhanti* > hearing this, the sage Śuka after having smiled, says to the king : ibid., 'Rāsa-līlā,' < *pāṣiṇa gālē ēhi bātē, dēkhiṇa cāhanti ucātē* > entering, they went by this way ; seeing, they look sadly ; 'Rukmiṇī-haraṇa,' < *kānyāku kārāṇa snānā* > after having bathed the bride ; < *bhāṣiṇa sārbe kālē cūrā* > breaking, they pulverised everything, etc., etc., occurring side by side with the other Oṛiyā conjunctive affix < -i >, the one which in actual use now. But apparently this < -iṇā > form is obsolete now.

In the other Magadhan speeches, the < -i > affix is the only one which obtains, and in the Bibārti dialects this < -i > conjunctive is strengthened by the conjunctive of < ✓ kar >—< kar-i > (also in Oṛiyā, where it often becomes < kiri >, e.g., < *dekhi-kiri* > having seen), < kar >, or by a dative postposition < kai, kā, kē >. The < -i > conjunctive features in other NIA. : the < -i > is sometimes dropped (as in Awadhī and Hindōstānī), but generally it is reinforced by < kari, kar > or by some post-position.

So far as Bengali is concerned, we have thus these forms : < -i ; -i-ā ; -i-ā > ; and connected with the last is S.-E. Bengali < -i-nē, -iā-nē ; -i-nāi, -iā-nāi >, and Oṛiyā < -iṇā > .



In the Māl Pāharīā dialect of Western Bengali (Santal Parganas), the word হেনক < hēnākṣ > is added to the conjunctive, which sometimes retains the nasalisation characterising this West Rājha speech : *e.g.*, গুটিয়াই হেনক < guṭiyāi hēnākṣ > *having collected*, উঠি-হেনক < uṭhi-hēnākṣ > *having risen*, গায়ে-হেনক < gāyē-hēnākṣ > *having gone*, আসি-হেনক < āsi-hēnākṣ > *having come*, etc. (LSI., V, I, pp. 99, 100). This word < hēnākṣ > occurs also with the noun : *e.g.*, চালচলন-হেনক < cālṣ-cālāṣ-hēnākṣ > *following (bad) ways, through bad ways*. This < hēnākṣ > is obscure, but it may be a verbal noun from < √hā—hānṣ > (= Standard Bengali হান < hāṇṣ >) put in the dative and used postpositionally (cf. the change of < √kār > to < √kēr > in the same dialect). In any case, the conjunctive with < hēnākṣ > stands apart in Bengali dialects.

738. The conjunctive has always had a most important place in the history of IA., and in giving this place to this form in IA., Dravidian influences seem to have something to do. In the Vedic speech, the conjunctive is formed by < -tvī, -tvā, -tvāya >, which are old cases of a verbal noun stem in < -tu > (this < -tu > also figures, in the accusative and dative < -tum > and < -tavē >, as infinitive affixes in OIA.), and by < -yā, -yā (t-yā, t-ya) > (Whitney, 'Sanskrit Grammar,' §§ 989 ff.). The < -tvī, -tvā, -tvāya > group occurs with the root not compounded with a preposition, adverb or substantive, and the < -(t)yā, -(t)ya > group occurs with the root when it is so compounded : but this rule was not adhered to in many early Skt. works (Whitney, 'Sanskrit Grammar,' § 990, 2), and was entirely ignored in MIA., no discrimination along that line being made in their use. In addition to these affixes, it can be assumed, from the statements of grammarians (*e.g.*, Pāṇini, VII, i, 48) and from the forms actually in use in Early MIA. (Pālī, Aśōkan Prakrits), that other ones—< -tvī-nam > and < -tvā-nam >, and probably also < tū-nam >—were also in use in OIA., although they have not been found in Vedic and Skt. literature. In Early MIA., the affixes employed are : (Pālī) < -tvā, -tvāna, -tūna, -ya > (the last often assimilated with preceding consonants), < -iya > (with a developed < -i- >, from the preceding one), and < -yā-na, -iyā-na > (a comparatively rare form, with < -na > added to < -ya >, or < -yā >, by analogy of < -tvā :

-tvā-na > : cf. W. Geiger, 'Pali Grammatik,' §§ 208 ff.), as well as < -tuṃ > of the infinitive (in a few rare cases : E. Müller, 'Pali Grammar,' p. 128); and (Asōkan) < -tpā < -tvā >, < -ti = -tti < -tvī >, < -tunaṃ >, < -ya, -tya > (assimilated), besides < -tu > (= < tuṃ > of the OIA. infinitive, transferred to the conjunctive : cf. A. C. Woolner, 'Asoka Inscriptions, Text and Glossary,' Calcutta, 1924, I, p. xxxvii). In Second MIA. the forms employed or noted are : < -tvā > -ttā, -tā (after nasals) > ; < -tvā > \* -tu(v)ā > -dua > ; < -tvānam > -ttāṇaṃ > ; < -tvānam > \* -tuvāṇaṃ > -tuāṇaṃ > ; < -tūṇa(ṃ) > -dūṇa > -ūṇa(ṃ) > ; < -tvī > -ppi, -pi, -vi > ; < -tvīnam > -ppiṇu, -piṇu, -viṇu > ; < -tya > -cca > ; < -ya > -ia > (also assimilated forms) ; and also < -(i)yāṇa(ṃ) >, like the Pali < -(i)yāna > ; and through a blend of < -tvā > and < -tyā, -tya >, there is < -cā >, and through contamination with < -tvāṇa(ṃ) > -ttāṇa(ṃ) > and < -yā > -yāṇaṃ >, there arose also the further extended form < -cāṇa, -cāṇaṃ > ; besides, there is < -ā > (< OIA. -āya), as well as < -ya > -ia > -ī > as in Apabhraṃśa (Pischel, 'Grammatik der Prakrit-Sprachen,' §§ 581-594). And in addition to all these, a form < -dāṇi > is given by Vararuci (X, 16) for Māgadhi (this < -dāṇi > is probably for < -ttāna >, with < -d- > on the analogy of < -dūṇa < -tūna >).

Of all these forms found in Second MIA. through the whole of the Indo-Aryan tract, the employ of particular ones in different parts of the country can roughly be noted. The < -tvī(naṃ) > -ppi(ṇu), -vi(ṇu) > form occurred in the Gujarātī-Rājasthānī area (cf. H. Jacobi, 'Bhavisatta-kaha,' p. 42 ; 'Sanatkumāra-carita,' p. 18 ; Tessitori, 'Grammar of OWR.,' § 131, 1). The < -tūna > -dūṇa > -ūṇa > affix was current in Mahārāṣṭrī (but the Modern Marāṭhī < -ūn > for the conjunctive, with the dental < -n- >, does not represent the Mahārāṣṭrī < -ūṇa >, but is another form, < -ō-n-i, -au-n-i > in Early Marāṭhī, of nominal origin, in which < -n-i > is a post-position : cf. Jules Bloch, 'Langue Marathe,' pp. 261-262). The affix which seems to have been commonly employed in the North-East, in the Midland, and in the North-West, and also in the South-West, in the Late MIA. period, was < -ya > -ia, -i >, and probably also < -ī >. The MB., Oṛiyā, Assamese, Bihārī, as well as Eastern Hindī and Western Hindī < -ī > is



obviously derived from it : also the OB. strengthened form « -ī » ; and « -ia » occurs also as an archaic literary form in OB. It also seems very probable that the extended form of « -ya », namely, « -iyāṇa, -(i)yāṇa(m) » (as in Pali and Ardha-māgadhī, the latter an eastern speech : Pischel, § 592) was current in the form of Māgadhī Apabhraṇśa prevailing in Bengal : and this « -(i)yāṇa(m) » can easily give the dialectal Bengali *ইয়াঁ* « -iyā », *ইয়াঁ* « -iñā » : cf. MIA. « tāṇa(m) » > *তাঁ* « tā », « tēṇa(m) » > *তৈ* « tē » (*supra*, p. 373). In S.-E. Bengali, the nasal could well be preserved (cf. East Bengali *তান* « tāṇ » honorific genitive < « tāṇa[m] = tēsām ») ; and this « -iyāṇa(m) » form (of which « \*-iṇa, -ina » is evidently a contraction), looking like a verbal noun, was put in the locative in Chittagong Bengali and in Chakma (-iyān-ē, -in-āī). Cf. the use of « -mi » in Haijong : *দেখিয়ামি* « dēkhiyā-mi » *having seen*, etc. (*supra*, pp. 751, 775). We cannot postulate any postpositional form « -inai » for the S.-E. Bengali (like the suffix in Gujarātī « karī-nē » *having done*, « thāī-nē » *having been*) : such a post-position (« -nai < kaṇṇahī- < karṇa- » : 'Tessitori, 'Grammar of OWR.,' § 131, § 71) is unknown to Bengali. The Oriyā « -i-ṇa » is simply by analogical addition of the « -ṇa » to the « -i » form : MIA. « \*calia, caliyāṇa(m) » probably gave rise to a similar juxtaposition in Māgadhī Apabhraṇśa « calī, calīṇa(m) ». The Bengali strong form, and the most characteristic one, *viz.*, « -iā, -iyā » is apparently the « -i » form fortified either with the definitive « -ā » or with the « -ā » from « -iyāṇa(m) » > -iā ».

739. Tessitori derived the Gujarātī conjunctive in « -ī » (as in « cālī-nē » *having walked*, « mālī-nē » *having struck*) from the passive participle in « -ia » (nom. « -iu », locative « -ii », whence « -ī »), rather than from the Apabhraṇśa absolute in « -i » ('Grammar of OWR.,' § 131). This is quite likely, and the use of the postpositional affixes is indeed a strong support. It is even probable that in the North Indian languages, where the conjunctive has been fortified by a postposition (like « kē » in Hindōstānī), the passive participle form had exerted some influence. But « OIA. \*cal-ya » > calia > calī, cali > NIA. calī, cal » is a perfectly normal development. And even the OB. form in « -ī », « cāpi » *having pressed*, etc., can represent a MIA. « -ia » : it can be well surmised

that in some dialects of Apabhraṃśa, Second MIA. <-ia> became <-i> in the NIA. (cf. *supra*, 'Phonology,' pp. 302-303, 307), side by side with <-i> by simple dropping off the <-a> in this most commonly used affix.

**740.** The lavish use of the conjunctive is a noteworthy characteristic of Bengali, as of other NIA. speeches. Tibeto-Burman (Boḍo) influence has been suggested in this connexion (J. D. Anderson, 'The Origin of Bengali,' JRAS., 1911, p. 524). Dravidian influence is equally likely, or perhaps likely to a greater extent, from MIA. times (see *supra*, p. 175). For NIA., this is a characteristic inherited from MIA. There is nothing unnatural in a Bengali sentence like ভোরে উঠে, হান সেরে চারটি খেয়ে নিয়ে, জিনিষগুলো সঙ্গে বেধে নিয়ে গাড়ীতে চড়িয়ে দিয়ে, পথে তার বাড়ী হ'য়ে তাকে তুলে নিয়ে, সময় থাকতে ষ্টেশনে পৌছে টিকিট ক'রে আটটার গাড়ী ধ'রে চ'লে বেও <bhōrē ũṭhē, snāṇḍ sērē cār-ṭi khēyē-niyē, jiniṣḍ-gulō sāṅgē bēdhē-niyē gārī-tē cāṇiyē-diyē, pathē tāṛḍ bārī hā'yē tākē tulē niyē, sāmāyḍ thāktē ṣṭēṣāṇē pāuchē, ṭikiṭ kārē āṭ-ṭā-rḍ gārī dhārē cālē jēō> (with 15 conjunctives and only one finite verb) = *get up early, finish your bath, have some breakfast (of rice, etc.), bind up the articles and take them with you, put them down on the top of the cab, go to his house on the way and pick him up, arrive at the station in time, buy your ticket and catch the 8 o'clock train and leave*: and such <-iyā> <-ē> sentences have their prototype in MIA. —in Pali and in Classical Sanskrit : e.g., Pali, <cōrā kujjhivā...tiṇhēna asinā brāhmaṇaṃ dvidhā chinditvā, maggē chaḍḍetvā, vēgēna anubandhitvā, tēhi cōrēhi saddhim yujjhivā, tē sabbē pi mārētvā, dhanam ādāya puna dvē kōṭṭhāsā hutvā, aññamaññam yujjhivā, adḍhatiyāṇi purisa-satāṇi ghātētvā, etēna upāyēna yāva dvē janā avasiṭṭhā ahēsuṃ tāva aññamaññam ghātayimṣu> (Vēdabbha Jātaka); and Sanskrit, <atha sa brāhmaṇas tam paśuṃ rākṣasam matvā bhayād bhūmau nikṣipya dāivam nirbhartsya gṛham uddiṣya prasthitah>, or <sa duṣṭāśayō bakah kramēṇa tām prstham ārōpya jalāśayasya nātidūrē śilām samāśādy tasyām ākṣipya svēcchayā bhakṣayitvā bhūyō' pi jalāśayam samāśādy jalacarāṇām mithyā-vārttā-sandēśāḥ manāṃsi rañjayann (=rañjayitvā) ābhāra-vṛttim akarōt> (Pañca-tantra).



741. The conjunctive in «-iyā» is frequently used as an adverbial gerundive: it is either repeated, or is used singly: in the latter case, generally it is of similar meaning with the finite verb modified by it, and the two form a compound verb: e.g., কান্দিয়া কান্দিয়া রাণী আইল বাহিরে «kāndiyā kāndiyā rāṇī āilā bahirē» *the queen came out weeping* (Kṛttivāsa, 'Ayōdhyā-kāṇḍa,' p. 20); কবিরী বঁধা «kāṣiyā bādhā» *to bind tight*; টানিয়া ধরা «ṭāniyā dhārā» *to hold tight*; চুটিয়ে বলা «cuṭiyē balā» *to speak fully, not to mince matters* (colloquial); চাপিয়া বসা «cāpiyā bāsā» *to sit heavy*; হাঁটিয়া > হেঁটে চলো «hāṭiyā > hēṭe calō» *walk quick!*; চ'লে এসো «cā'le ēsō» *come quick!* (see *infra*, under 'Compound Verbs.')

742. Occasionally in MB. we find «-ā» for the «-i» of the conjunctive: e.g., ŚKK., p. 348, পরিধান কর নেত বাসে «pāridhānā kārā nētā bāsē» *having put on a fine garment*; p. 361, কেহে সর জাইতে যোকে বোল «kēhē sārā jāite yōkē bōlā» *why do you ask me to move away?*; VSP., p. 860, চরণ পাখাল আশুন মহাশয় «cārāṇḍ pākhalā āsunā mahāśayā» *please go wash your feet, sir* (lit. *come after having washed*). Cases like these do not demonstrate the presence of a form in «-ā» in MB., either a verbal noun, or due to the loss of «-i», for the conjunctive: these are simply due to scribe's mistakes for করি, সরি, পাখালি, etc. In 'aryā 27: «adha-rāti bhara kamala bikasin» *through half the night the lotus blossomed*, where «bhara» may be for «bhari», as in other NIA. speeches, or it may be regarded as the second part of an adverbial compound «adha-rāti-bhara» (see *supra*, p. 702).

[K] VERBAL NOUNS, AND THE INFINITIVE IN ইতে «-ite»

743. The following are the forms for the Verbal Noun in Bengali:

- (1) the অন «-āṇḍ» noun, with extensions of the affix as অনা, না «-āṇā, -nā» and অনী, উনী, নী «-āṇī, -unī, -nī»;
- (2) the অ «-ā, -ḍ» nouns, with an extension ই, ই «-ī, -i»;
- (3) the ই «-i» nouns;
- (4) the nouns in আ «-ā» from the simple passive participle;
- (5) the nouns in ইল «-il-» from the «-il-» passive participle;
- (6) the nouns in ইব «-ib-» from the future passive participle.

**744.** (1) This group of affixes has been discussed before ('Formative Affixes, No. 5, 5a, 5b,' pp. 656-658, *supra*). It is one of the most widely used forms from OB. times. Instances from the Caryās: \* (2) dharāṇa; (22) marāṇa; (36) cēṇa, bēṇa (< cētana, vēdana); (46) phuḍaana = phuḍaṇa (sphuṭana) >; MB. examples are copious. The extended \* -ā > form is also found in the Caryās: *e.g.*, (21) \* jēṇa tuṭaa (= tuṭai, tuṭai = truṭyati) avaṇā-gavaṇā (= āgamana-gamana) >; cf. also (7) \* avaṇā-gavaṇē Kāṇhu bimana bhaṭilā (= bhaṭilā) > *K. has become sad at this coming and going* (= saṁsāra): this \* avaṇā-gavaṇā >, or \* āvaṇā-gavaṇā > of OB. has given the NB. আনাগোনা < ānā-gōnā >.

In Hindōstānī the \* -nā > affix (= \* -nau > in Braj-bhākhā, \* -nō > in other W. Hindī dialects), same as the Bengali অনা < -anā >, is used as the infinitive: also its equivalent \* -ṇā > in Panjābī.

**745.** (2) This is a verbal noun in অ < -ā > which is quiescent, but which is traceable only in roots ending in a consonant (see *supra*, pp. 895-896). Thus, NB. বোল < bōlā > *speech*, eMB. (ŚKK.) \* bōl-ā >, OB. (Caryā 41) \* bōl-ā >, MIA. \* bōll-ā > (cf. Suffix No. 1, p. 652). There was a feminine (diminutive) extension of this by \* -ī > < \* -ī < -ia > < \* -ikā > (see *supra*, Suffix No. 24, pp. 672 ff.): thus, NB. and MB. বুলী < bul-ī, bul-i > *speech*, OB. (Caryā 41) \* bōl-i >, MIA. \* \* bōlliā < bōlliā >; so ফেরি, ফিরি as in ফিরি করা < phēri, phiri kārā > *to hawk goods*, মুড়ি as in মুড়ি দিল < muṛi dilā > *covered (oneself) up* (< gave a covering up), etc.

This verbal noun affix (-ā, -ā), and the next one (-ī), have become much confused in Bengali (in the Standard Colloquial), owing to the formative affix being dropped in each case: but it is still possible to distinguish the latter by the presence of the epenthetic \* -ī > in the dialectal forms of words which originally had it.

**746.** (3) The verbal nouns in ই < -ī > form a much larger class, but the affix is now no more a living one (see *supra*, Suffix No. 25, p. 674). The verbal noun in \* -ī > is known to Maithilī, *e.g.*, \* dekhi, dēkh > (Grierson, 'Maithilī Grammar,' p. 109); and it seems that it is used to form the compound tenses like \* dēkhai-chī > *I am seeing, I see*



(*\* dēkhai* = oblique of *\* dēkhī*), *\* dēkhai-achī*, *dēkhaichī*, *dēkhaich* = *he sees*, etc. It seems to occur in the other Bihārī speeches—*\* dēkh* = *\* dēkhi*, oblique *\* dēkhē*.

747. The Infinitive in Bengali appears to be the Verbal Noun (3) put in the locative. The Infinitive proper in Bengali has the characteristic affix ইতে *\*-itē* (in the Standard Colloquial reduced to তে *\*-tē* with mutation of preceding vowel) : e.g., করিতে, চলিতে, বাইতে *\*kār-itē*, *cāl-itē*, *khā-itē* = *to do*, *to go*, *to walk*. This *\*-itē* of course is entirely different from the present participle affix *\*-itē* (*ante*, p. 999). The *\*-itē* of Bengali is best explained as the old verbal noun in *\*-i*, plus the locative affix *\*-tē*, dialectally *\*-t* as in Chittagong. The formation seems to a new one in Bengali. Thus, আমাকে বাইতে হইবে *\*āmākē jāitē haibē* = *I shall have to go, I must go* (lit. *with-reference-to-me in-the-act-of-going* i.e. *to-go it-will-be*); সে চলিতে পারে *\*sē cālītē pāre* = *he can walk* (= *he in-the-act-of-walking is-able*); করিতে লাগিল *\*kārītē lāgilā* = *began to give*, দিতে চাহিল *\*ditē cāhilā* = *wanted to give* (but দিতে দিতে চাহিল *\*ditē ditē cāhilā* = *wanted [or gazed] while giving*); বাইতে দাও *\*jāitē dāo* = *let go*. The *\*-itē* form is used with roots like চাহ *\*cāh* = *to want, to look at*, হ *\*hā* = *to be*, দে *\*dē* = *to give, to allow*, পার *\*pār* = *to be able*, যা *\*jā* = *to go*, to denote Acquisitives, Permissives, Desideratives and Gerundives (see below, under 'Compound Verbs'). In other NIA. speeches, a verbal noun is also used : e.g., *\*mōtē jibāku hēbā* = *I shall have to go*, besides *\*jāi hēbā*, where *\*jāi* is certainly a verbal noun in the locative; Bhōjpuriyā *\*bahē lāgal*, Maithilī *\*bahē, bahai laglāh* = *began* (plural or honorific) *to blow*; Assamese *\*bābā-lāi dhārē* = *blows*; Early Awadhī *\*lagē parōsana nipuna suārā* = *clever cooks began to serve* (Tulasī-dāsa, 'Rāma-carita-mānasa'); W. Hindī *\*bolnē lagā* = *began to say*, *\*jānē dō* = *let go*, *\*khānē hōgā* = *will have to eat*, etc., etc. Cf. the use of the *\*-ibā-* noun in OB. and MB. (below, pp. 1017-1018). For the use of a verbal noun form in a similar construction in OWR., see Tessitori, 'Grammar of OWR.', §§ 132, 134.

There is in Ardha-māgadhī an infinitive in *\*(i)ttāē* (cf. Pischel, § 578) : *\*pucchittāē* = *to ask*, *\*sumarittāē* = *to remember*, *\*tarittāē*

to cross, etc. This could easily give the Bengali ইতে <-itē>, through a Māgadhi Apabhraṃśa form <\*-ittai> (this form <-ittāē>, attested from Ardha-māgadhi, could very well have occurred in Māgadhi Prakrit also). But it is not likely that this has been preserved in Bengali. The <-itē> form does not occur in any other Magadhan language. The Standard Bengali <-i-tē> has a dialectal form <-i-tā>, where the <-tā> is obviously the locative <-tā>, and this <-i-tā> cannot represent the MIA. <-ittāē>—the loss of two final syllables would be an insurmountable difficulty. The evidence in favour of a later, nominal origin of <-i-tē> as a locative form is exceedingly strong, not only from Bengali itself (with its use of the <-iba> noun), but also from other cognate speeches.

The OIA. infinitive affixes were <-tum>, <-i-tum> and <-(i)tavē>, respectively the accusative and dative forms of the verbal noun in <-(i)tu>. They are preserved in Pali as <-(i)tuṃ>, <-(i)tavē>, and in Asokan as <-(i)tuṃ> which passed on to the conjunctive in some dialects (cf. A. C. Woolner, 'Asokan Text and Glossary,' I, p. xxxvii), but it remained in Second MIA. as an Infinitive as <-(i)ḍuṃ>, <-(i)uṃ> (Pischel, § 573 ff.). This affix is not preserved in NIA, and neither is <-(i)tavē>, which seems to have fallen into disuse in Second MIA. itself (unless <-ittāē> is its form in Second MIA., as Pischel thinks with E. Müller, 'Grammatik der Prakrit-sprachen,' § 578).

The <-itē> Infinitive is liable to be confused with the <-itē> Present Participle, and it is at times difficult to decide which form it really is: e.g., তাহাকে যাইতে দেখিলাম <tāhākē jāitē dēkhiḷām> I saw him going, where <jāitē> may be equally the Present Participle = (while) going, or the Verbal Noun locative = in the act of going. (See *infra*, under 'Periphrastic Tenses.') In Chittagong Bengali, this verbal noun has become so much confused with the participle that by contamination it takes personal affixes: e.g., অঁই যাইতাম লাগুগিলাম <āi jāitām lāggilām> I began to go, তুঁই যাইতা লাগুগিলা <tūi jāitā lāggilā> you began to go, হিতে যাইতা লাগুগিলা <hitē jāitā lāggilā> he began to go, (Basanta Kumār Chatterji, VSPdP., 1926, p. 114); Noakhali dialect,



খাবাইতা লাইগজ *khābāitā laig-ja* [laigzo] > *to feed you have begun* = Standard Bengali খাওয়াইতে লাগিয়াছে *khāwā-itē lāgiyāchā* (LSL, V, I, p. 309). The *«itē»* also figures in Chittagong as ইতু *«-itu»* e.g., বাইতু লাইল [zaitu lail] *began to go* (= Standard *«jāitē lāgilā»*), where the *«-u»* seems to be for *«-ō»* < *«-ā»*, by confusion with the present participle base in *«-it-ā»*.

748. (4) The passive participle in *«-ta, -ita»* can be used as a noun of action in Skt. and in Pkt.: e.g., *«na bahunā śrutēna; tasya gatāgatam kō'pi na jānāti; nṛtyād asya sthitam manōharam; mahā-svanāir dundubhi-nāditāis ca; madhuraṁ hasitam, madhuraṁ aśitam, madhuraṁ calitam madhuraṁ ramitam; madhuraṁ tassa bhāsitaṁ; ēkassa caritaṁ seyyō; kataṁ ca sukataṁ seyyō; sucaritaṁ carē; avakidē viśumalēdi (= apakṛtam vismarati)»*; etc. The passive participle in *«-(i)ta»* > *«-(i)a»* obtained the definitive *«-ā»* in OB., and from that resulted the Bengali verbal noun as well as passive participle in *«-ā»* (see *supra*, 'Formative Affixes, No. 7,' p. 660; also non-l passive participle form, *supra*, p. 944). The *«-ā»* form occurs in Assamese: e.g., *«jowā»* [zowa] *going*, *«śowā»* [xowa] *sleeping*, *«kārā»* *doing*, etc. It is found in Oṛiyā: e.g., *«dēkhā»* *sight, seeing*, *«jāñā»* *knowing*, etc. It does not occur in the Bihārī dialects and in Eastern Hindī. But in the Hindōstānī passive participle formation (e.g., in expressions like *«kiyā-karnā, jāyā-karnā, dēkhā-cāhnā»*, compound verbs) the form is really a verbal noun.

In MB., the *«-ā»* verbal noun is not so prominent, nouns in *«-ibā»* and *«-ānā»* being more popular: but its occurrence is not rare. Thus, VSP., p. 68, বান্ধা নিছে *bāndhā nichē»* *taken in pledge*; p. 83, চিনা পুছা *cinā puchā»* *recognising and enquiring*; p. 123, দিয়া নাড়া দেই তাড়া *diyā nārā dēi tārā»* *gives a shake, and then drives away*; elsewhere MB. and NB. লেখা জোখা *lēkhā-jōkhā»* *writing and computing*, নাচা *nācā»* *dancing*, কেনাবেচা *kēnā-bēcā»* *buying and selling*, রান্নাবান্না *rādhā-bārā»* *cooking and serving*, etc., etc.

The Bengali *«-ā»* form has been derived by some from the verbal noun in ইবা *«-ibā»*: *«cālibā»* > \**cāliwā»* > \**cālīwā»* > *cālā*; *khāibā»* > \**khāiṭwā»* > *khāwā»* (cf. 'Prabāsi' for Aṣṭāḍha, 1324, p. 264). But this line of

derivation is inadmissible: the MIA. < -bb- > results in < -b- > in Bengali, whereas a form like < khāwā > can be written and pronounced < khāā >, and the < w̄ > there is euphonic only (see *supra*, pp. 338-342, 533). To derive < khāā > from < khāibā > would be to postulate the entire loss of a MIA. double consonant group in a NIA. language—a phonological development not found in the Bengali Standard Dialect: and the < -ā > form is a Standard Dialect form. It would indeed be difficult for the same form to occur as < -ibā > and as < -ā > side by side in the same dialect and at the same time.

749. (5) The verbal noun in ইল < -ilā > is now obsolete in Bengali, but it occurred in Early Bengali, though not very commonly. The verbal form in < -ilā > in the locative figures partly as the absolutive conjunctive (in < -ilē >), for which see *supra*, p. 1004. It occurs also in Assamese and Early Oṛiyā. In the Bihārī dialects its equivalent, the < -al > verbal noun, is exceedingly common. It figures also in Marāṭhī. Examples in Bengali: OB.: < bhēlā bihani > (Caryā 23) = হইলো বিহনে (বিনে, বিনা) < hāilē bihānē (binē, binā) > *without having been*; MB.: ŚKK., p. 249, বিনি বাচিলে < bini jācīlē > *without asking*; Vaṇṣī-dāsa's 'Padmā-purāṇa,' p. 435, হারাইলা হেনা বাসি < hārāilā hēnā bāsi > *I regard it as lost = as a loss*; তুমি জনমিলা হতে < tumi jānāmilā-hātē > *from your birth*; 'Caitanya-Bhāgavata,' p. 71, তুমি দিলে বিনা < tumi dilē binā > *without your giving*; etc., etc. Cf. Oṛiyā, 15th century Inscription of Puraṣottama-dēva at Puri Temple (see *supra*, p. 107): < hārīlā-dōṣā > *sin of robbery*, < kālā > *doing*, genitive < kālā-rā >; Early Assamese, 'Ādi-caritra,' p. 72, < Śaṅkārē dēkhāilā cāhilā > *wanted to show Śaṅkara*; Modern Assamese < bul-il-āt > *on having said*.

For Bihārī, cf. Grierson, 'Maithilī Grammar,' § 183; for Marāṭhī, see LSI., VII, pp. 27, 31.

750. (6) The verbal noun in ইব < -ibā > is from the same source as the future base. This form occurs in all Magadhan languages: it is regularly declined like any other verbal noun, although in NB., its employ has been restricted to the base ইবা < -ibā > (combined with মাত্র < mātra > to form an adverb—e.g., বলিবামাত্র < bālibā-mātra > *immediately*



after speaking, দেখিবামাত্র < dēkhibā-mātrā > on seeing, etc.) and the genitive ইবা-র < -ibā-rā > (e.g., দিবার < dibā-rā > for giving; ইবা < -ibā > itself may represent an old genitive form: see *supra*, p. 752). Thus, OB. (Caryā 8) < bāhaba-kē (= bāhiba-kē) pāraa (= pārai) > is able to row, = MB. বাহিবারে পারে < bāhibārē pārē >; eMB. (ŚKK.), p. 3, মানুষ নিয়োজিল মারিবাক তাঁও < mānuṣā niyōjilā māribā-kā tāē > employed a man to kill him; p. 200, ফুল তুলিবাক তরে < phulā tulibā-kā tārē > with a view to pluck flowers; p. 395, হাতিবাক < hāṭhibā-kā > to walk, etc.; 'Caitanya Bhāgavata,' p. 11, মথুরা দেখিব করি < Māthurā dēkhibā kārī > for to see Mathurā; Vāṇṣī-dāsa's 'Padmā-purāṇa,' p. 108, আছে আছিবার মত নদীয়া নগর < āchē āchibārā mātā Nādiyā-nāgarā > there is the city of Nadiyā (if at all a town were) to exist; p. 165, লাগে বলিবার < lāgē bālibārā > begins to say; p. 473, আছুক ছুইব আরে < āchu-kā chuibā ārē > ah, let alone merely touching; p. 592, দেখাইব করি < dēkhāibā kārī > with a view to show; p. 608, দিবা করি < dibā kārī > with a view to give; VSP., p. 609, ভূমিতে টালিব করি < bhūmitē ṭālibā kārī > with a view to throw on the ground; p. 620, মারিবার মোক < māribārā mōkā > to kill me; etc., etc. The < -ib- > form is much used in North Bengal. The present progressive tense is formed in Assamese with the verbal noun in < -iba >: e.g., < kārībā-lāi dhārē > is doing. In Assamese, the < -iba > noun is fully declined: e.g., < kārībā, kārībā-r, kārībā-lāi, kārībā-t >; so in Oṛiyā: < kārībā, kārībā-ku, kārībā-rā, kārībā-ru >, etc.; also in the Bihārī dialects, e.g., Maithilī < karab, karābā-k, karāb-ē, karābā-sā, karābā-mē >. The use of the < -(i)tavya > form as a verbal noun is found in other NIA., like E. Hindī, e.g., < calab, karab >; W. Hindī, e.g., Brajbhākhā < calibāū, karibāū >, oblique < calibē, karibē >; Rājasthānī (Mārwarī), e.g., < mārabō, calabō >; Gujarātī, e.g., < mārṇū, calṇū >; and Marāṭhī, e.g., < uṭhāvayā-, mārāvayā- >, etc. In most of these (e.g., E. Hindī, Brajbhākhā, Rājasthānī, Gujarātī) this form is used as an infinitive.

751. Relative Participle Adjectives are formed in Oṛiyā and in the Bihārī dialects with the past and future passive participles used adjectivally: e.g., Oṛiyā < mu-dēbā dhānā > money that is to be given by me, < mu-kālā kāmā > work that was done by me = Bihārī < hamar kail kām >. The < -ib-, -il- > forms are not used in Bengali as adjectives for this purpose.

The past participle in « -ā » is so used, to denote the past relative idea : *e.g.*, আমার পরা কাপড় « āmarā pāra kāpāṛṛ » *cloth (dhōṭī) worn by me*, তার করা কাজ « tāṛā kāṛā kājā » *work done by him* : the employ of the « -il- » form is unknown. The « -ib- » verbal noun is used in the genitive, beside the verbal nouns in « -ā » and in « -āṇṛ » , to indicate the present or future relative participial idea : *e.g.*, আমার পরিবার (পরার, পরনের) কাপড় « āmarā pāribā-rā (pāra-rā, pāraṇ-ērā) kāpāṛṛ » *'dhōṭī' worn by me, to be worn by me* ; ভিক্ষা দেবার চাঁল « bhikṣā dēbārā cā'la » *rice set apart for giving as alms* ; জল খাবার ঘটা « jāla khābārā ghāṭi » *(water) vessel to drink water from* ; etc., etc. We have this genitive use of the verbal noun, rather than mere adjectival juxtaposition, from Early Bengali times.

Verbal Nouns of Reciprocity are treated below, under 'Reduplicated Verbs.'

[L] THE COMPOUND OR PERIPHRASTIC TENSES :

PROGRESSIVE AND PERFECT.

752. The following are the types of these tenses which are found in New Bengali :

(1) চলিতেছে, চলিতেছিল (চলিতে থাকিবে) « cālītēchē, cālītēchila (cālītē thākibē) » *is walking, was walking (will be walking)* ; করিতেছে, করিতেছিল (করিতে থাকিবে) « kārītēchē, kārītēchila (kārītē thākibē) » *is doing, was doing (will be doing)*. This is the typical Progressive Form of Standard Literary Bengali. It is made up of the verbal form in « -itē » plus the substantive verb « āch » conjugated and employed as an 'auxiliary' (« āch » for the past, « thāk » for the future). The « ā- » of « āch » is absorbed by the preceding « -ē » of « -itē », but in dialectal Bengali of East Bengal the full forms চলিতে আছে, চলিতে আছিল, করিতে আছে, করিতে আছিল « cālītē, kārītē + āchē, āchila » etc. still occur.

This progressive form is the recognised one in the « sādhū-bhāṣā », and is found in the Vanga dialects : some typical forms may be given [tso(I)ltese, tso(I)ltesilo, ko(I)rtese, ko(I)rtesilo ; tso(I)lte ase, tso(I)lte asilo, ko(I)rte ase, ko(I)rte asilo], also [tsoltase, tsoltasilo ; kortase, kortasilo]. But it is not current in the spoken dialects of Rāḍha (including



the Standard Colloquial of Calcutta and the Bhāgirathī basin), of Varēndra, and of Kāmarūpa.

(2) A type, which occurs in MB. as a verbal form in ই < -i > *plus* the substantive verb < āch > (contracted to < -ch- >), in the present generally, and rarely in the past. The future with this < -i > form is unknown. Thus, MB. চলিছে, চলিছ < cāli-chē, cāli-chā >, করিছে, করিছ < kārī-chē, kārī-chā >, চলিছিল < cāli-chila >, করিছিল < kārī-chilā >. This form is used in MB. in a vaguely continuative or progressive sense, and also in a perfect sense. With static verbs, it can easily indicate the progressive idea. In NB., the < -i > of < cāli >, which underwent epenthesis, is now dropped. It occurs in Assamese (where the < -i > is retained), generally as a progressive in the present, and always as pluperfect in the past, but the perfect sense for the present form is also found.

This ill-defined tense form of MB. has given the West Bengali (including the Standard Colloquial) present and past *progressive* forms, like চলছে, চলছিল, করছে > করছে, করছিল > করছিল [ cōlō(h)e, cōlō(h)ilo ; korō(h)e, korō(h)ilo, korōhilo, korōhilo ] ; in North Central Bengali and North Bengali, it retains its vague employ, being used both for the present progressive and the present perfect in the present form, and for the simple past or past perfect in the past form, exactly as in Assamese. In the East Bengal dialects, it is used regularly for the *perfect* only, e.g., [ tsolse, tsolsilo ; korse, korsilo ; tsolse, tsolsilo, korse, korsilo ] = *has walked, had walked ; has done, had done*,—the progressive sense being indicated by the < -itē > form in the East Bengali dialects.

The < -i > form occurs also in Oṛiyā, but here it is definitely perfect, and in the past and future Oṛiyā employs its characteristic root < √tha > : thus < kārī-āchāī, kārī-chāī > *has done*, < kārī-thilā > *had done*, < kārī-thibā > *he will have done*.

(3) A Perfect form made with the passive participle adjective in ইল < -il- > *plus* the substantive verb < āch > (contracted as usual). This is comparatively a rare form, and occurs in West and Central Rāḍha dialects (e.g., হ'লছে < hōlā-chē > *has become*, ম'লছে < mōlā-chē > *has died*, গেলছে, গেলছিল < gēlā-chē, gēl-chilā > *has gone, had gone*, in Murshidabad, Birbhum

etc. ; cf. LSI, V, I, p. 72) ; and also in North Bengali (e.g., আইন্ চে < āin-cē = āil-chē > *has come* : LSI, V, I, p. 174) ; and it seems to be confined to intransitive verbs and to denominatives and causatives of denominative origin.

(4) A Perfect form in ইয়া < -iyā > plus the substantive verb (< āch > in the present and past, and < thāk > in future) : in the MB., < -iyā >, or < -iā >, occurs also in the nasalised form < -iñā, -iyā, -iā > : thus, MB., and NB. < sādhu-bhāṣā > চলিয়াছে, চলিয়াছিল ( চলিয়া থাকিবে ) < cāliyāchē, cāliyāchilā (cāliyā thākibē) > *has walked, had walked (will have walked)* ; করিয়াছে, করিয়াছিল ( করিয়া থাকিবে ) < kāriyāchē, kāriyāchilā (kāriyā thakibē) > *has done, had done (will have done)* ; MB. (generally in West Bengal), besides the simple < -iyā > form in a variety of spellings, we find also চলিয়াছে, চলিয়াছে, করিয়াছে, করিয়াছে < cālīñāchē, cāliyāchē, kārīñāchē, kārīyāchē > etc. This perfect is found in NB., specially in the Rāḍha dialects, with < -iyā > contracted to < -ē, -iyē > and < -iñā, -iyā > to < -ē, -iyē > [ -ē, -iē ] : e.g., Standard Colloquial চলেছে, ক'রেছিল [c̣ʰolec̣ʰ(h)e, korec̣ʰhilo], in other Rāḍha dialects, চলছে, ক'রেছিল [c̣ʰolēc̣ʰhe, korēc̣ʰhilo], etc. It occurs also in the Vangā dialects, but never with the nasalised form : and it seems there it is less common for the perfect than the < -i > form (No. 3 above). The < -iyā, -iyā > form seems properly not to belong to the dialects of the North, and its presence there is due to literary and other influences. In some cases, this form indicates a static or continuous process also : see *infra*, § 757.

753. The progressive (whether in the < -itē > form or in the < -i > form), as can be plainly seen from MB. literature, is comparatively a late time-idea in the Bengali verb. The progressive does not seem to have been fully established in the language before the 17th century ; and although both the < -itē > and < -i > forms occur in literature of the 15th, their occurrence is but extremely rare and hesitating, in authentic texts, and the < -i > form is found both for the progressive and the perfect. In Early MB., the simple present is used for the progressive. The beginnings of the development of the compound progressive in < -itē > and of the compound indefinite tense in < -i >, however, can be taken back to the 14th century : for



already in the ŚKK. we have instances of both : thus, *e.g.*, কালিনীর তীরে বহে মন্দ পবনে। তোম্বাক চিলিত্তে আছে নান্দের নন্দনে। « Kālinirā tīrē bāhē māṇḍā pābanē : tōmbākā cintitē āchē Nāṇḍērā nāṇḍānē » *the gentle breeze is blowing (lit. blows) by the bank of the Kālindī (= Yamunā) : the son of Nanda is thinking of you* (p. 202 : here in « cint- » we have not a native Bengali root, but a *ts.* one, as described *supra*, p. 879), and ধিরে ধিরে কাহ্নাঈ মো আইলো নিকটে। নিহুড়িঁ চাহোঁ পাণি লইছে মোকটে। « dhirē dhirē Kāṇhāṇi mō āilō nikṭē, niḥuṛiṇā cāhō pāṇi lāichē mōkṭē » *gently, O Kṛṣṇa, I have come closer : I bend down and look, the water has come up (or is coming up ?) to the brim* (p. 153). The form লইছে « lāi-chē » would show that it was an old one, some time having elapsed for the fuller « lāi+āchē » to be so contracted. The « -itē » form for the progressive is thus certainly found in West Bengali of the ŚKK., but it is most curious that it would not be used in the West Bengal dialects of present day as a proper native dialectal form.

The origin of these different periphrastic methods may be now discussed.

754. (1) The « -itē », MB. « -itē », is doubtless the present participle : চলিতেছে = চলিতে আছে « cālītēchē < cālītē+āchē » *he is walking < he is while in the act of walking*. The « -it-ē » is apparently the locative : or is it merely the nominative—MIA. « calanta-ka- », nom. Māgadhi « calantakē » calantaē > calantaī > calantē > cālītē ? (see *supra*, p. 741). The non-locative form, presumably the nominative, occurs in dialects as « cālīt-āchē = cālīt-āchē » etc. But « -itē » is more likely the locative. In Early Assamese, there was a similar construction with the locative, but the periphrasis here did not develop into a compound tense by combining the participle of the verb substantive, as it has in Eastern Bengali and in Standard Bengali : thus Śaṅkara-deva (15th century) and other Early Assamese writers frequently employ constructions like « sūryā-sāmā sâbē jwālāntē āchāhā » *you are all shining like the sun*, « āchē prākūśāntē » *ore manifesting*, « upāsāntē āchē » *are worshipping*, etc. As in Assamese, so in W. Bengali this participle progressive did not catch on in the spoken dialect, although the « sadhu-bhāṣā » took it up. It does not seem to occur in Kṛttivāsa (VSPd. edition), nor even in Kavi-kanṇa, both West Bengal writers (of the 15th and 16th centuries). But

in East Bengal writers, *e.g.*, Mādhavācārya, author of 'Caṇḍī-kāvya' (16th century : cf. VSP., p. 335, হোতেছে < hōtēchē > *is happening*), Chuṭi Khān (Noakhali : 'Māhābhārata,' VSPd. ed., p. 59 : তবে সেই রক্ষিণ দেখিতে আছে < tābē sei rakṣi-gaṇḍa dēkhitē āchēntā > *then the guards remain watching*), Vaṇṣī-dāsa ( 'Padmā-purāṇa,' p. 380, দেখিতেছি < dēkitēchi > *I am seeing*, p. 580, করিতেছে < kāritēchē > ) etc., the < -itē > is well-established from the 16th century. And from the early 17th, it is found in the West Bengal writers also, like Kāśī-rāma Dāsa (*e.g.*, VSP., p. 676, হইতেছে < hāitēchē >, p. 685, দিতেছে < ditēchē > ). The prose documents, whether in East or in West Bengal, had to employ a definite form for the progressive, and it seems < -itē > became accepted in epistolary and documentary Bengali in the 17th century, and from that it was adopted into the < sādhu-bhāṣā > of the 18th and 19th centuries ; but West Bengal spoken dialects did not use it. The progressive < -i > form of the spoken dialects of West Bengal has now been adopted for the progressive, as a matter of course, in the new literary dialect of Bengali based on the Calcutta Colloquial.

The construction, present participle ( < -ant- > of OIA. ) *plus* verb substantive, occurs in other NIA (excepting Oriyā and Assamese) : in the Magadhan speeches (*e.g.* Maithilī < dēkhait-chī, dēkhait-chalahū >, Magahī < dekhait-, dekhit-, dekhat + hī, halu > ; Bhōjpurīyā < dēkhāt bānī > dekhatānī >, etc.); in E. Hindi (*e.g.*, Awadhī < dēkhat ahū, dēkhat raheū > ); in W. Hindi (*e.g.*, < dēkhtā hai, dēkhtā thā > ); in Panjābī (*e.g.*, < jāndā hai, jāndā sī > ), in Rājasthānī and in Gujarātī (*e.g.*, Gujarātī < mārātō batō >, Mārwarī < mārātō hō > *was beating* ); in Marāṭhī (*e.g.*, < uṭhat āhē, uṭhat hōtā > *is, was rising* ); in Pahārī (*e.g.*, Khas-kurā < garda-cha, garda thīyo > *is doing, was doing* ), etc., etc.

755. (2) The < -i > form is rather rare in eMB., but it becomes noticeable from the 15th and 16th centuries : *e.g.*, KKC. (Vanga-vāṣī edition), p. 112, পীত তড়িত বর্ণে, হেম মুকুলিকা কর্ণে, কেশ মেঘে পড়িছে বিজলি < pitā tāritā bārṇē hēma-mukulikā kārṇē kēśa-mēghē pārichē bijuli > *yellow, like lightning in colour, a little flower of gold has fallen (= is disposed) like lightning in the clouds of her hair* ; p. 122, কেমনে ধরিছ হিয়া < kēmātē dhārichā hiyā > *how are you holding your heart (= how can you remain*



unconcerned)?; Vanṣī-dāsa, p. 3, শোভিছে • śōbhichē • is appearing beautiful; p. 34, ভাবিছেন • bhābichēṅ • is thinking, etc. Cf. also Chuṭī Khān's 'Mahābhārata' (VSPd. ed.), p. 10, এহেন বুলিছে পূৰ্বে বৰ্ষ মহীপাণ • ēhēṅ bulichē pūrbhē dhārmma-māhīpāl • so has said formerly the righteous king (Yudhiṣṭhira); p. 21, বত পুণ্য কৰি আহম কায় বাক্য মনে • jāta puṇyā kāri ācham kāyā-bākya-mānē • all the merits I have earned in body, word and mind; p. 22, রাজার সাক্ষাৎ বসিছন্ত মুনিগণ । পাৰ্শ্ব মিত্র চারি পাশে কৰিছে শোভন • rājār sāksāt bāsichāntā muni-gaṇ, pātrā-mitrā cāri pāsē kārichē śōbhānt • in front of the king are sitting (were seated) the sages, and courtiers and friends are adorning in the four sides; etc. It is of comparatively frequent occurrence in Late MB., but the meaning is not often fixed for either of the two tenses. In Early Assamese of the 15th century, this • -i • form is already well established.

The source of this form in this construction is not clear. It would appear at first sight to be merely the conjunctive in • -i •. The perfect in • -iyā, -iyā • would similarly appear also to have the conjunctive in it. But the conjunctive would not accord well with the progressive sense, which we see is connected with this construction, side by side with the perfect one, in both MB. and NB. and in Early and New Assamese. The • -i • form, to indicate the perfect, might be, in the case of the intransitive verb, the non-l passive participle in • -ita > -ia > -ī, -ī •: • calia > calī > calī + āchē • gone + is = is gone, has gone (= calitō' sti). The Maithili Progressive tense in • -ai • + • √ch •, e.g., • calai-chī • I am walking, • karaī-ch • he is doing, seems to indicate a possible source for the • -i • form of Bengali. Grierson explains this • -ai • progressive of Maithili as being a contracted form of the • -ait • present participle ('Maithili Grammar,' p. 173: • dēkhai chī < dēkhait chī •). But, as suggested in the present work, p. 1022 *supra*, the • -ai • may well be a verbal noun locative: for it would be strange indeed for the full • -ait • and a contracted • -ai • to be in living use side by side in the same dialect and at the same time. So also compare the Magahi forms like • dēkha, dēkhē + hī • I see, beside progressive • dēkhait (dēkhat, dēkhit) + hī • I am seeing. The Rājasthānī dialects and Gujarātī, as well as some forms of Western Hīndī, have a periphrastic

present in which the present forms of the verb properly conjugated are used with the verb substantive in the corresponding person and number: e.g., Marwārī «caḷḷ-hū» *I go*, «caḷḷ-hā» *we go*, «caḷai-hai» *he goes*, «caḷai-hai» *they go*; Jaipurī = «caḷḷ-ehū, caḷḷ-ehā; caḷai-ehai, caḷai-ehai»; Gujarātī «cālū-chū, cālī-ehi; cāl-ehē»; Brajbbhāḥā «calaū-haū, calai-hai; calai-hai, calai-hai», etc. The Bihārī compound tenses are not of the type found in the Western languages: here the form of the principal verb is unchanged—it is «-ai, -a, -ē» in all cases. Can the «-i» in Bengali-Assamese be a locative form of an OB. verbal noun in «-ia» = the OIA. passive participle in «-(i)ta»? OIA. «calita» > «calia», in Late MIA. (Māgadhi Apabhraṃśa); locative OIA. «calitē» > «calī» > \*calīi; this would become «\*calī, calī» in OB., and then used with the root «āch»: «calī-āchē, calī-ehē» therefore would mean *in-the-act-of-walking is = is walking*; so «dēkhi-ehē» *in-the-act-of-seeing is = is seeing*. The «-i» form in Bengali can thus include both the locative (to develop into the progressive) and the nominative (in the case of the intransitive verb, to indicate the perfect—later this sense occurring with the transitive verb also by extension) of the «-ita > -ia» passive participle—in the former case it being the verbal noun, in the latter the participle. The Oriyā «-i» form, indicating as it does the perfect tense only, naturally is to be taken as the Oriyā variant of (4), for which see below (p. 1027).

With the idea that the composite «sādhū-bhāṣā» is the source of the dialects, the W. Bengali চ'লছে, চ'লছিল, ক'রছে (ক'ছে), ক'রছিল (ক'ছিল) etc., are commonly regarded as contracted forms of the «sādhū-bhāṣā» চলিতেছে, চলিতেছিল, করিতেছে, করিতেছিল, etc. But that such is not the case is seen from the occurrence in MB. and in the NB. language of poetry of forms like চলিছে, করিছে in the progressive. The «sādhū-bhāṣā» চলিতেছে করিতেছে, etc. can only give চ'লতেছে, ক'রতেছে [çʰolteçʰhe, kʰorteçʰhe], etc. in the Standard Colloquial, but such forms are not proper to the dialect, and when they occur at all, they are artificial, being due to an attempt to find colloquial equivalents of a literary form which is only too familiar: the forms চলিতে, করিতে «calitē, kārītē» (as participles and verbal nouns in «-itē») occur as চ'লতে, ক'রতে [çʰolte, kʰorte (kotte)]. The doubling of the



affricate in the case of roots which end in a vowel, like খাচ্ছে, যাচ্ছে, পাচ্ছে, দিচ্ছে, শুচ্ছে « khācchē, jācchē, pācchē, dicchē, śucchē » [khac̣ʃ(h)e, ʃṭac̣ʃ(h)e, pac̣ʃ(h)e, dic̣ʃ(h)e, ʃuc̣ʃ(h)e] *is eating, is going, is receiving, is giving, is lying*, with past tense in ছিল « -cchilā », would at first sight suggest that it is a case of assimilation of the « -t- » of « -itē », and would thus connect these with the « -itē » form (« ditēcchē » > \*dit-chē > dicchē). But other West B. and North B. dialects do not show the doubling, even when in West B. these forms indicate the progressive. MB. দিছে « di(i)chē », বাইছে « jāichē » should occur in West Bengali as দিছে « dichē », বেছে « jēchē » (see *supra*, pp. 386-387), and so they do, for example, in Murshidabad and Birbhum (as present progressive: the corresponding past progressive forms are দিয়েছে « diyēcchē < diyā-chē, গেলছে « gēl-chē »). But in the Standard Colloquial, MB. « jāichē » became « \*jāy-chē », and it is this « -y- » which assimilated with the following « -ch- »: « jācchē »; so in « \*di(i)chē » it assimilated (it is possible by first becoming a glottal stop) to the « -ch- », as « \*diy-chē [diʔ̥che] > dicchē »; so śui-chē > \*śuy-chē > śucchē », etc.

The Oṛiyā speech forms its progressive tenses with the help of a verbal form in « -u », + the substantive verb: *e.g.*, « kārū-chi, kārū-chū; kārū-chu, kārū-chā; kārū-chi, kārū-chānti ». (For this « -u » affix, see *supra*, p. 678.) It is not unlikely that a similar form in « -u » was used in Rāḍha dialects contiguous to Oṛiyā, and that in Late MB. this form with the « -u » (not understood, and becoming quiescent in the middle of the word) merged into the « -i » form, or restricted the « -i » form to the progressive in West Bengali. But from extant documents, we cannot postulate with any amount of certainty a Rāḍha form « \*cālu-chē, \*kārū-chē » beside « cālī-chē, kārī-chē ».

756. (3) The perfect with the participle in « -la » is very much restricted in Bengali, and is only local for West Bengal, and probably also for North Bengal. In eMB. it may have been more prominent.

The construction, restricted as it seems to be to a few intransitive verbs, and to denominatives and causatives, is perfectly plain: W. Bengali আলছে « āl-chē » *has come*, হ'লছে « hōl-che » *has happened*, ম'লছে « mōl-chē »

*has died* (< MB. « māilā-chē » = « mṛtō'sti »). From the intransitive, the « -l- » affix first spread to the denominative and then to the causative. It agrees with the Bihārī perfect of the intransitive verb; but is different from that of the transitive (and by analogy, often of the intransitive) verbs (in the present and past perfect tenses) in Bihārī, where we have either the juxtaposition of two tenses (the past in « -l- » and the substantive verb present or past) each properly conjugated, or the instrument of the « -al- » participle used with the substantive verb (cf. LSI., V, II, pp. 28-29, 38-39, 52-53).

757. (4) The perfect in « -iyā, -iñā » is by far the most common of the compound tenses in eMB. It is found in a number of instances in the ŚKK.; and in Kṛttivāsa (VSPd. ed., Ayōdhyā, Uttara) it is well-established, and may be said to be fairly common in subsequent MB. literature. In Early Assamese, the « -iyā » form occurs with the substantive verb, but only as a separate word, and the « -iyā » and the substantive do not express the perfect idea. This « -iyā » form fell into disuse in later Assamese. Oriyā never developed the « -iyā » form, but had only the ones in « -i » and « -inā ».

Examples from eMB.: ŚKK.: p. 143, পাতিয়াছে « pātiāchē » *has established*; p. 175, শুণিয়াছ « ṣuṇiāchā » *you have heard*; p. 317, সূতিয়া আছিলো « sutiā āchilō » *I was asleep, I was sleeping*; p. 325, নিয়াছিস « niāchisā » *thou hast taken*; p. 376, বসিয়া আছেন্ত « bāsiā āchēntā » *has sat down, is sitting*; Kṛttivāsa, 'Uttarā-kāṇḍa,' p. 16, হঞাহেত « hāñā-chēkṣ » *has become*; p. 24, দিয়াছি « diñāchi » *I have given*; p. 177, সোয়া আছে « suā āchē » *is lying*; p. 201, জড়িয়া আছে « juriñā āchē » *is spread*, পড়িয়া আছে « pāriñā āchē » *lies*; etc., etc. The form is found copiously in other MB. works.

It would be seen that progressive or continuous action may be indicated in the case of intransitive verb; and such action is emphasised upon by keeping the « -iyā, -iyā » separate from the verb, in both MB. and NB.

The « -iyā, -iñā » form is doubtless the conjunctive: « niāchisā » being « niā + āchisā » = *having taken thou art* = *thou hast taken*. The nasalised form, current in West Bengal, is sufficiently indicative of its



proper nature. But that is not all. In the case of intransitive verbs, the « -iyā » form can equally represent the passive participle (see *supra*, p. 955): *সুযা আছে* « *suā āchē* » *is lying (has lain)* < *lain* (\* *svapita-* > *suvia-* > *suia-* > *su-ā*) + *is*, *চলিআছে* « *caliāchē* » *has gone* < *gone* (*calita-* > *caliā*) + *is*. Cf. NB. *এখানে বে বেশ গান চলছে!* « *ēkhānē jē bēśā gānā cālēchē* » *so, fine singing is going on here*; *মাদ্রাজে খুব উদ্বোধন চলিয়াছে* or *চলিতেছে* « *Mādrājē khubā udyōgā cāliyāchē* (*cālītēchē*) » *great preparations are going on in Madras*; *রাস্তার কাঁদা হ'য়েছে* « *rāstāy kādā hōyēchē* » *there is mud in the street*; *র'য়েছি* « *rōyēchi* » *I am staying*, etc. Cf. also the perfect with the participle in « -la »; and the perfect of the intransitive verb in the Bihārī dialects, and in other NIA. languages, like W. Hindi, etc. (e.g., Hindōstānī « *wuh gayā hai* » = « *asāu gataḥ asti* »; Gujarātī « *hū cālyō chū* » = « *aham calitaḥ asmi* »). The static and continuous use with the substantive verb separated or united can in this way be explained. So that the « -iyā, -iñā » form would seem to combine in Bengali both the conjunctive and the passive participle (the latter in the case of intransitives); but from Early MB., from the similarity of forms (« -iyā » for both of them) and from the nature of the constructions, any such original distinction was lost sight of.

The participle in « -iyā, -iñā » and the auxiliary have coalesced but loosely in Bengali. To emphasise an « -iyā-chē, -iyā-chilā » > « -ē-chē, -ē-chilā » form, the emphatic particles *ই* « *i* » and *তো* « *tō* » *indeed, surely* generally come in between, and not at the end. This is especially noticeable in the Standard Colloquial. Thus, *প'ড়ে-ই-ছে* « *pōrē-i-chē* » *it has fallen, to be sure*; *দিয়েই-তো-ছিলুম* « *diē-i-tō-chilum* » *I had indeed given, I had very nearly given*; *দিয়ে-তো-ছি* « *diyē-tō-chi* » *I have given in truth*; etc. The emphatic, however, can also come at the end: e.g., *প'ড়েছেই* *প'ড়েছে* « *pōrēchē-i pōrēchē* » *it has certainly fallen*; etc.

The use of root « *thāk* » for the future progressive and perfect is rather rare in MB.: « *√thāk* », when not put in the future, expresses a continuous state in compound verbs with the « -iyā, -iñā » form: e.g., ŚKK., p. 176, *বসিআ থাক* « *basiā thākā* » *remain sitting, remain seated*.

758. Two dialectal forms for the progressive tense may be noted.

(5) The 'South-West Bengali' progressive, made by combining the present tense of principal verb with  $\sqrt{\text{t̥ha}}$  'to remain' regularly conjugated: e.g., করিছি  $\sqrt{\text{kāri-t̥hi}}$  'I do + I remain = I am doing'; যাউছ  $\sqrt{\text{jāu-t̥hu}}$  'thou goest + thou remainest = thou art going'; হয়ছে  $\sqrt{\text{hāyā-t̥hō}}$  'he is + he remains = he is' (= Standard Colloquial হ'চ্ছে  $\sqrt{\text{hōcchē}}$ ). In some cases, the principal verb is not conjugated, but put in the conjunctive: খাবায়ছে  $\sqrt{\text{khābāyā-t̥hā}}$  'you are feeding'. (See LSI., V, I, pp. 108, 109 ff.) The Common Bengali  $\sqrt{-i}$  +  $\sqrt{-āch}$  >  $\sqrt{-ch}$  form is also known in this dialect. The root  $\sqrt{\text{t̥ha}}$  (< sthā) is not found elsewhere in Bengal. This use of two finite forms side by side is exactly of the type found in Brajbhākhā and in Rājasthānī-Gujarātī noted at pp. 1024-1025.

(6) In the district of Bogra, and in some other North Central Bengal tracts, there is a progressive form in  $\sqrt{-(i)t}$ ,  $\sqrt{-it}$  + root  $\sqrt{-āch}$ : thus করিতেছি  $\sqrt{\text{kāritē-chi}}$  'I am doing', করতুছ  $\sqrt{\text{kāritū-chu}}$  'thou art doing', করতিছে  $\sqrt{\text{kāriti-chē}}$  'he is doing', খাটিতেছি  $\sqrt{\text{khāṭṭitē-chi}}$  'I am labouring' (LSI., V, I, pp. 152-153). This form appears to be merely the  $\sqrt{-itē}$ ,  $\sqrt{-it}$  + participle further strengthened by the locative affix  $\sqrt{-tē}$ —it is really a double locative form:  $\sqrt{\text{kāritē}} + \sqrt{-tē}$ . The personal termination of the auxiliary substantive verb seems to have influenced the  $\sqrt{-itē-tē}$  of the principal verb form, and to have altered it accordingly, at least in the 2nd person:  $\sqrt{\text{kāritētē}}$ ,  $\sqrt{\text{kāritātē}} + \sqrt{-āchu}$  >  $\sqrt{\text{kārit(ē)tē-chu}}$  >  $\sqrt{\text{kāritū-chu}}$ .

The use of the  $\sqrt{-r}$  affix for the progressive in E. Vanga and S.-E. Vanga has been discussed before (pp. 994 ff.).

#### [M] CAUSATIVES.

759. The Causative in Bengali is made by adding the affix আ  $\sqrt{-ā}$  to the root, with euphonic  $\sqrt{-w}$  or  $\sqrt{-y}$  between vowels: e.g., কর  $\sqrt{\text{kār}}$  'to do' > করা  $\sqrt{\text{kārā}}$  'to cause to do'; খা  $\sqrt{\text{khā}}$  > খাওয়া  $\sqrt{\text{khāwā}}$  'to cause to eat'; দে  $\sqrt{\text{dē}}$  > দেওয়া, দেয়া  $\sqrt{\text{dēwā, dēyā}}$  'to cause to give'; জী  $\sqrt{\text{jī}}$  > জীয়া  $\sqrt{\text{jīyā}}$  'to cause to live'. There are of course old causatives of OIA. which do not add this  $\sqrt{-ā}$  affix, but show original root-modification (Ablaut) and behave like independent roots, which have been noted before (*supra*, pp. 876-877).



The source of this «-ā-» is the MIA. «-āva-», from OIA. «-āpa-ya-», which has been indicated above (*supra*, p. 880). The normal OIA. form «-aya-», with modification of the root vowel, became considerably curtailed from First MIA., and «-āpaya-» largely took its place. Thus we have in the Aśoka Inscriptions forms like «kārāpita-, pārāpita-, vivāsāpaya-, sāvāpaya-» (= Skt. *kārita, hārita, vivasaya-, śrāvaya-*), and in Pali «vasāpēti, sarāpēti (√smṛ), pucchāpēti (√pṛech), siñcāpēti, palāpēti», etc. This «-āpaya-» even invaded the domain of the denominative. In Second MIA., it became «-āva-, -āv-ē-», and when there grew a confusion between the «-aya- > -ē-» causative and the simple verb (see *supra*, pp. 933-934), the «-āv-, -v-» form with the unmistakable «-ā-, -v-» in it easily became established as the causative affix in Late MIA. and NIA.

In the Caryās, the causative affix occurs as «-āva-», as in «bandhāvaē» *causes to bind* (Caryā 22); and this «-āva-» was contracted to «-ā-» in MB. (*supra*, p. 350, *Phonology*). The «-ā-» causative has been extremely common in Bengali from its very origin.

**760.** The Verbal Noun from causative roots takes the affix আন, আনে, «-ānā-, -ānō-», which represents «-āpa-» base + «-na-»: cf. Skt. «dā-pa-na» *causing to give*, «jñā-pa-na» *causing to know, announcement*, etc. On the model of these, First MIA. built up forms like «\*kārāpana, \*cālāpana» etc.; and a generalised «-āpana» gave Second MIA. «-āvaṇa-», extended to «-āvaṇa-a-» by the «-(k)a» affix, which became the Bengali causal noun affix «-ānā-, -ānā-, -ānō-» ('Formative Affixes Nos. 13, 13a,' *supra*, pp. 664, 665).

**761.** Participles of the Causative.

The Active Present Participle has the usual affix ইত, ইতে «-it-, -itē-», contracted to «-t-, -tē-» in the Standard Colloquial (see *supra*, 'Formative Affix No. 10,' p. 663). The archaic form «-anta-» is not found with causative verbs. Assamese has «-āñtā»: «kārāñtā» *one who causes to do* (beside «kārāñwā» = «kārā-ñ-ā» with «-ñ-ā» affix, for which see pp. 678, 679), «khuwāñtā» *one who causes to eat* (beside «khuñwā»). Bengali has to indicate the active causative participle idea by a clumsy phrase—যে কৰায় সে, যে খাবায় সে «jē kārāy sē, jē khāwāy sē», etc.

The Causative Passive Participle affix is আন, আনো « -āna, ānō » (see *supra*, p. 666). Instances of « -ānā » are not very common in MB., but they do occur: thus, ŚKK., pp. 109, 116, 318 শুখান « śukhānā » *dried*; KKC. (Vajga-vāsi edition), p. 147 হারান « hārānā » *lost*; VSP., p. 263 (17th century text), সিঁজান « sijānā » *boiled*; etc. The more favourite way seems to have been the « -il- » affix (see *infra*, p. 1032). On the analogy of the verbal noun in « -ā », presenting an identical form with the passive participle in « -ā » (« cālā » = *a going*, also *gone*; « kārā » = *a doing*, also *done*), the « -ānā » affix, found also in the causative verbal noun, seems to have been strengthened for the passive participle in Modern Bengali.

The « -ānā- » affix does not seem to occur in Assamese, in Oṛiyā, and in the Bihārī dialects, but it is found in E. Hindī, and in W. Hindī, and it also occurs as a passive form in Rājasthānī-Gujarātī; thus, Tulasī-dāsa has forms like « phirānō, juṛānī, harakhānē, lapaṭānī, akulānī », etc.; in Early W. Hindī, the « -āna » was found, but now it seems to have fallen into disuse: thus, Kabīr has (ed. Kshiti-mōhan Sēn, III, p. 62) « māyā dēkha-kē jagata lubhānō, kāhē rē nara garabānō?.....prēma-kē hāṭha kāhē na bikānō? » *the world has been charmed seeing Māyā; why, O man, has been this boasting? why hast not been sold in the hand of love?* (it would be seen that in « bikānō » we have the causative passive participle; in the other two cases, and also in E. Hindī « harakhānē, akulānī, lapaṭānī » given above, the forms are denominative passive participles); in Rājasthānī, forms like « suṇāṇō, batāṇō » *was heard, was displayed*, etc., are past passive forms (from passive participles: cf. LSI., IX, II, p. 58); and in Northern Gujarātī, « -āṇō » is the passive participle affix for roots in « -ā », e.g., « mārāṇō » *was killed*, « dīṭhāṇō » *was seen*, « bharāṇō » *was filled*, etc. (LSI., IX, II, p. 343).

The source of this « -ānā » seems to be « -māna », the OIA. affix for the present participle for *ātmanē-pada* and passive verbs. The past sense can easily evolve in the passive verb: *being done, being caused to be done, caused to be done*, and also simply in the passive participle, *done*. There might be in this matter some influence from the « -na » passive participles of OIA., which in some cases came down to Late MIA., e.g.



• *diṇṇa*, *kiṇṇa*, *ruṇṇa*, \**liṇṇa* » etc. ; and already in one instance at least we have a passive participle use of « -*māna* » in Pali, in combination with « -*ta* », in « *vibhāta-māna* » *become bright* (Geiger, 'Pali Litteratur und Sprache,' § 191, note : Geiger, however, regards the reading as doubtful). The form « -*māna* » in Epic and Classical Sanskrit becomes « -*āna* », and « -*āna* » is the more common form (Whitney, 'Skt. Grammar,' § 1045 f.). The form « -*āna* » also occurs in Pali, and in later MIA. it is also found as « -*āṇa* », though there it cannot be said to be common. The passive participle use of « -*āṇa* » came in during Second MIA. : a form like « *palāṇa* » (= Skt. « *palāyita* » = Bengali † পালান, পালানো « † *pālāṇā*, *pālānō* ») already occurs in Jaina-Mahārāṣṭrī (Tessitori, 'Grammar of OWR.,' § 126 [2]).

**762.** In MB. and dialectal NB., the passive participle of causatives occurs with the usual « -*il-* » affix : e.g., ŚKK., p. 58, লোটাইল « *lōṭāilā* » *caused to be rolled, rolled* ; p. 318, আধাইল « *ākhāilā* » *soured, washed* ; East Bengali করাইল « *kārāilā* » *done, caused to be done*, জুড়াইল « *jurāilā* » *cooled* = Standard Literary and Colloquial « *kārāṇā*, *jurāṇā* ». In West Bengali, as in W. Murshidabad for instance, the « -*il-* » participle (contracted to « -*l-* ») occurs in the compound tense (perfect), but not independently : e.g., লাগালচে [lagalēʃho] *have you fixed?*, কি খেদালছিল [ki kholdēʃhila] *what were you feeding with?*, দেওয়ালচে [dēwālēʃe] *is causing to give*, etc. The « -*l-* » form occurs in the Oṛiyā and in the Bihārī dialects. Assamese however prefers the « -*ā* » form (« *kārōwā* » *caused to be done* = « \* *karāpita-* » + « -*ā* »).

**763.** Double Causatives—such as are found in Bibārī (e.g., Maithilī « *dēkhab* » *see*, causal « *dēkhāēb* » *show*, double causal « *dēkhābāēb* » *cause to show* ; « *girab* » *fall* > « *girāēb* » *fell* < « *girābāēb* » *cause to fell* ; Bhōjpuriyā « *dēkhal*, *dēkhāwal*, *dēkhāwāwal* », etc.), in Eastern Hindi (e.g., Lakhimpurī Awadhī « *hāsab* » *smile*, « *hāsāwab*, *hāsāwāwab* »), in Western Hindi (e.g., Hindōstānī « *karnā*, *karānā*, *karwānā* ; *dēnā*, *dilānā*, *dilwānā* »), in Panjābī (e.g., E. Panjābī « *sikkhnā* » *learn*, « *sikkhāṇā* [sikkhlāṇā, sikkhālāṇā], *sikkhwāṇā* »), in Rājasthānī-Gujarātī (e.g., Gujarātī « *karvū*, *karāvavū*, *karāvāvavū* »)—have not been found in Bengali and in Oṛiyā.

But they occur in a restricted way in Assamese (e.g., «kār, kārā, kārōwā»). The «-l-» causatives of Western Hindi and Panjabi, and of Rājasthāni-Gujarāṭī, and the «-ḍ-, -r-» causatives as in Rājasthāni-Gujarāṭī (cf. Tessitori, 'Grammar of OWR.', § 141 [3]), are also unknown in Bengali and its sister speeches. A few Hindōstānī «-l-» forms occur as loans: e.g., বাতলান «bātālānā» *to inform, to describe*, in slang or familiar colloquial; দেলান «dēlānā» *to cause to give* in Late MB.; and the nouns ধোলাই «dhōlāi» *a causing to wash > cost of washing*, সেলাই «sēlāi» *sewing* and ঢোলাই «cōlāi» *distilling*.

764. There is in Bengali a periphrastic way of forming the causative with the verbal noun in «-ā» and the verb করান «kārānā» *to cause to do*. This method is exceedingly common in Rājha Bengali, outside the Standard Colloquial: thus রাখ «√rākḥ» *to keep*, রাখা করান «rākḥā-kārānā» *to cause to keep*; so আনা করান «ānā-kārānā» *to cause to bring*, ডাকা করান «ḍākā-kārānā» *to cause to call*, খাওয়া করান «khāwā-kārānā» *to cause to eat*, দেওয়া করান «dēwā-kārānā» *to cause to give*, etc. The use of the causative form করান «kārānā» with *ts.* or *sts.* nouns is also common in Standard Bengali: e.g., স্নান করান «snāṇḍ-kārānā» *to cause to take a bath*, গান করান «gāṇḍ-kārānā» *to make sing*, নাচ করান «nācḍ-kārānā» *to make dance*, দাঁড় করান «dāṛḍ-kārānā» *to cause to stand*, etc.; such instances are extensions of nominal compound verbs with কর «√kār», and we have cases in the ŚKK. also—e.g., চেনন করান «cētānā kārānā» *to bring to senses*, পান করান «pānā kārānā» *to cause to drink*, etc.

#### [N] DENOMINATIVES.

765. Denominatives have occurred in all the periods of the language: e.g., «mātēla» (Caryā 50: mātā < matta); ŚKK., p. 159, খাঙ্গায়ে «khāṅgāyē» *will be angry* (khāṅgā *anger*); p. 158, খেআইলো «khēāilō» *I ferried* (khēā = *ferry*); p. 191, ভাঙলি «bhāṅḍāsi» *jestest*, ভাঙাইলি «bhāṅḍāili» *didst jest* (bhāṅḍa *fool, buffoon, knave*), আউলাইল «āulāilā» *dishevelled* (ākula); p. 372, বিষাইল «biṣāilā» *poisoned* (viṣa), etc.

Commonly in Bengali, the noun, if it is a short form (disyllabic > monosyllabic), is used as a root: চিন «cinḥ» (cihna)—চিনিবে, চিন্বে



• cinibē, cinbē > *will recognise*; তাত < tāṭṭ > *heat* (tapta)—তাতিল, তাত্‌ল  
 • tātilā, tātlā > *became hot*; পাক < pākṣ > (pakva)—পাকিতেছে, পাক্‌ছে  
 • pākītēchē, pākchē > *is becoming ripe*; কম < kām > *small, less* (Persian kam)—  
 কমিল, ক'মল < kāmīlā, kām'lā > *became less*. জম < jām > *gathering* (Perso-  
 Arabic jam\*)—জমিবে, জ'ম্বে < jāmibē, jām'bē > *will gather, will flourish*; etc.  
 But the distinctive affix for the denominative in Bengali is অ < -ā- > :  
 শাঁপ < śāṇṇ > *hone, whet-stone*, শাঁপাইল শাঁপাল < śāṇāilā, śāṇā'lā > *whetted*;  
 দাঁড় < dāṛṇ > *stick, rod*, দাঁড়ায় < dāṛāy > *stands upright, stands*; তল < tālṇ >  
 bottom, তলায় < tālāy > *goes to the bottom*; ঘন < ghāṇā > *thick*, ঘনাইতেছে  
 • ghāṇāitēchē > *is thickening*; MB. দঢ় < dāṛhā > *firm*, দঢ়ান < dāṛhāṇā >  
 to make firm; etc., etc. No definite rule can be laid down where the  
 formative affix is employed and where it can be dispensed with. Here-  
 in the NIA. Bengali is as arbitrary as OIA. and MIA.: cf. Sanskrit  
 • bhiṣakti, kṛṣṇati > beside • kṛṣṇāyatē, kavayati >. It may be noted  
 that in Dravidian, Kōl and Tibeto-Chinese, the root could be used both  
 as a noun and a verb.

The OIA. affixes to form the denominative (apart from cases where  
 no such affix was used) were • -a-, -ya-, -ā-ya-, -a-ya-, -i-y-a-, -i-y-a-, -ū-ya-,  
 -u-ya-, -s-ya (-ṣ-ya) >. The form • -ā-ya- >, resembling the causative  
 affix • -āpaya- (-āvaya) >, seems to have become more common than the  
 rest in Early MIA.; and the colourless or • -a- > form also was largely used  
 (cf. Geiger, 'Pali Litteratur und Sprache,' § 186, § 188). The causative  
 largely influenced, and then encroached upon the domain of the deno-  
 minative. In Pali, e.g., we find denominatives with the generalised MIA.  
 causative affix • -āpaya- >, like • ōpnñjāpēti > = Skt. • ava-puñjayati >,  
 • ussukāpēti > = • utsukāyatē >, and also causative-denominatives like  
 • sukhāpēti, dukhāpēti > (Geiger, § 187). In Second MIA., there is a  
 greater mix-up with the causative; the old forms are retained, but • -āya- >  
 is more prominent, and • -āya- > -āa- > and • -āpaya- > -āvē- -āv- >  
 approach each other (Pischel, §§ 557 ff.). As it has been seen before  
 (Bengali Denominative Passives in • -ā- >, *supra*, p. 929), the distinction  
 between the denominative and the causative is all but lost in NIA.,  
 being preserved only in the Bihārī dialects.

The verbal noun as well as the passive participle affix for the denominative is আন < -ānā >, which seems to be extended from the causative (see *above*, pp. 1030-1032). The verbal noun in < -ila > is also found in dialectal Bengali: OIA. < daṇḍāyita > > MIA. < daṇḍāña > + < -illa > > Bengali দাঁড়াইল, as in W. Bengali (Murshidabad) দাঁড়ান্ছে < dāṛāḍ-ḥē > *has stood so*; জুতুছিল = জুতাইছিল < jutulḥchilā < jutāilḥchilā > *gave a beating with the shoe*, < jutā shoe >; etc.

[O] VERB SUBSTANTIVE, AND DEFECTIVE VERBS.

766. Five roots express the substantive idea in NB.: আহ্ < āch >, হ or হো < hā, hō >, থাক্ < thāk >, রহ্ < rāh > and বট্ < bāt >.

Of these, < āch > is the most important. Bengali < āchē > *is, are* comes regularly from Second MIA. < acchaī > (which is found in Mahārāṣṭrī, Jaina-Mahārāṣṭrī, Ardha-māgadhī, Āvanti, Pāśācī and Western Apabhraṇśa: cf. Pischel, 'Grammatik der Pkt.-Sprachen,' § 480), First MIA. < acchati > (as in Pali). Various derivations of this MIA. root < acch > have been proposed, connecting it with either < √ās > *to sit* or < √as > *to be* (see Pischel, *loc. cit.*) The derivation favoured by Pischel is from OIA. < √r, rēch > *to go*, which also meant < mūrṭti-bhāva, indriya-pralaya, dravya-kāṭhinya > *to take a form, to have loss of the senses, to become hard*, according to the *Dhātu-pāṭha*. A verb meaning *to go* may develop the sense of *being*, and we find that in Kāśmīrī < gatsh > *to go* is very often used in the sense of *being, becoming* (cf. Grierson, 'Dictionary of the Kāśmīrī Language,' ASB., pp. 313, 315). But it is highly unlikely that this most widely used IA. substantive root (see following paragraph) should be merely a semantic development out of a verb meaning *going*, and that this development should have taken place as early as the First MIA. period, if not earlier. The most satisfactory derivation of < √acch, āch, ch > is from an OIA. < \* √acch >, which is not preserved in Vedic or Sanskrit. The Indo-European root < \*es >, = < as > of OIA., occurred in thematic forms as well: < \*es-e-ti > (which would correspond with a possible OIA. < \*as-a-ti >) and < \*es-ske-ti > (which would agree with an OIA. < \*as-cha-ti, \*acchati >), beside the athematic < \*es-ti > (= OIA. < as-ti >). Sanskrit grammarians do not recognise < -cha-, -ceha- >



as a verbal theme (= \* \* -ske-, -sko- > of Indo-European), occurring as it does in less than a dozen roots of Skt., *e.g.*, \* icch (< iṣ), uccch (< uṣ), ṛccch (< ṛ), gacch (< gam), pṛccch (< \* pṛṣ, cf. pṛṣ-ṭa), mṛccch (< mṛ), mūrch (< mūr), yacch (< yam), yuccch (< yu), vāncch (< van) > : but the source of this \* -cccha > in Indo-European, namely, \* \* -ske-, -sko- >, was a distinctive verbal theme which is of greater frequency and importance in other branches of IE. (cf. Brugmann's *Short Comparative Grammar*, French trans., pp. 549, 550 ; A. Meillet, 'Introduction à l'Étude comparative des Langues indo-européennes', pp. 185, 186). The \* \* -ske/o- > theme is found with \* \* √es > in a number of ancient Indo-European speeches—Greek (*e.g.*, Homeric preterit \* éskon, éske >), Latin (Old Latin future \* escit >) ; Tokharian (\* sketar > *is*, \* skente > *are*), Armenian (subjunctive \* ičem >). This derivation of \* acch, acchati > has been suggested by Sylvain Lévi and A. Meillet ('Remarques sur les Formes grammaticales de quelques Textes en Tokharien B : I, Formes verbales,' p. 28, from the 'Mémoires de la Société de Linguistique,' 1912). Cf. पृच्छ √pābhūch >, *supra*, pp. 344, 473.

The root \* āch (ch) > is now found in all Magadhan speeches except Magahī and Bhōjpuriyā. It seems that these two dialects also at one time possessed them, for it is occasionally met with in old poetry in Bhōjpuriyā (see *supra*, p. 167). Eastern Hindī similarly seems to have had it also : in Early Eastern Hindī, as in Malik Muhammad Jāyasī for instance, it figures (*e.g.*, at pp. 31, 35, 45, 53 of the ASB. edition,—\* āchahi, āchaī, āchahī >, which have been explained as meaning *good*, \* acchā >, by Sudhākara Dvivedī). The MIA. source dialect of Western Hindī, Śaurasēni, possessed it, according to Vararuci (XII, 19 : \* astēr acchah >) ; \* achnā > is recognised in Hindī as a root, and it seems that instances of it occur in Old Western Hindī poetry, but it is no longer a living form in that speech. It is found in Gujarātī as much as in Bengali, and it is equally common in some of the Rājasthānī dialects. In Marāṭhī, it is common as \* asṇē >. It figures also in most of the Pahārī speeches. The range of \* acch > thus appears to have been fairly extensive (see *supra*, p. 167). The loss of it in some of the NIA. speeches is nothing exceptional : witness the disuse of the Old English substantive verb \* weorðan > in New English,

while it is retained (as « werden ») in New High German. But it seems this root, despite its mention as a Śaurasēnī form by Vararuci, was not a popular one in the Midland: its being ignored by Sanskrit may be due to a restricted occurrence in the Midland; and Midland influence may have further curtailed it in Eastern Hindī and in Bhōjpuriyā and Magahī in recent times.

« āch » is a defective root in NB. as well as in MB. It occurs only in the present and the past in NB., but in MB. the imperative, present participle, conjunctive and verbal noun in « -iba » also are found. Thus,

Present: 1. আহি « āchi », 2. আহিস, আহ « āchis, āchā », 3. আহে « āchē », MB. আহএ « āchāē »; 2 and 3 honorific আহেন « āchēnē », MB. আহন্তি, আহেন্ত, আহন্ত « āchānti, āchēntā, āchāntā »;

Past: 1. (আ)হিলাম, ছিলুম, ছিলেম « (ā)chilām, chilum, chilēm », MB. (আ)হিলেঁ « (ā)chilē » etc.; 2. (আ)হিলি, হিলিস « (ā)chili, chilis », (আ)হিলা « (ā)chilā », হিলে « chilē », etc.; 3. (আ)হিল « (ā)chilā », ‡ আহলেক « āchālēk », MB. also (আ)হিলা « (ā)chilā »; 2 and 3 honorific ছিলেন « chilēnē », MB. (আ)হিলন্তি, (আ)হিলন্তি, (আ)হিলেন্ত, (আ)হিলন্ত « (ā)chilānti, (ā)chilānti, (ā)chilēntā, (ā)chilāntā »;

Imperative, MB. 3. আহউক « āchāuk », (আ)চুক, « (ā)chuk »;

Present Participle, MB. (আ)হিতে « (ā)chitē »;

Conjunctive, MB. (আ)হিয়া « (ā)chiyā, হিঅঁ « chi(y)ā »;

Verbal Noun, MB. আহিবা « āchibā ».

The aphæresis of the initial « ā- » is as old as eMB.: e.g., ŚKK. p. 124, হিতে « chitē », p. 232, চুক « chukā »; cf. also p. 124, আগুহিঅঁ « āguchiā » *having been before*.

In Oṛiyā, the past and future tense of « āch » shows another root, « tha » (as in « thilā » *he was*, « thilū » *I was*, « thibē » *they will be*, etc.), of which the source seems to be OIA. « √sthā » (« sthita > thia + -illa > thilā »; but cf. Early Assamese « thāilā » *remained* < \**thayā-* + « -illa »). 'S.-W. Bengali' uses a base « ṭha », also from « √sthā », but with cerebralisation, in the equivalents of Bengali হিল « chilā » etc., in



the compound tenses (see *supra*, p. 1029). Beside equivalents of « \*acehita + -illa », MIA. forms based on « sthita + -illa » were thus current in the Prakrit dialects brought to Bengal.

767. Root ह, ह (ह) « hā, hō ». This is apparently a single root in NB., but the form really represents two roots which have merged into one—one being « √ah » or « √ha » from OIA. « √as », the other « √hō » from OIA. « √bhū ». The distinction between the two is preserved in many NIA. speeches, at least in form : Thus, we have Magahi past forms « hal, halai » from « √ha », beside « hōl, bhēl » from root « √hō, bha = √bhū » ; W. Hindi has « hai » *is*, « hū » *am* (in Early W. Hindi literature frequently occurring as « ahai, āhai ; ahaū, ahū, āhū » etc., from « √ah, as »), beside « hōwē, hōē ; hōwū, hōū » *may be* (from « √hō = bhū »). Cf. Grierson, ' Maithili Grammar,' § 219, for « √ah » in Maithili. And in West Bengali, in the Khārīā-ṭhār dialect of Manbhum District, the verb occurs as আহর « āhāy » *is* (LSI., V, I, p. 97).

The OIA. « √bhū » became « hō, hū » in the NIA. languages. In MB., we have হু, হো « huē, hōē », with its equivalents « huāī, hōī » in Oṛiya and « hōwē » in Early Assamese. MB. and Assamese show beside these the form হা, হর « hāē, hāy », honorific MB. হরন্তি « hāyānti = hāānti » (p. 9, Chuṭī Khān's ' Mahābhārata '), হরন্ত « hāyāntā = hāāntā » (ibid., p. 56), হন্তি « hānti », etc. In the ŚKK., however, the « hō » form is extremely rare, occurring only once, and « hā » is the common form. In the Caryās, we find « hōi » and « hōnti », and the « ha, ah » form does not occur. The past tense of « √hō », apart from হোইল « hōilā » which has merged in হইল « hāilā » (< \*āh-il-ā), shows in OB. and MB., as well as in Early Assamese, the forms ভইল, ভয়িল, ভেল, ভেলা « bhāilā, bhāyilā, bhāilā, bhāilā », etc. A conjunctive ভই « bhāī » is also known. The « bha » base occurs also side by side with « hō » in other NIA. (e.g., W. Hindi (Hindōstānī) « hūā » beside dialectal « bhayā » ; and we can also note the Hindi verb « bhāwē » = « bhāvayati », (cf. the MB. ভাব « bhāy ») *seems*. OIA. « √bhū » gave « hō » through the occurrence of the verb in the middle of the sentence (see *supra*, p. 553), and side by side with this intervocal « -h- » modification, the original initial « bh- » seems to have remained as a stereotyped form in the same area.

In MIA., all roots of OIA. tended to conform to the thematic «-a-» group. Root «as», athematic in Vedic and Sanskrit, would thus seem to have developed a thematic form «\*as-a-ti» beside «as-ti», if this did not already exist in OIA. OIA subjunctive forms, like «ásati, ásat» might have exerted some influence here. The OIA. athematic «as-ti» survives through MIA. «atthi» in the Gujarātī negative form «nathī <nāsti», and is not found elsewhere in NIA. The form «\*as-a-ti» seems to be the source of NIA. আহর «āhāy» (West Bengali), हए हय «hāē, hāy» (Standard or Common Bengali), «ahāi, hai» (W. Hindī), «āhē» (Marāṭhī), etc. This «\*as-a-ti» however, has not been found in MIA., and the phonetic puzzle of the change of «-s->-h-» remains unsolved (*supra*, pp. 549-550). Jules Bloch suggests connecting Marāṭhī «āhē» with OIA. «ā-bhavati», as a likely derivation of it ('Langue Marathe,' p. 294). But the loss of prefix «ā-» over a great part of the North Indian area would be strange. In any case, with the distinct occurrence in NIA. of «hō, ha» side by side, «ha» cannot with any certitude be derived from «bhū». Bengali phonology shows that the source of «ha» in OB. was «\*ah» and not «hō=bhū»: নর «nāy» is not <ন-হর «nā-hāy» = «na + \*ahāi»; নইলে <নহিলে «nāilē <nāhilē» on not being <«na + \*ahilē»; MB. নহিব «nāhibā» shall not be = «na + \*ahibā»: the change is of «ā+ā > ā > ā» (for which see *supra*, pp. 347, 555). In the Standard Colloquial, MB. করিব, চলিব «kāribā, cālībā» I shall do, I shall go by loss of the interior «-i-» and mutation of the preceding «-ā-» give [korbo, ʃolbo], but there is no such mutation in the case of বহিব, সহিব «bāhibā, sāhibā» I shall bear, I shall suffer > [bābo, ʃābo], when the «-i-» is dropped; but when the «-i-» is retained (the presence of «-h-» preventing the hiatus in OB. and eMB. has something to do with the preservation of the «-i-» in such cases), we have mutation: [boibo, ʃoibo]. Now হইব «hāibā» shall be gives in the Standard Colloquial [ʃābo]: this would seem to be based on \*অহিব, \*অহব «\*āhibā, \*āhbā», which then by metathesis becomes হব «hābā» [ʃābo]. A form from «hō=bhū», হোইব «hōibā» would give in the Standard Colloquial \* [ʃābo], with «-ū-» in the root, but such a form is unknown. In the past tense (first person), we



have for the above roots, respectively, [korum (kollum), *q̣ollum*], but [boilum, *foilum*] and [*fiolum*] : [bolum, *folum*] would be exceedingly rare, and wrong for the Standard Colloquial dialect ; and [*fiolum*] never occurs. [*fiolum*] apparently is not based on \* *āh-il-um* < √ *ah* >, but rather on \* *hō-il-um* < √ *bhū* > : in the former case it would have fallen in line with [boilum, *foilum*], and with [*koilum*] < \* √ *kāh* > *to speak* etc., and preserved the \* *-i-* > (in the Standard Colloquial). The future tense thus seems to preserve \* √ *āh* >, and the past \* √ *hō* >.

768. The root रह् *rah* > *to remain, to continue to be* (the causative of which occurs in the ŚKK., रह् *rahāē* > *stops*), is a regular verb which can be said to form one of the substantives in Bengali. It occurs in other NIA.—Marāṭhī *rahāṇē, rāhṇē* >, Gujarati *rahēvū* >, Sindhi *rahaṇu* >, Panjābī *rahiṇā* >, W. Hindī *rahnā* >, E. Hindī *rahab* > : it is found also in the Dardic Kāśmīrī.

This root is of obscure origin. A common derivation is to regard it as an intransitive formation from a passive verb : Skt. *rakṣyatē* > *is preserved, is kept* > MIA. *rakkhiaī* > *rākhiaī*, \* *rāhiaī*, \* *rāhiaī* > NIA. *rahaī* > *remains* (cf. Platts, 'Hindustānī Dictionary,' under *rahnā* >). Despite the presence of the Marāṭhī *rāhṇē* >, this derivation is not convincing. Then the NIA. form *rah* > cannot be affiliated to any of the Sanskrit roots, *rah* > *to separate, to abandon*, *rañh* > *to hasten, to speed*, and *lañgh* > *to leap over*, because of the insurmountable difference of meaning. This root however occurs in MIA., e.g., Jaina Prakrit *rahaē* > *remains, stays*, and MIA. *dēṣī* *rāho* = *nirantaraḥ* > (as referred to by Jules Bloch, 'Langue Marathe,' p. 393).

It would be strange indeed if such an important NIA. root, a root of elementary significance, and so widely spread too, should not be of OIA. origin. There is the Skt. root *arh*=*argh* > *to deserve, to merit, to be worthy of, to have a claim to, to be entitled to, to be worth, to be able*, etc. This is connected with the Greek *alphē* > *worth, value* ; and Skt. \* √ *arj* > *to acquire* is also supposed to be related to this \* √ *argh*, *arh* > (Uhlenbeck, 'Etymologisches Wörterbuch der altindischer Sprache' ; also J. Leumann, *ibid.*, I Theil, Dissertation, Strassburg, 1893). In Pali

« √ rah » figures as « araha- » : but the old meaning is preserved. Skt. « √ arh » in the present tense second person is used with the infinitive as a polite request : « kartum arhasi, dātum arhasi » *please do, please give*. This « arh, araha- » does not agree with the NIA. « rah » in sense, although in form they are almost identical.

There is in Middle High German a verb « rēgen » meaning *to raise oneself up, to be rigid, to be fixed*, in Modern German « emporragen » *to tower*, « hervorragen » *to rise above, to project, to stand out*. There is also in Latin a verb « rigeo, rigēre » *to be fixed, to stiffen*. It has been suggested that the Latin and the German forms are connected, and the hypothetical Indo-European root « \* régh-o-, \* řgh-é- » has been proposed as the source of both (August Fick, 'Vergleichendes Wörterbuch der idg. Sprachen,' Göttingen, 1890, p. 517 : Fick regarded this as belonging specially to the West European i.e. "centum" group of Indo-European, and he further connected the Greek « √ arkh » *to be first* and Lithuanian « rāgas », Old Slav « rogŭ » *horn* : W. Prellwitz accepts all this in his 'Etymologisches Wörterbuch der griechischen Sprache,' Göttingen, 1905, under « árkhō » ; E. Boisacq, however, regards these etymologies as dubious, 'Dictionnaire étymologique de la Langue grecque,' Heidelberg, 1906, under « arkhós » ; and A. Walde also disputes them, 'Lateinisches etymologisches Wörterbuch,' Heidelberg, 1910, under « rigeo, recens, frigeo »).

Was there a root « \* ragh, rah » = *to stand, to be fixed, to be stiff* also in OIA. ? The possibility of an OIA. form like « \* ragh, rah » is made a probability by the presence in most NIA. of « √ rah », and also of « √ raha » in MIA. (as in Jaina Mahārāṣṭrī « sō ŷa alva jūṷa-pasaṅgi ; nivasapa-mēttam pi na rahaē » *he is exceedingly addicted to gambling : not even his clothes remain* : Jacobi, 'Ausgewählte Erzählungen in Mahārāṣṭrī,' Leipzig, 1886, p. 58 : it features also in the Jaina kāvyā « Sīri-sirivāla-kahā » : cf. 'Pāṣa-sadda-mahagṇavō' by Hargovinddas Trikamchand Seth, Calcutta, 1925 ; it occurs also in the late work 'Prākṛta-Pāṅgala'). The use of this root in MIA. Jaina texts favours the assumption that it also occurred in the traditional Ardha-māgadhī from Early MIA. times. The eastern dialect of Aśoka undoubtedly



is Ardhā-māgadhi of the Early MIA. period (cf. H. Lüders, 'Bruchstücke Buddhistischer Dramen,' p. 41). In that puzzling passage in Aśoka's Pillar Edict IV, « lajūkā pi laghamti paṭicalitavē maṁ (,) pulisāni pi mē chaṁdamnāni paṭicalisaṁti », the word « laghamti=laghanti » has been interpreted to mean *are eager* (= « raṅghantē » : Bühler) and *they must* (= « arhanti » : *auch die Lajjukas müssen mir gehorchen*, H. Lüders, 'Sitzungsberichte der kön. preuss. Akad. der Wissenschaften,' Vol. LIII, 1913, p. 993). But it seems very likely that it means *remain*, and is the Aśōkan equivalent of the NIA. « rah » : *the Lajjukas also remain (are staying) to serve (obey) me, and they will also serve (obey) the officials who know my will* seems to be the proper translation (cf. A. C. Woolner, 'Asoka Text and Glossary,' 1925, II, p. 86). The sense of « √arh », with an implication of compulsion, is hardly suitable in this general statement in the above passage. In Bhabra Inscription, however, we have the OIA. « √arh » in the form « alah » with the « a- » retained : thus, « alahāmi hakaṁ taṁ vatavē » (= arhāmy ahaṁ tad vaktavē=vaktum). The assumption of an OIA. root « \*ragh, rah, lagh », from the occurrence of it in NIA. and in (Late) MIA. (Jaina Prakrit) and from the presence in extra-Indian Indo-European of « rēgen, rigeo » etc., seems to be borne out by the Aśōkan « laghamti ». And it is not unlikely that there was a confusion between this « \*ragh, rah, lagh » and « argh, arh, arah, alah » in MIA.

769. Root थक् « thāk » *to remain < to be fixed*. It is commonly derived from the OIA. « √sthā », but Hoernle connects it with « √stabh + kṛ » > MIA. « thakka » (see *supra*, p. 680). This is certainly the true derivation, although it is possible that OIA. « √sthā » > « thā, tha » has merged into it : cf. Oṛiyā « √thā » beside « √thāk », Assamese past form « thāilā », Bengali causative थक् « thōy » *places* (sthāpayati). Equivalents of this root occur in other NIA.—in Bihārī, in W. Hindi, in Gujarātī ; and it is found in Late MIA.,—in the 'Prākṛtā Paṅgala,' for instance.

770. Root बट् « bāṭ » as a substantive verb in the Standard Colloquial is frequently used to express doubt or polite assent, and as such is ordinarily restricted to the 3rd person present only—बट्टे

« bātē »—which has practically been reduced to a particle of assent or query in Standard NB. The root is defective in not having past and future forms, and conjunctives, participles and verbal nouns. The forms for the 1st and 2nd persons, and the honorific, are sometimes used: বটি « bāṭi » *I am, I may be*; বটিস, বট « bāṭis, bāṭā »; বটেন « bāṭēn » , generally with the conjunction যদি, যদিও « yādi, yādi-ō » *if, although*. The 3rd personal form is sometimes used for emphasis—সেই বটে « sei bātē » *it is he indeed*. In the West Rājha dialects, the use of « bātē » as the equivalent of « āchē » and « hāy » is still preserved: e.g., in Manbhum, তোমার হাতে বটিতে কি ? « tōmārā hātē ghāṭi-tē ki ? » *what have you got in the vessel in you hand ?* জল বটে « jāḷā bātē » *it is water*.

In Oṛiyā, the counterpart of « bāt » is « āṭ », also a defective verb. The loss of the initial « b (<v) » in Oṛiyā seems to have been brought about by the occurrence of the verb in the middle of the sentence, which helped to reduce the « v- », which became « b- » in Bengali, to a glide « w » which came to be dropped. Maithilī and Magahī have not preserved the root, but in Bhōjpurīyā it is a very common and useful substantive verb, its forms there being « bāt-, bār-, bā, bā-ni » etc.

The source of this root is the OIA. « vṛt » *to turn, to revolve, to roll, to take place, to occur, to exist, to remain* etc.: « vartatē », MIA. Māgadhi « vaṭṭati, vaṭṭai » > বটে « bātē » (see *supra*, p. 319).

771. Some Bengali verbs present irregularities in their conjugations, especially in the past bases. But these irregularities are not so great as in Panjābī or Marāṭhī. The process of standardisation early levelled down the passive participle bases derived from MIA. to a regular « -il- » form in Bengali. A few survivals, however, remain. Thus কর « √kār », past tense MB. করিল « kārila » (> NB. কর'ল কর'ল, কর'লে কর'লে [korlo, kollo, korle, kolle]) is a new and regular formation in eMB. from the root, but the earlier form derived from MIA. « \*kaṣa-illa » is the OB. and MB. কৈল « kailā », now obsolete or dialectal: cf. Oṛiyā « kālā », Bihārī « kail ». So মরিল « mārila » *died* > ম'রল ম'ল [morlo, mollo], beside the older মৈল « mailā », which is found in both standard and dialectal Bengali as ম'ল [molo]; and on the analogy of « kailā, mailā », we have in MB.



a seemingly archaic মাইল *\*māilā* (whence the dialectal West Bengali মেলে *\*mēlē*, i.e., *\*māil-ā*) for a regular মারিল *\*mār-il-ā* *he struck* (*\*mārīta + -illa*, a causative form, which occurs in the Standard Colloquial as মারলে, মাললে [marle, malle < *\*marile*]); and also পৈল *\*pāilā* *fell* in MB., for পড়িল *\*pārila* > NB. পড়ল [porlo]. Root যা, জা *\*jā* (OIA. *\*yā*) has the past base গেলে *\*gēlā* = Early Assamese *\*gālā*, Oriyā *\*gālā*, Bihārī *\*gail*, from OIA. *\*gata* + *\*-ila*; this is the genuine and current form, and যাইল *\*jāilā* is a regular *\*sādhubhāṣā* creation out of যা *\*√jā*, which is not the spoken form. The conjunctive forms are গেলে *\*gēlē* and গিয়া, গিয়ে *\*giyā, giyē* *on going, having gone* (cf. Early Bengali, Early Assamese গই *\*gāi*, also found in OB.); but যেলে *\*jēlē* and যেয়ে *\*jēyē* would appear to be extremely uncommon in colloquial Bengali, and would seem to be based on the literary forms বাইলে, বাইয়া *\*jāilē, jāiyā*.

772. The roots meaning *give* and *take* have had a close inter-influence in their history. OIA. root *\*dā* *to give* did not use its reduplicated forms in MIA., and already in Transitional MIA. (Bharhut), it figures as *\*dēti* < *\*dayati*, apparently through analogy of *\*nayati* > *\*nēti* (from *\*√nī* *to lead, to take away*). The passive participle base was *\*datta* in OIA. (which seems to be preserved in the Panjābī *\*dittā*); and a form *\*dita* also occurred in OIA., which gave W. Hindi *\*diyā*, Bengali দিল *\*di-lā*; beside another in *\*-nn-*, attested from MIA. *\*dinna-* and NIA. *\*dīnau* (W. Hindi, Brajbhākhā), *\*dīnha* (Early Awadhī), *\*dīdhō* = *\*dīndhau, dīnhau* (Gujarātī: cf. Tessitori, 'Grammar of OWR,' § 126 [3]). We have besides the form *\*dēl-* in Bihārī, in which occurs the vocalism of the present. NB. Vowel Harmony has largely modified the original disposition of the *\*-i-* and *\*-ē-* vowels (see *supra*, p. 894). For *take*, we have as many as *three* roots in Bengali. The standard *\*sādhubhāṣā* knows only ল, লহ *\*√lā, lāh* (which, if it is not the Skt. *\*labh*, is at least influenced by its *tbh.* form *\*√lah*): Present 1. লই *\*lāi*, 2. লইস, ল'স *\*lāis, lā's*, লহ, লও *\*lāhā, lāō*, 3. লহে, লয় *\*lāhē, lāy*, honorific ল'ন, লয়েন, লহেন *\*lānā, lāyēnā, lāhēnā*; Imperative 2. ল *\*lā* < *\*lāhā*, লও, লহ *\*lāō, lāhā* < *\*lāhāhā*,

3. লউক < lauk >, honorific লউন < laün >; Past base লইল < lailā >, Future base, লব, লইব < lābā-, lāibā- >, Conjunctive লইয়া < lāiyā >, Passive Participle লওয়া < lāwā >. This < lāh, lā > root occurs in MB. literature also. But it is never used in spoken Bengali. The vocalism parallels that of roots সহ, বহ < sāh, bāh > as given above (e.g., Future [śoṣibo > ſoibo, ſobo], so [loṣibo > loibo, lobo]), and thus indicates the form < lah > (< labh >) as a source of the NB. root. The dialects (other than Standard Colloquial) use a root লে < lē >, e.g., Present 1. লি(ই) < li(i) >, 2. লিন্ < lis >, লেও > লাও < lēo > lāo >, 3. Present লেয় < lēy > [læŋ], Past লিলে < lilē >, Future লিবে, লেবে < libē, lēbē >, Conjunctive লিয়ে < liyē >, etc.: this root is now regarded as vulgar; but it figures in MB., and in OB. (e.g., Caryā 14, < kawaḍī na lēi, bōḍī na lēi > takes not a cowrie shell, takes not a farthing; Caryā 10, < lēmi > I take; 32, < lēhu > you take; 49, < lēli > taken). It seems that this < √lē >, and < lā, lāh > were confused with each other: < lē > was made to approach < lāh > as an elegant, literary form. The OB. conjunctive forms < lai > (Caryās 29, 38, 47), < lāiā > (28, 45), < laiā > (26) seem already to be the result of this confusion in changing the root vowel of < lē > to < la > as in < lah > (cf. NB. dialectal < liyē > having taken < √lē >). This < lē > is found in Bihārī, in E. Hindī, in W. Hindī (lē-nā), etc. The source of it seems to be the OIA. root < lā > to take, as in Sanskrit. In Sanskrit, however, this root is not so common. The popular Skt. root is < grah >, which is represented by forms in some of the NIA. speeches. The change of < lā > to < lē > is probably the result of the influence of < dāi, dēti = dāti, dadāti > (cf. Jules Bloch, 'Langue Marathe', p. 400, under *lepen*). The Standard Colloquial root meaning to take (occurring also in MB.) is নি, নে < ni, nē >, now conjugated exactly on the model of < dā > (see *supra*, p. 894). It may be that this form is due to the change of the initial < l- > of < lē > to < n- > (see *Phonology*, p. 545); but it is at least equally likely that here we have the OIA. root < ni > to lead, to carry off for one's self > to take. We have আন < ān > = < ā + √ni > as a common verb in Bengali; and it is exceedingly likely that OIA. < √ni > has also survived in Bengali.



OB. had the root « ghēn » *to take* (< OIA. gṛhṇāti) : cf. Caryā 6, « ghini (= ghēni) mēli » = « gṛhītvā muktṵā », according to the Commentary. It is lost to Bengali now, but Oṛiyā still retains this root in a common form (√ghēn).

It is curious that the root for *taking* also means *wearing (clothes)*, in Oṛiyā (« √ghēn »), in Marāṭhī (lēṇē), and in MIA. (« laīaṁ parihitaṁ : laīaṁ aṅgē pinaddham ity anyē » — 'Dēśināma-māla' quoted by Jules Bloch, 'Langue Marathe,' p. 400 : cf. Skt. « vāsāṁsi jīrṇāni yathā vihāya navāni gṛhṇāti narō' parāṇi »).

773. Root आ « √ā » *to come* is a defective root, which is affiliated to root আইস, আস « √āis, ās » *to come* (< OIA. ā + √viś), to supply an optional past form and the familiar imperative (= singular). Thus—

3 Present, MB., NB. (sādhū-bhāṣā) আইসে, আসে « āisē, āsē », NB. Standard Coll. আসে « āsē »; 3 Past, MB. আইসিল « āisilā », NB. (sādhū-bhāṣā) আসিল « āsilā », also MB. আইল « āilā », NB. Standard Coll. এল [elo], East Bengali আসল [aślo]; 3 Future, MB., NB. (sādhū-bhāṣā) আসিবে « āsibē », NB. আসবে [aśbē]; Imperative, 2 familiar or inferior আর « āy », 2 ordinary « sādhū-bhāṣā » আইস « āisā », Standard Coll. এসো [eśo], আইসুক, আসুক « āisukṣ, āsukṣ », 2, 3 honorific আ(ই)সুন « ā(i)sund », Future Imperative 2 inferior আ(ই)সিস « ā(i)sis », ordinary NB. আইসিও « ā(i)siō » > এসো [eśo]; Conjunctive আসিরা « āsiyā », এসে « ēsē »; Absolute, আসিলে « āsilē » > আসলে « āslē », beside আইলে « āilē » > NB. এলে « ēlē »; Present Participle আসিতে « āsitē » > আসতে « āste ».

The form « ā » comes from OIA. « ā + √yā » : « āyāta + -ila- > \*āñilla- > \*āilla- > আইল « āilā » > এল [elo]. The verbal noun connected with this root is আনা « ānā », which is not found by itself : but here, as the OB. form « avaṇā-gravaṇā » *coming and going* (found in the Caryās : = NB. আনাগোনা « ānā-gōnā ») shows, we have « √gam » — « āgamana- + gamana- ». It seems a MIA. form like « \*āwāi » (= OIA. \*ā-gamati) has merged into « ā + √yā ». The present tense of « √ā » is not found in NB., but OB. shows « āvai » (Caryā 42; also spelt « āvayi » in Caryā 44). Corresponding to this OB. « āvai, avaṇā- » we have W. Hindi 3 Present « āwē », Verbal Noun or Infinitive « ānā »; in Bihari

(Maithili), Verbal Noun « āb », Present Participle « ābait » beside « āōt », 3 Future and Conditional Past (= original Present Participle) « āuta », Present 3 person original singular « āē » beside « ābai », plural > honorific « ābathī », Future 1st person « āōb, āōb », conjunctive « ābi, āī, āy ». (Grierson, 'Maithili Grammar,' §§ 312, 313). The Maithili « -b-, -o- » forms, both from original « -w- », clearly show that as in Bengali, we have also the OIA. « \*āgamati » > MIA. « \*āwāi » form: Maithili « āē = āī < āyāti », and « ābai = āwāi < \*āgamati, ābathi < āgamanti, āēb < āyātavya, āob < \*āgamitavya ». The Maithili past base always is « āil- », where it is < « āyāta + -illa », as in Bengali « āilā »: cf. W. Hindī « āyau, āyā » (< ā-yāta-ka).

Three OIA. roots preceded by the « ā » particle thus feature in the Bengali verb for *coming*: « ā-viś », « ā-yā » and « ā-gam ».

#### [P] DUPLICATED VERBS.

774. Certain verb-forms are doubled in Bengali to indicate repeated, intense or continuous action. These are either conjunctives in « -iyā » (or « -i » in Early Bengali), or present participles in « -itē », used with an adverbial force with reference to the finite verb. Thus we have in OB. (Caryā 10) « chaī chōī = chōī chōī » *frequently touching*; (26) « dhuni dhuni » *by continually carding (cotton)*; (31) « cāhantē cāhantē » *continually scrutinising*; MB., Caṇḍi-dāsa, ঝুরিয়া ঝুরিয়া কান্দে « jhuriyā jhuriyā kāndē » *weeps (silently) shedding tears continually*; Gōvinda-dāsa, উড়িয়া পড়িয়া মাতল ভ্রমর ঝুরিয়া ঝুরিয়া বু- « uriyā pāriyā mātālā bhrāmārā ghuriyā ghuriyā bulē » *the drunken bee flies and moves and circles round and round*, হাসিয়া হাসিয়া অঙ্গ দোলাইয়া নাচিয়া নাচিয়া যায় « hāsiyā hāsiyā āṅgā dōlāiyā nāciyā nāciyā jāy » *goes smiling always, swinging the body and dancing always*; NB. দেখে দেখে « dēkhē dēkhē » *seeing for a long time*, খেটে খেটে « khēṭē khēṭē » *working continuously*, etc. This usage goes back at least to MIA.: cf. Late Skt. « pītvā pītvā punaḥ pītvā, patitvā ca mahītalē », an idiom based on MIA.

775. There are a number of roots which are used in pairs—roots similar in meaning, or indicating connected ideas, and together they



convey an intensive idea, or the idea of the entire process involved (cf. under 'Onomatopoeitic Roots,' p. 891). These do not make what are known as 'Compound Verbs,' as both the roots take inflexions; e.g., NB. বুঝে-সুঝে < bujhê-sujhê > *understanding well*, ধুয়ে-মুছে < dhuyê-muchê > *washing and wiping = making clean completely*, মেরে-খঁরে < mērê-dhōrê > *striking and restraining = forcibly*, কাঁদে-কাটে < kādê-kātê > *weeps and fidgets*, past tense কাঁদল-কাটল < kādla-kātla >, future কাঁদবে-কাটবে < kādbe-kātbe >; নাচে-কোঁদে < nācê-kōdê > *dances and capers*, past নাচল-কুঁদল < nācla-kūdla >, future নাচবে-কুঁদবে < nācbe-kūdbê >; লাফাল-ঝাঁপাল < lāphāla-jhāpāla > *leapt and jumped*; হটুকানো-পাটুকানো < huṭkānō-pāṭkānō > *to turn topsy-turvey, to ransack*; etc. They occur in earlier Bengali as well: ŚKK., ছিড়ি-জুলি < chirdi-juli > *tearing and scattering*; so ভাঁগি-জুলি < bhāgi-juli >; উথালি-পাথালি < uthāli-pāthāli > *cheering and heartening*; 'Sayings of Dāka,' ধোইরা-পৌছিরা < dhōiyā-pāucchiyā > *washing and wiping = thoroughly washing*; etc.

There is another kind of reduplication, behaving like the roots which are used in pairs, in which, following the habit of Bengali with regard to nouns, the verb is repeated by an artificial form in which the vowel or the consonant in the initial syllable of the verb is changed, and a jingle thus results, which continues the idea of the verb, or brings in notions of a similar nature: e.g., খেয়ে-দেয়ে < khēyê-dēyê > *having finished one's meal*; জিরিয়ে-তিরিয়ে < jiriyê-ṭiriyê > *resting and reposing*; কাঁদে-তাদে < kādê-tādê > *weeps and sorrows*; ঝাড়লে-ঝুড়লে < jhāṛlē-jhūrlē > *scraped and cleaned* (see *supra*, p. 176, on 'Echo Words'). This form is also found in MB.: e.g., Dāka, খায়-দায়, না পালে হাতী < khāy-dāy, nā pālê hāṇḍi > *eats and enjoys, but does not attend to the cooking pot*.

776. There is in Bengali, as in other NIA., a common Verbal Noun of Reciprocity, which may be noted in this connexion. The verbal root or the noun is doubled, and they are connected by a link vowel < -ā- >, and the second part of this reduplicated form takes the affix < -i < -I >: e.g., জানা-জানি < jānā-jāni > *knowing in common*, বলা-বলি < bālā-bali > *informing each other*, হড়া-হড়ি < huṛā-huṛi > *pushing and pulling each other*, মারামারি < mārā-māri > *striking each other > fighting*, দেখা-দেখি

« dēkhā-dēkhi » *seeing each other, mutual seeing*, ঘৃণাঘৃণি « ghuṣā-ghuṣi » *fighting with fist-cuffs*, কানাকানি « kānā-kāni » *talking with mouth by each other's ears, whispering*, হাতাহাতি « hātā-hāti » *hand-to-hand fight*, মুখামুখি « mukhā-mukhi » *face-to-face*, etc. These nouns can be used adverbially.

Similar formations are known to OIA. Pāṇini has already noted them, under *Bahu-vrīhi* compounds (cf. 'Aṣṭādhyāyī,' II, ii, 27, and V, iv, 127 : « kēśā-kēśi, daṇḍā-daṇḍi, karṇā-karṇi, muṣṭā-muṣṭi, jalpā-jalpi » etc.) In OIA., these are nominal compounds only, the « -ā- » being the modification of the stem-vowel of the word. This formation occurred with concrete nouns as well as verbal nouns in OIA. (cf. « jalpā-jalpi ») ; and the final « -i » seems to have been strengthened by « -ka » in MIA., so that it could be retained in NIA. as « -ī, -i » (-ika > -ia > -ī, -i : \* karṇā-karṇi-ka > \* karṇāṣkaṇṇia > kārṇāṣkārṇī, -nī).

Repeated roots of the type noted above in § 775 form by analogy compounds of a similar type, only the reciprocal sense is absent : e.g., চেচামেচি « cēcā-mēci » *shouting and noise (singly or by many)*, কাঁদাকাঁটি « kādā-kāṭi » *weeping and sorrowing*, etc.

#### [Q] COMPOUND VERBS.

777. Modern IA. languages agree in having a remarkable idiomatic use of verb roots in connexion with a noun or a verbal conjunctive or participle. The noun which is compounded is in the accusative, and occasionally in the locative; and the verbal form remains unaffected, the root following taking the temporal and personal affixes. The two parts combined form one idea. The inflected root in such a group, though outwardly in form the principal part modified by a noun or by a participle, is properly the auxiliary; and sometimes it has no special force, although generally it strengthens or otherwise modifies the idea of the preceding verbal participle or noun. The use of this 'Compound Verb' or 'Group Verb' construction amply compensates for the loss of the root-modifying prefixes which form such a characteristic feature of Sanskrit and of Indo-European speeches outside India. In English, the modifying prefix now comes after (e.g., *to lie down, to sit down, to put off, to put out*), though



we have older forms (like *to with-stand, to for-give, to for-get, to up-set*, etc.). So for English *sit down*, and Skt. « ni + √sad », we have in Bengali বসিয়া পড়া « *bāsiyā pārā* », lit. *having sat, to fall*, = Hind. « *baith jānā* » *having sat, to go*. The loss of the root-prefix both in form and significance (e.g., « *upa-viśati* » becoming « *bāisē, bāsē* », « *pra + √āp* » becoming « *√pā* ») as well as the absence of new root-modifying prefixes or particles when the old ones were lost by assimilation, has gradually brought about this make-shift of the Compound Verb. These compound verbs supply to some extent the want of modal and temporal affixes, and are as characteristic of the modern Indo-Aryan speeches as the 'aspects' of the verb in the Slav languages.

In this point there is a remarkable agreement with Dravidian (see *supra*, p. 174). In the Dravidian languages, compound verbs of exactly similar formation and function occur, e.g., in Tamil, with « *koḷḷu* » *take*, « *varu* » *come*, « *viḍu* » *leave*, « *pō* » *go*, « *uru* » *come*, « *adi* » *strike*, « *paḍu* » *suffer*, etc.; in Telugu, with « *konu* » *buy, take*, « *vesenu* » *throw*, « *iecu* » *give*, etc. It is very likely that here we have another contribution of Dravidian in the formation of Modern Indo-Aryan speeches.

**778.** The Compound Verb occurs from the earliest period in NIA. We have, e.g., in the Caryās, « *diṭa* (= *diḍha*)-*karia* » (1), « ? *cauri-nila* » (2), « *ṭuṭi-gēli* » (36), « ? *saḍi-paḍiā* » (44), « *uṭhē* (= *uṭhi*)-*gēli* » (47); in the ŚKK., আনি দিবো « *āni dibō* » *I shall bring*, কাড়ি নিলে « *kārhi nilē* » *snatched away*, লাগি গেল « *lāgi gēlā* » *become fixed*, কহিআ দেহ « *kāhiā dēhā* » *do describe*, মুছিআ পেলাইবো « *muchiyā pēlaiḍō* » *shall wipe off*, etc., etc. Examples are common in MB.

**779.** Types of the Compound Verb in Bengali.

(Cf. J. T. Platts, 'Hindustāni Grammar,' pp. 169-180; S. H. Kellogg, 'Hindi Grammar,' pp. 257-279; Grierson, 'Maithili Grammar,' pp. 289-298.)

### I. Nominals.

(a) Accusative: জমা করা « *jāmā-kārā* » *to gather*, দর্শন করা « *dārsāṇā-kārā* » *to see* (e.g., *the deity in a temple*), দর্শন দেওয়া « *dārsāṇā-dēwā* » *to*

*show oneself*, আহাৰ কৰা « āhārḥ-kārā » *to eat*, আহাৰ দেওয়া « āhārḥ-dēwā » *to feed*, পাস or ফেল কৰা or হওঁতা « pāsḥ-, phēḥ, kārā, hāwā » *to pass or fail (in examination)*, স্বাদ নেওয়া « swādḥ-nēwā » *to taste*, জল দেওয়া « jāḥ-dēwā » *to water*, নাম নেওয়া « nāmḥ-nēwā » *to repeat the name (of God)*, লাফ দেওয়া « lāphḥ-dēwā » *to jump* (Sanskritised in the « sādhu-bhāṣā » as লক্ষ প্রদান কৰা « lāmphā-prādāṇḥ kārā »), etc., etc.

(b) Locative : আগ বাঢ়া or বাঢ়ান « āgḥ-bārā, -bārāṇā » *to advance*, গা কৰা « gā-kārā » *to receive properly, to attend (receive on body, cf. গাৱে মাখা « gāwē mākhā » = to smear on the body in the same sense )*, etc.

(c) With the locative verbal noun (or infinitive) in ইতে « -itē » :

(i) Inceptives (with « √lāg » *to be attached*) : কৰিতে > ক'বতে লাগা « kārītē > kōrtē lāgā » *to set to do*, খাইতে > খেতে লাগা « khāitē > khētē lāgā » *to set to eat*, etc.

(ii) Desideratives : দিতে চাওয়া « dītē cāwā » *to wish to give* (with « √cā, cāh » *to want*) ;

(iii) Acquisitives : দেখিতে > দেখতে পাবা « dēkhitē > dēkhtē pāwā » *to be able to see* (with « √pā » *to get*),

(iv) Permissives : বসিতে > ব'সতে দেওয়া « bāsītē > bōstē dēwā » *to allow to sit* (« √dē » *to give*) ;

(v) Potentials : চলিতে > চ'লতে পাবা « cālītē > cōltē pāwā » *to be able to walk* (« √pār » *to be able*).

(d) With the verbal noun in « -i » and in « -ā » : Reflexives : মুড়ি দেওয়া « muḥ-dēwā » *to wrap oneself up*, গুড়ি মাৰা « guḥ-mārā » *to creep, to cower*, হামা দেওয়া « hāmā-dēwā » *to crawl on all fours*, etc., etc.

## II. Verbals.

(a) With the conjunctive (in « -iyā, -ē ») :

(i) Intensives : কাড়িয়া > কেড়ে নেওয়া « kāḥiyā > kēḥē nēwā » *to snatch away*; ভাঙিয়া > ভেঙ্গে দেওয়া « bhāṅgiyā > bhēṅgē dēwā » *to break fully*; আসিয়া > এসে পড়া « āsiyā > ēsē pārā » *to come along, to reach*; উঠিয়া > উঠে পড়া « uṭhiyā > uṭhē pārā » *to get up*; দিয়া > দিয়ে দেওয়া « diyā > diyē dēwā » *to give away*; ভাগিয়া > ভেঙ্গে পড়া « bhāgiyā > bhēṅgē pārā » *to decamp*; সরিয়া > স'রে পড়া « sārīyā > sōrē pārā » *to retire (silently)*;



উঠিয়া পড়িয়া > উঠে পড়ে লাগা « uṭhiyā-pāriyā > uṭhē-pōrē lāgā » *to be up and doing, to be at something tenaciously*; etc., etc.

(ii) Intensives and Completives : খাইয়া > খেয়ে ফেলা « khāiyā > khēyē phēlā » *to eat completely, to finish entirely*; মুছিয়া > মুছে ফেলা « muchiyā > muchē phēlā » *to rub off*; কাটিয়া > কেটে ফেলা « kāṭiyā < kēṭē phēlā » *to cut down*; বলিয়া > বলে ফেলা « baliyā > bōlē phēlā » *to blurt out*; বসিয়া > বসে পড়া « bāsiyā > bōsē pārā » *to sit down*, etc., etc. Generally with « √phēl » *to throw, to cast* with transitives, and « √par » with intransitives.

(iii) Inceptives, with যা « √jā » *to go*; লাগিয়া > লেগে যাওয়া « lāgiyā > lēgē jāwā » *to start*; বসিয়া > বসে যাওয়া « bāsiyā > bōsē jāwā » *to sit down for something*, etc.

(iv) Staticals : বসিয়া > বসে থাকা, রহা (রওয়া) « bāsiyā > bōsē thākā, rāhā (rāwā) » *to continue to sit, to remain sitting*; লাগিয়া > লেগে থাকা, রহা « lāgiyā > lēgē thākā, rāhā » *to be fixed or working at something*; জাগিয়া > জেগে থাকা, রহা « jāgiyā > jēgē thākā, rāhā » *to keep awake*, etc. (The « -iyā » forms here may be the passive participle rather than the conjunctive).

(v) Continuatives : বকিয়া > বকে যাওয়া « bakiyā > bōkē jāwā » *to go on chattering*; খাইয়া > খেয়ে যাওয়া « khāiyā > khēyē jāwā » *to go on eating*, etc. (খাইয়া যাওয়া « khāiyā jāwā » is also passive, *to get eaten*, where the « -iyā » form is not the conjunctive : see *supra*, pp. 922 ff.).

(vi) Miscellaneous : e.g., করিয়া > ক'রে দেখা « kāriyā > kōrē dēkhā » *to experiment (to do and see)*; বুঝাইয়া > বুঝিয়ে দেওয়া « bujhāiyā > bujhiyē dēwā » *to explain*; ছিটকাইয়া > ছিটকিয়ে পড়া « chīṭkāiyā > chīṭkiyē pārā » *to be scattered*; etc., etc.

(b) With the Present Participle in ইতে « -itē » :

(i) Continuatives or Frequentatives : দিতে, করিতে > ক'রতে, হাসিতে > হাসতে থাকা « dītē, kārītē > kōrtē, hāsītē > hāstē thākā » *to remain giving, doing, smiling*; etc.

(ii) Staticals : করিতে করিতে যাওয়া « kārītē-kārītē jāwā » *to go while doing*, নাচিতে নাচিতে গাওয়া « nācitē-nācitē gāwā » *to sing while dancing*. (Here the form is strictly not of the compound verb, as both roots retain their independent meaning : but the « -itē » forms have an adverbial sense.)

## APPENDIX.

**780.** The following are the main or typical stages in the development of Bengali as a Modern Indo-European language from the Primitive Indo-European speech :

- (1) Indo-European, c. 2500 B.C. ;
- (2) Indo-Iranian or Aryan, c. 1800 B.C. ;
- (3) Old Indo-Aryan (Vedic Dialects), c. 1200 B.C. ;
- (4) Transition to Middle Indo-Aryan in the Prācya or Eastern speech, c. 700 B.C. ;
- (5) Early Middle Indo-Aryan of Magadha (Old Māgadhi), c. 300 B.C. ;
- (6) Transitional Middle Indo-Aryan of Magadha, about the time of Christ ;
- (7) Second Middle Indo-Aryan of Magadha, c. 300 A.C. ;
- (8) Late Middle Indo-Aryan of Magadha and Bengal, or Māgadhi Apabhraṁśa, c. 800 A.C. ;
- (9) Old Bengali, c. 1100 A.C. ;
- (10) Early Middle Bengali, c. 1400 A.C. ;
- (11) Late Middle Bengali, c. 1600 A.C. ;
- (12) New Bengali or Modern Bengali, after 1800 A.C.

In the preceding pages, this development from the third stage as above, from Old Indo-Aryan, has been sought to be indicated in its general lines, both in sounds and in inflexions. The development of Old Indo-Aryan from the parent Indo-European speech properly forms a distinct branch of the subject. To illustrate the transformation of Indo-European to Bengali, however, a few sentences in New Bengali are taken below, and their equivalents through the typical preceding stages are given, and in this way the hypothetical Indo-European source-forms are worked back. This will indicate within a short compass the processes underlying this transformation.



All the words in OIA., Indo-Iranian, and Indo-European sentences below have been accented.

(i) মা ঘরে আছে • mā gharē āchē • *mother is in the house* < eMB. মাও ঘরে আছে (আছে) • māo gharē āchē (āchāē) • < OB. \* • māwa gharē (gharai, gharahi, gharahi) āchāi • < Māgadhī Apabhraṇśa \* • māa (māwa) gharahī (gharahi, ghalahī, ghalahi or ghari) acchāi • < Māgadhī Prakrit \* • māā (< māōā, mādā) ghalahī (< ghalaḍhi, ghaladhī; or ghalaśśi, or ghalē) acchāi (< acchaḍi, acchadi) • < Old Māgadhī (Prācya) (= First MIA.) \* • mātā ghaladhī (ghalaśśi, ghalē) acchati • = Late OIA. (not Prācya) \* • mātā gharadhī (< garhadhi) or gharassi (< garhasmin, gharē) acchati • < OIA. • mātā \* gṛhā-dhi (gṛhē) \* ācchati (\* ācchāti) • < Indo-Iranian \* • mātā gṛdhā-dhi (gṛdhāi) as-ṣ(h)ā-ti (< as-skā-ti) • < Indo-European \* • mātē(r) gṛdhō-dhi (gṛdhēi) es-skē-ti •.

(ii) সাধ হয় মোর মনে • sādha jāy mōr mānē • *a longing is in my mind* (the form মোর • mōr • *my* is archaic for the NB. Standard Colloquial) < eMB. সাধ হোঁ মোর মনে • sādha hōē mōrā mānē • < OB. \* • sādha hōi mōra mānē (maṇai, maṇahi, maṇahī) • < Māg. Ap. \* • śaddha hōi mōarahī (= mō-alahī, māwa-kalahī) maṇahī • < Māg. Prakrit \* • śaddha hōi (< hōḍi, hōdi) mama-kalabi maṇahī (< maṇaḍhi, maṇadhi, maṇaśśi) • < Old Māgadhī \* • śaddha hōti (or bhōti) mama manadhi (manaśśi) • < Transitional OIA. \* • śarddhā bhavati mama manadhi (manasmin) • < OIA. • śrāddhā bhāvati māma mānasi • < Indo-Iranian \* • ṣrād-dhā bhāvati māna mānasi • < Indo-European \* • kréd-dhē bhéweti méne ménesi •. (হয় • jāy • also represents an OIA. \* • as-a-ti •, IE. • es-e-ti •: see *supra*, pp. 1038-1040).

(iii) দাঁড়ে না বায় • dāḍē nā bāy • *rows a boat with an oar (= stick)* (the word না • nā • is rather archaic for the NB. Standard Colloquial) < eMB. দাঁড়ে (দাঁড়ে) নাও বাহে • dāḍē (dāḍē) nāo bāhē • < OB. \* • dāḍē nāwa bāhāi • < Māg. Ap. \* • daṇḍēm (daṇḍē) nāam (nāwā, nāā) bāhēi • < Māg. Prakrit \* • daṇḍēṇa(n) nāam vāhēi (< vāhēḍi, vāhēdi) • < Old Māgadhī \* • daṇḍēna nāam vāhēti (< vāhaiti, vāhay'ti) • < OIA. • daṇḍēna, daṇḍā (\* dandrá) nāvam vāhāyati • < Indo-Iranian \* • dandrá nāwa (nāwm) wāzhāyati • < Indo-European \* • dendró (? derdró) nāwm wēghēyati •.

(iv) গোৱালা গাই দৌয় • *gōwālā gāi dōy* • *the cowherd milks the cow* < eMB. গোৱালা গাই দুহে (দুহে) • *gōālā gāi duhē (duhāa)* • < OB. • *gōāl-ā (gōwāl-ā) gāi (gāwī) duhaī* • < Māg. Ap. • *gōāla (gōāli) gāīm (gāi) duhaī* • < Māg. Prakrit • *gōvālē ( < gōbālē, gōbālē) gāvīm duhaī ( < duhaḍi, duhadi)* • < Old Māgadhī • *gōpālē gāvīm duhati* • < Transitional OIA. • *gōpālāḥ gāvīm duhati* • < OIA. • *gō-pālāḥ (gō-pālāḥ) gāvīm (gām) dōgdhi* • < Indo-Iranian • *gau-pās (gau-pālās) gā(w)m dhāugdhi* • < Indo-European • *gʷon-pós (gʷon-pōlós) gʷó(w)m dhéugh-ti* •.

(v) বর বে (বিব্রে) ক'রে বউ আনে • *bārāḥ bē (biyē) kōrē bāu ānē* • *the bridegroom brings (leads) the bride after having married* < eMB. বর বিব্রা (বিব্রা) করিয়া বহু আনে (আণে) • *bārā bi(h)ā kariā bāhu āṇē (āṇāe)* • < OB. • *bara biāha (= biyāha, biwāba) kariā (kari) bahu āṇai* • < Māg. Ap. • *bara (bari) biāhan (biwāhā) kariā bahum (bahū) āṇēi* • < Māg. Prakrit • *valē vivāham kalia (kadua) (or ūddhā) vahum āṇēi ( < āṇēḍi, āṇēdi)* • < Transitional OIA. • *valah (varah) vivāham karya (kṛ-t-ya, kṛtvā) (or ūdhvā) vadhūm ānaiti (ānay'ti)* • < OIA. • *vārah (\* vālāḥ) vi-vāhām kṛtvā (or ūdhvā) vadhūm ā nāyati* • < Indo-Iranian • *wāras (wālas) wī wāzhām kṛtvā (or ūzdhwā, ūzhtwā) wadhūm ā nāyati* • < Indo-European • *wélos wī wēghóm kṛtwó (or ughtwó) wedhūm ó néyeti* •.

(vi) মানুষের আই শ বছর • *mānuṣērā āi śā bāchārā* • *a man's life-time is a hundred years* (the word আই • *āi* • *life-time, man's age*, is by itself rather archaic for New Bengali, but it occurs in পরমাই • *pārāmāi* •, আইবুড় • *āi-burā* •, etc.; and বছর • *bāchārā* • seems to be a *sts.*) < eMB. মানুষের আউ শ (শঅ) বছর • *mānuṣērā āu śā (śāā) bāchārā* • < OB. • *mānuṣērā āu (āwu) śaa (śāwa) bacchara* • < Māg. Ap. • *mānuṣa-ēra āu (āwu) śaam baccharā (bacchalā)* • < Māg. Prakrit • *mānuṣa-kēlē (= mānuṣaśśā) āu śaam ( < śaḍam, śadam) vacchalā* • < Old Māgadhī • *mānuṣaśśā āvu (āyu) śatām vacchalā (vacchalāśśē)* • < OIA. • *mānuṣasya (= mānuṣasya) āyūḥ śatām vatsarāḥ (vatsarāśah; \* vatāḥ)* • < Indo-Iranian • *mānuṣasya āyūś ṣatām watsarās (watsarāśas; watās)* • < Indo-European • *mónusosyo āyús kmtóm wetós (? wetserós)* •.

(vii) সে দৌড়ে এল (গেল) • *sē dāurē ēlō (gēlā [gælo])* • *he came (went) running* (lit. *having run*) < eMB. সে দৌড়িয়া আইল (গেল) • *sē dāuriā*



āilā (gēlā) > < OB. \* < sē daūḍiā (daūḍi) āīlā, āyilāwa (gēlāa, gēlāwa) >  
 < Māg. Ap. \* < sē (śaī, śi) dāva-ḍ-ia āyillāa (gaillāa, gayāillāa) > < Māg.  
 Prakrit \* < sē (śaē < śagē, śagē) dāva-ḍ-ia (dāvia) āāē (āyāē < ayāḍē, āyāḍē)  
 (gaē < gaḍē, gadē; gaḍē) > < Old Māgadhī \* < sē (śakē) dāvia (dāva-ṭ-iyā)  
 āyātē (gatē; gaṭē) > < Transitional OIA. \* < saḥ (sa-ka-ḥ, sa) dravya  
 (dru-t-ya, drutvā) āyātāḥ (gataḥ) > < OIA. \* < sa drutvā (= drāvan) ā yātāḥ  
 (gatāḥ) > < Indo-Iranian \* < sa drutwā (= drāwan[ts]) ā yātās (gatās) >  
 < Indo-European \* < so drutwō (= drōwonts) ó (e)yātós (gʷm̥tós) >.

(viii) জায়ে দেখে না, ম'লে পায় \* jyāntē [j̥j̥ænte] dēkhē [dækhe] nā,  
 mā'lē [mole] pāy > *does not see while living, obtains when dead* < eMB.  
 জায়ে দেখে (দেখএ) না, মৈলে পায় \* jiyāntē dēkhē (dēkhāē) nā, māilē pāē >  
 < OB. \* < jīantē (= jīyāntē, jīwāntē) nā dēkhaī, māilē pāāī (= pāwāī) >  
 < Māg. Ap. \* < jīantahī na dēkkhaī, maillahī (< maṣaillahī) pāvēi > < Māg.  
 Prakrit \* < jīvantahi (< jīvantadhi; jīvantaśśi) na dekkhaī (< dekkhaḍi,  
 dekkhadi), maahi (< madadhi, madaśśi; maḍadhi, maḍaśśi) pāvēi (< pāḍeḍi,  
 pāḍēdi) > < Old Māgadhī \* < jīvantaśśi (jīvantē; jīvantadhi) na dēkkhati  
 (dakkhati), maṭaśśi (maṭadhi; maṭē) pāpēti (pappōti) > < Transitional OIA.  
 \* < jīvantē (= jīvantasmin, jīvati; jīvan) na drekṣati (derkṣati < dr̥kṣati,  
 drakṣati, *present form*), m̥ptē (m̥ptaḥ) prāpaiti (< prāpay'ti, prāpayati =  
 prāpnōti) > < OIA. \* < jīvan na \*drakṣati (= \*dārṣati), m̥ptāḥ prā āpnōti >  
 < Indo-Iranian \* < g'īwan(ts) na dārṣati, m̥ptās prā āpnānti > < Indo-  
 European \* < gʷīwonts ne (nē) dérketi, m̥ptós prō āpnēuti >.

## ADDITIONS AND CORRECTIONS





## ADDITIONS AND CORRECTIONS

---

### PAGE

- 1, *l.* 8 : the number of Bengali speakers according to the Census of 1921 is 49,290,499.
- 4, *l.* 13 : *read* 1915 *for* 1914, *and* F. *for* W.
- 8, *ll.* 20-23 : these voiced stops accompanied by closure of the glottis are as a matter of fact found in certain East Bengali dialects, as regular substitutes for the voiced aspirates, [g', dz', d', b'] for [gñ, ḡñ, ḍñ, ḏñ, bñ], as I have found out subsequently. In East Bengali there is accompanying high tone.
- 12, *ll.* 12-17 : Amīr Khusrau was born at Patiyālī in 1253, and died at Delhi in 1325 (E. G. Browne, 'Literary History of Persia,' II, p. 540). The first authentic poet of Urdū seems to have been Muḥammad Qulī Quṭb Šāh, king of Goleonda in the Deccan, who died in 1611 A.C. He used a vernacular Western Hindī speech with Panjābī affinities, not exactly identical with the Hindōstānī of later times. (Cf. Braj-ratn Dās, 'Urdū-kā Pratham Kavi' in the 'Nāgarī Pracāripī Patrikā,' Benares, New Series, Vol. 4, No. 2.)
- 27, *footnote l.* 17 : *after* 1916, p. 364, *add* : R. G. Bhandarkar, in the JBBRAS., Vol. 25, 1917, pp. 76-81.
- 28, *footnote l.* 10 : *in the list of references on the Harappa seals, add at the beginning* : A. Cunningham, (Archæological) Reports, Vol. 5 (1875), pp. 105 ff. ; J. F. Fleet, JRAS., 1912, pp. 699 ff.

About the recent discoveries in Sindh and at Harappa, see Sir John Marshall's article in the 'Illustrated London News' for September 20, 1924, and further articles by Prof. A. H. Sayce and Messrs. C. J.





Gadd and Sidney Smith in the same journal for September 27 and October 4, 1924, respectively. Cf. also S. K. Chatterji, 'Dravidian Origins and the Beginnings of Indian Civilisation' in the 'Modern Review' for December 1924; also the 'Modern Review' for February, 1925, and the 'Journal Asiatique' for 1925, p. 371. See also 'Sumerian Connexions with Ancient India,' by Ernest Mackay, JRAS. for 1925, pp. 697-701. Further articles on these 'Indo-Sumerian' antiquities by Sir John Marshall have appeared in the 'Illustrated London News' for February 17 and March 6, 1926 and in the 'Times of India Illustrated Weekly' for March 7, 1926.

31, l. 7 : *read* dialects *for* languages.

44, l. 16 : *read* Kauṣītaki.

46, l. 8 : the Vṛātyas. Mm. Haraprasād Śāstri derives « vrātya » from « vrāta » *horde*, in a suggestive paper containing some interesting information about the Vṛātyas or 'the Original Inhabitants of Magadha,' one of six lectures on 'Magadhan Literature,' delivered in the University of Patna, 1923.

47, l. 12-21 ; « hēlayaḥ (hēlavaḥ) ». This form has been sought to be explained as a Semitic word, the same as the Hebrew « ʾēlōāh » = Arabic « ʾilāh » (K. P. Jayaswal, in the ZDMG., Vol. 68, p. 719 : cf. R. G. Bhandarkar in the JBBRAS., Vol. 25, pp. 76 ff.). But this is extremely unlikely. Hebrew (as well as Arabic) was rather removed from the tracts where the Aryans moved much or were settled in, in North Mesopotamia and North-Western Iran, at this early period (B.C. 2000-B.C. 1300); and Hebrew conquest of Palestine took place during the closing centuries of the 2nd millennium B.C. The Semitic word for *god* which the Aryans would be likely to pick up, if they did pick it up at all, would be the Babylonian and Assyrian « ilu », which makes the connexion with the Indian form remote. Jayaswal also derives the Indian « mlāccha (Pkt. mlakkhu) » *foreigner* from a Semitic word « mlk », in Hebrew « mēlēx ». But there is no reason not to regard this word as Indo-European (see Uhlenbeck, 'Altindisches Etymologisches Wörterbuch').

- 54, l. 33 : after « -āni », add : the dative plural affix « -āhi » (= -ābhiyaḥ, \* -ābhiḥ ) rather than the genitive-dative affix « -ānaḥ » (= -ānām) which characterised the Midland, North-Western and Southern speeches as in the Aśōka Inscriptions and in Pali (cf. Surendranāth Majumdar Sāstri, 'The Dative in Pali,' in 'Sir Asutosh Mookerjee Silver Jubilee Volumes, III,' Calcutta University, 1925).
- 56, l. 3 : read presents for present ; and in l. 19, read dramas for drama.
- 59, l. 17 : read nama for nāma.
- 59, footnote : Cf. K. P. Jayaswal in the JBORS. for 1924, pp. 189 ff., for further Brāhmi seals from Magadha with « -śa (= -śśa) » for the genitive affix « -sya » (e.g., Mamaśa, Citaśa, Bhadaṃta Lōpagōraśa, Abhaya-vamaśa).
- 65, l. 19 : read Mōlājandī for Mōḍālandī.
- 66, l. 6 from bottom : read  for .
- 67, l. 27 : read Bāgādīs for Bāgūdīs. (The « Vāthurīs » are different from the « Bāurīs ».)
- 68, l. 24 : read Mangalore for Bangalore.
- 71, l. 4 : read Gaina for Gaina.
- 72, footnote, l. 2 : read Lāla- for Laḷa-. Also in l. 11, correct Dīpa to Dīpa.
- 75-76. King Candra-varman of Puṣkaraṇā. Mr. K. N. Dikshit, of the Archaeological Survey of India, definitely suggested the identification of Puṣkaraṇā of the Susunia Rock Inscription with a place in Bengal—in the district of Bankura, and not with Pokharaṇ in Rajputana. Also Mr. Nikhil-Nāth Rāy B.L., in the 'Bhārata-varṣa' for Jyaiṣṭha, 1330, p. 832. There is actually in that district a village 'Pokharna' (vulgo 'Pākhānnā, Pōkhānnā') on the Dāmōdar river, some 25 miles east of Susunia Hill (23 N 87 E, Bengal Survey, scale one inch = one mile, Sheet No. 238, Survey Season 1854-64). This is conclusive, and it would show that Rāḍha at least was entirely Aryanised, and had a Hindu Vaiṣṇava king in the 4th century A.C. ; and it may be concluded that Aryanisation was already some centuries old.
- 90, l. 19 : add at the end, after Jan. 1923, the following : C. D. Dalaland P.D. Gune, 'Bhavisayattakaha by Dhanapala,' Baroda, 1923, Introduction.



- 94, *ll.* 18-20 : the future in « -t- », from the old Present Participle, occurs in East Vanga Dialects : see under *Morphology*, pp. 961-963.
- 100, *l.* 6 : for *rahalaũ*, read *rahalaũ*.
- 104, *l.* 2 : after in Brajabuli., add : The Braja-buli dialect also spread into Assam, or rather, an Assamese Braja-buli was developed, as early as the 15th century, Śaṅkara-dēva and others having composed poems and dramas in it. From the biographies of Caitanya, we learn that it had also spread into Orissa during that century, Braja-buli songs being sung by Vaiṣṇavas in Orissa as much as in Bengal.
- 104, *footnote* : the 'Kīrtti-latā' has been published in the Bengali character, with Introductions and Translation in Bengali, by Mahāmahōpādhyāya Haraprasād Śāstrī, in 1924 (Hṛṣīkēśa Series).
- 106, *ll.* 21-24 : the earliest specimen of connected Oṛiyā seems to be in the newly discovered bilingual inscription (Oṛiyā and Tamil) of Nṛsiṅha-dēva II (13th Century) from Bhubaneswar, very carelessly edited in the JASB. for 1924, pp. 41 ff. Among some of the noteworthy things in this inscription, we may mention the following : (i) the vowel [ɾ] was pronounced as [ri] and not as [ru] as in Modern Oṛiyā : cf. the spelling « Kṛiṣṇa » in *l.* 3 ; and (ii) the word « ācārya < ācārya », which occurs here, also occurred in Old Bengali (see pp. 121-122, *Introduction*). The writing differentiates between the dental and cerebral « l » sounds, and the former, marked with a diacritical sign below as in Modern Oṛiyā (see under *Phonology*, p. 538), has been wrongly transcribed as double « ll », in the verb past tense.
- 109, *ll.* 13-21 : the 'Ṭikā-sarvasva' was written Śaka 1082 : Paṇḍit T. Gaṇapati Śāstrī published the first part in 1911, and completed the entire work in 1917.
- 110, *footnote, l.* 2 : read *Caryā* for *Carjā*.
- 123, *footnote* : the OB. line quoted was evidently a proverb, and it occurs in another MB. work, the 'Caṇḍī-kāvya' of Kavi-kaṇkaṇa Mukunda-rāma Cakravartī, in the form হরিণ জগতবৈরী আপনার মনে « hāriṇḍ jāgātā-bāiri āpanār māse » (as pointed out to me by my friend Mr. Charu Chandra Banerji of Dacca University).

127, after line 2, add :

**65a.** The Sanskrit encyclopædia 'Mānasōllāsa' or 'Abhilāṣārthacintāmaṇi' (of which the first volume has been published in the Gaekwad's Oriental Series, 1925), composed in Śaka 1051 or 1129 A. C. under the auspices of king Sōmēśvara III Bhūloka-malla of the later Cālukya dynasty of Mahārāṣṭra, who ruled from 1127 to 1138 A.C., seems to contain a few Old Bengali lines. (Sakhārām Gaṇeś Dēuskar in the Bengali journal 'Āryāvartta' for Māgha 1317, pp. 678-679; R. G. Bhāṣṇārkar, 'Early History of the Deccan', Bombay, 1895, pp. 89-90; Dēuskar mentions a Marāṭhī article by V. K. Rājawādē on this work read before the 1st Mahārāṣṭra Sāhitya Sammēlan which I have not seen. I am indebted to my friend and colleague Mr. Kshitish Chandra Chatterji, M.A., for bringing Dēuskar's article to my notice.)

In the section on Poetry and Music ('Gīta-Vinōda') in this work, short poems and verses in Sanskrit, Prakrit, Apabhraṃśa, Lāṭī, and in the Dravidian Kaṇṇaḍa speech have been given; and besides a few verses occur, which are undoubtedly in the various NIA. speeches—Old Marāṭhī, Old Braj-bhākhā, and Old Bengali, to judge from at least some of the forms. The work is preserved in various MSS. at Poona, Tanjore, Bikaner, and elsewhere. I could consult one of the Poona MSS. (copied Śaṃvat 1930=1874) which happened to be in the Indian Museum at Calcutta in 1923, and through the kind offices of my friend Mr. Sris Chandra Chatterji, Engineer and Architect, lately in the service of the Bikaner State, I also obtained (December 1923) transcripts of the relevant parts from an old MS. of the work (dated Śaka 1593=1671 A.C.) in the Fort Library of Bikaner. Both the MSS. are very corrupt, and although there is a close agreement between them (both seemingly being based on the same original), the bad readings make it almost impossible to restore the text of the non-Sanskrit portions from these only. Instead of attempting to give a critical edition of these portions in question, I give below tentative readings of some of the vernacular passages based on a comparison



of the two MSS., wherever they can be made out with any degree of certainty. We have thus—

• ..... chāṁḍu chāṁḍu mai jāivō (= jāibō ? jāiba ?) Gōvinda-saha khēlaṇa ..... Nārāyaṇu jagaha-kēru ( -kāṛā) gōsūmvi » (Bikaner, fol. 141a ; Poona, fol. 168b) = *Leave (me), leave (me), I shall go to sport with Gōvinda.....Nārāyaṇa the lord of the world.*

Bikaner folia 141b and 142a and Poona fol. 169(a, b) give a song praising the ten Avatāras of Viṣṇu, which seems to represent more than one form of NIA. The first verse is in Old Marāṭhī, and runs thus : • jēṇē rasātala-uṇu matsya-rūpēm vēda aṇiyalē(m).....tō samsāra-sāyara-tāraṇu, maha-tē(m) rākhō Nārāyaṇu » *by Whom the Vedas were brought from Rasātala in the form of a fish.....the Saviour in the ocean of transmigration...He, Nārāyaṇa, (may) keep me.* The next verse (on the Tortoise Incarnation) is very corrupt. The third verse is as follows : • jō suvara-rūvēṁ pāyalu paīṣi dāṇau Haraṇa-kaebapu mācaviṁ (?), dāḍha Gōvinda dharāṇi uddharaiṁ sō dēu..... » *Who in the form of a boar entered Pātāla and killed the demon Hiraṇya-kaśipu, Gōvinda who rescued Earth with his tusk, that God.....* This verse has Śaurasēṇī affinities, as also the next two verses on Nṛsiṁha and Vāmana Avatāras, but both are hopelessly corrupt.

The sixth shows some distinctive Bengali features : • jē brāhmaṇēra kulē(m) upajiyā(m), Kātavi(r)yā jēṇē bāhu-pharasē khāṇḍiyā : Paraśarāmu dē(v)u sē māhara (mōhara ?) maṅgala karaū » *Who was born in the family of a Brāhman, by Whom with the touch of his arm Kūrttavīrya was cut down, He, the God Paraśurāma, may work my welfare.* The above reading is substantially that of the Bikaner MS., and the Bengali character of this passage is shown by the pronoun • jē », and • -ē(m), -ēra » affixes for the locative and genitive ; and • -iyā » would be the non-1 passive participle adjective ( > verb past) which featured in Old Bengali (see pp. 946 ff.)

The verse describing Rāma is missing in both the MSS. That on Kṛṣṇa is apparently in Old Braj-bhākhā : • Nanda-gōula jāyaṇ Kanhu jō gōvi-janē(m) vaḍihē..... » : but it is corrupt. The

verse on Buddha runs thus : « Buddha-rūpeṃ jō dāṇava-surā vañcaūṇi veda-dūsaṇa bōllaūṇi māyā mōhiyā, tō dēu mājhi pasūu karu » *Who in the form of Buddha, after having Cheated Gods and Demons and having said words of scorn for the Vedas, led (them) astray by his Māyā—that God may grant grace to me : it is distinctly Old Marāṭhī. The last verse on Kalki is in Sanskrit.*

131, ll. 27 ff. *Ḍāk* the Gōwālā (cowherd) is also well-known in Bihār as a sage and author of proverbial sayings, as Sir George Grierson tells me. See also Mm. Haraprasād Śāstrī on *Ḍāk* and *Khānā* in the Bengali journal 'Prāci' (Dacca) for Śrāvaṇa, 1330.

137, l. 13 : *read* form *for* from.

148, l. 30 : *read* « bhāṣā » *for* « bhasā ».

156, l. 13 : *read* vēlā *for* vēla ; l. 15, *correct* to between.

157, l. 13 : *read* « nīb » *for* « nīb » ; l. 14, *read* tāmra *for* tamra.

159, ll. 14, 15 : Pischel gives ('Grammatik der Prakrit-sprachen,' § 304) « uṭṭa, iṭṭa » as MIA. forms. The deaspiration in these words thus goes back to MIA. times, and the W. Hindi « ūṭ, iṭ » are obviously based on MIA. « \* uṇṭa, \* iṇṭa » showing Spontaneous Nasalisation (discussed at pp. 366 ff.).

166, l. 6 : *after* mī *read* :, myā.

171, l. 5 *from bottom of page* : *after* Dravidian sounds, and *add* : these (barring the last, which is found in Dravidian—in Tamil only, to be precise).

176, l. 7 : *read* « ghōṛā-ṭōṛā » *for* « ghōrā-ṭōṛā ».

176, l. 11 : *read* « kudure-gidure » *for* « kudire-gidire ».

177, ll. 21 ff. : This idiomatic use of a verbal conjunctive meaning *having said* is a common idiom in Tibeto-Burman as well—in Kuki-Chin, for instance—and it is also found in Burmese (see LSI., III, Part III, p. 5) ; and it is common in Boḍo also, which was the original language of a large section of present-day Bengali-speakers in North and East Bengal (J. D. Anderson in the JRAS., 1913, pp. 867 ff).

180, *after* l. 14, *add* :

In connexion with the above is to be taken (iv) the Ghugrahati Copper-plate of Samācāra-dēva (cf. Ep. Ind., 1925, Vol. XVIII, pp.



74 ff., ed. by Nalinī-Kānta Bhaṭṭaśāli, M.A.), which mentions « Navyāvakaśikā », as well as « Vāraka-maṇḍala », and « Vyāghra-cōraka » and « Gōpēndra-cōraka » village, and « Vidyādhara-jōṭikā »; and among personal names it gives « Pavitruka, Dāmuka, Vatsa-kunḍa, Śuci-pālita, Vibita-ghōṣa, Śūra-datta, Priya-datta, Janārdana-kunḍa ».

*Para 87*: This Copper-plate Inscription has been edited and published by Dr. L. D. Barnett in the *Ep. Ind.* ('Vappaghoshavāṭa Grant of Jayanāga,' Vol. XVIII, pp. 60 ff.).

182, l. 24: « koppam ». Compare also Tamil « kuppam » *village*.

187, l. 10: The Gōvindapur Grant has since been edited by Prof. A. C. Vidyābhūṣaṇa in the 'Bhārata-varṣa' for Phālguna, 1932.

188, after line 5, add:

[27a] A new Copper-plate Grant of Viśva-rūpa-sēna has been recently discovered in Maimansing, and has been edited by Mm. Haraprasād Śāstri in the 'Indian Historical Quarterly,' Calcutta, Vol. II, No. 1, March 1926, pp. 77-86. This gives quite a number of place-names in Vāṅga, besides some personal names.

195, after l. 6, add: (অ)সওয়ার « (ā)sāwār » *horseman, trooper*, সওয়ারী « sā-wārī » *rider (on horse, in carriage)*: occurs in the Bharhut and Sanchi inscriptions as « asavārī »: from Old Persian « asa-bāri- » *horseman* (=New Persian « suwār »).

195, after l. 18, add: কোণ « kōṇ » *corner*, from MIA., and Skt., = Greek « gōnos ».

196, last line but one: read « śuruṭṭu » for « śuluṭṭu ».

197, l. 1: after Tibetan « blama », add: টাঙ্গান « tāṅgān » *a hill pony, Bhotia pony* = Tibetan « rta-ṅāṅ ».

198, 199: The word « dhītā » (as the source of « jhi ») has also been derived from the Indo-European « √ \* dhē » *suck* (=OIA. « dhā »), which we find in the Latin « fi-lius ».

203, l. 22: read « faṭh » for faṭḥ.

213, last line in footnote 1, read 'khājāñci' for 'khajañci'

215, ll. 9 ff.: the word মেটে « mēṭe », a slang term to denote dark-skinned

Eurasians, is at least influenced by the French « métis », if not actually derived from it. The word may be from « māṭiā » *earthen*, by Umlaut.

215, l. 22 : read ইম্‌কুপ for ইম্‌কপ.

232, l. 7 : read rasūla and mōhāmōti ; l. 20, read pūṣē for pusē.

233 : immediately before § 126, add : Bengali MSS. in the Persian character are but rarely found in other parts of the country. One such MS., however, has come to light recently—a Bengali version of the 'Qissah-i-Amīr Hamzah'—from Jessore district. It was exhibited by Maulavi 'Abdu-l-Wali in the ASB. (November 1925). In its transcription, unlike the Chittagong MSS., it employs regularly হ্ and ঢ্ for চ and জ.

235, heading, read : SILĒṬ ; footnote, l. 4, read in for is.

245, l. 22 : read tzāndanon for tsāndanon.

254, 255 : loss of « -tr- » > « -tt- » : W. Geiger cites also (Festschrift E. Kuhn, p. 186) Sinhalese « hū » (sūtra), « mū » (mūtra) « rā » (rātri).

256, l. 21 : « ratta (< ratna) » actually occurs in MIA. (in the Pali 'Sutta-nipāta,'—'Sabhiya-sutta' : « ratta-ñña » = « ratna-jña », explained in the Commentary of Buddha-ghōṣa as « ratana-ññū »).

260, l. 25 : read « -vā » for « -ā ».

263, l. 18 : read 'fi(ṣ)ā:la for fi(ṣ)ā'la.

264, l. 14 : read kōfi for kōhi ; l. 17 : read ṣupōri for ṣupāri.

265, l. 5 from bottom : read monḍ for monḍ.

269, l. 3 from bottom, add : The glottal stop occurs with the voiced stops and palatal or dental affricates [g', ṣṣ' (dz'), ḍ', d', b'] in some East Bengali dialects as the regular substitutes for the corresponding aspirates [gh, ṣṣh, ḍh, dh, bh] of Standard Bengali.

272, l. 17 : correct the figure for : [h] from 2·02 to 0·02.

282, l. 12 : read pāṇiya- for pāṇiya.

287, ll. 11, 12. It should be noted that the « Payār » has also 16 moras, including the pauses, although the number of syllables is 14.

293, l. 6 : read bācṣia for bācṣia.

294, l. 12 : read 'cā(ṣ)e for 'ca(ṣ)e.



- 298, l. 6 : read 'jaṅṅo for jaṅṅo.
- 301, last line : read pātā for pātā.
- 302, l. 20 : read kārā for kārā.
- 305, l. 20 : after (grīvā), add : MB. ঘড় < ghārā > array (ghaṭā);
- 307, last line but one : read < āc > for < āc >.
- 309, l. 8 : read MB. for MA.
- 313, l. 11 : after (alābu), add : হেঁটে < hēṭā > below > in a crouching position (\*ahēṇṭa, \*ahēṭṭha < \*adhiṣṭāt, Buddhist Sanskrit hēṣṭā, = OIA. adhistāt); MB. পানরে < pāsārē > forgets (apasmarati);
- 315, l. 19 : read māśānā for māśānā.
- 315, l. 12 : read < ātā > for < ātā >; after (antra), add : আশথ beside অশথ < āśāthā, āśāthā > (āśvattha); and in l. 15, delete : খাজ < khājā > a sweetmeat (khāḍya), and take this deleted portion to p. 321, l. 23, before the word খাড়, adding khājja before khāḍya.
- 319, l. 20 : the word < sabbā > forming the plural. Mr. Sukumār Sen has drawn my attention to the word < yuvati-sabbā > young women in Song 18 of the 'Gīta-gōvinda' (Canto IX). Cf. also pp. 732-733.
- 324, l. 6 : read < niṣuti > for < niṣuṭi >; l. 10, read \*piuṣi for piuṣi; l. 25, read চীহ for চীহ.
- 325, l. 20 : read \*ūru- for \*uru; l. 21, read -aṣṭhi- for -asthi-.
- 329, l. 8 from bottom : correct bōḍṛa to bōḍra.
- 331, l. 20 : read 'যদ্দিন' for যদ্দিন; l. 25, read caritavya for cartavya.
- 333, l. 8 : after [fidne], add : ঘটটা < ghāṭi-tā > that water-vessel, বাটাটা < bāṭi-tā > that cup > Standard Coll. ঘটটে, বাটেটে [ghoṭṭe, baṭṭe].
- 334, l. 7 from bottom, add : করমোচ < kārāmōcā < kārā-mōcā > a fruit, Cassia carondas (Skt. kara-marda, Hind. karaundā : cf. 'Devatā,' Pāṇini Office, Allahabad, 1917, p. 155).
- 335, l. 7 from bottom : correct persons to person.
- 337, l. 10 : correct -ū- to -ū-.
- 341, l. 6 from bottom : read jāer for jāer.
- 342, l. 10 : read chāyārā for chāyārā; l. 19, delete MB.
- 349, l. 1 : after NIA., add : (where no special force of the < ā > is present or evident).

- 350, *l. 4*: *before etc.*, *add*: বাই, তাই < jāi, tāi > (yadā-hi, tadā-hi).
- 351, *l. 13*: *add at the end*: But পৌনে [poune] *less by a quarter* has < -āu- > for MIA. < -āō- > (pāōṇa, pādōṇa).
- 352, *l. 15*: *read* \*duūlia *for* duulia; *l. 8 from bottom, after* (dēva, dēha), *add*: ‡ রে [re:, ræ:] *line for plough to follow* (\*rēā, rēhā, rēhā, rēkhā);
- 353, *l. 7 from bottom*: *read* \*ghrata.
- 355, *l. 8, after* (nacca, nṛtya), *add*: ‡ বাসোয় < bāswā > *or*, Maithili < basahā > (vasaha-, vṛṣabha-); *in l. 21, read* \*tāḍṛśana.
- 356, *l. 2*: *before etc.*, *add*: বুক < buka > *chest* (cf. Skt. vṛkka, Avestan vərəḍka *kidney*, MIA. bukka);
- 357, *l. 5 from bottom*: *correct* egreja *to* igreja.
- 358, *l. 3, l. 6*: *read respectively* [abrito] and [abbrito]; *last line, correct to* ghanakam.
- 359, *l. 12*: *for* < 𑂔 > *read* < 𑂔 >.
- 364, *l. 7, add*: But we have the *sls.* বেন্নন < bēnnanā > [bænnon] *curry* from < vyañjana >.
- 365, *l. 12*: *read* ṣaṇḍa *for* saṇḍa.
- 366, *l. 7 from bottom*: *read* śimulā *for* śimula.
- 367, *l. 12, add*: and ŚKK. চাম্বলী < cāmbhālī > *a flower* for < cāmēli >.
- 369, *l. 7 from bottom*: *read* \*inṭa *for* \*inṭa.
- 370, *l. 6*: *read* sēcayati *for* sēcayati; *l. 19, bāṭulā* *for* bāṭulā.
- 373, *ll. 11-12*: *read* ṣ for ṣ.
- 378, *l. 13*: *after e.g.*, *add*: Pali < issēra, acchēra < \*ēssaira, \*acchaira < \*essairīa, \*acchairīa < āiśvarya, āścarya >.
- 386, *l. 18*: *after* < gāṭṭā >, *add*: beside গোট < gōṭṭā >.
- 392, *l. 19*: *read* [jōṭṭa] *for* [jōṭṭa].
- 396, *l. 3 from the end*: *read* [borp(h)i] *for* [borp(h)i].
- 398, *l. 10 from bottom*: *read* \*কুড়ালি *for the first* কুড়ালি, *and* kuṛālī *for* kuṛālī.
- 402, *l. 14, before origin, add to their*: *l. 5 from bottom, read* [fore ɔ].
- 424, *l. 6 from bottom*: *add*: MB. < -āhā-, -aṣa- > *also occur as* [əḥ]: গহনা < gahna > < \*gāhānā > *ornaments, jewels* (grahaṇa-); ময়না [məṇa] < \*māyānā > *a talking bird, 'myna'* (madana-). *In l. 16, read* bhāṣṣa *for* bhāṣṣa.



- 430, *ll. 4 and 2 from the end*: [ʃts] (as in [kəʃtsit] and [dzoŋk:həʃtsək:re:]) is pronounced also as [reʃ] and [ceʃ].
- 438, *l. 9*: read §84 for §86.
- 440, *l. 21*, read gār for gār; *last line*, correct † to ‡.
- 441, *l. 3*: *The Aspirates*. It should be noted that the aspirate nasals and liquids (◀ nh, mh, rh, lh ▶: cf. 'Prākṛta-Pāṇḍala,' Bib. Ind. ed., p. 6) occurred in OB. and Early MB., and these became deaspirated in the Late MB. stage.
- 443, *l. 5 from bottom*: read ◀ ādāḷā ▶ for ◀ ādla ▶.
- 449, *l. 5*, add recent before foreign, and put a comma after words. *After l. 8*, add: Other instances of assimilation: ◀ n > m ▶: মোহনভোগ ◀ mōhāṇḍ-bhōgḍ ▶ pudding made of flour, sugar and ghee > [mo(ḥ)on-bhōg > mombhōg > mumbhōg] in the Calcutta Colloquial; ◀ ṇḍ > n > ṇ ▶: ডাঙগলি ◀ ḍāṇḍā-guli ▶ tip-cat (game) > ডান্গুলি, ডাংগুলি [ḍaṅguli, ḍaṅguli].
- 451, *l. 22*: correct pañca to pañca; *l. 24*, at the beginning, add: [r] is similarly assimilated to a following [ʃ], as in মাকড়সা ◀ mākarḍṣā ▶ spider > Calcutta Coll. মাকসা ◀ mākaśā ▶ [makarṣa > makorṣa], হাঁড়ীশাল ◀ hāṛīśālḍ ▶ room for pots, kitchen > [hāṛṣāl] by Epenthesis > হেঁশেল [hēṣel].
- 452, *l. 5*, and *l. 4 from bottom*: correct < to >.
- 453, *l. 17*: correct gh to gḥ.
- 456, *l. 14*: correct kākḍ to hākḍ.
- 460, after *l. 8*, add, in a new paragraph: OIA. ◀ -ksy- ▶: ভেখ, ভেক ◀ bhēk(h)ḍ ▶ mendicancy, the life of a monk, monk's garb (bhāṇikṣya).
- 468, *l. 13*: add so before long.
- 470, *l. 2 from bottom*: correct the semicolon before পেঁচা to >.
- 471, *l. 8 supply*, after jēācḍ: woman with first child living. *L. 9*, before etc., add: MB. আচাভুয়া ◀ ācābhua ▶ (accabbhua-, atyadbhuta-). After *l. 11*, add as a new paragraph: OIA. ◀ -re- ▶ > MIA. ◀ -ce- > -ñc- ▶: আচ ◀ ācḍ ▶ heat of flame (arciḥ); কুঁচি ◀ kūci ▶ brush (kūreikā).
- 472, *l. 2 from bottom*: read \*es-ské-ti for \*es-sko-ti.

- 473, l. 2: read \*pró + bhu-ské-ti; l. 3, read \*prk-ské-ti; l. 17, add at the end: MB. নেউছা, নিছা « nēuchā, niehā » adorn (« nēvaccha-, nēpathya- »: there is another form in MB., নিছা « niehā », for which see *infra*, p. 551).
- 475, l. 13: read 'fry' for 'try'; l. 3 from bottom, correct † to ‡.
- 480, l. 15: delete \*before dhītā, and add after duhitā): (the MIA. « dhītā » is derived by some scholars from the IE. « \*√dhē » suck = OIA., « √dhā », which is found in the Latin « filius, filia ».)
- l. 7 from bottom, read ঝুঁঝা for ঝুঁঝা; l. 5 from bottom, read ঝুঁটা for ঝুঁটা.
- 484, l. 18: read « mardā-mi » for « mardāmi »; l. 5 from bottom, delete one and.
- 488, l. 26: read ḍāṣḍ for ḍāṣḍ.
- 490, l. 16: read টাট্ট for টাট্ট.
- 495, l. 5: read ḍimba for dimba.
- 498, l. 15: read ডেগ for দেগ.
- 502, l. 9 from bottom: correct > to <.
- 509, l. 21, read পুঁটা মাছ for পুঁটা মাছ.
- 510, l. 10 from end: add, after « rūpā »: silver; and after rūpya: stamped coin.
- 513, l. 2 from bottom: correct to বেওয়া.
- 514, add after l. 17, as a separate para.: OIA. « -vy- »: the future base ইব « -ibā- » (OIA. « -itavya- », MIA. « -iavva-, -iabba- »).
- 515, l. 5, read bhukhḍ for bhukha; after l. 23, add as a separate para.: OIA. « -dbh- »: MB. আচাভুখা « ācābhuxā » (atyadbhuta-); and then after that add the portion from উভিয়া বাওয়া to (ud + √bhr, bhar) in ll. 31-33 (by mistake entered under OIA. « -rbh- »).
- 520, l. 9: before MB. গোড়াঞ, add: গুঁই « gūi » a surname (« -gōmin »: cf. Candra-gōmin, the Bengal grammarian of c. 600 A.C.);
- 521, l. 11: before ছাতিম, add: Standard Coll. গোম্বে [gomne] late, a sts., for গোণে « gāṇḍ [goune, gōwne] » (< gāṇa);
- 523, l. 10: read ḥ for ḥ.
- 525, l. 9 from bottom: read most for all; l. 3 from bottom, correct to intervocal.



- 527, l. 9: *correct to* বিষ্ট পুরের.
- 534, l. 11 *from bottom*: *correct to* পর.
- 535, l. 2: *read* [ð] *for* [ð].
- 536, l. 13 *from bottom*: *read as follows*: at a later time, Early Braj-bhākhā in the West as well), to change....
- 548, l. 11 *from bottom*: *read* apasmarati *for* prasmarati.
- 549, l. 1: *read* śimśapā *for* śimsapā.
- 550, l. 9: *read* si *for* sī; l. 2 *from bottom*, *read* śatāyuh.
- 556, l. 9 *from bottom*: *read* bālei *for* bālei.
- 557, l. 10: *read* sāhā *for* sāha; 11, *read* nēhā *for* nēha.
- 560, l. 9: *read* regarded *for* regard; l. 12, *read* Saifi *for* Saifi.
- 563, l. 3 *from bottom*: *correct to* syllable.
- 570: l. 8, *read* 'Moghals' *for* Moghals; and in the Table of Consonants, take h *from the* Semi-vowel *to the* Fricative line.
- 576, l. 7: *read* [tābu] *for* [tābu]; l. 11, *correct* Hindōstani *to* Hindōstāni; l. 23, *read* fiab(e)li *for* fiab(e)i; l. 25, *read* হালুয়া *for* হালুয়া; and l. 26, fiabfi *for* fiabfi.
- 577, l. 4 *from end*: *read* বিশবৎ *for* বিশ্বৎ.
- 580, l. 9: *read* হিন্দু *for* হিন্দু; and l. 5 *from bottom*, *before* and, *add*: and আমারী = āmāri = canopied seat on elephant (imāri).
- 581, l. 14: *read* corpses *for* corpses.
- 593, last line: *add* In *as the* last word.
- 608, l. 12 *from bottom*: *correct* phāṣṣad *to* phāṣṣad.
- 613, l. 5 *from bottom*: *before* হাজির, *add*: নজর [naḡḡar] *present* (naḡr);
- 621, l. 10: *correct* Collected *to* Collected.
- 623, l. 11: *read* তোলা *for* তোলা.
- 625, l. 5: *read* 'coffee' *for* 'caffee.'
- 643, l. 6: *before* 'theatre,' *add*: (also থিয়েটার [thiēṭar] commonly in Calcutta cockney, through assimilation with the following cerebral).
- 656, l. 13: *read* ghūrṇ- *for* ghūrṇ-.
- 658, l. 4: *read* রাধনী *for* রাধনী.
- 670: *read* rūpālī *for* rūpālī in l. 7, and rūpuli *for* rūpuli in l. 8.
- 672, l. 17: *read* রাধনী *for the* first রাধনী.

- 673, l. 2: read বহু মী for বহু মী.  
 677, last line: read peonastically for peonastically.  
 682, l. 13: read dholla for dholla; l. 20, before পুটকে, add: মেচকে in মেচকে  
 কের • mēcākō • in • mēcākō phēṣ • a strong knot, a complication < a  
 knot in a jute rope ( < মেচ • mēcā • jute in the Standard Dialect in  
 tracts to the south of Calcutta);  
 688, l. 5: read s̄ap̄ariyā for s̄ap̄ariyā; l. 6, read লুটিয়াড়া.  
 697, l. 6 from bottom: add: • ugra-rūpa • exceedingly fierce, Pali • kalya-  
 rūpa • exceedingly pleased, etc., etc.  
 699, l. 5 from bottom: read ঝুপসা for the second ঝাপসা.  
 702, l. 4 from bottom: read thānī for thanī.  
 703, l. 1: correct to Perso-Arabic.  
 706, under (9) মর, add: It is likely that in the locative sense, as in দেশমর,  
 the affix is partly based on the NIA. locative suffix from • madhya •  
 noted *infra*, p. 751.  
 706, before last line add:

(12) স্থ • -sthā •.

- 467a. Following Skt. forms like দেশস্থ • dēśā-sthā • remaining in  
 the land, সভাস্থ • sābhā-sthā • present in the assembly, মধ্যস্থ • mādhyā-  
 sthā • remaining in the middle, arbitrator, etc., etc., the compounded  
 • -sthā • has come to be used as an affix with *tōh*. and foreign words, in  
 the sense of occurring at, present in, etc.: e.g., কলিকাতাস্থ • Kālikāta-  
 sthā • of Calcutta, from Calcutta, staying at Calcutta; লড়াইস্থ সংবাদদাতা  
 • lārāi-sthā sambādā-dātā • war correspondent; কর্ণওয়ালিস-স্ট্রীটস্থ দোকান  
 • Kārnāwālis-Strīṭā-sthā dōkāna • shop in Cornwallis Street; etc.  
 712: Add at the beginning:

(5a) পাতি, পাত • pāti-, pāt- •.

- 473a. This word, in the sense of small, occurs with a number of  
 terms, like পাতি-কুয়া or পাতকো • pāti-kūā, pāt-kō • a small well (as  
 opposed to an ইদারা • Idārā • a large masonry well < • indrāgāra •),  
 পাতি-শিয়াল • pāti-ṣiyālā • small jackal, পাতি-লেবু • pāti-lebu • a kind of  
 tiny lemon (as opposed to other kinds), পাতি-হাঁস • pāti-hāsa • duck



(as opposed to রাজ-হাঁস • rājā-hāṣa > *goose*), পাতি-ভাঁড় • pāti-bhāṛa > *small earthen cup*, পাতি- or পাত-মৌড় • pāti-, pāt-māuṛa > *an ornament for the head* (< mukuta), পাতি-কাক • pāti-kāka > *crow* (as opposed to দাঁড়-কাক • dāṛa-kāka > *jack-daw*), পাতি-নেড়ে • pāti-nēṛe > *shaveling, small shaven-headed one* = *Mohammedan of the lower castes* (a term of abuse), etc. The form occurs in East Bengal as পেতি • pēti, as in পেতি-কোয়া • pēti-kauā > *crow*, পেতি-মেকুর • pēti-mēkur > *kitten*. The source seems to be OIA. • patra > *leaf* > • patrika, MIA. • pattia > NIA. • pāti > *thin as a leaf* > *small, insignificant*: cf. পাতলা • pātālā > *thin, not deep* (patra-la). The French • petit [pēti, pti] *small* has been suggested by some as the source of this form, but it is exceedingly unlikely, despite the fact of the presence of the French in Bengal (at Chander nagore), and of the East Bengali form • pēti presenting an unexpected vowel in the • -ē- (the East Bengali form, however, seems to be a borrowing from Standard Bengali with irregular alteration of the vowel).

712, l. 13: correct • nābālākā > to • nābālākā.

720, ll. 8, 9: delete • বৎসহারী গাভী • bātsā-hārā gābhī > *a cow which has lost her calf*. In l. 11, read form for from.

731, ll. 11, 13: read 'professors' for 'scholars'; and in last line but two, put an \* before মাহবদ.

733, l. 5: read rājā-nāitika.

740, l. 7 from bottom: read: a form of Māgadhī.

741, l. 9: read \* thāwī for thāwī; l. 12, add after NB.: so Assamese • gādhāī (< \* gaddahi, gaddahē, gardabbah), • lātāī (< ts. latā + -i). In l. 24, read p. 1 for p. 2.

744, l. 6: read • gōru-ē for • gōru-ō.

745, l. 2: read • -ānām for • -anām.

751: add as a new paragraph, after l. 16:

In dialectal Bengali, as in Sylhet, there is a locative affix in • -ō, -ā > ; e.g., ঘরো, ঘরা • ghārō, ghārā > *in the house* (LSI., V, I, p. 225). This would seem to be based on a MIA. • \*gharaha > ,

where « -ha » is the OIA. affix « \* -dha », of a locative character, which is found in Sanskrit in « i-ha (cf. Prakrit i-dha), ku-ha, sa-ha (cf. Vedic sadha) », and which seems to have been extended to the noun also. (This « -dha » seems to be connected with the other locative affix « -dhi » discussed before at p. 745, and has cognate forms in the Latin « in-de », Slav « kŭ-de » : cf. Thumb, 'Handbuch des Sanskrit,' Heidelberg, 1905, § 407).

751, l. 8 from bottom : read an unsolved problem.

756, l. 8 : « udyāna-kṛtam āsanam » (cf. Grierson, 'On Certain Suffixes in the Modern Indo-Aryan Vernaculars,' Kuhn's Zeitschrift, Vol. 38, pp. 478 ff. : also « karaṇḍē mālā-kṛtē », in the 'Mahā-vastu,' etc.).  
Last line but two : read puruṣāṇām.

759, l. 12 : the affix in Assamese seems to be ৭ « sā » : cf. also the genitive form « tōmāsā-rā » and the locative « tōmāsā-tā » in Early Assamese.

762, ll. 2, 3 from end : a solitary example of an ablative form in OB.

There is another instance of an ablative in « -hu » in the Caryās, viz., « raṇṇahu ṣahajā kabēi » (Caryā 27), which the Sanskrit Commentary translates and explains as « sadguru-vacana-tattva-ratna-prabhāvāt sa mayi saha-jānandam kathayati ».

772, under Post-position No. (26), বই « bāi ». My friend Mr. Sailēndranāth Mitra, M.A., of the Department of Pali in Calcutta University draws my attention to the use of « bahiddhā » in Pali, with the ablative, to mean *apart from, outside of* : e.g., « itō bahiddhā samaṇō'pi n'atthi » *outside of this, there is no monk* (Mahāparinibbāṇa-sutta, V, 27). The use of « bahiḥ, bahirdhā (= bahiḥ + dhā) », with the ablative as well as genitive, to denote *outside*, occurred in OIA. (cf. Speijer, 'Vedische und Sanskrit-syntax,' §§ 88, 89, 90). The source of the Bengali post-position বই, বহি, বহী « bāi, bāhi, bāhī » would thus be the OIA. « bahiḥ », and not « vyatīta » as suggested in the text.

790, l. 14 : correct to Wackernagel.

800, l. 15 : read śō for sō.



- 801, l. 21 : A MIA. form for « sahasra » seems to have been « sahaṁsa » (beside « sahasa »), and this nasalised form occurs as « saḥāsa » in Early Western Hindi. An old spelling of the place name 'Sasseram' or 'Sahasram' in Bihar is 'Sahansram.'
- 802, l. 11, *add at the end*: There is also the word সিকি « siki », সিকা « sikā » a quarter, a silver coin equal to the fourth of a rupee. The word occurs dialectally as « suki, sukā », and is apparently the same word as the Hind. « sūkā ». Platts derives « sūkā » from « sapādaka » with a quarter ('Hindustani Dictionary'). It may be that here we have the influence of the MIA. « sikka » (see *supra*, pp. 194-195) or the Perso-Arabic « sikkah » coin, in connexion with the « -k- » consonant as well (as the « -i- » vowel in the Bengali form).
- 811, l. 17 : *read* মুঁহি, *for* মঁহ,
821. *In the Table, under Old Plural, Oblique, read* তী *for* ভী; *under New Plural, Nominative, read* ভা(হা)রা, *and oblique, ভা(হা)দের*; *and in connexion with what has been said in l. 8 in § 555, note: the form « sa-kaḥ » actually occurs in OIA. (Rig-Veda, Śatapatha Brāhmaṇa, etc.): see below, note on p. 993.*
- 823, l. 13 *from bottom* : *read* তী *for* ভী.
- 825, l. 17 : *read* possesses *for* possess.
- 828, l. 10 : *read* tāṁḍ-rā-rā *for* tāṁḍ-ra-rā.
- 829, l. 2 in § 566 : *delete comma after* « ē-ta- »; l. 5, *read* : base « \*to- ».
- 832, l. 3 *from bottom* : *read in the Shahbazgarhi Aśōkan.*
- 835, l. 7, *read* উহা *for* উহা; *in the Table, under Oblique of Old Plural, read* ওহী *for* ওহা.
- 839, *read* [F] *for* [D] *before the heading THE RELATIVE PRONOUN*; *and in the Table, under Oblique of Double Plural, read* যা(হা)দের *for* যা(হা)দের.
- 840, l. 6 : « ya-kaḥ » as the source of « jē » occurs in OIA., like « sa-kaḥ » the source of « sē » : see *supra*, note on p. 821, and *infra*, on p. 993.
- 861, l. 14 : *read* \*-n- *for* -n-.
- 862, l. 4, *read* div-ya-ti *for* div-ya-ti.

- 867, l. 3 from bottom : read *cār-i-tav-āī* for *car-i-tav-āī*.
- 869, l. 12 from bottom : read *NOUN* for *VOUN*.
- 871, l. 15 : read *seem* for *seen*.
- 873, l. 12, read *es-ské-ti* for *es-sko-ti*; l. 15, read *বুজ* for *বুজ*; l. 24, read *ধস* for *ধর*.
- 874, l. 5 : read *lāj* for *āj*; last line, read *Bengali*.
- 875, l. 12 : read *es-ské-ti*; l. 14, read *pró + bhu-ské-ti*.
- 882, l. 22 : read *vyākhyāna* for *vyyākhāna*.
- 884, l. 16 : read *দাগা* for the second *দাগ*.
- 885, heading line : read **COMPOUNDED AND SUFFIXED ROOTS**.
- 898, ll. 18-19 : The dative-accusative with the post-position occurs in OB. : e.g., Caryā 12, « *matīē ṭhākura-ka parinivittā* » = « *matyā prajñāpāramitānubuddhyā ṭhākuraṃ iti saṅklēśārōpita-cittaṃ parinirvvā-ṇārōpitaṃ kṛtaṃ* », according to the Commentary.  
L. 3 from bottom : read *like* for *ike*.
- 900, l. 12 : read *labh-ē-ta* for *labh-i-ta*.
- 901, l. 3 : read *NB.* for *MB*.
- 904, l. 5 : read « *-aū* » : « *kar-aū* ».
- 907, l. 16, add : The affix in the form of « *-ūt* », however, is actually found in S.-W. Bengali : চলুৎ « *calūt* », etc.
- 908, l. 15 : read *later* for *latter*.
- 909, l. 15 : add : The form « *gā* » (earlier form « *gai, gaē* ») is also optionally added in Maithili to emphasise the future (cf. Grierson, *Maithili Grammar*<sup>2</sup>, pp. 136-137).  
L. 4 from bottom (=heading line) : read as (1) **PASSIVE INDICATIVE**.
- 924, l. 18 : read *lālāṭā-* for *lālāta-*.
- 932, l. 7: read *খোয়ে* for *খোয়ে*; l. 11, read *পায়ে* for *পায়ে*.
- 941, l. 11: correct to *Grammatik*.
- 956, l. 4: read « *cālī, jāī* ».
- 961, headline : correct to **FUTURE**.
- 968, l. 13: read *is* for *in*.
- 975, l. 9, from end : read « *pāṛilāhō* » for « *pāṛilāhō* ».



984, l. 19 : *correct the first वृत्ति to वृत्ति.*

993, last line, after 'e.g.' add : MIA. « aha-ka-m, tva-ka-m », OIA. (Rig-Veda) « asa-ka-, sa-ka- », (Kauṣītaki Brāhmaṇa) « yāma-k-i », (Sata-patha Brāhmaṇa, etc.) « sa-kā, sa-ka-, ya-ka-, ya-kā, asa-ka- », etc ; and note also.....( I am indebted to Mr. Sukumār Sen for drawing my attention to the OIA. forms occurring in the Vedic texts).

1019, l. 9 from the end : read « āch » for the present and the past.

1029, l. 13 : read « -(i)t- + -it- » + root « āch ».

1032, l. 10 : read pālānā for pālānā.

1035, l. 3 : read adjective passive participle for verbal noun ; and in l. 6, take the semicolon before so.

1040, last line but one : read altindischen.

---

## **INDEX OF BENGALI WORDS**





# INDEX OF BENGALI WORDS

[The Numbers refer to Pages]

- ঞ—(sound) 142, 258, 263,  
 271, 283, 303, 344, 391,  
 394, 396, 397, 402, 403,  
 413, 575, 576, 582, 623,  
 636, 638; (suffix) 652, 653,  
 678; (prefix) 397, 709, 710;  
 (noun stem) 716; (verb  
 inflexion) 903, 906, 925,  
 974, 977, 987, 989, 1012,  
 1013  
 ঞই—(sound) 344, 397, 425;  
 (suffix) 672; (pronoun)  
 539  
 ঞইহন—854  
 ঞউ—(sound) 427; (verb  
 inflexion) 903  
 -অউক—903  
 অএ—424  
 অঙ—425  
 অঙরংজব—588  
 অং—402  
 ঞ—346  
 ঞ—402  
 -অক—679, 681, 986  
 অকখা—406  
 -(অ)কা—681  
 -(অ)কি—681  
 -অকী—681  
 অকু—596  
 অকুমারী—378, 710  
 অকেও—710  
 অকু—616  
 অকোবর—642  
 অক—382  
 অখন—857, 997  
 অখুন—997  
 অখুদী—710  
 অগর (= Eng. auger)—636  
 অগেহান—462  
 অগুণা—431  
 অদর—710  
 অঘোর (নিজা)—710  
 অজা—431, 440, 463  
 অজার—440  
 অজ—533  
 অচিন—529  
 অচেনা—529  
 অছি—584, 612, 615  
 অছিল—612, 615  
 অজ্জল—473  
 অজা—710  
 অজের—578  
 অজাত—382  
 অঙ্গর—311, 481  
 অকোর—481  
 -অকি—989  
 অজলি—431  
 অটো—400  
 অটল—337  
 -অত -অং—653, 654, 655  
 অত—854  
 -অতী—653, 654  
 -অতি, -অতী—653, 654, 655  
 অতুল-উআ—333  
 অতক—855  
 অখায়র—346  
 অখির—336  
 অকুত—449  
 অকু—447  
 অখীর—303, 397  
 অখাক—216  
 -অন (verbal noun)—651,  
 656, 657, 924, 1012  
 অনক—533  
 -অনা—657  
 অনা—709, 710, 1012, 1013  
 অনাচিষ্ট—710  
 অনাধিনী—696  
 অনামু—710  
 অনামুষ্টি—710  
 -অনি—692  
 -অনী—657, 1012  
 অদুগ্রহ—304  
 অদুবাদিত—704  
 অনুদিত—304  
 অনেক—733  
 -অপ্ত—(present participle)  
 112, 653, 654; (verbal  
 affix) 903, 974, 986, 989,  
 999  
 অদুঃকরণ—558  
 অনুর—112  
 অনুরবাদী—376



অন্তরে—769  
 -অন্তি—974, 986  
 -অন্ত—796  
 অণ্ড—381  
 অণ্ডারী—473  
 অণ্ডাধা—89  
 অণ্ডাধু, অণ্ডাধু—716  
 অণেকা—767  
 অণ্ড—347  
 অমাই—422  
 অপরাজিতে—431  
 অঙ্গরী—673  
 অক্ষর—909  
 অবলা—413  
 অবনতি—710  
 অবিরত—419, 704, 710  
 অবিভি—705  
 অবুধা—710  
 অব—837, 856  
 অবের—712  
 অবেলা—710  
 অভাগিনী—694  
 অভাস, অভাস—393  
 -অন্—974, 975  
 অমত, অমন—851  
 অমন—378, 711  
 -অমি—666  
 অমিরা—355  
 অমৃত, অমৃত—357  
 অর (sound)—424, 426  
 অরি, অরী (sound)—425  
 অরু, অরু (sound)—427  
 অরে (sound)—424, 426  
 অ'রে (sound)—426  
 অনৈয়কলত, -অর—645  
 -অর—112  
 অররা—710  
 অরি—397

-অরি—668  
 অর্গান—214  
 অর্শা—884  
 অর্শান—582  
 -অল—669  
 অলিকুল—727  
 অলী—615  
 অশব—335, 504, 506, 1068  
 অশুদ—506  
 অশুদ—710  
 অধ—534  
 অষ্ট—792  
 অষ্টঅশী—792  
 অষ্টন(র)ই—792  
 -অসিরা—700  
 অস্থ—397  
 অস্থাদি(র)—814  
 -অহ—(sound) 425 ; (verbal  
 affix) 903, 906  
 অহিনু—710  
 অহিসাবী—710  
 -অহে—425  
 'অ্য'—271  
 অা—(sound) 258, 271, 272,  
 389, 393, 402, 404, 574,  
 575, 576, 579, 582, 622,  
 636, 637, 638, 639 ; (suffix)  
 656, 657, 658, 660, 664,  
 716, 734 ; (genitive affix)  
 162, 762 ; (in verb forms)  
 921, 922, 923, 926, 974,  
 980, 988, 1012, 1029,  
 1034 ; (prefix) 709, 710 ;  
 (verb-root) 874, 1046  
 আঅর—283, 314, 340, 349  
 আআ—429  
 আই—(sound) 421 ; (affix)  
 422, 661, 662, 663

আই (grandmother)—307,  
 421  
 আই (—Ayus)—310, 406,  
 662  
 আইথ—383  
 আইচ—342, 471  
 আইজ—269, 380, 385  
 -আইড—653, 655, 663, 676  
 আইদ—308, 380, 383  
 আইন—582, 584  
 -আইন—725, 974, 986  
 আইন্ডে—1021  
 আইবুড়—422  
 আইরা—416  
 আইরানে—1007  
 আইরারে—994  
 আইল—(verb) 320, 386,  
 544, 1046  
 আইলপনা—380  
 আইলা—386  
 আইলাম—383, 386  
 আইলাহে—975  
 আইলে—1046  
 আইলাই—987  
 আইলু—384  
 আইশ—892  
 আইস—123, 379, 874, 892,  
 1046  
 আইসই—350  
 আইসতে—385  
 আইসা—885  
 আইসি—340  
 আইসিও—1046  
 আইসিরা—352  
 আইসিল—1046  
 আইসিস—1046  
 আইহু—379  
 আইহুক—1046

- আইন—1046  
 আইসে—320, 345, 379, 383, 387, 550  
 আইহ—198, 283, 307, 314, 347, 383, 554  
 আইহা—198, 283  
 আইহুত—692  
 আই—162  
 আইব—372  
 আইশ—310  
 আঁগা—882  
 আঁক—260, 307  
 আঁলা—351, 704, 882  
 আলুসা—699  
 আউ (= *syna*)—310  
 আউ (sound)—423  
 আউআ (আঁগা)—664  
 আউখ—310  
 আউট—493, 554  
 আউট (= *Eng. out*)—639, 645  
 আউল—320, 342, 379, 383, 544  
 আউলা—345, 351, 386, 423, 704, 882  
 আউলাইল—353, 957, 1033  
 আউশ—320, 355  
 আউব—355, 547, 548  
 আও—(sound) 423 ; (suffix) 683  
 আওর—874  
 আওলা—320  
 আওট—349  
 আওটা—320, 423, 491  
 আওড়া—423, 887  
 আওতা—535  
 আওরাজ—314, 616  
 আওরাস—427  
 আওরাজেব—588, 607  
 আওরজেব—607  
 আওলা—522  
 আওটি—493  
 আওরজ—215  
 আই (= আনি)—521, 815  
 আই—726, 974, 986  
 আইব—336, 372, 519, 547, 550  
 আইবটিয়া—686  
 আইনি—423  
 আইগা, -নে (= আপনা, আপনি)—850  
 আইগা (= আমরা), -রাই, -রাই—815  
 আইগা—519, 544  
 আইক—316, 380, 362  
 আইকড়া—887  
 আইকড়া—691  
 আইক—333, 550  
 আইকাড়—880  
 আইকড়া—880  
 আইকাড়ে—880  
 আইকর—337  
 আইক—337, 550  
 আইকোর—337  
 আইখ—140, 307, 316, 369, 460  
 আইখর—369, 540  
 আইগি—150, 316  
 আইচ—( *heat, flame* ) 307, 316, 369, 1070 ; ( *to guess* ) 878  
 আইচড়া—887  
 আইচল—335, 361, 471  
 আইচা—874  
 আইচান—664  
 আইচা—519  
 আইচা—364  
 আইজুলি—398  
 আই—878  
 আই—316, 369, 493  
 আই—311  
 আই—496  
 আইড়া (= আনা, আনি)—526  
 আইড়ি (= আনি, আনি)—526  
 আইড়া—365  
 আইত—316, 502  
 আইকা—882, 886  
 আইকে—449  
 আইড়া—691  
 আইড়া—661  
 আইধার—317, 345, 366, 507  
 আইধা—882  
 আইধি—366, 507  
 আইনে, -না (= আপনি, আপনা)—850  
 আইব—301, 321, 637, 514, 531  
 আইরা, -রাই, -রাই, -রাই, -রাই—  
 আইরা (= আমরা etc.)—815  
 আই (= আমরা)—142, 815  
 আইরা, -রাই (= আমরা, -রাই)—815  
 আই—215, 310, 362  
 আই—372, 519, 547, 550  
 আইটে—491, 686  
 আই—558  
 আই (suffix)—681, 974  
 আইচা—473, 574, 612  
 আইক—456  
 আইব—577, 598, 605  
 আইক—597  
 আইকমন্ট—592  
 আইকা—454  
 আইকা—710  
 আইকা, -কা—710  
 আইকা—710  
 আইকা—314, 378, 710  
 আইকা—526



আকীড়া—710  
 আকেন—574, 592, 597, 619  
 আক্কা—599  
 আখ—310  
 আখড়া—282, 331, 460, 495, 688  
 আখনী—599, 614  
 আখ(ি)ছা—710  
 আখর—316, 369  
 আখাইল—1032  
 আখুড়ি, -জী—578, 584, 618  
 আখের—599  
 আগ (= agni)—302, 461  
 আগ (= agra)—767  
 আগত—767  
 আগড়—687  
 আগন—440, 461, 463  
 আগবাড়া, -বাড়ান—1051  
 আগমন—462  
 আগর (= Eng. anger)—636  
 আগল—462, 544  
 আগলা—888  
 আগলার—330  
 আগা—213, 461  
 আগি—152, 302, 316, 461  
 আগুআ, -রা—882, 883  
 আগুছা—885  
 আগুছিআ—1037  
 আগুন, -নি—152, 376, 398  
 আগুে—787  
 -আগুে (in কার্যকরণে)—462  
 আগুন—440, 461, 463  
 আগুটে—710  
 আগুর—314  
 .আহ—974, 976  
 আহটে, -জী—685  
 আহেল—522  
 আহেলা—889

আহিনা—363  
 আহুর—574, 607  
 আহুল—544  
 আহু—360  
 'আহ' (= হ)—377  
 আহ—361  
 আহটে—685  
 আহটা—333, 685  
 আহটী—333  
 আহন—335, 528  
 আহরা—331  
 আহিনা—335, 383  
 আহুটি—493  
 আহুর—574, 607  
 .আহ—684  
 আহকান—574, 577, 601  
 আহকা—522, -মকা—314, 522  
 আহখা—314  
 আহখিত—314  
 আহতুআ—1070  
 আহাখি—406  
 আহার—628  
 আহাখি—406  
 আহ—112, 114, 167, 443, 873, 926, 1035, 1037  
 আহউক—1037  
 আহএ—1037  
 আহুত, আহুখি—1037  
 আহন—1024  
 আহলেক—1037  
 আহাড়—874, 888  
 আহি—1037  
 আহিতে—313, 1037  
 আহিহর—314  
 আহিহা—1037  
 আহিহার—1018  
 আহিহা—1037  
 আহিল—313, 1037

আহিলত, -খি—1037  
 আহিলা—1037  
 আহিলাখি—1037  
 আহিলাখ—1037  
 আহিলাহা—981  
 আহিলাহী—975  
 আহিলি—1037  
 আহিলেস্ত—1037  
 আহু—980  
 আহুক—1037  
 আহে—316, 444, 465, 472, 875, 926, 1037  
 আহেন—1037  
 আহেস্ত—1037  
 আহের—995  
 আহৌ—932  
 আহ—269, 307, 316, 318, 354, 380, 385, 475  
 আ'জ—269  
 আহকাল—450  
 আহব—574, 596, 605  
 আহবুত—354  
 আহন—314, 398  
 আহলী—354, 475  
 আহাড়—888  
 আহান—314; 710  
 আহান—710  
 আহি—269, 307, 318, 380  
 আহি আহিমা (= আহিক)—307, 476  
 আহুলি, -লী—314, 398  
 আহা—393  
 .আহি—726, 974, 986, 989  
 আহকল—361  
 আহাম—601  
 আহুন—206  
 আহি—301, 316, 442, 491, 552, 792

-আট—664, 687  
 আটাই—303, 372, 512  
 আটক—457, 680  
 আটক—449  
 আটচল্লিস—796  
 আটটা—401, 447  
 আটরিস—330  
 আটপটরে—398  
 আটা—490  
 আটাত্তর—555  
 আটান(ক)ই—792  
 আটান—789  
 আটানী—792  
 আটাসে—700  
 -আটি, -টী—664, 687  
 আটুই—521  
 আঠ—301, 792  
 আঠা—441  
 আঠার—317, 347, 555, 792  
 আঠারুই—806  
 আড়—349, 497, 681, 802  
 আড়—500  
 আড়গড়া—497  
 আড়-চিবান—500  
 আড়ত—499  
 আড়গাগল(ী)—500, 802  
 আড়বীকা—802  
 আড়মাতলা—500  
 আড়মাতলা—802  
 আড়া—499  
 আড়াই—351, 500, 802  
 আড়াল—497, 689  
 আড়ানী—497  
 আড়ে—802  
 আড়ডা—497  
 আড়ত—499  
 আড়া—499  
 আঢেল—337

আশি-দিকো—1050  
 আশিলে—984  
 আশিলেই—981  
 আশিলে—981  
 আশেক—733  
 আশে ( = শ )—377  
 আশিল—677  
 -আতি—663, 676  
 আতর—580, 592, 596, 602  
 আতরদান—708  
 আতশবাহী—802  
 আতা—622  
 আতি—314  
 -আং—655, 682  
 আঙ্গা—373, 503  
 আখ(ী)দর—346, 504  
 আখির—336  
 আখ—308, 380  
 আখকোটী—449, 450  
 আখব—582, 602  
 আখরী—582  
 আখরা—698  
 আখল—698  
 আখলা—443  
 আখা—321, 505, 506  
 আখি—380, 383  
 -আখি—727, 730, 731, 732, 992  
 -আখিক—703, 727, 730, 731, 732, 992  
 আখিকের—732  
 আখিখোতা—705  
 -আখিগ—446, 732  
 আ-দিবস—710  
 আ-দেখ—710  
 আদেখলার—1004  
 আদোপে—446, 511  
 আদোবে—446, 511, 513, 514, 525, 678

আদাশ—574  
 আদ্য—381  
 আধ—507, 713, 802  
 আধধান—449  
 আধকোটী—713  
 আধলা—334, 443, 698  
 আধসেরা—451  
 আধা—802  
 আধিপত্য—314  
 আধীন—314  
 আধেলা—698  
 আ-ধোয়া—710  
 আন (verb)—874, 1045  
 -আন, -আন, -আনো—162, 348, 658, 661, 664, 666, 707, 880, 1003, 1030, 1031, 1035  
 আন (=anya)—367, 529  
 আনল—283  
 আনা—462  
 -আনা—658, 707  
 আনা করান—1033  
 আনাগোনা—281, 512, 535, 1013, 1046  
 আনাচ—336, 475  
 আনাড়—527, 528  
 আনাড়ী—527  
 আনাথী—695  
 আনার—314, 574, 609  
 আনারস—622, 623, 630, 631, 632  
 -আনি, -আনী—162, 665, 666, 658, 692, 695, 707, 725  
 আনিয়া—389, 416  
 আনিল—333  
 আনীয়—215  
 আনুপাম—283  
 আনুমতি, -বতী—283, 314  
 আনে—528



- আনো—345, 666, 664, 880,  
 1003, 1030, 1031  
 -আন্ত—653, 974, 986  
 আন্তরে—313, 770  
 -আন্তি—974, 986  
 আন্—453  
 আন্ডাজ—574, 613  
 আন্—440  
 আন্দেশ—585  
 আন্ডারী—361  
 আন্—440  
 -আন্—789, 796  
 আন্ডা—416  
 আপ—847  
 আপডা—526  
 আপন—434, 511, 849  
 আপনকার—755, 849  
 আপনা—849  
 আপনি—846, 849, 974, 985  
 আপনে—849  
 আপমান—314  
 অপরাধ—314  
 আপরিল (= April)—638  
 আপদোশ—574, -সোশ—605  
 আপস—699, 849  
 আপার—314  
 আপি আপি—846  
 আপিং—522, 590, 605, 642  
 আপিন—530, 605, 642  
 আপিম—522, 591, 605, 642  
 আপিমবোর—707  
 আপিস—216, 634, 636, 638,  
 643, 645  
 আপুপি, .পি. নি—849  
 আপেল—645  
 আপ্ত—449, 850  
 আপ্ত-গরতিয়া, -জ—850  
 আপ্ত-জন—850  
 আপ্ত-নারী—850  
 আপ্ত-স্থ—850  
 অকগানিহান—709  
 অকশোশ—580, -সোশ—574,  
 605  
 অফালে—512  
 অফিম—591, 605  
 অফিস—645  
 আব (= abhra)—301,  
 (= tumour) 514  
 আবকারী—582  
 আবছা—301, 443, 515, 609  
 আবতার—314  
 আবধা—504  
 আবরিল (= April)—638  
 আবর—582, 605  
 আবরোঁতা—608  
 আবলুশ, -ন—574, 585, 607, 612  
 আবসী—303  
 আবস্থা—314  
 আব্বা—574  
 আব্বাণী—314, 694  
 আব্বাণে—675  
 আব্বাজ—314  
 আব্বুজিয়া—314, 710  
 আব্বুধ—507  
 আব্বি, -বী—283, 314  
 আব্বুত—358  
 আব্বুধা—710  
 আব্বেলা—710  
 আব্বেশী—340  
 আব্বোলা—956  
 আব্বোয়াব—574, 616  
 আব্বোখা—314  
 আব্ব—515, 699  
 আব্ব—314  
 আব্বাং—363  
 আব্বাগিয়া—675  
 আব্বাণী—314, 694  
 আব্বাজ—363, 515  
 আব্বাজা—711  
 আব্বিয়ার—314  
 আব্ব—157, 301, 321, 366,  
 531, 582, 652  
 -আব, -ব—(suffix) 666, 667 ;  
 (verb affix) 974, 976, 987  
 আব্বা—682, .গা—758  
 আব্বা—282, 321, 497, 690  
 আব্বানী—578  
 আব্বা—735, 812, 813, 815  
 আব্বা—736, 815, 812, 815  
 আব্বাল—611  
 আব্বা—519, 522  
 আব্বা—760, 811, 812, 815,  
 819  
 আব্বাণে, আব্বাণে—758, 815  
 আব্বাধের—736, 812, 814, 815  
 আব্বাং—574  
 আব্বা—814, 816  
 আব্বাপানে—305, 771  
 আব্বা—816  
 আব্বা—142, 211, 758, 815,  
 926  
 আব্বা—735  
 আব্বা—1072  
 আব্বি—145, 309, 334, 350,  
 367, 515, 531, 533, 554,  
 734, 809 ff., 818, 921  
 -আবি—(suffix) 666, 667 ff. ;  
 (verb affix) 976  
 আব্বা—314  
 আব্বি—584  
 আব্বি—667  
 আব্বি—706  
 আব্বি—812  
 -আবি—666

আনীর—314, 574, 584  
 আনুদে—399  
 আনুল—314  
 আমেজ—574, 585  
 আমের—557, 619  
 আমেরিকা—638  
 আমোল—337  
 আর (diphthong)—422  
 আর (verb)—1040  
 আরনা—588  
 আরমা—588  
 আরর—340  
 আরা—622, 625  
 আরান—198, 314  
 আরি (diphthong)—421  
 আরি—307  
 আরিলারী—975  
 আরী (diphthong)—421  
 আরি (grandmother)—421  
 আরে (diphthong)—422  
 আরেন্দা—578, 588, 614  
 আরেশ, -স—574, 596  
 আর্য—198, 383  
 আর্যত—692  
 আর—314, 340, 349, 540  
 -আর—350, 668, 669  
 আরংজেব—588  
 আরজা—314, 710  
 আরজ—574, 596  
 আরতি—302, 501  
 আরতিল—677, 957  
 আরত্ব(ন)—314  
 আরবী—596  
 আরবীজ—703  
 আরশি, -শী, -নী—256, 375,  
 540, 545  
 -আরি (-আরী)—668, 669  
 -আর—669

আরুচ—500  
 আট—217  
 আর্দালী—636, 645  
 আর্দাস—574  
 আর্বা, আর্বা—534  
 -আল, -ল—669, 670  
 আলক—283  
 আলকাতরা, -কাংরা—622, 624,  
 626, 629  
 আলখালা—213  
 আলগা—882  
 আলগোছা—700  
 আলগোছে—551, 700  
 আলতা—314, 502, 544  
 আলপ—314  
 আলপনা—372, 380  
 আলপিন—622, 625, 626, 629,  
 631  
 আলব(ী)ৎ—574, 578, 591, 602,  
 618  
 আলমারি, -রী—622, 652, 626,  
 630  
 আলহ—424  
 আলস—314, 544, 548  
 আলুহে—1026  
 আলুসে—699  
 -আলা—669, 670  
 আলাদা—590, 594  
 আলাদী—672  
 আলাহিদা—590, 594  
 আলি—389, 544  
 আলিপন(ী)—336, 372, 380, 383  
 আলিবর্দী—616  
 আলিলা—699  
 -আলী—669, 670  
 আলু (=skula)—320, 379, 383  
 আলুখালু—320, 383  
 আলুয়াইন—383

আলুনি, -নী—314, 334, 709  
 আলেকোস—587  
 আলেন—590  
 আলো—353  
 আলোনী—334  
 আবু\*—354  
 আলাদা—383  
 আলা—574, 582, 610  
 আলাতাল—583  
 আশ—305, 312  
 আশখ—335, 1068  
 আশনাই—588  
 আশরফী—574, 612  
 আশা—312  
 আশিন—336  
 আশী—309, 314, 351, 799  
 আশু—320  
 আশুভ—314  
 আশোরান—427, 534  
 আষ্টা—314, 551, 792  
 আস—548, 574, 892, 1046  
 -আস—700, 701  
 আসওয়ার—1068  
 আসপাস—312, 548  
 আসবাব—574, 605  
 আসনান—314  
 আসনান—612  
 আসল—574, 611, 612  
 আসা—885  
 আসানী—574  
 আসি—340, 379  
 আসিখী—379  
 আসিফা—313  
 আসিফে—385, 387, 1046  
 আসিৎ আসিৎ—1000  
 আসিব—379  
 আসিবে—379, 1046  
 আসিবেক—379



আসিরা—313, 352, 387, 389,  
1003, 1046  
আসিরা (এসে) পড়া—1051  
আসিরা (= Asia)—641  
-আসিরা—700  
আসিরাহে—387  
আসিল—386, 1046  
আসিলাহ—386  
আসিলে—1003, 1046  
আসিন্—1046  
আসিহ—379, 908  
আসিহেনক—1008  
আসী—379  
আত্—379  
আত্—1046  
আত্—283, 314  
আত্খিল—957  
আহিন—1046  
আহির—314  
আসে—350, 387, 550, 1046  
-আসে—700  
আপ (= প)—377  
আপ্তাবল—640, 645  
আপ্তে—590, 594  
আপ্তে—1046  
আপ্তে—385, 387  
আপ্তে ব্যাপ্তে—314  
আরান—377  
আপ্পদা, -দা—314, 377  
আপ্তে—1046  
আপ্তে—388  
আপ্তে—1046  
আহমদ, আহমদ—557, 609,  
619  
আহর—1039  
আহরিত—704  
আহা—557  
-আহা—974, 980, 988

আহামক—574  
আহামদ—557  
আহামক, -খ—574, 591, 597,  
609, 619  
আহার—554  
আহীর—386  
আহুঠ, -ট—493, 554, 830  
-আহে—422  
আহেরি—553  
-আহে—974, 975  
-আহে—974, 975  
আকা—734, 751, 811  
আকারা—735, 812  
আফি, -ফী—734, 810  
আফে—734, 810, 812  
আফে—810  
আফাদ—557  
আফা—879  
আফান—200  
'অ্যা'—142, 271, 410, 696  
অ্যাফিন—331  
অ্যাফ—421  
ই—(sound) 271, 299, 381,  
382, 383, 392, 397, 402,  
405, 521, 584, 614, 636 ;  
(suffix) 406, 522, 655, 662,  
663, 671, 672, 673, 674 ;  
(case affix) 925 ; (verbal)  
337, 915, 923, 974, 975,  
978, 988, 989, 1002, 1006,  
1012, 1013, 1020, 1028 ;  
(pronoun) 834  
ইঅ—(passive affix) 112 ;  
(imperative) 352  
ইঅ (verbal affix)—112, 370  
ইঅ (noun suffix)—674  
-ইঅ—1002  
ইই (sound)—429

ইউ—(sound) 419 ; (suffix)  
919, 920  
ইউনাইটেড ষ্টেট্—419  
ইউনানী—585, 614  
ইউনিভার্সিটি—419  
ইউরোপ—533  
ইউরোপনয়—706  
ইউয়ক—614  
ইউ (suffix)—903  
ইএ (suffix)—675, 915  
ইও (sound)—418  
ইংরাজ, ইংরাজ-রাজ—585  
ইংরেজ—215, 585, 607, 620,  
631  
ইংলণ্ড—524, 639  
ইংলণ্ড, ইংল্যান্ড—639  
ই—522  
-ইএ (suffix)—370  
ইট—322, 324, 369, 444  
ইটগা—451  
ইদরা—324, 349, 365, 1073  
ইদুর—324, 337, 365, 540  
ইদেরা—324  
ইহ—725  
ইহাফে—522  
ইহারে—522  
ইকুন—408  
ইগড়া—66  
ইগা—736  
ইকমটেল—645  
ইঙ্গলণ্ড—524  
ইহ—873  
ইহিল—324  
ইহে—875  
ইজিত—704  
ইজ্জ—400  
ইজার—579  
ইজারা—579

- ইজের—579, 583  
ইজৎ—579, 596, 613  
-ইঞ (suffix)—370, 522, 1002,  
1006, 1010  
-ইঞা—1006  
ইকি—305, 645  
ইট—322, 324, 369, 444, 491  
ইটা—882  
ইটালীজ—703  
ইটি—859, (suffix) 687  
ইটে—543  
ইতিহাস—640  
-ইত—335, 348, 372, 406,  
502, 503, 653, 654, 676,  
704, 959, 1030  
ইতহভাষা—89  
-ইতু—1016  
-ইতে—335, 393, 999, 1000,  
1012, 1014, 1015, 1030,  
1051, 1052  
ইখ—504, 834, 839  
ইখ—584, 603  
-ইখ (noun affix)—162  
ইখান—579, 596  
ইখি—829, 831, 835  
-ইখি (suffix)—692  
ইনেপেই(টি)র—640, 645  
ইনকমটেক্স—645  
ইনাস—349, 701  
ইনির—376  
ইকে—859  
ইনসাক—579  
ইনসালভেট—644  
ইনসেল—626  
-ইব—112, 141, 331, 348,  
661, 676, 988, 1012, 1017  
-ইবা—393, 631, 1016, 1017,  
1018  
-ইবাম—136, 141  
-ইবার—1018  
ইবে—856  
-ইবো—141  
-ইবো—136, 141  
-ইম—667  
ইমরা—834  
-ইমা—667, 703  
ইমান—584, 607  
ইমাম—579, 609  
ইমারা—528  
-ইমু—136  
ইয় (sound)—418  
ইয়—377  
-ইয়—(sound) 417 ; (suffix)  
133, 352, 370, 406, 409,  
416, 512, 614, 662, 674,  
682, 806, 923, 1002, 1003,  
1006, 1021  
ইয়াকুব—614  
ইয়াক—614  
ইয়ার—418, 534, 614  
ইয়ারিং, ইয়াররিং—640, 645  
-ইয়ী—370, 406, 1002, 1006,  
1010  
ইয় (sound)—419  
-ইয়ে (sound)—416 ; (suffix)  
675  
-ইয়ে—1006  
ইয়েস—533  
ইয়ো—(sound) 418 ; (suffix)  
908  
ইয়োরোপ—419, 533  
ইয়োর্ক—419, 533  
ইয়াদা—579  
ইয়াদ—609  
ইয়ান—584, 609  
-ইরি—688  
-ইল—112, 331, 333, 348,  
676, 677, 922, 974, 982,  
1012, 1017, 1020  
-ইলু—973, 974, 982  
-ইলা—982  
-ইলাম—141  
-ইলাহী—975  
-ইলুম—141  
-ইলু—141  
-ইলে—112, 677, 901, 1003,  
1004  
-ইলো—974, 982  
-ইলোহী—975  
-ইলৌ—141  
ইলৎ—579, 610  
-ইহ—908  
-ইখ—633  
ইখলিফত্ নাহ—626  
ইখ—558  
ইখানী—579, 602, 612  
ইখার—579  
ইখেরা—583  
ইখিমার—645  
ইখিরিট—645  
ইখিন(টি)ন—640, 645  
ইখিট, ইখিট—645  
ইখিলপেন—645  
ইখিশান—640  
ইখ্যাম্প—645  
-ইস—974, 979  
ইসবগল—577  
ইসবী—616  
ইসা—584  
ইসানী—595  
ইসাই—616  
ইসাপ—614  
ইসে—833, 834  
ইস্কাতোর—215



ইকবন—215  
ইকুপ—215  
ইকুল—216, 640, 645  
ইকুপ—215  
ইকুপ—579, 612  
ইকুহার—594  
ইকিবি, ইকি—823  
ইকী—377  
ইকী—624, 630  
ইকাত—624, 628, -ক—622,  
631  
ইকিবি—641  
ইকি—641, 645  
ইক—689  
ইকিবি—645  
ইকান—610  
ইক—352, 555  
ইক—533, 735, 829, 830, 831,  
834  
ইকান—736  
ইকানি—820, 834  
ইকান—829  
ইকান—831  
ইকান—834  
ইকান—578, 586, 601, 614,  
615  
ইক—359, 829, 831  
ইক—829  
ইকানি—829  
ইকান—829  
ইক—831  
ই—(sound) 271, 402, 405,  
584, 636; (prefix) 834;  
(suffix) 406, 655, 661, 662,  
663, 671, 672, 673, 1012  
ইক—645  
ইক—584, 596, 603

উঠোন—401  
উড়পেনিল—645  
উড়(ণ)ন—664  
উড়ানী—665  
উড়িমা—329, 417, 496, 675  
উড়িমা—106  
উড়ু—678  
উড়ুনি—398, -নী—415, 665  
উড়ে (= উড়িমা)—408, 496, 675  
উড়ে—326, 497  
উত্তর—874  
উত্তরল—698  
উত্তরলী—698  
উত্তরাই—662  
উত্তরে—322, 501, 540  
উত্তরোল—698  
উতি—692  
উত্তম—533  
উত্তরিসা—409, 674  
উত্তীর্ণ—541  
উত্তরে—409, 674  
উৎস—326  
উৎসর্গ-পাখা—1048  
উৎ—326, 505  
উদা—519  
উদেগ—337  
উদ্যাটন—449  
উদ্যোগ—663  
উদ্যার—313  
উদ্যারে—877  
উদ্যে—507  
উদ—326  
উদ—792  
উদ—907  
উদ্যাদি—799  
উদই—185, 529  
উদইয়া—806  
উদকা—347, 789, 796

উদনই—347  
উদপকা—347, 789, 796  
উদাট—798  
উদলভ—555, 792, 798  
উদা—881  
উদান, উদানী—326, 529  
উদা—709  
উদনি, -নী—657, 658, 665, 692  
উদনি—835  
উদিশ—330, 792, 796  
উদিশ-বিশ—794  
উদিশে—806  
উদিস—325  
উদী—1012  
উদুই—185, 529  
উদুন—275  
উদু—728, 903  
উদে—859  
উদকা—451, 452  
উদ—874  
উদ—875  
উদ—874  
উদ—875  
উদ—475, 510  
উদ—275, 331, 877  
উদ—275, 331  
উদ—407, 770  
উদ (তে)—770  
উদা—533  
উদা—888  
উদা—275, 510, 877  
উদা—533  
উদা—325, 349  
উদা—337, 874  
উদ—311  
উদে—881  
উদ—515  
উদ—889

উদা—326, 437, 515  
উদিসা বাওয়া—515  
উদু—311  
উদে—881  
উদ—974, 975  
উদ—326, 530  
উদা—881  
উদান (= to be hot)—521, 531  
উদান (= to weigh)—530  
উদা—326  
উদ—666  
উদেগওয়ার—617  
উদেগার—350, 616  
উদা—(sound) 428; (suffix)  
381, 662  
উদারী—325, 352  
উদ (sound)—428  
উদে (sound)—428  
উদে (verb)—325, 342  
উদে (sound)—429  
উদ—377  
উদ—540, 874  
উদ—696  
উদ—325  
উদ—668  
উদ—325, 502  
উদ—213, 581  
উদ—213  
উদ—586, 602  
উদ (= Eng. wool)—636  
উদ—874  
উদ—326  
উদ—874  
উদ—550  
উদ—671  
উদ—615  
উদা—651  
উদ—527



-উন—700  
 উসক—886  
 উল—615  
 উই—835  
 উহা—835  
 উহাধিগ—835  
 উই—835  
 উহ—557  
 উ—974, 975  
 উচকপালী—335  
 উচলা—888  
 উচা—326, 369, 470, 659, 882  
 উচু—333, 369, 678  
 উট—369, 444  
 উরান—521  
 উ—(sound) 271, 402, 407,  
 585, 638; (affix) 662,  
 677, 920  
 উল—645  
 ঝ—356, 358, 402, 625, 627  
 ঝড় (= Reid)—358  
 ঝবিবর (= receiver)—358, 648  
 ঝড়ানী—696  
 ঝ—358, 402  
 ঞ—402  
 ঞ—(sound) 142, 271, 327,  
 344, 389, 391, 394, 402,  
 406, 408, 410, 411, 412,  
 585, 616, 624, 639;  
 (nominal suffix) 133, 162,  
 163, 303, 386, 925; (verb  
 suffix) 350, 674, 739, 915,  
 974, 981, 983, 988, 989,  
 1003; (pronoun) 555, 829,  
 830, 834, 835  
 ঞ্জ—412  
 ঞ্জা—830

এই—(sound) 419; (pronoun)  
 830, 834  
 এইখানে—834  
 এই—(sound) 420; (pronoun)  
 834  
 এএ—429  
 এও (sound)—430, 421  
 এও (= avidhavā)—198, 307,  
 314, 420  
 এও (pronoun)—834  
 এওজ—616  
 এওং—692  
 এক—142, 301, 302, 328, 396,  
 411, 454, 455, 456, 780,  
 783  
 এক—778, 974, 986, 989  
 একঘেরে—705  
 একচালিশ—796  
 একত(ি)শ—784, 796  
 একত্রিবিংশ—645  
 একটা—396, 401, 656, 784  
 একটিনি—642, 645  
 একটা—396, 686  
 একটু—211, 396, 781, 992,  
 998  
 একটুক—992  
 একত্রিশ, -ত্রিশ—784  
 একত্রি—704  
 একদার—579, 597, 609  
 একলা—659  
 একদর—577  
 এক-শ—800  
 এক-শ-পঁচিশ-তম—804  
 এ(ট)কদর—700  
 একদ্বি—784, 796  
 একদর—700  
 একদা—700  
 একদর, একদর—551

একহারা—701  
 একা—302, 396, 411, 659,  
 786  
 একাত্তর—502, 555, 784  
 একান(ক)ই—784, 800  
 একান্ন—784, 789  
 একুইতি—692, 785  
 একুশ—363, 456, 784, 795  
 একে—445  
 একেবারে—448  
 একেকালে—785, -বারে—448,  
 785  
 একার—579, 590, 599, 615  
 একিয়ার—579, 590, 599, 615  
 একিবিংশ—645  
 এখন—857  
 এখনী—396  
 এখনকার—755  
 এখানে—401, 458, 859  
 এখনি, -নী—398  
 এখেনে—401  
 এয়ার—327, 336, 341, 462,  
 555, 784  
 এতলা—829  
 এগে—882, 883  
 এগুজামিন—645  
 এগুত্রিবিংশ—645  
 এছা—211  
 এজমাল—601  
 এজনাস—579  
 এজার—579  
 এজারী—579  
 এজারী—580, 594  
 এজিব—577, 614  
 এজহার—580  
 এজো—393  
 এজরি—327  
 এটি—859

এড়—497, 878  
 এড়া—956  
 এড়িলেই—961  
 এত—328, 351, 854  
 এতদিন—450  
 এতলা—596  
 -এ-তে—739  
 এতক—855  
 এতলা—580  
 এতলা—602  
 এতলা—580, 619  
 এখা—328, 412  
 এখিগ—829  
 এদের—829  
 এখারে—859  
 -এন (verbal)—335, 409, 974,  
 986, 988, 989  
 এনটেল, এনটেল—645  
 এনা-, এনালের—829  
 এনাম—579  
 এনারা—829, 835  
 এনে—389, 416  
 এনে (pronoun)—853  
 এন্টাল—645  
 -এত—335, 974, 988, 989  
 এত—389  
 এত—416  
 এত—626  
 এনালফ—579  
 এপ্রিল—638  
 এবি—328, 856  
 -এম—974, 976  
 এমত—529, 696, 851  
 এমতে—852  
 এমন—211, 411, 529, 851  
 এমন্ত—708  
 এমন্তারা—708  
 এমনে—852

এমেরিকা—638  
 এমেনে—853  
 এম—421  
 এম—420, 412  
 এমনারা—835  
 এমানে—853  
 এমারিং—845  
 এমি, -মী—419  
 এম—420  
 এমো—420  
 এমো (-avidhava)—198, 554  
 এম—409  
 -এম—95, 112, 337, 386, 540,  
 717, 718, 734, 739, 776  
 এমগে—835  
 এম—829, 835  
 -এম—734, 735, 776  
 এমদা—579  
 এমদাব—735  
 -এম—739  
 এম—388, 1046  
 এম—882  
 এমকা—580, 597  
 এমাম—386  
 এমাবিত—704  
 এমাল, এমালে—383  
 এমাহি—579, 582, 694  
 এমি—389  
 এমুম—386  
 এম—1003, 1046  
 এমেন—592  
 এমেনান—215  
 এমো—(adjective) 845, 350,  
 386; (verb) 350, 386  
 এমিরা—418, 641  
 এমাকিন—530, 642, 646  
 এমাপ—640  
 -এম—974

-এম—979  
 এমব—735, 829  
 এমি—830  
 -এমি—974, 979  
 এমো—350, 352, 387, 389,  
 918, 1046  
 এমো—389  
 এমো—1046  
 এমো—579  
 এমিহা—594  
 এমতে—387  
 এমেরারী—579  
 এমো—389  
 এমো—389  
 এমো—610  
 এম—412, 555  
 এমো—412, 829, 830  
 এমি—830, 852  
 এমেন—313, 350, 555, 853  
 এমো—830  
 এম—829  
 -এম—974, 981, 988  
 এমো—831  
 এম—522, 829  
 -এম—303, 974, 981, 988  
 এম(হা)দিগ—829  
 এম(হা)দিগ—829  
 এমো—365  
 এমো—829  
 এম(হা)দিগ—829  
 এমনি—349, 666  
 এম—558  
 এম—636  
 ই—344, 383, 402, 415, 425  
 ই (pronoun) = ওই  
 ইন—854  
 ইরি—380, 397



- ও—(sound) 142, 271, 272,  
341, 391, 394, 397, 402,  
413, 586, 793; (suffix) 652,  
653, 678, 679; (verbal)  
906, 974, 975, 987;  
(pronoun) 555, 835, 851  
ওআ, ওঁ—227, 534, 616  
ওই—(sound) 425; (pronoun)  
838, 839  
ওউ—427  
ওও—429  
-ওক—974, 986  
ওকালং—577, 602, 615  
ওকালতী—556  
ওকু—506  
ওকু—578, 593, 597, 615  
ওখন—857  
ওখনি—836  
ওগুল—835  
ওছমনি—581, 611  
ওছন—592, 613, 615  
ওছর—592, 596, 613  
ওজু—585  
ওজুহাং—594, 601, 615  
ওকা—199, 302, 329, 481, 542  
ওঠ—329  
ওড়ন—329  
ওড়না—330, 415  
ওড়িয়া—329, 675  
ওঢ়ন—329  
ওঢ়নী—665  
ওংলো—333  
ওদিগ-, ওদের—835  
ওধারে—859  
-ওন—651  
ওনা—835  
ওনারা, ওনারের—835  
ওদত—851  
ওদরা(হ)—581  
ওদার—581  
-ওনি—666  
-ওন—974, 975  
ওয়ানি—645  
ওহ—341, 426  
ওহা—227, 426, 534, 616  
-ওহা—663, 664  
ওয়াকপ—606  
ওয়াকফ—592, 606, 615  
ওয়াকিব—580, 616  
ওয়াকিব—580, 616  
ওয়াজ—596  
ওয়াজিব—616  
ওয়াজু—426  
ওয়াদা—615  
-ওয়ান—707  
ওয়ামস—604, 616  
ওয়ার—426  
-ওয়ারা—671  
ওয়ারিন—641, 646  
ওয়ারিস—580, 612  
ওয়ারী—325, 349  
ওয়ারেন—646  
ওয়ার্ডস্‌ওয়ার্থ—645  
-ওয়ারী—196  
ওয়ার্ডা—612, 616, -রু—211  
ওয়ার্মিল—616  
ওয়ারহাবী—615  
ওহে—426  
ওহেটিং রুম—646  
ওরফে—581  
ওরা—835  
ওল—544  
-ওল—669  
ওলগা—628, 629  
ওলন্দাজ—215, 623, 625  
ওলা—413, 544  
-ওলা—671  
ওলাউরা—413  
ওলা(হা)—981  
ওলী—615  
ওদু—710  
ওন—305, 329  
ওন্দান—581  
ওন্দর—835  
ওস্তাগর—603  
ওস্তাদ—581, 612  
ওহ—555  
ওহা—(sound) 426; (pronoun)  
835  
ওহি—839  
ওহো—557  
ওহে—974, 975  
ওই(ই)—835  
ওহে—974, 975, 987  
ও—360, 519; (pronoun) 835;  
(affix) 974, 975, 987  
ওঁহা—588  
ওঁদিগ, ওঁদের, ওঁরা—835  
ওঁশ—215  
ওঁ—558  
ও—154, 402, 415, 427  
ওউ—639, 645  
ওউংলব—697  
ওবলভব—588  
ওবদ—427  
ং—271, 363  
ং—271, 360  
ক—(sound) 271, 411; (suffix)  
679, 681, 682, 703, 727, 756,  
885, 903, 907; (pronoun)  
844  
কআ—425

কই—(a fish) 308, 344, 346,  
425; (where?) 344, 384,  
844, 853  
কইয়ে—394, 675, 676  
কইরা—370, 383  
কইরাছি—474  
কইতে—384, 542  
কইয়া—370  
কইল—084  
কইলা—315, 342, 344  
কইলে—084  
কইলে—081, 1005  
কউৎ—427  
কউনে—417, 675  
কও—425  
কওয়া—425  
কঠ—082  
ক'ক—427  
কখন—317, 857  
কখনার—629  
কড—614  
কট্টা—685, 886  
কটল—483  
কটু—318  
কটুয়ান—646  
ক'টি—444  
ক'চ্ছ—392  
ক'চ্ছিল—1020, 1025  
ক'চ্ছ—541, 1020, 1025  
কট্টা—452  
কট্টা—896  
কট—614  
কটকট—371  
কটকটা—891  
কটমটা—891  
কটাস্—700  
কটী—672  
কড়—315, 343, 355, 495

কড়কা—886  
কড়চা—541  
কড়মড়া—891  
কড়া—302, 336, 346, 348, 497,  
886  
কড়াই—396  
কড়াক—681  
কড়াকিরা—682  
কড়ায়—610  
কড়ি—348, 396  
কড়ুয়া—315  
কণিয়ার—520  
কণিয়ার—330  
কত—854  
কতক—855  
কতল—203  
কতলা—483  
কতক—855  
কতোক—855  
কত্কা—541  
কতাব—705, -বি—705  
ক'ন্তু—542  
কথ—369, 504  
কথা—454, 455, 505  
কথরা—780  
কথি, -র—844  
কথো—855  
কথবেল—606  
করম—366, 531, 574, 596  
করনা—331  
কর—574, 592  
করুণি—432  
করকন—455  
করকনাইয়া—890  
করহা—659  
করুই—315, 337, 452  
কনে—853  
কনোজ—344

কনক'নিহে—890  
কক (-কাটা)—438  
ককা—330  
কক—545  
ককা—382, 384, 455  
কপচা—700, 880  
কপাৎ—855  
কপি—624, 627, 628, 631  
কপি (= copy)—646  
কবচ—574, 614  
কবজ—574, 592, 596, 614  
কবলা—884  
কবর—574, 592, 605  
কবুল—575, 611  
কবে—856  
কভু—454  
কর—315, 574, 575, 597  
1034  
কমণ, কমন—843  
কমবজ—599  
কমর—577  
কমান—665  
কমিল—1034  
কমী—575  
কমেডি—217  
কন্তি—655  
কম্নে—853  
কফ(টি)—646  
ক'নল—1034  
কন্দ—541  
কহ—(= speaks) 403, 424, 455,  
554; (pronoun) 844, 881  
কয়লা—404, 424  
কয়ল—084  
কহেথ—369, 500, 504, 506  
কহেদ—587, 596, 603  
কর (verb)—258, 348, 455,  
536, 873, 890, 902, 906,  
1012, 1029, 1033, 1043



-কর—683, 707  
 করই—309  
 করএ—424, 533  
 করকচ—541  
 করগা—885, 909  
 করগে—909  
 ক'রগে—909  
 করগা—541  
 ক'রুছে—1020  
 করজ—592  
 করত—654  
 করতঃ—654  
 করতিতিয়ে—1029  
 করতিতেছি—1029  
 করতুতু—1029  
 ক'রুতে—767  
 ক'রুতেম—392, 400  
 করনা—330  
 করশু—545  
 করবাকি—752  
 ক'রুখে—393  
 করবের—401  
 করম—375, 531, 541  
 করমু—531  
 করমোচা, করমুচা—1068  
 করহ—424, 533  
 করয়ে—424  
 করর—994  
 করনা—334, 403  
 ক'রুলেম—392  
 করম—994  
 করহ—348, 903, 906  
 করা—393, 660, 896, 1019,  
 1029  
 -করা—702  
 করাইয়া—417  
 করাইল—956, 1032  
 করাড়—574

করাড—336, 349, 403, 501,  
 692  
 করান—348, 666, 1033  
 করার—334, 351, 422  
 করারিলে—981  
 করার—574, 610  
 করি—302, 380, 396, 994,  
 1012  
 করিএ—915  
 করিগা—908  
 করিগে—908  
 করিছ—392, 1020  
 করিছিল—1020  
 করিছে—1020, 1024, 1025  
 করিঞা—522  
 করিঞাছে—1021  
 করিঠি—1029  
 করিত—704, 901  
 করিতাম—392, 901  
 করিতে—384, 542, 767, 901,  
 1014, 1025  
 করিতে আছ—392, 1019  
 করিতে আছিল—1019  
 করিতেছ—392  
 করিতেছি—1023  
 করিতেছিল—137, 1019, 1025  
 করিতেছে—541, 1019, 1025  
 করিতে থাকিবে—1019  
 করিতে ( ক'রুতে ) থাকা—1052  
 করিতে ( ক'রুতে ) লাগা—1051  
 করিত-কর্দা—704  
 করিনা—401  
 করিমু—545  
 করিনে—401  
 করিব—331, 348, 375, 391,  
 487, 531, 1039  
 করিবা—393, 988  
 করিবার—393, 449, 752

করিবেক—990  
 করিবেই—988  
 করিবে—531  
 করিম—531  
 করিমু—531  
 করিয়া—299, 352, 379, 383,  
 388, 392, 409, 417, 522,  
 655, 682, 739, 747, 767,  
 1004  
 করিয়াছি—144, 394, 474, 1002  
 করিয়াছিল—1021  
 করিয়াছিলাম—1002  
 করিয়াছে—1021  
 করিছা থাকিবে—1021  
 করিছা (ক'রে) দেখা—1052  
 করিয়ারে—994  
 করিরে—337, 675, 932  
 করিরের—994  
 করিরিছে—1021  
 করির—994  
 করিল—343, 383, 392, 984,  
 1043  
 করিলাম—392, 545  
 করিলুম—545  
 করিলে—984  
 করিলেক—457  
 করিলাই—726  
 করিলু—545  
 করিলে—1005  
 করিসুগা, করিসুগে—908  
 করিহ—908  
 করিহলি—997  
 করি—302, 351, 904  
 করী—396  
 কর—310  
 করক—310, 397, 683, 903  
 করকগা, করকগে—909  
 করন—903

ককনগা, ককনগে—৩০৯  
ককম—৫৩১  
করে—৩১৫, ৩৯১, ৫৪০, ৯১৭,  
৯৯৪  
ক'রে—১৪১, ৩৫২, ৩৮০, ৩৮৮,  
৩৯১, ৩৯২, ৪০৯, ৬৫৫, ৬৮২,  
৭৩৯, ৭৪৭, ৭৬৭, ১০০৪  
ক'রেটি—৪৪৪  
ক'রেতি—৩৯৪  
ক'রেহিল—১০২১  
করেন—৩৩৫, ৫২৮, ৭২৫  
করেত—৩৩৫  
করেলি—৬৪৬  
করেত—৯৯৪  
করেলি—৩৩৪, ৪০৩, ৫৪৪  
করো—৯০২, ৯০৬  
করোলা—৪০৩  
করোঁহিল—১০২১  
করোঁ—৫২০  
করু—৯০২  
করুগা—৯০৮  
করুগিলা—৯০৯  
করিগা—৪৭৪  
ক'রুগে—৯০৮  
করু—৩৯২  
ক'রুহ—৩৯২  
ক'রহিল—১০২০, ১০২৫  
ক'রুহে—৫৪১, ১০২৫  
করু—৫৭৪, ৫৯২, ৬১৩  
করেল—২১৪, ৬৮৯, ৬৪৬  
করুতাছে—১০০৯  
করতে, ক'রতে—৩৮৪, ১০২৫  
ক'রতেছে—১০২৫  
করুত—৭০৫  
করুত—৭৬৮  
করু—৯৯৪  
করু, ক'রু, করু—৩৯১  
করুবার—৪৪৯

ক'রুবে—৩৬৮  
ক'রুবে—৩৯১  
করু—৫৪১  
করু—২৯৯, ৩৮৩, ৩৯২  
করু—৩৯২  
ক'রুল—৯৮৪, ১০৪৩  
করুলে, ক'রুলে—৩৫২, ৯৮৪,  
১০৪৩  
কল—৩০৫  
কলকা—২১৩  
ক'লকাতাই—৬৭২  
কলগা—২১৩  
কলক—৪৫৪  
কলনা—৩৩১  
কলমদান—৭০৮  
কলম—৫৯৭  
কলমী—৩৩১  
কলা—৩৪৬, ৪৫৫, ৫৪৪  
কলাই—৫৮৮  
কলি—৫৪৪  
কলিকাতা—৬৫  
কলিকাতা—১০৭৩  
কলিগা—২৮২, ৪৭৬  
কলিম—২০৩  
কলিয়ার—৫২৯  
কলু—৫৪৪  
কলেটর—৬৪৬  
কলেজ—৬৩৬  
কলেজা—২৮২, ৪৭৬  
কলুবিন—৬৪৪  
কলা, কলমা—২০৩, ৬১০  
কলাগা—৪১৩  
ক'লুল—৯৮৪, ১০৪৩  
কলা—৩৩১, ৬১০  
কলে, ক'লে—৩৯২  
ক'লুলে—৯৮৪, ১০৪৩  
কলাই—৬১২  
কলিম—৫৮৪

কদ—৬৭৩  
কদটা—৮৮৬  
কদটা—১৪২, ৩০০, ৬৮৭  
কদা—৮৮২  
কদি—৩১৮  
কদী—১৪২  
কদম—৫৯২  
কদমং, কদমং—৬১০  
কদাই—৫৮৮, ৫৯৬  
কদু—৫৮২  
কদুটা—৬৫৫  
কদ—৬১৩  
কদতবা—৭০৫  
কদনিয়া—৩৯৯, ৪১৭, ৬৭৫  
কদস্থি—৯৩৩  
কদা—৪২৫  
কদিয়ারে—৯০৫  
কদাই—দেহ—১০৫০  
কদি, কদির—৮৪৪  
কদিরার—৯০৫  
কদিরে—৬৭৫, ৬৭৬  
কদিলি—৯৬০  
কদিলে—৯৬৬  
কদিলাই—৬৮৭  
কদক—৪২৭  
কদনে—৬৭৫  
কদে—৩১৫, ৫৫৪, ৮৮১  
কদি—৮৪৪  
কদর—৫৫৭  
কদল—৫১৮  
কদশ—৩৬১  
কদার—৬২৯  
কদা—৬৮১, ৬৮২, ৭৫৬, ৮৪১  
কদাই—৩২০, ৪৫৫  
কদাইট—৩৮০  
কদাইল—২৬৯, ৩৮০, ৩৮২  
কদাইলা—৩৮০



কাল—289, 308, 380, 382, 392,  
539  
কালী—388  
কাউ—310  
কাউখা—320, 345  
কাউকে—845  
কাউলিল—639  
কাউর—542, 845  
কাউর—381  
কাওয়ার—590, 604, 616  
কাওড়া—423  
কাওয়ালী—576  
কাউল—520  
কাক (Eng. cork)—636, 646  
কাকইকু—646  
কাকড়া—627, 628  
কাকী—672, 695  
কাকো—845  
কাগ—320, 445  
কাগচ—614  
কাগজ—461, 577, 582, 597,  
603, 614  
কাগতী—603  
কাঙাল—520  
কাঙালী—520  
কাঙুর—299, 303, 381, 520,  
607  
কাঙ—361  
কাঙার—646  
কাচ—320, 470, 471, 878  
কাছ—316, 455, 473, 708  
কাছারী—317, 355, 471  
কাছি—473  
কাছিম—335, 473, 521, 531  
কাছে—702, 708  
কাজ—227, 321, 455, 476, 652  
কাজ-ঘর—622, 631

কাজল—475, 544  
কাজী—559, 584, 613  
কাজু—627, 628, 629  
কাটি—380, 442, 492, 573  
কাটিইটি—896  
কাটনা—657  
কাটা—956  
কাটারী—317, 491  
কাটিএ—919  
কাটির (কেটে) ফেলা—1052  
কাটিয়ে—337  
কাটিল—957  
কাটে—491, 919  
কাঠ—443, 492, 493, 664  
কাঠ-কাঠা—691  
কাঠ-কাটা—449  
কাঠা—331, 541  
কাঠরা—541, 691  
কাঠরিয়া—542  
কাঠি—664  
কাঠি—673 ; (in place-names)  
183  
কাঠিহা—679  
কাঠুরে—542  
কাড়—873  
কাড়া—499  
কাড়িহা (কেড়ে) নেওয়া—1051  
কাড়ে—881  
কাচ—442  
কাগ—499  
কাচি-নিলে—1050  
কাচিলিহা—986  
কাগ—277, 523, 529  
কাগা—528  
কাঠোখাল—283  
কাওয়ার—669  
কাওয়ারী—440, 669  
কাটার—361, 365

কাটারী—440  
কাতল, কাতলা—698  
কাতান—215, 623, 626  
কাতি—502, -তী—302  
কতুর—215  
কালা—347, 372, 506, 521  
কালিদহ—706  
কালিগ—841  
কালের—841, 845  
কালের (name)—580  
কালো—347, 506, 521  
কালানী—610  
কান (=ear)—227, 316, 367,  
455, 529  
কান (=Kṛṣṇa)—191, 355,  
367, 529  
কানড়(ী)—492, 529  
কান(ী)ড়ী—197, 672  
কানাই—191, 283, 355, 455,  
529, 662  
কানাকানি—1049  
কানচ—684  
কানৎ—576  
কানাসোখা—520, 701  
কানাস্তারা—622  
কানু—191, 355, 367, 455,  
529, 677  
কানুন—582, 586, 607  
কানুনগো—586, 598  
কানুনগারা—622  
কান্দি—361  
কান্দি—366  
কান্দ—361  
কান্দনা—657  
কান্দিতে—1002, 1003  
কান্দিয়া—389, 1003, 1012  
কান্দিয়ে—4932  
কান্দিয়া—389

কান্না—331, 360, 366, 667,  
985  
কাপ—511  
কাপড়—511, 691  
কাপড়খালা—670  
কাপড় ও(রা)লা—671  
কাপড়-কাচা—659  
কাপড়-চোপড়—176  
কাপড়সহ—706  
কাপাস—321, 336, 511  
কাপি—629, 637, 638, 646  
কাপুর—337  
কাপ্টেন—624  
কাগুন—624  
কাগুন—624, 626  
কাবরি—623, 624, 629  
কাফি—622, 625, 629  
কাফের—582, 597, 606  
কাবলী—590  
কাবা—578  
কাবাব—576, 605  
কাবার—622, 627, 628, 630  
কাবু—213  
কাবুলী—590  
কাব্য—382  
কাব—301, 316, 455, 531, 541,  
651, 667  
কামড়—482  
কামতা—239  
কামনী—522  
কামরা—623, 630  
কামর—520, 303  
কামলা—520  
কামান—203, 576, 597, 607,  
609  
কামার—581  
কামার—608  
কামিল—622, 625, 631

কামিনা—667  
কামিনী, কামিনী—667  
কাম্প—361  
কা—227  
কাহন—558  
কাহিনী—695  
কাহেত—320, 504  
কাহেনী—697  
কাহেথ—504  
কাহেম—578, 588, 609  
কার (= Eng. cord)—680,  
641, 646  
কার—842  
-কার—855  
কারণ—768  
কারদানী—610  
কারনিস—636, 646  
কারা—841  
কারাও—845  
কারিকর—707  
কারিগর—597, 707  
কার, কার—542, 845  
কারেজি—646  
কারো—542, 845  
কার্ভিদ—636, 638  
কার্ভুজ—215  
কার্ভী—382, 448, 474  
কার্ভীকাগে—482  
কাল—269, 302, 308, 348, 380,  
382, 455, 652  
কাল—269, 382  
কালকিস্টা—527  
কালন্দর—576, 596, 602  
কালশিরা—348  
কালী—302, 348  
কালপাতি—624, 629  
কালহ—382

কালি—269, 308, 380, 382,  
455, 539  
কালিমা—703  
কালিয়া—380, 383, 417, 674  
কালিয়া—597  
কালী—454  
কালীকেশ—65  
কালুরা—381, 679  
কালেক্টর—638  
কালেক্টার—633  
কালেক্টর—642  
কালেক—638  
কালো—302, 320, 348, 652  
কালোয়াং—196  
কালু—347, 348  
কালুচে—700  
কাল্যা—383  
কালিয়াল—670  
কাহন—556  
কাহন—556  
কাহা—841, 845  
কাহান—844  
কাহিনী—307, 336, 554, 696  
কাহোকে—845  
কাহ—191, 367  
কাহাফি, কাহাফি—283, 523  
কাহো—845  
কাহনী—522  
কি—323, 842  
-কি—681, 682  
কিক—844  
কিখাব—577  
কিছু—372, 464, 455, 465, 845,  
846  
কিনারা—579, 582, 597  
কিন—873  
কিনি—841  
কিনে—323, 455, 539, 875



কিছু—992	কুণ্ডার—325	কুয়া—682
কিছুক—683, 992	কুচ—601	কুশিলা—342
কিপটা—527	কুচাল—711	কুশিলী—396
কিমেনে—852	কুচি—532	কুরনিশ—586
কিম্বা—367	কুচ্ছা—471	কুরনী, কুরনী—658
কিম্বৎ—619	কুচ্ছিত—471	কুশ—627
কিহা—682	কুটনা—657	কুশীশ—580
কিরে—417	কুটিল—677	কুশী—333
কিরিচ—625, 627, 631	কুটিনাটা—459	কুল—325
কিরিমা—376	কুটে—491	কুল—727, 732
কিরিস—625, 631	কুটনী—332	কুলকণী—197
কিরে—376	কুঠ—301	কুলদী—459
কিল—323	কুঠারী—493	কুলটী—446, 471
কিলা—882	কুঠিগাল—670	কুলডী—372, 446, 471
কিলা—577	কুড়—301	কুলখী—504
কিশন—375	কড়মী—333	কুলা—544
কিশনিশ—579, 613	কড়মুড়া—891	কুলাপ(ি)না—696
কিষণ—191	কড়ার—882	কুলী—213
কিস, কিসে—749, 833, 842, 843	কুড়াল—499	কুলুদী—459
কিষ্ঠী—579, 612	কুড়ালি, লী—159, 398	কুলুটী—446, 471
কিহে—417	কুড়ি—499, 704	কুলুটী—446
কিংবা—201, 367	কুড়িমা—144, 463	কুলুপ—453, 581, 593, 596, 606
কী—323, 842	কুড়ুল—398, 499	কুলুপা—884
কী—681, 682	কুড়ে—496	কুলোপনা—696
কীড়া—323	কুচালী—499	কুলে—611
কীর্ভ—879	কুহ—878	কুশারী—668
কীমে—843	কুনরৎ—581, 597	কুষ্ঠী—612
কু—455, 711	কুনজর—711	কুহ—429
কুইনাইন—197, 646	কুনবী—196	কুয়া, কুয়া—325, 342, 659
কইলপেন—646	কুপন—215	কুকেট—358
কুইলা—329, 342	কুপিল—415, 957	কুপা—455
কুউ—429	কুপী—182	কুনিমাল—358
কুকাল—711	কুমড়া—282, 326, 332, 367	কুশ—304
কুহুর—337, 456	কুমার—326, 350, 367, 531, 668	কুশান—624, 641
কুহুল—488	কুনীর—326, 336, 367, 531	কুট—527
কুকেছা—711	কুমোর—668	কুক—191
কুডর—520	কুমোরনী—695	কক—412, 455, 460, 841, 842

কে—553, 728, 739, 775,  
921, 927  
কেঅট—335  
কেউ—327, 420, 542, 845, 846  
কেওট—335, 411, 423, 491,  
685, 688  
কেওড়া—342, 352, 421, 688,  
611  
কেঅরি—646  
কেঅা—572, 580, 612, 619  
কেটুকো—679, 682  
কেটুলি—641  
কেটো—679  
কেতা—579, 781  
কেতাৰ—203, 580, 582, 597,  
602, 605  
কেতুন—431  
কেদারা—622, 623, 625, 628  
কেন—95, 142, 313, 344, 454,  
455, 555, 852, 853  
কেনমণে, -মটে, -মনে—852  
কেনাহের—841  
কেনাবেড়া—1016  
কেনে—(buga) 455 ; (why) 853  
কেফায়েৎ—578, 694  
কেমণ, কেমণে—852  
কেমত—843, 851  
কেমতে—852  
কেমন—411, 843, 857  
কেমনতর—708  
কেমনে—852  
কেমন্ত—843  
কেমিষ্ট—217  
কেয়া—342, 420  
কেয়ার—646  
কেয়ারী—327, 336, 342, 540  
-কেয়—355  
কেয়া—540

কেরালি, -নী—540, 672  
কেরালিগিরি—707  
কেয়ামৎ—577  
কেরানি—646  
কেওঁ—619  
কেলাস—646  
কেলে—380, 417, 674  
কেলো—381, 679  
কেলা—203, 559, 577, 597,  
619  
কেল—411  
কেশেল—670  
কেই—191, 492, 527  
কেটো—191  
কেই—542, 845, 846  
কেহেন—95, 313, 344, 555,  
853  
কেহো—327, 542, 845  
কেই, কেহ—95, 344, 853  
কেই—841  
কৈকেয়ী—425  
কৈছন, কৈছে—854  
কৈখিয়ৎ—586, 605  
কৈল—344, 350, 355, 455,  
517, 1043  
কৈলু—980  
কৈলুম—971  
কৈলে—342, 984  
কো—413  
কোইরুতে—384  
কোইল—329  
কোক—427  
কোঙর—325, 520  
কোঙল—520  
কোঙ—215, 627, 630  
কোঙর—520  
কোন্না—215  
কোচ—214, 329

কোচমান—646, 707  
কোচুমান—707  
কোচ্ছ—392  
'কোচ্ছাচ্ছ'—332  
কোট—490, 492, 640, 646  
কোটাল—329, 349, 426, 490,  
560, 670  
কোট, -টী—801  
কোটপতি—801  
কোটেশ্বর—801  
কোটোয়াল—426  
কোড়াকর—758  
কোং—329, 344, 842, 1066  
কোণাট—684  
কোণোহো—842  
কোথা—455  
কোথায়—858  
কোথেকে—332  
কোনাল—505  
কোন—842  
কোনাট—471  
কোনো—842  
কোন্—344, 385, 841, 842  
কোপ—182, 415, 482  
কোপা—182  
কোপি—624  
কোণা—556, 597, 602  
কোবি—624  
কোমণ—842  
কোমর—557, 577  
কোম্পানী—633, 646  
কোরভে—394  
কোরবান—559  
কোরবানী—596  
কোরাণ, -ন—203, 523, 559,  
583, 596  
কোর—141, 380, 388, 391,  
392



কোরেয়া—623, 624, 630  
 কোরোক—593, 596  
 কোরু—392  
 কোট—646  
 কোতে—384  
 কোঠা—454  
 কোর্ক, কোর্কো—391  
 কোর্থা—213  
 কোর্লে—392  
 কোর্লো—392  
 কোল (the people)—329, 544  
 কোল (=lap)—229, 455, 543  
 কোলু—544  
 কোল্ল—392  
 কোল্লো—392  
 কোল্হান—726  
 কোশ—455  
 কোষা—329  
 কোছো—842  
 কোড়ী—348, 427  
 কোণ—842, 843  
 কোড়ু—899  
 কোড়ুকাগর—216  
 কোঁল—365  
 কোঁ—841  
 কোই—422, 483  
 কোইবি—483  
 কোঁর—608  
 কোঁই—398  
 কোঁড়া—368, 369, 456  
 কোঁণ—301, 316, 362, 456,  
 523  
 কোঁর—456  
 কোঁল—317, 322  
 কোঁলী—317  
 কোঁই—398  
 কোঁড়—309  
 কোঁ—369, 460, 768

কোঁ—320, 361, 370, 470  
 কোঁ—361, 892  
 কোঁ—213, 557, 601, 608  
 কোঁ—491  
 কোঁল—317, 322, 491  
 কোঁল—283  
 কোঁ—493  
 কোঁ—365, 496  
 কোঁর—669  
 কোঁরী—365  
 কোঁহালী—673  
 কোঁর—361  
 কোঁতি—321, 361, 502  
 কোঁ—361  
 কোঁতে—366  
 কোঁ—305, 362  
 কোঁ—312  
 কোঁ—361, 365, 405, 873  
 কোঁ—কোঁ—653, 678  
 কোঁতে—366  
 কোঁ—316, 335, 400, 656,  
 657, 985  
 কোঁনা—331, 360, 657  
 কোঁনিয়া—394, 675  
 কোঁনী—657  
 কোঁ—985  
 কোঁ-কাঁ—1049  
 কোঁগ—841  
 কোঁতে—366  
 কোঁহা—389  
 কোঁনি—657  
 কোঁনে—394, 675  
 কোঁ—455  
 কোঁ-কাঁ—1048  
 কোঁ-টাঁ—1048  
 কোঁ—841  
 কোঁ-কোঁ—653, 678  
 কোঁলে—985

কোঁল-কাঁল—1048  
 কোঁ-কাঁ—1048  
 কোঁ—316, 366, 438, 456, 507  
 কোঁ—882  
 কোঁ—361, 362, 510, 873  
 কোঁ—841  
 কোঁ—361  
 কোঁ—321, 362, 548, 659  
 কোঁই—421  
 কোঁরী—322, 362, 608  
 কোঁ—841  
 কোঁকি—419  
 কোঁড়া—659, 887  
 কোঁড়া—659  
 কোঁড়া—326, 369, 659  
 কোঁড়া—333  
 কোঁ—446, 457, 471  
 কোঁকি—326, 681  
 কোঁড়া—887  
 কোঁ—326, 1070  
 কোঁহা—325  
 কোঁল—677  
 কোঁ—325  
 কোঁ—326, 369  
 কোঁ—475  
 কোঁ—67, 180, 496, 878  
 কোঁহা—496  
 কোঁ—326, 873, 878  
 কোঁ—369, 656  
 কোঁ—326, 369, 506  
 কোঁকি—421  
 কোঁই—337  
 কোঁ—324, 337, 361  
 কোঁলী—670, 673  
 কোঁরা—365  
 কোঁ—389  
 কোঁরী—519  
 কোঁল—520

কৌশলী—519, 695  
 কৌকড়া—887  
 কৌশ—327, 369  
 কৌচ—329  
 কৌচকা—885  
 কৌচড়া—887  
 কৌচা—471  
 কৌতকা, কৌৎকা—213, 608  
 কৌদল—865, 405  
 কৌয়রী—519  
 কৌয়লী—519  
 কৌয়া—627, 630  
 কৌয়ার—325, 520  
 কৌয়া—521  
 কৌতুহি, -দী—633, 639, 646  
 কৌতুহি—427  
 কাণ্ট—685  
 ক্যাকরি—646  
 ক্যানেস্তা, ক্যানেস্তা—622  
 ক্যামন—391  
 ক্যার (= Eng. care)—640, 646  
 কমে—357  
 ক্রিপিক—357  
 ক্রিশান—641  
 ক্রিস—631  
 ক্রিগাঠ—624  
 ক্রিগান—624, 625  
 ক্রুশ—627, 628, 630, 632  
 ক্রোক—581, 593, 596  
 ক্রোড়—801  
 ক্রোড়পতি—801  
 ক্রোড়েশ্বর—801  
 ক্রোর—801  
 ক্রাইব—644  
 ক্র(ী)সিক—217  
 ক—144, 228, 382, 406, 458  
 কং—459, 528, 857  
 কমা—382

কা—413  
 কুর—325  
 কেশ—459, 501  
 কাচকাচ—891  
 কাটকাট—371  
 ক—271, 411, 438, 599, 600, 643  
 ক্যালহিলা—1032  
 কই—344  
 কইল—380, 384  
 কউস—310, 381, 551  
 ককার—599, 618  
 ককায়িবে—1038  
 ককর—601, 607  
 কটকটা—891  
 কড়—459, 497  
 কড়কিয়া—497  
 কড়িটি—687  
 কড়ী—459, 496  
 কং—459  
 কঙউ—903  
 কঙায়—929  
 কত—599  
 কতা—884  
 কতাল—459  
 ক'দেব—399, 572, 575, 583, 591  
 কন—528, 628, 857, 873, 997, 998  
 কনকার—593, 599  
 কনিত—704  
 কনতা, কন্থা—315, 332, 459, 501  
 কক—440  
 কপর—574, 599, 605  
 কপরী—318  
 কবর—351, 574, 599, 605

ববীস—584  
 বরগা—424  
 বরগাত—587, 599  
 বরোর—342, 459, 540  
 বরোরবা—587, 599  
 বরগোশ, -স—574, 596, 613  
 বরস—574, 592, 601  
 বরতাল—459  
 বরল—459  
 বরিন—575  
 বল—318  
 বল—380  
 বলি—380, 384  
 বলিত—704  
 বলীকা—575, 579, 605  
 বল—878  
 বল—391  
 বলড়া—610  
 বলম—592  
 বলু—551  
 বলুরী—459  
 বা—873, 927, 1029  
 বাখ—441, 906  
 বাখন—656  
 বাখা—341, 350, 429, 600, 1029  
 বাখার—995  
 বাই (noun)—320, 459, 488  
 বাই (= I eat)—344, 422, 994  
 বাইয়ার—994  
 বাইত—335  
 বাইতে—333, 389, 393, 1000, 1014  
 বাইতে (খেতে) লাগা—1051  
 বাইবার—458  
 বাইরা—522  
 বাইরা (খেয়ে) ফেলা—1052  
 বাইরা বাওয়া—1052



- খাইব—994  
 খাইল—351, 386  
 খাইলে—983  
 খাইল—983  
 খাওক—351, 423  
 খাউখাউ—678, 896  
 খাউজাইতে—458  
 খাও—348, 421, 423, 906  
 খাওয়া, খাও—241  
 খাওয়া—885  
 খাওয়া—459, 475  
 খাওয়ান—656  
 খাওয়া—371, 350, 429, 660  
 1029  
 খাওয়াই—422  
 খাওয়া করান—1033  
 খাওয়ার—994  
 খাও—932  
 খাক—598  
 খাকী—206  
 খাক—351, 907  
 খা-খা—896  
 খাগড়—185, 461, 691  
 খাচ্ছে—1028  
 খাছ(ি)না—579, 590, 599, 613  
 খাছা—316, 459, 475, 519,  
 599, 601, 1068  
 খাছাকী, খাছান্দি, -চি—213,  
 601  
 খাছাইতে—458  
 খাছুর—316, 337, 459, 475  
 খাঞা—522  
 খাট (noun)—305, 316, 459,  
 491; (verb) 878  
 খাটতেছে—1029  
 খাটান—878  
 খাটায়—491  
 খাটে—491
- খাটিল, খাটিলে—985  
 খাড়া—459  
 খাড়ী—179, 181, 488  
 খাড়ু—311, 408  
 খাত—628  
 খাতবা—705  
 খাতা—576, 618  
 খাতি—389  
 খাতির—580, 599, 609  
 খাতুন—213  
 খাতো—383, 389, 393  
 খান (=খাঁ)—213  
 খান (=piece)—365, 459  
 খান (=place)—859  
 খান(ি)—779  
 খানকী—598  
 খান-দশ, -দশেক—778  
 খানসাহা—590, 608, 612  
 খানা (=ditch)—215, 626, 628  
 খানা (=eating)—365  
 খানা (=place)—707  
 খানি, -নী—365, 779  
 খানুম—213  
 খানে—859  
 খাপ—511, 609  
 খাপরা—318, 437, 511  
 খাপা, খাপা—606, 619  
 খাবল—159, 438, 459  
 খাবাইতা—1016  
 খাবার—1029  
 খাবার—1019  
 খাবো-খাবো—678  
 খামকী, খামখা—600  
 খামচা—884  
 খামরি—317, 367, 459, 531,  
 553  
 খামা—183, 367  
 খামা—367
- খায়—320, 344, 409, 422,  
 459, 533, 917, 994  
 খায়—341  
 খয়ের—994  
 খয়-দায়—1048  
 খায়গ—446, 582, 599, 605  
 খারিজ—801  
 খাল (=skin)—459  
 খাল (=channel)—482  
 খালস—458, 576, 599, 613  
 খালে—983, 986  
 খালেক—683  
 খাম—613  
 খালী—576, 612  
 খাম্বা—600  
 খাহ—348, 441, 903, 906  
 খাহা—903  
 খিচুড়ী, খিচুড়ী—438, 459  
 খিড়কী—459, 498  
 খিড়কী—406  
 খিহমৎ—603  
 খিবা—460  
 খিদির—604  
 খিদে—406  
 খিনচা—884  
 খিল—438, 459  
 খীন—323  
 খীর—323, 459  
 খুইরী—522  
 খুকী—695  
 খুহু—677  
 খুলী—432  
 খুঞা—459, 520, 522  
 খুকিপোষ—599  
 খুড়ুতা—503  
 খুড়া—326, 459, 497  
 খুড়ী—695  
 খুড়ুত—692, -তা—503

খুড়া—401  
 খুদ—326, 459  
 খুলী—672  
 খুন—586, 599, 607  
 -খুন—857, 997  
 খুনহটা—886  
 খুব—586  
 খুদ—325  
 খুল—878  
 খুলী—586  
 খুচি—581  
 খুলী—599  
 খুন্তে—358, 641  
 খুন্তান—624, 641  
 খে—419  
 খেয়াইলে—1083  
 খেই—327, 419  
 খেউড়—421  
 খেহু—883  
 খেজমত—603  
 খেজুর—337, 459, 475  
 খেটে-খেটে—1047  
 খেড়—327, 497  
 খেড়—421  
 খেত—(noun) 322, 411, 459, 501  
 খেতে—389, 393  
 খেদড়া—887  
 খেদমৎ—603  
 খেদা—887  
 খেদাইয়া—458  
 খেপা—883  
 খেমটা—685  
 খেনা—351, 459  
 খেনা—327, 342, 420, 459, 659  
 খেনারী—668  
 খেনাল—584, 611

খেয়াস—589, 594, 600  
 খেয়ে, খেয়ে, খেয়ে—392, 429, 918  
 খেয়ে-খেয়ে—1048  
 খেল—(= play) 305, 306, 327, 438, 459, 543; (= ate) 873, 985  
 খেলন, খেলনা—657  
 খেলা—306  
 খেলাৎ—580, 596  
 খেলাপ—606  
 খেলিয়ে—675  
 খেলে—386, 983, 1003  
 খেলোয়াড়—688  
 খেনারৎ—580  
 খোকা—677  
 খোকা—482  
 খোজা—599  
 খোদ—581, 599  
 খোদ হাগিরা—598  
 খোদা—203, 581, 582, 599, 602  
 খোদাই—661  
 খোন্দকার—593, 599, 603, 618  
 খোন্দকার—582, 593, 599, 603  
 খোপা—510  
 খোবানী—604  
 খোয়া—427  
 খোয়াব—599  
 খোয়াবগা—599  
 খোয়াস—882  
 খোয়াস—599  
 -খোর—707  
 খোরাক—458  
 খোল—394  
 খোলদা—459

খোলস—699  
 খোলসা—581, 583  
 খোলা—532  
 খোলাইতে—454  
 খোলতাই—662  
 খোলামুচি—532  
 খোস—310, 381, 440, 561, 599  
 খোসলা—888  
 খোস—387  
 খোশা—598  
 খোশামব, -খোদ—586  
 খা—213, 599, 608  
 খাকতি—655  
 খাখার—459  
 খাখা—655  
 খাটি—646  
 খাড়—316, 365, 459, 496  
 খাড়া—365, 496, 659  
 খাড়লে—196  
 খিচকা—886  
 খিচড়া—887  
 খিচী—459  
 খিজ—873  
 খিট—878  
 খিটনাটা—459  
 খিড়—459  
 খিহা—522  
 খিহে—459, 520  
 খিচ—886  
 খোড়া—482  
 খোড়—496  
 খোদাই—661  
 খোপা—329, 510  
 খোয়াড়—688  
 খোয়াড়ী, -রী—609, 610  
 খ্যাতি—460  
 খ্যাল—584



- বিষ্ণু—358  
 ঐষ্ণু—358, 641  
 ঐষ্টান—624, 641  
 ঐষ্টী—703  
 বাঁৎ বাঁৎ—411  
  
 গ—271, 600, 629, 643  
 গালা—425  
 গাই—1044  
 গাউ—427  
 গাউন—304  
 গঙ্গাশ্রীর—551  
 গঙ্গ—574  
 গঙ্গনভী—617  
 গঙ্গরা—452  
 গঙ্গল—315, 400, 574, 600, 611  
 গঙ্গা—592  
 গঙ্গি, -গী—396, 646  
 গটাই—492  
 গড় (noun)—343, 500  
 গড় (verb)—440, 498, 499  
 গড়াগড়া—891  
 গড়ান, -ব—665  
 গড়াহলি—997  
 গড়িয়ান্—498  
 গড়ুর—315, 453  
 গড় (verb)—440, 499  
 গড় (noun)—500  
 গড়ই—492  
 গড়িলে—981  
 গগ—304  
 গগ—727, 731, 732, 733, 873  
 গগেশ—337  
 গগ্গা—334  
 গগাকিয়া—682  
 গত্ত—304  
  
 গত্তর—255  
 গদকা—682  
 গদ (= way)—346  
 গদগদা—891  
 গগাৎ—655  
 গগুড়ে—398  
 গবরনর—643  
 গবরাট—317  
 গব(ভ)মেন্ট—524, 638  
 গবর্গর—30, 643  
 গবর্গর জন্দাল—633  
 গব—449  
 গভ(ট)র্গর—639  
 গম—347, 554  
 গমক—482  
 গমনা—461, 557, 657, 1069  
 গমনা—332, 403, 424, 670  
 গমনানী—694  
 গমালী—349, 425, 670  
 গর—713  
 -গর—707  
 গরজ—574  
 গরজে—375  
 গরব—375, 400  
 গরবা—196  
 গরম—592, 598  
 গরনা—884  
 গরমিল—713  
 গরহাজির—713  
 গরাদি—623, 624  
 গরাদিয়া—623, 627  
 গরাবে—623, 628  
 গরাস—303, 375  
 গরীব—396, 575, 600  
 গরীবনেওয়ার, -নেবার—616  
 গর—397, 697  
 গরুড়—337  
 গরে—768  
  
 গর্জ—879  
 গর্দা—574, 598  
 গর্দ—449  
 গর্হিত—304  
 গল—185  
 গলগলা—891  
 গলদ—602  
 গলা—491  
 গলাবাঁজী—709  
 গলাধি—315, 349  
 গলিবর (= Gulliver)—638  
 গলে—461, 877  
 গলুই—673  
 গহনা—461, 557, 657, 1069  
 গহির—540  
 গহীর—336, 554  
 গা—255, 461, 739, 885  
 -গা—756, 908, 909  
 গাঅ—255  
 গাই—351, 421  
 গাইতে—393, 1000  
 গাইয়ে—394, 416, 675  
 গাইল—674  
 গাল—539  
 গাউন—646  
 গাও—255, 423  
 গাওনা—657  
 গাওনা—582, 598  
 গা-করা—1051  
 গাও—305, 363  
 গাও—183, 305, 363  
 গাঙ্গিনী—181  
 গাং—301, 472, 779  
 গাংগাছড়া—691  
 গাং—779  
 গাং, -হী—779  
 গাংগা—395  
 গাংগী—204, 600

গাজে—316, 475  
 গাজি—522  
 গাজেন—522  
 গাটার—646  
 গাড়ী(ী)-জান—333, 707  
 গাড়ীখানা—535  
 গাড়ী(ী)ওরান—707  
 গাড়ীওলা—535, 671  
 গাড়ুর—698  
 গাড়ুল—335, 698  
 গাড়ী—498  
 গাড়ু—311, 498, 678  
 গাড়ুরী—672  
 গাড়ু—882  
 গাঢ়—499  
 গাঢ়িল—957  
 গাভ—255, 501  
 গাভ—878  
 গাধা—316, 331, 440, 507  
 গনি—461  
 গাপ—587, 605  
 গাব—318  
 গাবরাট—317, 332, 684  
 গাবান—318, 514  
 গাবায়—882  
 গাবিন—308, 336  
 গাবীন—516  
 গাবুর—381, 697  
 গাভর—697  
 গাভিন—308, 336  
 গাভীন—516  
 গাভুর—381, 515, 697  
 গামছা—334  
 গামলা—625, 629, 630  
 গামোছা—334  
 গায়—255, 422, 582  
 গায়ন—656

গায়ন—522, 656  
 গায়-নাগা—1051  
 গায়ব—587, 605  
 গায়দ—216, 400, 642, 646  
 গায়ব—376  
 গায়েজন—646  
 গাটার—646  
 গাল—461  
 গাল—674  
 গালা—186, 883  
 গালি—316, 461, 539, 543  
 গালিচা—213, 591, 600  
 গালিম—605  
 গালে—877  
 গালুডে—591  
 গাহনা—637  
 গাহি—933  
 গাহা—892  
 গাহিতে—393  
 গাহিয়ে—394  
 গাহে—882  
 গাহ—305, 363  
 গাইছি, গিছি—398  
 গিধ—355, 507  
 গিধিনী—507  
 -গিন্—728  
 গিন্ন(ী)ম—667  
 গিরি—541  
 গিন্নোপনা—696  
 গিম—305, 323, 461, 521  
 গিন্নরা—625  
 -গিরি—707  
 গিরিজা (= church)—626  
 গিরিৎ—376  
 গিরিমাটি—407  
 গিরিমেট—639, 646  
 গিরিৎ, গিরিৎ (= griffin)—376  
 গিরিরা—376

গিন্নরা—629  
 গিন্না—357, 622  
 গিন্ন—307, 873  
 -গিন্না—728  
 গিন্নি—397  
 গিন্নক—397  
 গিন্নে—323, 544  
 গিন্নি—641  
 গিন্না—885, 909, 1044  
 গিন্নাহি—398  
 গিন্নাহিল—146  
 গিন্নাহিলে—474  
 গিন্নাহে—416  
 গিন্নে—1044  
 গিন্নেহি—398  
 গিন্নেহিলিস—979  
 গিন্নেহে—416  
 গিন্ন—304  
 গিন্ন—355  
 গিন্ন—305  
 গিন্না—625, 627  
 গ—325, 554  
 গুচের—471  
 গুছান—336  
 গুছা—882  
 গুজরা—884  
 গুজরাট—326, 672, -টী—672  
 গুজরাত—672  
 গুজরান, -না—581, 603  
 গুটা—892  
 গুটি—395, 779, -টী—686, 779  
 গুটির\*ইহেনক—1008  
 গুড়—496  
 গুড়া—892  
 -গুড়ি—67  
 গুড়িমারা—1051  
 গুণ (= rope)—461  
 গুণ (= to count)—461, 873



গুণন—153  
 গুণবস্ত্র—607  
 গুলী—671  
 গুণ—528  
 গুদাম—624, 627, 629  
 গুদাম—624  
 গুন (=gunny)—461  
 গুন (verb)—461  
 গুনি—396  
 গুনো—545  
 -গুনো—728  
 -গুনোগার—583  
 গুন্ডি—655  
 গুলি—695  
 গুমট—376, 408, 461, 531, 889  
 গুমটী—686  
 গুমস—331, 889  
 গুমান—598  
 গুফা—512  
 গুফ—809  
 গুয়া—325  
 গুফতর—708  
 গুল—545  
 -গুল(ী)—94, 97, 144, 173, 446, 453, 725, 727, 732, 992  
 গুলকঁদ—608  
 -গুলাইন—727  
 -গুলাক—727, 992  
 -গুলান—725, 727  
 -গুলি—173, 725, 727  
 -গুলিক—727  
 গুলিখোর—707  
 -গুলিন—725, 727  
 গুলো—446, 727  
 গু—554  
 গুলী—357, 627

গৃহিনীশনা—696  
 -গে—908, 909  
 গেইলে—474  
 গেঙা—891  
 গেছিলে—474  
 গেছে—412, 416  
 গেছো—390, 395  
 গেজেট—217  
 গেজি—646  
 গেজ—463  
 গেজান—462  
 গেজাফি—482  
 গেজাম—377  
 গেজিমাটি—407  
 গেজা—407  
 গেজরা—328, 461, 540  
 গেজেরগার—583, 602, 606  
 গেজো—357  
 গেজ (=swallow)—397  
 গেজ (=went)—343, 411, 461, 677, 983, 984, 956, 1044  
 গেজা—397  
 গেজাফি—986  
 গেজাপ, গেজাব—606  
 গেজাস—216, 377, 640  
 গেজাই—981  
 গেজাহো—975  
 গেজি, -গী—721, 984  
 গেজির—995  
 গেজু—980  
 গেজল (=swallows)—397  
 গেজল—397, 1003, 1005, 1044  
 গেজেন—725  
 গেজেন—606  
 গেজো—397  
 গেজ—983  
 গেজুলি—146, 1020  
 গেজুছে—1020, 1026

গৈরী—587, 600  
 -গো—739, 756  
 গোআর—441  
 গোআলা—329  
 গোআলিনো, -লী—694  
 গোকল—347  
 গোখরা—381  
 গোফা—692  
 গোফা—520, 877  
 গোফা—464  
 গোফ—683  
 -গোফার—451, 471  
 -গোফ—683, 684  
 গোফা—327, 413, 473, 684  
 -গোফের—683  
 গোটি—779  
 গোটিচার—451  
 গোটি—396, 686, 779, 780  
 গোটি—329, 461, 493  
 গোড়—439, 498  
 গোড়া—498  
 গোত—329  
 গোনা—203, 581, 598  
 গোন—396  
 গোপলা—332  
 গোফা—329, 512  
 গোবর—400  
 গোমেন—1071  
 গোমরা—608, 617  
 গোমরা—583  
 গোমরা—180, 349, 688  
 গোমরা—426  
 গোমরা—332, 326, 426, 670  
 গোমালিনো—694  
 গোম—892  
 গোম—586, 596  
 গোম—330, 461, 540, 659

গোব্দ—303, 329, 352, 397,  
461, 646, 697, 744  
গোব্রহ্ম, -তে—744  
গোকুদের—732  
গোল (=crowd, noise) 586  
গোলক্কদ—606  
গোলা—461  
গোলাপ—581, 598, 605  
গোলাপী—671  
গোলাম—600  
গোসা—581, 600  
গোসাই, গোসাঁই—155, 329,  
520, 548  
গোসাঞি, গোসাঁঞি—155, 523,  
519  
গোষ্ঠ—586, 593, 598, 612  
গোষ্ঠা—581  
গোহার—555  
গোহারী—441  
গোহাল—306, 336, 426  
গৌড়জন—149  
গৌণ—304  
গৌণে—1071  
গোন—646  
গোরব—427  
গঁধা—366  
গঁয়েহেনক—1008  
গী—320, 461, 520  
গাই—422, 520, 522, 671  
গাইট—308, 380, 385, 386,  
674  
গাঁট—308  
গাঁজলা—506  
গাঁজা—364, 475  
গাঁটি—308, 380, 385, 386, 443,  
461, 674  
গাঁঠ—308, 362, 493  
গাঁড়ী, -নী—691

গাঁঠি, -জী—380, 671  
গাঁধাঘর—461  
গাঁদলা—506  
গাঁদ্রি—522  
গঁই—1071  
গঁড়া—592  
গঁতা—884  
গঁগ—420  
গঁগা—891  
গেট (=গাইট)—386, 1066  
গেড়—498  
গেড়, রা—328  
গোঁজা—883  
গেঁড়ে—67, 329, 365, 498  
গোঁড়া—498  
গোঁতা—608  
গোঁৎ—608  
গোঁস্তা—608  
গোঁপ—443, 448  
গোঁক—329, 362, 443, 512  
গোঁয়ার—668  
গোঁয়ারা—608, 617  
গোঁরাবৃত্তি(টি)মি—667  
গ্যাং—980  
গ্রহ—357  
গ্রহ(=বৃহ)—357  
গ্রহ—482  
গ্রিজা—622, 625  
গ্রেশ্বর—583, 602, 606  
গ্রী—728  
গাঁ গাঁ—412  
ঘ—271, 600  
ঘটকালী—331  
ঘ'টে(=ঘট্টা)—1068  
ঘড়—1068  
ঘড়া—440, 496  
ঘড়ি—396

ঘড়িকর—758  
ঘড়িয়াল—553  
ঘড়ী—463  
ঘড়িয়াল—670  
ঘ'ড়ল—670  
ঘন—463, 1034  
ঘনা—883  
ঘনাইতেছে—1034  
ঘর—315, 355, 440, 452, 463,  
540, 765, 768, 922  
ঘর ঘর—312  
ঘরনি—773, -নী—332, 694  
ঘরানী—667  
ঘরুয়া—679  
ঘরে—163, 350, 409, 746, 768  
ঘরেই—419  
ঘরের—164  
ঘরে—746  
ঘরে—1074  
ঘরোয়া—664  
ঘব—463, 548  
ঘট্টা—886, 887  
ঘবড়া—887  
ঘব্টা—685  
ঘা—302, 320, 463  
ঘাট—463, 490  
ঘাটা—464  
ঘাটাল—670  
ঘাটিয়াল—670  
ঘোটোআল—670  
ঘট্টি—655  
ঘাড়—464, 498  
ঘানী—320, 463  
ঘাপটা—685, 887  
ঘাবড়া—464, 887  
ঘাবড়াও—663  
ঘাম—301, 316, 463, 531, 563  
ঘামাটা—684



বাঁমে—৪৪২  
 বাঁহ—৪২২  
 বাঁহল—৩৩৫  
 বা(হে)র—৭১৪  
 বাঁহেল—৩৩৫  
 বাঁহ—৪৬৩  
 বাঁহিরাড়া—৬৪৪, ৩০৭  
 বাঁ, বাঁ—৩০৩, ৩০৭, ৩২৩, ৩৫১,  
 ৩৫৫, ৪৬৩  
 বাঁহর—৪১৭  
 বাঁহি—৪৬৪  
 বাঁহ—৪৬৩  
 বাঁহ—৩০৫, ৩২৩, ৩৫৫  
 বাঁহ—৪৭৪  
 বাঁহনী—৪৬৪  
 বাঁহনী—৪৬৪  
 বাঁহনী—৪৬৪, ৫২২, ৭০০  
 বাঁহনী—৪৬৪  
 বাঁহর—৪৬৪  
 বাঁহ—৪৭৪  
 বাঁহ—৪৩৭  
 বাঁহনী—৬৭৫  
 বাঁহি, বাঁহী—৪৩৪, ৪৬৪, ৬৭২, ৬৭৫  
 বাঁহি—১৩৭, -হী—৪৬৪  
 বাঁহী—৪৬৪  
 বাঁহজী—৬৪৫  
 বাঁহ—৪০৪, ৪৬৪, ৪৮০, ৪৮২  
 বাঁহ—৬৫৩  
 বাঁহনী—৪৬৪, ৫২২, ৭০০  
 বাঁহ—৪৪৩  
 বাঁহন—৬৫৬  
 বাঁহিরা—বাঁহিরা—১০৪৭  
 বাঁহ—৪৬৪  
 বাঁহখের—৭০৭  
 বাঁহখের—৪৬৪  
 বাঁহখেরি—১০৪৭  
 বাঁহখেউ—৪২১

বাঁহ—৪২০  
 বাঁহ—৪৬৪  
 বাঁহ—৪১২  
 বাঁহেড়া—৬৪৪  
 বাঁহেটা—৪৬৪  
 বাঁহা—৪৬৪  
 বাঁহ—৬৫৪  
 বাঁহগাড়ী—৩৩১  
 বাঁহতোলা—৪৩৭  
 বাঁহশাল—৪৫১  
 বাঁহা—৩২৭, ৪৬৩, ৪৭৬, ৬৫৪,  
 ৭৪৪  
 বাঁহা—১৬২, ৭৪৪  
 বাঁহাশাল, -শাল—১৬২  
 বাঁহাটা, -টা—৩৪৪  
 বাঁহাটোড়া—১৭৬  
 বাঁহাতে—৭৪৪  
 বাঁহাদের—১৬৪  
 বাঁহা—১৬২, ৪২২, ৫৩৩, ৭১৭,  
 ৭৪৪  
 বাঁহা—১৬১, ১৬৪, ৭১৪, ৭৫৪  
 বাঁহা—৬০৭  
 বাঁহ(ী)—৬৪৬  
 বাঁহটা—৪৬৪, ৫২২  
 বাঁহতর—৭০৪  
 বাঁহে—৭৬৪  
 বাঁহো—৬৭৭  
 বাঁহ—৩২৭, ৪৬৩, ৫৪৩  
 বাঁহাটে—৬৪৫  
 বাঁহাটে—৬৪৬  
 বাঁহে—৪৪২  
 বাঁহা—৬৪৪  
 বাঁহি—৩৫৫, ৩৭০, ৪৬৩, ৪৭১, ৪৭২  
 বাঁহি—৩৭০, ৪৬৩  
 বাঁহ—৩৭০  
 বাঁহি—৩৫৫, ৩৭০, ৪৬৩  
 বাঁহি-কড়ি—৪৬৪  
 বাঁহ—৩৭০

বাঁহা—৪৪৭  
 বাঁহ, বাঁহ—৩৫৭  
 বাঁহ—১৫৫, ২৭১, ৩৬৩, ৩৭৭, ৫১৭,  
 ৫২১, ৫২২  
 বাঁহ—৭৭৬, ৭৪৭  
 বাঁহ—৬০৭  
 বাঁহ—৩৭৭  
 বাঁহ—৩৬৩  
 বাঁহ—২৭২, ৪১১, ৪৪৩, ৪৬৪, ৪৬৫,  
 ৫৪৭, ৬০০, ৬১৪, ৬২৪, ৬৩০,  
 ৬৪২  
 বাঁহ (verb)—৫৪৪  
 বাঁহ (affix)—৬৪৪, ৪৪৫, ৪৪০  
 বাঁহ—৩৪৪, ৪২৫  
 বাঁহ—৩৪৫  
 বাঁহ—৩৪২  
 বাঁহা—৩৪৫  
 বাঁহ—৭১৬  
 বাঁহে—৭১৬  
 বাঁহা—৩৪২  
 বাঁহা—৩৪২  
 বাঁহ—৩৪৫, ৭১৬  
 বাঁহে—৭১৬  
 বাঁহ, বাঁহ—৩৪৫  
 বাঁহা—৪০৫  
 বাঁহা—৪২৫  
 বাঁহ—৩৪৫, ৪৪৫, ৪৫৬  
 বাঁহ—৬৭৭  
 বাঁহ—২১৩, -হী—৫৭৪  
 বাঁহ, -হা—৩১৪  
 বাঁহ—৬৭৭, ৪৪০  
 বাঁহ—৩০০, ৩৪৭, ৪৭০  
 বাঁহা—৩৪৭, ৪৩১  
 বাঁহ—৩৭৫  
 বাঁহ—৪৪৭, ৪৫৪

চক্ৰ—385, 558, 716  
 চক্ৰঃ—558  
 চক্ৰ—716  
 চক্ৰ—716  
 চক্ৰ—197  
 চক্ৰ—348, 520, 680  
 চক্ৰ—682  
 চক্ৰ—891  
 চক্ৰ—478, 878  
 চক্ৰ—457, 680  
 চক্ৰ—450  
 চক্ৰ—67, 183, 346  
 চক্ৰ—439  
 চক্ৰ—452, 886  
 চক্ৰ—(=slap) 346, (=to ride)  
 500  
 চক্ৰ—457, 679  
 চক্ৰ—891  
 চক্ৰ—708  
 চক্ৰ—885  
 চক্ৰ—(=sparrow) 672, (=to  
 ride) 883  
 চক্ৰ—(=sparrow)—336, 672  
 চক্ৰ—(=uphill)—682  
 চক্ৰ—663  
 চক্ৰ—336, 672  
 চক্ৰ—495  
 চক্ৰ—664  
 চক্ৰ—500  
 চক্ৰ—958  
 চক্ৰ—483  
 চক্ৰ—483  
 চক্ৰ(f)লবী—696  
 চক্ৰ—694  
 চক্ৰ—670  
 চক্ৰ—304, 375  
 চক্ৰ—399  
 চক্ৰ—399

চক্ৰ—304  
 চক্ৰ—431, 541  
 চক্ৰ—431  
 চক্ৰ—545  
 চক্ৰ—795  
 চক্ৰ—348, 457, 520, 680  
 চক্ৰ—886  
 চক্ৰ, চক্ৰ—882  
 চক্ৰ—185, 282  
 চক্ৰ—873  
 চক্ৰ, চক্ৰ—499, 609  
 চক্ৰ—335  
 চক্ৰ—600  
 চক্ৰ—501  
 চক্ৰ—540  
 চক্ৰ—575  
 চক্ৰ—302, 554, 873, 896, 902,  
 906, 926, 932  
 চক্ৰ—309, 933  
 চক্ৰ—350, 932  
 চক্ৰ—933  
 চক্ৰ—679  
 চক্ৰ—886  
 চক্ৰ—933  
 চক্ৰ—654  
 চক্ৰ—400  
 চক্ৰ—709  
 চক্ৰ—683, 933  
 চক্ৰ—933  
 চক্ৰ—496  
 চক্ৰ—932  
 চক্ৰ—550  
 চক্ৰ—302, 554, 932  
 চক্ৰ—554  
 চক্ৰ—932  
 চক্ৰ—544, 902  
 চক্ৰ—396  
 চক্ৰ—422

চক্ৰ—933  
 চক্ৰ—933  
 চক্ৰ—891  
 চক্ৰ—351, 372, 512, 932  
 1006  
 চক্ৰ—908  
 চক্ৰ—1028  
 চক্ৰ—932  
 চক্ৰ—348, 418, 906  
 চক্ৰ—1020  
 চক্ৰ—1020  
 চক্ৰ—146, 1020, 1025  
 চক্ৰ—1021  
 চক্ৰ—304, 335, 348  
 চক্ৰ—1014, 1025  
 চক্ৰ—1019  
 চক্ৰ—1019, 1022  
 চক্ৰ—1019  
 চক্ৰ—146, 1019, 1022,  
 1025, 1028  
 চক্ৰ—1019  
 চক্ৰ—1051  
 চক্ৰ—1001  
 চক্ৰ—545  
 চক্ৰ—331, 1039  
 চক্ৰ—988  
 চক্ৰ—393  
 চক্ৰ—908  
 চক্ৰ—382, 1006  
 চক্ৰ—144  
 চক্ৰ—1021  
 চক্ৰ—1021, 1028  
 চক্ৰ—1021  
 চক্ৰ—908  
 চক্ৰ—1021  
 চক্ৰ—333, 348, 974  
 চক্ৰ—545  
 চক্ৰ—721, 968



- চলিলে—677  
 চলিল্—983  
 চলিস—550, 908, 932  
 চলিসি—932  
 চলিহ—348, 352, 908  
 চলিহলি—997  
 চলী—551, 932  
 চলী ভেলী—956  
 চল্—310, 350, 932  
 চলুক—310, 350, 908, 989  
 চলুন—903  
 চলে—84, 315, 319, 382, 403,  
 414, 877, 933  
 চ'লে—382, 1006, 1012  
 চ'লেছে—1021, 1028  
 চলেন—409, 528, 933  
 চলেন্ত্র—933  
 চলো—554, 902, 906, 932  
 চ'লো—348, 352, 418, 908  
 চলোঁ ছে—1021  
 চলোঁ—520, 932  
 চল্কা—681  
 চ'লবে—988  
 চ'লবেক—980  
 চলো—382  
 চলো—908  
 চ'লহিল—1020, 1025  
 চ'লছে—1020, 1025  
 চ'লতে—1025  
 চ'লতেছে—1025  
 চ'লল—93, 983  
 চল্লিশ—336, 363, 470, 796  
 চল্লিশে—806  
 চ'ল্লে—981  
 চলম—592  
 চব—483  
 চা—197, 628  
 চা—699, 708
- চাই—911  
 চাইনা, চাইনি, চাইনে—401  
 চাইর—380, 386, 464, 787  
 চাইর—308, 787  
 চাইল—386  
 চাউল—316, 379, 386, 471,  
 483, 517  
 চাও—911  
 চাওন—656  
 চাক—316, 456, 470  
 চাকতি—692  
 চাকর—596, 600  
 চাকররাক—736  
 চাকরী—578  
 চাহু—213, 597  
 চাহুরী—578  
 চাকরান—589  
 চাকলা—318  
 চাপ—482  
 চাপে—460, 470  
 চাঙড়া—363  
 চাঙা—363  
 চাঙারী—363  
 চাঙড়া—691  
 চাঙা—363  
 চাঙারী—691  
 চাট—491, 878  
 চাটী—176 -বাটী—176  
 চাটুতি—409, 501, 692, 741  
 চাটু—409  
 চাটুজো—409  
 চাটুজ্যা—409  
 চাটুজো—409  
 চাটকিনী—695  
 চাতর—316  
 চাতাল—316  
 চান—471, 551  
 চানকা—886
- চান্—386  
 চান্—361  
 চাপ—404, 408, 517, 878  
 চাপকান—576, 598  
 চাপড়—510  
 চাপড়া—66, 883, 887  
 চাপিরা—1012  
 চাব—404  
 চাবান—514  
 চাবার—877  
 চাবী—623, 624, 628, 631  
 চাবুক—582, 598, 601  
 চাম—367, 651  
 চামড়া—181, 691  
 চামদা—699  
 চামাতি—692  
 চামার—638  
 চামারনী—695  
 চামেলী—516  
 চাম্চা, চাম্চে—708  
 চাম্বলী—1069  
 চাম্বলী—516  
 চারনা—639  
 চার (=four)—308, 380, 386,  
 787, 788  
 চার—652  
 চার-কেলে—788  
 চার-পেয়ে—788  
 চারাইরাছে—929  
 চারি—308, 380, 464, 787, 788  
 চারি-কালিরা—788  
 চারি-পাইরা—788  
 চাল, চ'ল—386, 652  
 চালচলন হেনক—1008  
 চ'ল-ধোরা—659  
 চালান—684  
 চালার—404, 533  
 চালিশ—543, 796

চালু—৪৭৯  
 চাল—৩১৯, ৩৩৪, ৪১৪, ৪৭৭  
 চালিশ—৭৯৬  
 চাল—৫৪৪  
 চালা—৪৪৩  
 চাল—৪৭৪, ৪১১, ১০১৪  
 চালন—৬৫৬  
 চালিত—৪৬০  
 চালিতে—৭৬৪  
 চালিতে—১০০২  
 চালিহা—১৯৬  
 চালি নাহি—৪০১  
 চালিহা—৭৬৯  
 চালিলাহ—৪৪৬  
 চালিলেক—৪৯০  
 চালিলে—৪৪১  
 চালিহ—৪০৪  
 চি—(affix) ৭০৪ ; (root) ৪৭৩  
 চিক—২১৩  
 চিকটা—৫২৭  
 চিকণ—৪৭০  
 চিকন—৩২৪, ৪৫৬  
 চিকুরভার—৩০৫  
 চিঙড়ী, চিঙড়ী—৪৬৩  
 চিচিঙ্গা—৪৪০  
 চিঠাবন্দী—৭০৪  
 চিড়—৪৯৬  
 চিড়া—৩৫১, ৬৪৫, ৬৯১  
 চিত—৪৭০  
 চিতল—৩৩১  
 চিতা—৫০১  
 চিথল—৩৩১  
 চিন—৩০১, ৩২৪, ৪৭০, ৫২৯, ১০৩৩  
 চিনাপুছা—১০১৬  
 চিনিবে—১০৩৩  
 চিনে—৪৪২  
 চিন্—৩২২  
 চিন্ত—৪০৪

চিন্তাবিহীন—৫৪২  
 চিত্তিতে আছে—১০২২  
 চিত্তির—৪৯৫  
 চিন্বে—১০৩৩  
 চিপ—৪০৪, ৫১০  
 চিপটা—৪৪৬  
 চিপসা—৬৯৯, ৪৯২  
 চিপসা—৪০৪  
 চিব—৪০৪  
 চিবান—৫১৪  
 চিবাব—৪৭৭  
 চিমটা—৪৪২  
 চিমড়া—৪৪২; ৪৪৭  
 চিনি—৬৪২  
 চিন্টা—৬৪৫  
 চিন্টা—৬৪৬  
 চিয়ার—৬৪০  
 চিহ্ন—৪৭০  
 চির—৪৯৬  
 চিরাতা—৩২৩, ৩৩৬, ৩৪০, ৪৭১, ৪৪২  
 চিরায়িত—৬২৩  
 চিরন-নৌতী—৩৩৩  
 চিরনী—৩৩৩  
 চিহ্ন—৪৪২  
 চিরেতা—৩২৩  
 চির্ণ—৫৪২  
 চিল—৩২৪  
 চিলবিলা—৪৯১  
 চিল্লা—৪৯১  
 চিল্প—৪৬৪, ৫৫৭  
 চিঙড়ী—৩৬৩  
 -চী—২১৩, ৬৯৯, ৭০৪  
 চীজ—৫৪৪  
 চীতা—৪৭০, ৫০১  
 চীনা—৩২৩  
 চু—৪৭৩  
 চু—৩২৬, ৪৫৬, ৬৯০, ৪৪৫

চুক্তি—৬৫৫  
 চুপী—৪৪২  
 চুটিয়ে—১০১২  
 চুড়ী—৬৬১, ৭২১  
 চুড়ীখানা—৬৭০  
 চুন—৪৭৩  
 চুনাত্তি—৬৯২  
 চুন—৪৭৫  
 চুপ—৫১০, ৬৯১  
 চুপড়ী—১৭৬, ৬৯১  
 চুপসা—৪০৪, ৬৯৯, ৪৪৯, ৪৯২  
 চুপড়ী—৬৯১  
 চুন—৪৭৩  
 চুনচুড়ী—৬৯১  
 চুনড়া—৪৪৭  
 চুনরা—৪৪৭, ৪৪৪  
 চুনা—৩৬৬  
 চুকা—৪৪৬  
 চুমে—৩২৬, ৪৭০, ৫৩১  
 চুখ—৪৭৯  
 চুখা—৪২৯  
 চুখাভর—৫৫৫, ৭৪৪  
 চুখা—৭৪৪, ৭৪৯, ৭৭৭  
 চুখাশিশ—৭৪৪, ৭৯৬  
 চুয়ে—৪৭০  
 চুর—৪৪১, ৫৪০  
 চুরণী—৩৯৬, ৬৯৪  
 চুরনী—৬৯৪  
 চুরান(ক)ই—৭৪৪, ৪০০  
 চুরাশি—৭৪৪, ৭৯৯  
 চুরাশি-তন—৪০৪  
 চুরি—৩০৭  
 চুরিনী—৩৯৬, ৬৯৪  
 চুরী—৩৯৬  
 চুরট—১৯৬, ৬৪৬  
 চুল (= hair)—৪৩৯, ৪৭০, ৫৪৩  
 চুল (= to distil)—৫৪৩  
 চুলকা—৪৪৬



চুলবুল—৪৪৬  
 চুলবুলা—৪৭১  
 চুব—৬৪৪  
 চুবী—৬৭৪  
 চুষে—৩২৫  
 চুশাড়—১২৭  
 চুড়া—১৩৭  
 চুড়ো—৪০১  
 চুণ—৩২৬, ৫২৭  
 চুপারী—৬৬৪  
 চুন—৫২৭  
 -চে—৭০০  
 চেঅন—৩২৪  
 চেইন—৪৭০  
 চেঙড়া, চেঙ্গরা—৪৭১  
 চেড়ী—৩২৭  
 চেড়ালী—৪৫২  
 চেতন-করান—১০৩৩  
 চেতায়—৪৪২  
 চেনা—৫২৭  
 চেপটা—৬৪৫  
 চেয়ার—৪২০, ৪৪০, ৬৪৬  
 চেয়ে—৭৬৭  
 চেয়াণ—৬০০  
 চেয়েট—৬৪৬  
 চেয়ের পাঁচ—৩৪৬  
 চেলা—৩২৭  
 চেনের হাঁড়ী—৩৪৬  
 চেহারা—৫৪০, ৫৭৫, ৬০১  
 চেহেরা—৫৪০, ৫৭৫  
 চেই—৪২৬  
 চেদ—৭৪৪  
 চেখা—৫০৭  
 চেতন—৪২৫  
 চেতজ—৪২৫  
 চেপার—৪৪৫, ৭৪৪  
 চেপার-দিন—৪২৫  
 চে—৩৪৪

চেখ—৩৪৬  
 চেখানি—৬৬৬  
 চেখের—৭১৬  
 চেগা—৬০০  
 চেঙ্গা—৪৪২  
 চেদ—৩৪৭, ৭৪৪, ৭৭৪  
 চেগ—৪৫২, ৪৪৪  
 চেগড়—১৭৬  
 চেগর—৩৪৫, ৭৪৪  
 চেব—৪৪৫  
 চেবলা—৪৪৪  
 চেবানি—৬৬৬  
 চেবিশ—৪৪৪, ৭৭৫  
 চেমরা—৪৪৪  
 চেহাড়—৪২৭, ৪৭৪  
 চেহ—৩৩০, ৩৭৬, ৪৪৪, ৫৪০  
 চেহণী, -নী—৩৭৬, ৬৭৪  
 চেহা—৩৭৬, ৬৫৭  
 চেহাই—৬৬১  
 চেহাগোপ্তা—৬১৪  
 চেহা—৪৪২  
 চেহে-সেধে—৩৪৬  
 চেলা—৫৪৩  
 চেলাই—৬৬২, ১০৩৩  
 চেলে—৩৪২  
 চেধে—৩২৫  
 চেগু—৫৪১, ৫৭৩, ৬০০  
 চেহাড়—৪২৭  
 চে—৪২৭  
 চে—৩৪৪, ৪৭০, ৭৪৪  
 চেক—৪৪৫  
 চেকা—৪৫৬  
 চেকাঠ—৭৪৪  
 চেকাঁদার(ী)—৭০৪  
 চেগোপ্তা—৪৪৪  
 চেগুড়ী—৭৪৪  
 চেগা—৪৭৩, ৪০৫  
 চেগো—৪০৫

চেতিশা—২২৪, ৭৭৬  
 চেতিশ—৭৪৪, ৭৭২  
 চেখ—৫০৪, ৪০৫  
 চেদ—৭৭৪  
 চেদোল—৭৪৪  
 চেদ—৩৪৭, ৫০৬, ৫০৭, ৫৫৫  
 ৭৪৪, ৭৭৪  
 চেদুরানী—৬৭৫  
 চেদুরী—৭৪৪  
 চেগর—৩৪৫, ৭৪৪  
 চেবালা—৫৪৭, ৬০০  
 চেমাখা—৭৪৪  
 চেবটি—৭৪৪  
 চেমর—৭০০  
 চেহারা—৭০১  
 চেই—৩১০  
 চে—৪৭৪  
 চে—৪৭৪  
 চে—৩৭০, ৪৭৪  
 চেডাল—৩৩৬, ৩৬৫, ৪৭৬  
 চেডালনী—৬৭৪  
 চেহ—৩০১, ৩১৬, ৩৬১, ৩৬৫, ৪৭০  
 ৫০৬, ৬৫৭  
 চেদনী—৩৩২  
 চেদগানি—৬৭৬  
 চেদগা—৬৭৬  
 চেদগাল—৪৫০  
 চেদা—(subscription) ৩৬৫, ৫৭৬,  
 ৬০৪; (moon) ৬৫৭  
 চেদনী—৩৩২, ৩৩৬  
 চেদমা—৭০৩  
 চেদে—৩৬১  
 চেপা—৩১৬, ৩৬২, ৫১০  
 চেপাই—৪২১  
 চেডা—৩৬১, ৪৭৫, ৫২১, ৬৪৫, ৬৭১  
 চেডিডন—২১৫  
 চে—৩৭১  
 চে—৩৭০, ৪৭০, ৪৫২

টী—439  
 টা—891  
 টুড়ী—66  
 টে—370, 371  
 টেটান—324  
 টেটামেটি—1049  
 টোষানি—666  
 টোট—310, 470  
 টৌক—348, 520, 680  
 টৌকি—792  
 ট—443  
 টু—443  
 -টুল—1026  
 টু—523  
 টার—640, 646  
 টা টা—412  
 ট—272, 443, 465, 547, 611,  
 613, 789  
 টই—308, 344, 425, 472  
 টউই—372  
 টক—318, 456  
 টকড়া—331  
 টকড়—448, 551  
 টগড়, -ড়া—446  
 টচনি—796  
 টছল—551  
 টটাক—372  
 টড়িয়ার—708  
 টস্তর—472  
 টত্তিরি—502  
 টত্তি—324  
 টত্তী, -ন—502, 796  
 টত্তি, -ন—502, 795  
 টবি—612  
 টয়—424, 465, 789  
 টয়লাপ, -ব—473, 587, 612  
 টয়ান—190, 375, 377

টল—679  
 টলক—679  
 টলাং—655  
 টা—(*offspring*) 302, 472,  
 657, 691; (*to cover*) 873  
 -টা—699  
 টাখন—335  
 টাখনী—657  
 টাই—422, 472, 542  
 টাউনি, -নী—398, 423, 521,  
 657  
 টাও—342, 423  
 টাওন—335, 342  
 টাওরা—312, 342, 423, 472  
 টাওরাল—342, 464, 698  
 টাওরালিয়া—698  
 টাগল—461  
 টাকিঅণ, -রণ—335, 471, 521  
 টাড়—873  
 টাডন—656  
 টাড়পত্র—996  
 টাড়া—769  
 টাড়াও—663  
 টাডিহ—908  
 টাড়ে—114, 369, 472, 497  
 টাত—316, 472, 506, 673  
 টাতা—472, 501, 673  
 টাতিখন—335  
 টাতিস—335, 471, 521, 531  
 টাতী—763  
 টাতীঅণ, -ন—471, 521  
 টাতু—311, 472, 502  
 টাব—505, 506  
 টাদলা—505  
 টান—491, 551  
 টানা—657  
 টানি—612  
 টাপ—510, 878

টাপর—472, 511  
 টাপাখানা—707  
 টাপান—789, 797  
 টাবন—528  
 টাবিশ—514  
 টাবিশ—514, 795  
 টামলী—521  
 টামু—303, 472, 531  
 টাররা—342, 691  
 টারা—312, 342, 420  
 টার—320, 472  
 টাল—404, 408, 472, 482, 544  
 টালান—576  
 টালিয়া—698  
 টালা—390  
 টি—406, 472  
 টি—1037  
 টিট—324  
 টিটকা—886  
 টিটকাইরা দেওয়া—1052  
 টিটকানি—666  
 টিটকার—682  
 টিটকি—681  
 টিটকিনী—681  
 টিটায়—882  
 টিঙিজুলি—1048  
 টিতে—313, 1037  
 টিনা—472  
 টিনারী—396  
 টিনাল—472, 529, 669  
 টিনালী—670  
 টিনে—882  
 টিপ—472, 510, 878  
 টিপটা—886  
 টিরা—1037  
 টিরাত্তর—417, 555  
 টিরামি—406  
 টিরকা—612



ছিরাই—662  
 ছিরি, -রী—376, 472  
 ছিল—313, 405, 444, 1037  
 ছিলকা—404, 482  
 ছিলন্ত, -স্থি—1037  
 ছিলা—1037  
 ছিলান্তি—1037  
 ছিলাম—1037  
 ছিলি—1037  
 ছিলিক—880  
 ছিলিন—601  
 ছিলিন—979, 1037  
 ছিলুম—1037  
 ছিলে—1037  
 ছিলেন—1037  
 ছিলেন্ত—1037  
 ছিলেম—400, 1037  
 ছিলো—1037  
 ছিলুকা—408  
 ছী—376, 472  
 ছুইব—1018  
 ছুইল—396  
 ছুক—1037  
 ছুট—(=noun) 472; (=to  
 run) 414, 491, 878  
 ছুটি—414  
 ছুটে—414, 877  
 ছুত—326, 446, 472, 507  
 ছুতার—326, 472, 502, 668  
 ছুব—326, 446, 472, 503  
 ছুরি—307, 472, 673  
 ছুরিভির—431  
 ছুরী—073  
 ছুলা—408  
 ছুলি, -লী—408, 472, 482  
 ছে—327, 472  
 ছেঁকড়া—448  
 ছেঁগড়া—446, 454

ছেচলিশ—796  
 ছেংলা—481, 505  
 ছেদা—190  
 ছেনা—343  
 ছেনী—352, 472, 657  
 ছেপ—472  
 ছেমরা—471  
 ছেরাদ—190, 377  
 ছেলি—307, 343, 472, 544,  
 698  
 ছেলে—390, 698  
 ছেলেধরা—659  
 ছেলেপিলে, -পুলে—544  
 ছেলেম, ছেলেমি—667  
 ছেলেরা—735  
 ছৈ—344  
 ছো—396  
 ছোকরা—450, 691  
 ছোট—472, 491  
 ছোটকা—457  
 ছোটকী—682  
 ছোটক—705  
 ছোটনাগ—451  
 ছোটলোকমি—667  
 ছোটে—414  
 ছোড়—496  
 ছোড়ল—451  
 ছোড়ান—496, 665  
 ছোবল—482  
 ছোবলা—898  
 ছোবে ছোবেক—611  
 ছোরা—673  
 ছোলা (noun)—482  
 ছোলা (verb)—956  
 ছোলে—596  
 ইউই—805, 806  
 ইক—878  
 ইকনা—657

ইকনী—658  
 ইট—362, 471  
 ইট—878  
 ইদ—301, 316, 365, 506  
 ইদন—335, 656  
 ইদে—882  
 ইড—873  
 ইডে—324, 365, 472, 496,  
 875  
 ই—503  
 ইএ—325  
 ইচ—470, 472  
 ইচি—472  
 ইড়ি—414  
 ইত, ইং—370, 503  
 ইয়ে—472, 521  
 ইট—308, 325, 370, 468  
 ইট—411, 873  
 ইটু—472  
 ইচে—327, 370, 470  
 ইড়ে—919  
 ইলা—327, 370, 472  
 ইল—371, 503  
 ইএ—330  
 ইচ—330, 370  
 ইচা—883  
 ইড়—414  
 ইড়ি—471  
 ইড়ি—414  
 ইড়ে—414, 877  
 ইয়—325, 370, 426, 472,  
 521  
 ইয়ন—528  
 জ—227, 272, 340, 474, 569,  
 601, 613, 614, 629, 630,  
 642, 643, 840

জ' (= a measure)—302, 346

জই—344

জইলা—381

জলা—392

জট—310, 315

জখম—575, 592, 613

জগ—462, 474

জগাই—662

জঙ্গ—593, 598

জঙ্গনামা—598, 607

জঙ্গল—364

জঙ্গলিরা—364

জঙ্গলে—364

জঙ্গলা—364

জঙ্গ—636, 642, 656

জঙ্গিহী; জঙ্গিহ—656

জঙ্গলি—317

জড়ী—661, 721, 966

জড়ল—540

জড়োয়া—664

জত—227, 733

জন—315, 320, 474, 732, 780

জনতর—305

জনহুই, -হেক, -হের—778

জনম—375

জনমিলা—1017

জনাই—483, 506

জনাব—605

জনর্দ্দম—422

জনো—653

জন্ম—542

জন্মিত—704

জন্ম, জন্মে—769

জপ—873

জবজবে—887

জবাই—580

জবান—315, 575, 583, 605,

613

জবাব—583, 601, 605, 616

জবে—474

জবে, জবেহ—580

জব—452, 593, 602, 605

জম—884, 1034

জমক—482, 680

জমকা—886

জমা—575, 579, 596, 601, 88

জমাট—685

জবান—665

জমারং—583, 596

জমিবে—1034

জমী—575, 585, 608, 613

জমী জেরাং—590

জ'ব্বে—1034

জন্মিত—704

জয়—424

জয়ম—376

জরিমানা—592

জরী—575, 613

জরুল—540

জরুরী—613

জর্জ—376, 542

জল—315, 402, 403, 474, 873

জল (verb = হল)—534

জলজলা—891

জলটল—176

জলটুক, -টুক—781

জলব—575, 592

জলপাইগুড়ি—66

জলপিপা—510

জলময়—706

জলময়—532

জলমই—700

জলা—402

জলুখা—394

জলুরা—381, 428, 679

জলুশ—601

জলো, জ'লো—381, 391, 394

428, 679

জলে—474

জলুরী—575

জলি—431

জহর—588

জহরং—590, 617

জং—593

জংলা—364

জা—912, 923, 1044

-জা—302, 684

জাখ—906

জাই—419, 615

জাইউ—920

জাইত—308, 335, 380

জাইতে—1001, 1002

জাউ—310

জাউক—907

জাউ—906

জাউয়া—227

জাহু—907

জাগ—873

জাগানিরা—675

জাগানে—675

জাগিয়া থাক, রহা—1052

জাগে—320, 474

জাউ—932

জাউল—363

জাউ—364

জাউল—363

জাটা—442

জাউতুতা—503, 552

জাউ—475, 493

জাউ—301, 321, 405, 496

জাশ—524

জানিএ—932

জাউ—308, 380, 476

জাউ—380, 476



- জাতীয়তা—705  
 জন—524, 601  
 জন (= John)—637  
 জনিত—654  
 জনসা—625  
 জনাইব—299  
 জনাভিনি—1048  
 জনান—664  
 জনান—577  
 জনান—664  
 জনাব্য—299  
 জনাল—622, 625  
 জনিত—654, 704  
 জনিতো—960  
 জনে—474, 528, 875  
 জনেনা—622, 625, 629, 630  
 জনো—932  
 জাপট—684  
 জাপটা—886  
 জাকরান—583  
 জাবড়া—405, 887, 892  
 জাবল—393  
 জাম (= janma ; jambu)—301,  
 310, 316, 366, 376, 474,  
 531, 652  
 জামা—601  
 জামাই—306, 321, 474, 520  
 জামীর—336, 397, 440  
 জামীর, জামীর—367, 440  
 জায়—474, 615  
 জায়গা—557, 583  
 জায়গীর—584, 601  
 জায়তি—347, -তী—501  
 জায়কল—474  
 জায়ল—181, 396, 540  
 জর্জ (= George)—637  
 জাল—578, 601  
 জালা—610  
 জালিয়া—674  
 জালিয়াৎ—614  
 জালে—474  
 জাতি—618  
 জাতি—590, 604  
 জাতিত—552  
 জাহ—903, 906  
 জাহা—227  
 জাহাজ—576, 613  
 জাহান্নাম—203, 576  
 জাহির—594  
 জাহাপনা—608  
 জাং—305, 364, 482  
 জি—873  
 জিকির—598  
 জিগির—592, 598  
 জিজ্ঞানর—697  
 জিজির—579, 601  
 জিত—501  
 জিতে—882  
 জিব—803, 618  
 জিন—584, 873  
 জিনি—227  
 জিনিস—592  
 জিনে—875  
 জিব—305, 474, 516  
 জিবনাস্টিক—646  
 জিভ—324, 474  
 জিমনাস্টিক—646  
 জিন্দা—613  
 জিরা—892  
 জিরিরে-টিরিরে—1048  
 জিলা—613  
 জিলাহো—975  
 জিলী—958  
 জিহ্বা—200  
 জিহ—359, 839, 840  
 জী—323, 1029  
 জীজ—906  
 জীজন—335, 351, 418  
 জীজন-কাঠি—418  
 জীজহ—906  
 জীই—351  
 জীউ—419, 903, 906  
 জীউক—419  
 জীউলি, -লী—398, 419  
 জীএ—417  
 জীও—418, 906  
 জীওন—335, 351  
 জীওনো—418  
 জীক—419  
 জীভ—305  
 জীহত—412, 653, 1000  
 জীরা—1029  
 জীরান—418  
 জীহে—342, 417, 474  
 জীরত—999  
 জীহ—906  
 জুখা—429, 474  
 জুখাল—352  
 জুও—429  
 জুখ—461  
 জুগতি—503  
 জুগিং—503  
 জুগিয়া—598  
 জুখার—475  
 জুখে—326, 475, 875  
 জুটে—578  
 জুড়—495  
 জুড়া—405  
 জুড়াইন—956, 1032  
 জুড়াইলে—1005  
 জুড়িএ আছে—1027  
 জুড়ী—307  
 জুতা—302, 883  
 জুতাইলহিল—1035

জুতান, জুতানো, জুতানো—665  
 জুতুলিহিল—1035  
 জুতে—882  
 জুতানো—665  
 জুং—308  
 জুবা—581  
 জুদো—583  
 জুনি—474, 529  
 জুয়া—325, 429, 474  
 জুয়াচোর—448  
 জুয়াড়ী—668, 687  
 জুয়ারী—668  
 জুয়াল—474  
 জুরো—429  
 জুল—678  
 জুলপি—581, 613  
 জুলী—439, 481  
 জুলু—197, 643  
 জুলুম—581, 593, 609, 613  
 জুল্পী—593  
 জে—227, 474  
 জেই—419  
 জেই—474  
 জেঠা—328, 474, 498  
 জেঠাই—407, 695  
 জেঠাম—667  
 জেঠি—859, 407, -ঈ—695  
 জেঠুত—692, -তা—503, 552  
 জেদ—603, 618  
 জেনানা—577  
 জেনাভেস্তা—617  
 জেব—585, 601  
 জেব্রা—643  
 জেয়াদা—412, 584, 614  
 জের—577, 613  
 জেরা—613  
 জেল—639  
 জেলা—590

জেল—674  
 জেলের—592  
 জেলা—601  
 জেহাদ—594  
 জেহেন—555  
 জেই—839, 840  
 জৈ—344  
 জৈহে—474  
 জৈবন—426  
 জৈসাগে—854  
 জো—329, 419, 429, 474  
 জোকার—701  
 জোখ—461, 878  
 জোখ—461  
 জোঙ্গড়া—480  
 জোচ্চোর—448  
 জোচ্ছনা—375, 471  
 জোছনা—376  
 জোত—329, 502  
 জোতে—882  
 জোং—475  
 জোনাকি, -কী—329, 474, 529  
 জোবড়া—405, 887, 892  
 জোকা—581, 601, 604  
 জোরান—520, 601  
 জোরাল—352, 426, 521  
 জোর—586, 613  
 জোল—439, 521  
 জোলা—481, 544  
 জোলাপ—581, 623  
 জোলো—391  
 জোহারি—474, 701  
 জোড়া—329, 363  
 জো—315, 344, 427, 474  
 জঁড় (=জং)—526  
 জঁক—482  
 জঁকার—701  
 জঁতা—316, 475, 501

জঁদরেন—366, 506, 646  
 জঁহাপনা—608  
 জঁড়িস (=জঁড়িস)—526  
 জুই—(=a flower) 326, 371;  
 (fire) 428, 474  
 জুটী—439  
 জেহাচ—471  
 জেহাল—521  
 জে—482, 619  
 জে—144, 228, 373, 382, 406  
 -জা—413  
 জান—373, 413  
 জাখা—551  
 জাখা—412  
 জাখা—409, 412, 658  
 জায়রা—412, 614  
 জোতি, -তি—558  
 জ'রো—679  
 জরয়া—679  
 জল—439, 534, 873  
 জলন—656  
 জলান—665  
 জলহু—999  
 জলুনি—398, 408, 665  
 জলে—474  
 জালা—439  
 জালানি—665  
 জালে—474  
 ব—272  
 বক—457, 478  
 বকবক—478  
 বকড়া—446, 478  
 বকমক—478  
 বক—478  
 বকি—481  
 বকমারী—460  
 বক—460



কগড়া—446, 478, 691

কগড়াটে—686

কট—478

কটকা—478

কটপট—478

কট—439

কড়—315, 478

কড়কা—478

কড়তি-পড়তি—654

কড়ুয়া—381

কঙা—479

কনকন—478

কপ—478

কপাক—478

কপাৎ—478, 655

কপাস—478

কমকম—478

কমকম—891

কর—478

করকা—321, 478

করখা—321

করকরিয়া—478

করনা—478, 657

করি—481

করোখা—478

কল—439, 479, 878

কলক—457, 680

কলকা—479

কলমল—479

কলমলা—891

কলনা—479, 889

কব—438, 461

কাউ—310, 423, 479

কাউ—439, 478

কাড়—320, 479, 481, 495

কাড়ন—479, 656

কাড়া—479

কাড়—479

কাড়লে-খুড়লে—1048

কাঙা—479

কাখু—479

কাপট—684

কাপটা—480, 685, 886

কাপনা—480, 699

কামরা—480, 888

কামা—480, 520

কামেলা—480

কারী—478

কাল—439, 480, 878

কালর—479

কালী—479

কালাই—661

কালাপালা—480

কি—480

কিউড়ী—691

কিরা—480

কিটি—479

কিহুক—480

কিম—408, 482

কিমকিম—480

কিমা—480

কিমান—464

কিরাটী—668

কিরকির—478

কিল—480

কিলিক—457, 680

কিলিকিলি—479

কী—198, 323, 480, 668, 1066

কীয়ে—417

কী(কে)র—718

কীল—480

কুটা, কুয়া—480

কুনা—159, 326, 438, 480

কুপ—478

কুপা—699

কুমকা লতা—480

কুমকুম—480

কুমুর—480

কুরা—481

কুরি—481

কুরিয়া-কুরিয়া—1047

কুরে—481

কুল—479, 878

কুলন—479, 658

কুলী—479

কোড়—481

কোড়া—481

কোপ—481, 699

কোপড়া—481

কোকোখুরি—601

কোল—66, 439, 480, 481

কোলা—479, 481

কী—479

কীওঁ—520

কীক—479

কীকড়, কীকড়া—479

কীকনী—668

কীকরা—479, 888

কীকা—479

কীকানী—665

কীকুনি—665

কীজর—438

কীক—364, 479

কীকর—370, 479

কীকরা—479

কীকরী—479

কী-কী—479

কীট—479

কীটা—479, 883

কীটি—479

কীপ—478, 480, 878

কীপান—231, 438, 480, 510

কীপী—480

কীনা—480

বিক—481  
বিকি—480  
বিকিট—480  
বুক—878  
বুকি—481  
বুক, বুকি—481  
বুক—878  
বুকা—480  
বুকা—439, 479  
বুকা—481, 505  
বুকা, বুকা—481  
বুকা—479, 656  
এ—155, 272, 377, 519, 522,  
523  
এ—522, 1006  
এ—522  
একা, একা—831  
একা—831  
একা—522  
এ—519  
ট—(sound) 176, 272, 492,  
641, (suffix) 401, 684, 685,  
687, 780, 798, 885, 886  
টক—456  
টক—882  
টক—490  
টক—489  
টগর—490  
টগাই—483  
টন—638, 679  
টনক—490, 679  
টনটন—891  
টনটন—490  
টপকা—490, 886  
টপকা—457  
টব—638  
টমটম—646

টব, টব—639, 646  
টলটল—891  
টলবল—891  
টল—315, 489, 877  
টল—490  
টলকা—490, 886  
টল—878  
টল—646  
টল—489  
টল—179, 489  
টল—491, 685, 686, 778, 780  
টাইন—639, 642  
টাইন—639  
টাইন—639  
টাইনটল—217  
টাইন—639  
টাইন হল—639  
টাক—482, 878  
টাকরা—490, 878  
টাকা—322, 372, 454, 489  
টাকু—311, 490  
টাকু—679  
টাক—490  
টাক—482  
টাক—490  
টাক—439  
টাক—1066  
টাক—179  
টাক—489, 892  
টাক—489  
টাক—490, 491  
টাক—490  
টাক, টাক—490  
টাক—490  
টাক—483  
টাক—673  
টাক—1012  
টাক—877

টান—490  
টাপ—490  
টাপিন—647  
টাপ—641  
টালি—646  
টালি-করি—1018  
টালি—877  
টালি—482, 489, 493  
টালি—685, 686, 687, 780  
টিক—878  
টিকট—646  
টিকটিকি—490, 787  
টিকলি—408, -লী—489  
টিকি—489  
টিকিট—646  
টিকিন—530  
টিকিস—646  
টিকার—646  
টিক—489, 490, 878  
টিকিন—646  
টিক—416, 489  
টিক—686  
টিক—416  
টিক—489  
টিকার—646  
টিক—491, 685, 686, 778, 780  
টিক—490  
টিক, টিক—489, 780, 781, 998  
টিকট—371  
টিকরা—408, 489, 541, 691  
টিকরী—489  
টিক—414, 873  
টিক—956  
টিক—326, 490, 491, 875  
টিক—489  
টিক—891  
টিক—489, 510  
টিক—781



- টুপী, নী—639, 646  
 টুল—646  
 টুলী—489  
 টুনা—891  
 টে—416  
 -টে—401, 686, 778, 780  
 টেকা—679  
 টেকা—489  
 টেক—646  
 টেকরা—179, 405, 489  
 টেকরী—482  
 টেকনৌ—694  
 টেনা—490, 493, 530  
 টে-পাণী—416  
 টেবিল—216, 646  
 টের—490  
 টেরা—490  
 টেরেন—640  
 টেলিগেয়া—640  
 টেলিফোন—646  
 টেংরী—489  
 -টো—778, 780  
 টোকরা—489  
 টোকা—622, 627, 628, 631  
 টোড়ী—501  
 টোনা—489  
 টোপর—329, 489, 510  
 টোল (depression)—489  
 টোল (Sanskrit school)—489  
 টোলা—489  
 টোন-হাল—639  
 টোক—878  
 টোকশাল—331  
 টোকা—489  
 টোস—490, 878  
 টোক—489  
 টুটী—490  
 টোক—489, 878  
 টোকসই—709  
 টেকা—489  
 টেংরা—322, 372  
 টান্ন—646  
 টাভেডি—217  
 টি বিলিয়ান—644  
 টুইন—420  
 টাকটাক—371  
 ট—272  
 -ট—798  
 টক—492  
 টকটক—891  
 টকাম—667  
 টগ—492  
 টমকা—886  
 টমক—493  
 টা—492  
 টাউন্স—253  
 টাউর—254, 453  
 টাউরা—399  
 টাউরণ—453  
 টাউর্দা—253  
 টাওরা—888  
 টাক—492  
 টাকরন—333  
 টাকর(ি)ন—694  
 টাকরন—398, 694  
 টাকুর—254, 453, 455, 492  
 টাকুরদা—253  
 টাকুরাণি, -নৌ—254, 398, 453, 694  
 টাকুরানী—670  
 টাকুরানী—695  
 টাকরণ—453  
 টাকি—156  
 টাটি—491, 492  
 টাটি—492  
 টাটা—882  
 টাটা—492  
 টাটা—492  
 টাটা—492  
 টান—254, 453  
 টার—492  
 টান—494  
 টাহর—492  
 টাহরা—399, 888  
 -টি—769  
 টিক—492, 712  
 টিমেটার—1072  
 টুক—489, 493, 530  
 টুঙ্গরী, টুঙ্গরী—622  
 টুলী—493  
 টে—769  
 টেক—492  
 টেড—439  
 টেডে—523  
 টেক—493  
 টেয়া—493  
 টেয়ান—666  
 টেয়ে—523, 769  
 টেল—493, 878  
 টেস—493  
 টেস—493  
 টোক—493, 530  
 টোয়া—493  
 টোনা—493, 530  
 টাই—156, 320, 406, 422, 492, 620, 741, 769, 859  
 টাই-এ—769  
 টাইয়ে—523, 769  
 টাটি—694  
 টুটা—493  
 টেটা—493  
 টেটি—493

ট্রে—523, 769

ট্রাট—493

ড—272, 641

ডগা—495

ডক—495

ডজন—400, 638, 646

ডবডবে—495

ডব্কা—495

ডবটন—644

ডবল—400, 634, 638, 646

ডঘল—647

ডর—315, 494, 899

ডল—494

ডলা—494

ডশ—873

ডহ—873

ডহর—187, 328, 495

ডহর—495

ডা—686

ডাইন (witch)—308

ডাইন (right)—495

ডাইন—646

ডাইল—380, 494

ডাই-ফ্রিনিং—645

ডান—308

ডাঙলি—1070

ডাক—457, 495, 878

ডাকবর—450

ডাকর—405

ডাকহিত—655, 663

ডাকা-করান—1033

ডাকা(ই)তী—655, 663, 673

ডাকাড—663

ডাকিবে—454

ডাকর—647

ডাকার—216, 503, 634, 636,

637, 642, 646

ডাকারখানা—707

ডাকারনী—695

ডাগর—179, 405, 439, 495

ডাঙ্গ—363

ডাঙ্গ—495

ডাঙ্গস—363, 439, 495

ডাঙ্গা—179, 405, 522

ডাডুকা—495

ডাঙলি—1070

ডান—(= witch) 308 ; (= right) 495

ডান-গুলি—1070

ডাব—405, 495, 514

ডাবর—405, 494

ডাবা—494

ডামাডেল—439, 495

ডাঘেল—647

ডাঘমন—646

ডাল—(= pulses) 380, 494 ;  
(= branch) 494

ডালা—495

ডালি—(= pulses) 380 ; (basket) 383

ডালিম—337, 494, 543

ডাহা—495

ডাহিন—317, 336, 488, 495

ডাহক—494

ডি—557

ডিঙ্গা—408, 495

ডিঙ্গাইয়া—394

ডিঙ্গিয়ে—394

ডিপ টা—647

ডিবা—495

ডিবির—495

ডিন—366, 495

ডিহি—184, 498, 557, 603

ডী—686

ডুকরা—495, 888

ডুব—495, 878, 896

ডুবাই—668, 669

ডুবাক—669

ডুবুডুবু—678

ডুবুরী—668

ডুবে—326

ডুমা—495

ডুমুর—313, 326, 362, 494,  
540

ডুমুরী—694, -নীর—719

ডুমুর—362

ডুলী—414, 494

ডেঙ—495

ডেকটী—600, 603, 708

ডেকরা—405, 495

ডেকে—388

ডেঙ্গ—453, 641, 647

ডেগ—600, 603

ডেঙ্গর—495

ডেঙ্গো—522

ডেঙ্গো—522

ডেডু—494, 802

ডেনীহ—703

ডেপুটী—647

ডেন—495

ডেরা—495

ডেলা—439

ডেখ—453, 641, 647

ডোকরা—405

ডোকলা—405, 495

ডোকা—408, 494, 495

ডোবা—186, 405, 495

ডোম—329, 495

ডোমজুড়—65

ডোমনী—694

ডোর—494

ডোল—439, 495

ডোল—495



- ডাটা—492  
 ডাটা—492  
 ডাটা—495  
 ডাড—365, 488, 494  
 ডাশ—488, 494, 548  
 ডাশা—495  
 ডেও—522  
 ডেপ—495  
 ডেয়ো—522  
 ডাইভিং—644  
 ড—(sound) 138, 272, 411,  
 494, 526, 538, 539, 610 ;  
 (affix) 687, 688, 689, 880,  
 885, 887, 888  
 -ডা—66, 687, 688, 689  
 -ডি—688  
 -ডিয়া—687, 688  
 -ডী—687, 688, 689  
 -ডে—687  
 ডু—526  
 ঢ—272, 492  
 ঢাকা—500  
 ঢর—482, 498, 507  
 ঢনা—498  
 ঢল—498  
 ঢলে—877  
 ঢাউস—507  
 ঢাক—498, 873  
 ঢাকন—335, 656  
 ঢাকনা—657  
 ঢাকা (= *Dacca town*)—454  
 ঢাকাই—672  
 ঢাকী—671  
 ঢাকীশুজ, ঢাকীশহ—706  
 ঢাকে—457, 498  
 ঢাড়া—499  
 ঢাড়া(ই)ত(ী)—655, 663  
 ঢামালি, -লী—439, 498  
 ঢাল (noun)—498  
 ঢালা—495  
 ঢালাই—661  
 ঢালাও—663  
 ঢালু—498  
 ঢালে—498, 877  
 ঢিকা—499  
 ঢিট—444  
 ঢিপ—499  
 ঢিবরী—499  
 ঢিবি—499  
 ঢিমা—499  
 ঢিল—313, 499  
 ঢিলা—313, 498  
 ঢীট—324, 355, 491, 493,  
 498, 507  
 ঢীটগনা—696  
 ঢীড়—324, 355, 491  
 ঢুকে—498  
 ঢুল—499  
 ঢুন—499  
 ঢেউ—420, 499  
 ঢেউঝা—883  
 ঢেকা—328, 448, 499, 507  
 ঢেবুর (= *place name*)—185  
 ঢেবুর (noun)—328  
 ঢেউসা—522  
 ঢেয়া—439  
 ঢেড়স—499  
 ঢেবুয়া—499  
 ঢেনশ—499  
 ঢেনচা—498, 522  
 ঢেনসা—499  
 ঢের—328, 499  
 ঢেরা—499  
 ঢেলা—439  
 ঢো—499  
 ঢোকে—498  
 ঢোল—329, 439, 499  
 ঢোলক—682  
 ঢাটা—499, 507  
 ছা—498, 499  
 ছাডু—499  
 ছাড়ে—326, 365  
 ছাশ—498  
 ছেঁকী—328, 439, 499  
 ছেঁকুর—499  
 ছেঁটার—492, 499  
 ছেঁটা—370, 491  
 ছোটাম, -মি—657  
 ছেঁড়ন—328, 507  
 ছেঁড়ি, -ড়ী—699, 328, 499  
 ছেঁড়া (= *to search*)—495  
 ছেঁড়া (= *a snake*)—468, 507  
 ছ—133, 272  
 -ছ—304  
 খ—227, 272, 377, 523, 524,  
 528, 529  
 খ—(sound) 272, 602, 631,  
 642 ; (suffix) 112, 502,  
 654, 691, 692, 704, 739,  
 776, 854, 1000  
 খইয়ার—614  
 খইরুতে—380  
 খইল—304, 425  
 খওয়ারকা—616  
 খকমা—213, 575, 600, 617  
 খকরার—598, 609  
 খকলিখ—606  
 খকলিখ—606  
 খক—449  
 খসু—675, 699  
 খল্লা—443, 449, 599, 602  
 খড়ে খাউস—580  
 খবড় (= *তথ্য, তথন*)—526

তখন—317, 458, 857  
 তপনি—331  
 তপস্বী—582, 600  
 তহন—613  
 তহন—589, 612, 618 ;  
 -তপ—572  
 তহু—311, 474, 826  
 তজবীজ—584, 616  
 তড়—315, 355, 501  
 তড়কা—880  
 তড়বড়া—891  
 তড়াক—681  
 তত (= তত)—854  
 ততকণ—382  
 ততেক—854  
 ততৈকণ—136  
 তব-তবাস—590, 606  
 তখা, তখার—858  
 তখি—825, 834, 839, 858  
 তখিত, তখির—825  
 তখী—825  
 তদারক—575, 582, 598  
 তদের—820  
 তন—378, 503  
 তনখা—575, 599  
 তনে—770  
 তনস—213, 590, 606, 884  
 তফসীল—575  
 তফৎ—590, 617  
 তবক—213, 597, 602  
 তবলা—559, 575, 602  
 তবিরত—584  
 তবীল—585, 595, 616  
 তবে—114, 836, 856  
 -তব্য—705  
 -তম—304  
 তমরাহ—820  
 তমলুক—68

তমলুক—618  
 তমাক—623, 626  
 তমার—820  
 তমোলুক—68  
 তমঃক—558, 612  
 তখি, তখী—595  
 তম্হার—820  
 তম—820  
 তমনাতি—590  
 তমনাৎ—589, 590  
 তমকা—583  
 তমর—587, 614  
 তমের—583, 609  
 তম—576, 873  
 তম (= তোর)—820  
 -তম—304, 704  
 তমকচ, তমকোচ—613  
 তমজনা—602  
 তম্বতে—380  
 তমপ, -তম—575, 592, 606  
 তমন্ত—403, 501  
 তমজু—586  
 তমাস—376  
 তমিতে—380  
 তমহর—340  
 তমে—(post-position) 313,  
 372, 502, 750, 769 ; (verb)  
 877  
 তমে—770  
 তম্—449  
 তম—501, 1038  
 তমপ, -তম—605  
 তম—(noun) 623 ; (verb)  
 883  
 তমার—1034  
 তমুরা—630  
 তমার, -তম—610, 619  
 তমিল—557, 595

তমদীক—597  
 তমদীর—585  
 তমিন্—373  
 তমৈ—373  
 তমাক, তমার—826  
 তম্বীল—595, 616  
 তম্বীল—557, 595  
 তমি, তমি—825  
 তমিত, তমির, তমিঁর—825  
 তমখা—575, 600  
 তম—(noun) : (= heat) 302,  
 320, 349, 501, (= sheet of  
 paper) 595, 781 ; (pro-  
 noun) 555, 821, 822 ; (affix)  
 692, 705  
 তমি—827, 828, 1069  
 তমিৎ—603  
 তমিন—827  
 তমিই—545  
 তমিৎ—578, 597  
 তমিল—316, 471, 483, 517  
 তমিল—588  
 তমি—877  
 তমি—501  
 তমিৎ—659  
 তমিৎ—877  
 তমি (pronoun)—822  
 তমি (root)—806  
 তমিত, -তমি—597, 578, 602  
 তমিরা—583, 597  
 তমিরা—597  
 তমিরা—617  
 তমিরা—456, 880  
 তমিরা—576, 615  
 তমি—316, 456, 501, 880,  
 882  
 তমিরা—213, 610  
 তমিরা—583, 597, 604



তাগাবী—59, 7, 616  
 তাগিন—598  
 তাগৎ—578, 597  
 তাগে—758, 827  
 তাজি—(noun) 601, (verb) 873  
 তাজা—595  
 তাজিরা—578  
 তাজে—316, 501  
 তাক্কব—578, 601  
 তাক্—490, 878  
 তাক্‌স—699  
 তাক্‌জী—497, 501, 538  
 তাক্‌ - 301, 316, 501, 1034  
 তাক্‌ল—335  
 তাক্‌লি, তাক্‌ল—1034  
 তাক্‌তে—882  
 তাক্‌দিগ—821  
 তাক্‌দে—736, 761, 821  
 তাক্‌ন (pronoun)—162, 306,  
 725, 823, 827, 1010  
 তাক্‌নেনে—827  
 তাক্‌নরা—827  
 তাক্‌না—821, 823  
 তাক্‌নার—827  
 তাক্‌নি—827, 828  
 তাক্‌নাকার—827  
 তাক্‌নে—827  
 তাক্‌নেকার—827  
 তাক্‌পে—876  
 তাক্‌পা—606  
 তাক্‌বাস—590, 606  
 তাক্‌বিজ—579  
 তাক্‌মড়া—887  
 তাক্‌মরা—827, 828, 834  
 তাক্‌মরার—827  
 তাক্‌মলী—334  
 তাক্‌মস (= Thomas)—637, 642

তাক্‌ম—157, 321, 531  
 তাক্‌মাক—623, 626, 627  
 তাক্‌মাকর—758  
 তাক্‌মাক্—623, 626  
 তাক্‌মাক্‌টে—686  
 তাক্‌মাদী—576, 602, 609  
 তাক্‌মাম—576  
 তাক্‌মার—827, 828  
 তাক্‌মারা—827, 828  
 তাক্‌মানা—609  
 তাক্‌মিল—(= Tamil) 197; (*see*  
*cution of an order*) 585  
 তাক্‌মলী—282, 366  
 তাক্‌ম—822  
 তাক্‌মদাদ—596  
 তাক্‌মনাং—589  
 তাক্‌মালি—583, 596  
 তাক্‌ম—162, 754, 758, 827  
 তাক্‌মপলিন—642, 647  
 তাক্‌মপিন—503, 642, 647  
 তাক্‌মেনকার—827  
 তাক্‌মেনে—827  
 তাক্‌মা—576, 735, 736, 821,  
 827  
 তাক্‌মার—736, 827  
 তাক্‌মিখ—580, 602  
 তাক্‌মে—877  
 তাক্‌মজব—619  
 তাক্‌মে—827  
 তাক্‌লি—308, 320  
 তাক্‌লা—583  
 তাক্‌লাও—617  
 তাক্‌লাক—576, 602  
 তাক্‌লাস—610  
 তাক্‌লিকা—578  
 তাক্‌লিম—578  
 তাক্‌লুই—546  
 তাক্‌লাক—576, 602, 619

তাক্‌লাশ, তাক্‌লাহ—583, 619  
 তাক্‌লা—883  
 তাক্‌হি—555  
 তাক্‌হর—852  
 তাক্‌হরা—827  
 তাক্‌হলে—400  
 তাক্‌হা—820, 821, 822, 823  
 তাক্‌হাদিগ—729, 736, 821  
 তাক্‌হাদের—821  
 তাক্‌হান—824, 827  
 তাক্‌হানরা—827  
 তাক্‌হারি—114, 729, 754, 827  
 তাক্‌হারদিগর—729  
 তাক্‌দে—827  
 তাক্‌হিরা—736, 821, 827  
 তাক্‌হালে—400  
 তাক্‌হা-হইলে—400  
 তাক্‌হে—822  
 তাক্‌হের—822  
 তাক্‌ডা—887  
 তাক্‌ - 787  
 তাক্‌মস—351, 476, 805  
 তাক্‌মড়া—323  
 তাক্‌উড়া—323, 787  
 তাক্‌কিছে—503  
 তাক্‌কি—408  
 তাক্‌কন—525  
 তাক্‌কেন—622, 624, 625, 629,  
 631  
 তাক্‌ক—355  
 তাক্‌ক—372  
 তাক্‌কি—(adjective) 501, 532 ;  
 (verb) 956  
 তাক্‌তে—882  
 তাক্‌ন—308, 322, 324, 501,  
 786  
 তাক্‌ন (pronoun)—827  
 তাক্‌নটা, -টা—886

তিনটে—401  
 তিন-পো(কা)—803  
 তিনি—415, 725, 821, 823,  
 827, 831  
 তিনিটা, তিনটে—401, 686  
 তিগ্গা—789, 797  
 তিরজ—355  
 তিরর—418  
 তিরাত্তর—555  
 তিরাহ—797  
 তিরাস—305, 323  
 তিরহা—324  
 তিরান(স)ই—800  
 তিরানী, তিরিশি, তিরেখী—799  
 তিরি—376, 378, 503  
 তিরিশ—324, 303, 376, 795  
 তিরটে—225  
 তিল—501  
 তিলক—454  
 তিলি—407  
 -তিশ—363  
 তিষ্ঠ—879  
 তিষ্ঠাইতে, তিষ্ঠে—879  
 -তিদ—324, 363, 376  
 তিসি—313  
 তিই—306, 359, 821, 823  
 -তী, -তি—655, 691, 692  
 তীক্ষ্ণি, তীক্ষ্ণি—324  
 তীখ—324, 460  
 তীন—308, 786  
 তীর—203, 584, 602, 609  
 তীরনাড—574  
 তীরহত—357  
 তীস—336, 376, 502  
 তুই—303, 350, 428, 501, 816,  
 817, 818, 819, 820  
 তুই-নুই—809  
 তুই—820

তুগড়—408, 687  
 তুজুক—213  
 তুখ—819  
 তুখি—818  
 তুন—770  
 তুন্দু—673, 607, 618  
 তুদান—606  
 তুদরা—820  
 তুদাবর—820  
 তুদার—820  
 তুহি—309, 326, 334, 350, 367,  
 401, 516, 531, 554, 734,  
 816, 818, 819, 820, 846  
 তুহে—819  
 তুহা—819  
 তুরপুন, তুরগোন—583, 606  
 তুরিত, তুরিং—325, 335, 501  
 তুরক—204, 213, 581, 602  
 তুরপ—215  
 তুর্ক—213, 692  
 তুর্কান—709  
 তুল—873  
 তুলিবাঁক—1018  
 তুলু—551  
 তুখাটি, তুখি—687  
 তুখে—548  
 তুখী—527  
 তুখারি—819  
 তুহে—819  
 তুখি—818  
 তুকে—734  
 তুখি—818  
 তুলা—325, 544  
 তুখ—325  
 তুখ—304  
 তে—412 ; 824, 825, 827  
 তে—328, 501, 787  
 -তে—372, 502, 719, 739, 1014

তেএ\*—824  
 তেইশ, -স—419, 787  
 তেউড়ী—420  
 তেওড়—421, 863, 887  
 তেউড়ী—787  
 তেকর—683  
 তেকারণ—825  
 তেদাটী—180  
 তেহা—211  
 তেজ—351, 355, 476, 805  
 তেজ (=sharp)—585  
 তেজ-বরিয়া, -ব'রে—476, 805  
 তেজান—669  
 তেজুক—603  
 তেড়া—490  
 তেতাল্লিশ—796  
 তেন—355, 853  
 তেনা—490, 493, 530, 821,  
 823  
 তেনার—415  
 তেদিশ—787  
 তেপায়া—787  
 তেমত—851  
 তেনন—211, 411, 851  
 তের—302, 347, 411, 555,  
 787  
 তেরছ—473, 540  
 তেরছা—324, 473  
 তেরপল—642, 647  
 তেরহ—626  
 তেরা—211  
 তেরেজুরী—633, 640, 642  
 তেরেগা—622, 625  
 তেল—142, 301, 328, 501  
 তেল-চুক্চুক—456  
 তেলা—659  
 তেলাড়া—183



তেলি—407  
 তেলুগু, তেলুগু—197  
 তেরাং—260, 583  
 তেরাং—589, 615  
 তেরান্ন—797  
 তেবটি—798  
 তেঙা—492, 527  
 তেসর(ী)—700, 805  
 তেসাং—854  
 তেহাই—787, 802  
 তেহারা—701  
 তেহেন—355, 553  
 তেহু—853  
 তেই—306, 821, 823  
 তৈহুন—474  
 তৈয়ার—583, 587, 609  
 তৈয়ারী, তৈরী—590  
 তৈল—304, 425  
 তো (pronoun)—330, 802  
 তো (conjunction)—350  
 তো- (prefix)—413, 817  
 -তো (suffix)—854, 1025  
 তোএ, তোএ\*—818  
 তোক—586, 597  
 তোকমারী—587  
 তোগোর—820  
 তোঞ, তোঞি, } —818  
 তোঞে, তোঞে\* }  
 তোড়—414  
 তোড়ং—647  
 তোড়া—213, 610  
 তোড়ী—501  
 তোড়ে—329, 496, 501  
 তোতা—602  
 তোদিগ—816  
 তোদের—816, 820  
 তোন—770  
 তোয়ে, তোয়ের—820

তোপ—213, 604  
 তোকা—581, 595, 606  
 তোবড়—88  
 তোবা—586  
 তোমকা—682  
 তোমরা—735, 816, 819, 820  
 তোমরার—820  
 তোম—816, 819  
 তোমাদিগ—816  
 তোমাদের—731, 816  
 তোমানে—820  
 তোমার—211, 820, 846  
 তোমারী—835  
 তোম—818, 819  
 তোয়া—884  
 তোয়াক—590, 616  
 তোয়ালিয়া, তোয়ালে—418,  
 622, 623, 631, 633  
 তোয়—211, 828  
 তোয়গো—820  
 তোয়ক—647  
 তোয়ং—649, 647  
 তোয়—736, 816, 819, 820  
 তোয়াদের—820  
 তোয়ার—820  
 তোয়পাড়—396  
 তোলা—(noun) 623; (adj.  
 pass. part.) 956  
 তোলানি—665  
 তোলে—329, 501  
 তোলে—630  
 তোবক—586, 598  
 তোবিহ—908  
 তোহারি—819  
 তোহে—819  
 তোহীক—818  
 তোকা—734, 819  
 তোকায়া—735

তোকে—818, 819  
 তোজি—587, 595  
 তুই—818  
 তু—306, 821, 823, 824, 827,  
 828, 1010  
 তুই—825, 827  
 তুইর, তুইরা—827  
 তুইরার—827  
 তুগো—758  
 তুড়ুল—316, 337, 471, 483,  
 517  
 তুত—308, 310, 316, 362, 501,  
 502  
 তুদিগ—821  
 তুদের—821  
 তুনে—827  
 তুখা—321, 367, 514, 531  
 তুখাদী—576  
 তুবু—576  
 তুবে—563, 596  
 তুবোলা—327  
 তুর—827  
 তুর—758  
 তুরা—821  
 তুহা—821, 823  
 তুহাদিগ—821  
 তুহাদের—821  
 তুহালা—821  
 তুই—521, 820  
 তুতিয়া, তুতে—326, 370, 504  
 তুৎ—370  
 তুৎ—325, 371  
 তু—824, 1010  
 তুই—419, 825  
 তুউ—824  
 তুএ—824  
 তুতুল—308, 327, 398, 483  
 তুই—415, 725, 823

ভেহা—823  
ভো—818  
ভোএ—818  
ভোঞ—818  
ভোরার—820  
ভোরী—820  
-ব—705  
ভাঙ্গ—879  
ভিপল—647  
ভিশ—376, 795  
ব্রহ্ম—357  
ক্রপ—215  
ক্রপল—647  
  
ব—272, 643  
বই—344, 403, 553  
বইলী—321  
বক—315, 319, 457, 680, 683  
বকা—886  
বকিত—503, 704  
বতমত—504  
বন—503  
বনে—770  
বনক—680  
বনকা—886  
বর—503  
বরবর—504  
বল—315, 504  
বলী—321, 623  
বাই—553  
বাইকতে—380  
বাগকা, বাগকা—423  
বাক—112, 114, 318, 457,  
680, 683, 1035, 1042  
বাকন—656  
বাকা—886  
বাকিএ—932  
বাকিতা—960

বাকিতে—380, 1002  
বাকিরা—161, 172, 389, 455,  
728, 768, 770  
বাক্ত—903  
বাক্ত—455  
বাক্তে—503  
বাক্তে—251, 380, 449, 1000  
বান—301, 365, 770, 781  
বানত—770  
বানী—503  
বানে—770  
বাগড়—446, 448  
বাগড়া—446  
বাগড়—446, 448, 504  
বাবড়া—446, 504, 887  
বাবা—504, 887  
বাম—316, 503  
বামে—882  
বাল—504, 659  
বালী—544, 659  
বাস—504  
বাহ—503  
বিক—504  
বিকবিকা—891  
বিতা—504  
বিতার—882  
বিত্ত—504  
বিহেটার—643, 647  
বির—323, 504  
বিরার—882  
বুক—504  
বুড়—878  
বুড়া—504, 887  
বুত্ৰ, বুত্ৰ—504  
-বুন—770  
বুবড়া—504, 887  
বুর—878  
বুরা—504

-বে—161, 770  
-বেএ—770  
-বেকে—161, 388, 389, 390,  
477, 728, 768, 770  
-বেকা—389  
বৈলী—623  
বোড়—504  
বোড়া—211, 320, 353, 504  
-বোন—770  
বোবা—504  
বোর—330, 504, 877, 1042  
বোরে—932  
বো + সোত—183  
বোহ—903  
বুতনী—504  
বুতি, বু'তি—504  
বে'ত—888  
বে'তলা—888  
বে'তলান—504  
বে'তান—504  
বে'তা, বে'তাপা—504  
  
ন—(sound) 272, 602, 628,  
642, 643 ; (=noun) 452 ;  
(affix) 604, 729, 733  
দই—308, 315, 344, 425, 554  
দইসং—595  
দগলা—425  
দকিণা—659  
দখিন—317, 336  
দখিনিরা—417, 675  
দখিনে—417, 675  
দ'বনে—417, 659, 675  
দগবিলী—957  
দক্ষবাটি—65  
দজাল—601  
দড়—355, 499  
দড়—355, 499, 1034



দড়ান—1034  
 দড় (= দোয়াত)—403  
 দদাই—422, 483, 506, 662  
 দধুর—606  
 দফা—602  
 দমক—682  
 দমকা—682, 886  
 দহলং—595  
 দহা—420, 533  
 দহামই, দহামসী—425  
 দহাল—310  
 দহর—711, 713  
 দহগুহান—707  
 দহকচা—711  
 দহকার—602  
 দহকোচা—711  
 দহকাঁচা—711  
 দহখাণ্ড—593, 600  
 দহগা—598  
 দহল—592  
 দহদী—672  
 দহপত্তনী—713  
 দহপাকা—711  
 দহবেল—585, 616  
 দহমা, দহমাং—557  
 দহশ—883  
 দহশন—303, 376  
 দহাং—602  
 দহিলা—602, 615  
 দহিলাপ্ত—593, 606  
 দর্শন—303  
 দল—315, 873  
 দলই—309, 347  
 দলমলা—891  
 দলাই-মলাই—891  
 দলীল—595  
 দলীল—575  
 দলুই—309, 347, 397

দশ—505, 550, 792  
 দশরা—347  
 দশুখত, -বং—593, 602, 612  
 দস্তাবেজ—585  
 দস্তুর—575  
 দহ—452  
 দহর—187  
 দহরম-মহরম—617  
 দহলা—550  
 দহি—308  
 দংশিত—704  
 দা—255  
 -দা(=দাদা)—453  
 দাইল—494  
 দাঁদখানি—591  
 দাউদাউ—424, 678  
 দাউন—310, 381  
 দাউন—379  
 দাও—(noun) 255 ; (verb)—  
 421, 423, 904  
 দাওছাই—616  
 দাবিল—580  
 দাগ—602, 884  
 দাগা—884  
 দাগী—671  
 দাঙ্গা—506  
 দাড়া—372, 409, 505  
 দাড়িম—320, 336, 494  
 দাড়ী—499  
 দাঢ়া, দাঢ়ী—499  
 দাঙাইহ—908  
 দাঙাই—908  
 দা—310, 381  
 দানখানি—591  
 দাদা—453  
 দাদু (=দাউন)—379  
 দাদু (=দু)—381  
 দাদু—337

দান (=দানব)—302, 347  
 -দান, -দানী—708  
 দানবীর—305  
 দানা—595  
 দানুজ—679  
 দানো—302, 320, 347  
 দাপ—316, 446, 505, 511  
 দাপট—446, 684  
 দাপটা—886, 887  
 দাবড়া—887  
 দাবড়ী—446  
 দাবী—578  
 দাম—195, 316, 505, 520  
 দামড়া—334, 367  
 দামড়ী—195  
 দামায়া—576  
 দামী—671  
 দামের—585  
 -দার—708  
 দার—602  
 দারুণী—695  
 দারোগা—213, 583, 586, 600  
 দালাল—576, 610, 618  
 দালি—494  
 দামী, দাম্রাক—826  
 দাহিৎ—336  
 দি(=দিই, দেই)—352, 396, 429  
 -দি(=দিনি)—453  
 -দি(=দানি)—728, 729, 730,  
 732, 992  
 দিবার—995  
 দিবার—995  
 দিই—352, 398, 407, 419, 429  
 দিইছিল—398  
 দিইরে—394  
 দিউক—310, 353, 387, 419,  
 457  
 দিউন—419

দিউনে—675  
 দিও—352, 418  
 দিওনাক'—990  
 দিক্—310, 353, 387, 419, 454,  
 907, 989  
 -দিগ—94, 97, 446, 703, 728,  
 729, 730, 732, 992  
 দিগর—728, 729, 730, 731,  
 732  
 দিগধরী—673  
 দিগার—732  
 -দিগের—728, 729, 730, 732  
 -দিগ্—728  
 দিচ্ছে—444  
 দিচ্ছে—1026  
 দিছিল—398  
 দিছে—1026  
 দিঞাছি—1027  
 দিট—492  
 দিটি—308, 322, 324, 355, 505,  
 716  
 দিডে—716  
 দিড়—492  
 দিতে—1014  
 দিতে চাওয়া—1051  
 দিতেছে—1023  
 দিতে থাক—1052  
 দিতে-দিতে—1014  
 দিতে পারি—451  
 দিওঁ—980  
 দিদি, দিদি—453  
 দিন-ভর—702  
 দিনেবার—215  
 দিন্—419  
 দিব—331  
 দিবা-করি—1018  
 দিধাকে—752  
 দিবার—752, 1018

দিবেক—989  
 দিবেন—725  
 দিবের—401  
 দিবোঁর—995  
 দিবা, দিবি—447  
 দিনু—95  
 দিরডী—690  
 দিরনিয়া—675  
 দিরা—172, 416, 770, 995  
 দিরাই—420  
 দিরাছিল—398  
 দিরা-, দিরে-, (দওয়া)—1051  
 দিরায়ে—994, 995  
 দিরালা—324  
 দিরাশ(ী)লাই—324, 416  
 দিরে—416, 770, 918  
 দিরেই—420  
 দিরেই-তো-ছি(লুম)—1028  
 দিরেচে—444  
 দিরেছিল—398  
 দিরেছিলিস—979  
 দিরেশালাই—416  
 দিরে'ছে—1026  
 দিল (= gave)—35, 324, 351,  
 984, 985, 1044  
 দিল (= heart)—611  
 দিলাক—989  
 দিলীই—987  
 দিলাগি—725  
 দিলিস—979  
 দিলুম-খুব—997  
 দিলে—983, 984, 1003, 1004  
 দিলেক—989  
 দিলে না ক'—990  
 দিলে-বিনা—1017  
 দিলেম—400  
 দিলু (= gave)—983  
 দিশারী—349, 669

দিশার—989  
 দিশি—141, 398, 672  
 দিশ্বর (= December)—642  
 দিস্তে—583  
 দিহ—352, 908  
 দিহলি—997  
 দিহি—184  
 দৌল—324, 505, 696  
 দৌখি—323  
 দৌটি—308  
 দৌন—602  
 দৌপতি—376  
 -দৌ(ম)—505, 701  
 দু- (= দুই)—357, 505, 785  
 দুঅজ—476, 805  
 দুয়ার—376  
 দুই (= I milk)—428  
 দুই (= two)—357, 406, 428,  
 782, 785  
 দু(ই) জন—785  
 দু(ই)টা—357, 686, 785  
 দু(ই)টা—686  
 দুইয়ে—428  
 দুই-কয়ে—776  
 দুইই—786  
 দুও—554  
 দুওর—401, 429  
 দুকাল—456  
 দুকর—458  
 দু-কত—781  
 দুখ—458, 460, 505  
 দুখার—882  
 দুপি—462  
 দুধ—449  
 দুছুট—785  
 দুজুগ—402, 476, 477  
 দুটো—357, 686, 785  
 দু-তা—781



ব্র-খান—781  
 ব্রধ—326, 505, 507  
 ব্রধারী—785  
 ব্রখাল—669  
 ব্রধু—311  
 ব্রনা—352, 505  
 ব্রনিয়া—418, 581, 583, 607, 615  
 ব্রপুৰ—458, 785  
 ব্রবল, ব্রবলা—514, 544  
 ব্রবার (= বার)—376  
 ব্রমড়া—587  
 ব্রমুখো—785  
 ব্রখা—581  
 ব্রখার—376, 429  
 ব্রয়ে—428  
 ব্রয়োর—429  
 ব্রকবার—376  
 ব্রকবীন—586  
 ব্রকযোগ—376  
 ব্রকোণ—477  
 ব্রল—414, 873  
 ব্রলালী—675  
 ব্রলি—395  
 ব্রলী—352, 661  
 ব্রলুনি—414  
 ব্রলে—414  
 ব্র-শ, ব্র'শ'—215, 387  
 ব্রশো—800  
 ব্রব—873  
 ব্রবমন—581  
 ব্রবপু—551  
 ব্রষ্টে—311, 877  
 ব্রহ—873  
 ব্রহই—426  
 ব্রহা—554  
 ব্রহাতা, ব্রহাত্তা—785  
 ব্রহান—786

ব্রহে—428  
 ব্রহব—460, 558  
 ব্রহ খাকি—770  
 ব্রহবীন—602  
 ব্রে—(noun) 303, 311, 327, 352, 505, 557, 652, 701, 741; (verb) 352, 416, 770, 873, 903, 904, 1014, 1029; (post-position) 416, 770  
 ব্রেজ—903  
 ব্রেজনিয়া—675  
 ব্রেজর—335  
 ব্রেজলা—412  
 ব্রেজলিয়া—328  
 ব্রেজা—1029  
 ব্রেজালা—412  
 ব্রেই—352, 398, 419  
 ব্রেউ—310, 353, 419  
 ব্রেউক—353, 389, 907  
 ব্রেউটী—324, 398, 420, 491, 505  
 ব্রেউড়ী—328, 420  
 ব্রেউল—186, 346, 350, 420  
 ব্রেউলে—328  
 ব্রেও—(verb) 421, 904, 932; (noun, = giant) 617  
 ব্রেওর—328, 335, 352, 411  
 ব্রেওয়া—427, 660, 1029  
 ব্রেওয়াইয়া—394  
 ব্রেওয়া-করান—1033  
 ব্রেওয়ান—585, 607, 616  
 ব্রেওয়াল—684, 617  
 ব্রেওয়ালুড—1032  
 ব্রেঠ—932  
 ব্রেহু—907  
 ব্রেভে—443  
 ব্রেগ—600  
 ব্রেগটী—708

ব্রেথ—396, 397, 409, 411, 443, 505, 873  
 ব্রেথই, ব্রেথএ—280  
 ব্রেথতা—654  
 ব্রেথতার—962  
 ব্রেথতে—962  
 ব্রেথন—656  
 ব্রেথন্তী—653  
 ব্রেথন্তে—1002  
 ব্রেথমার—896  
 ব্রেথনা, ব্রেথনে—885  
 ব্রেথহ—906  
 ব্রেথা—397, 925  
 ব্রেথাইব করি—1018  
 ব্রেথাইয়া—394  
 ব্রেথাদেবি—1048  
 ব্রেথান—666  
 ব্রেথানি—686  
 ব্রেথি—396, 397  
 ব্রেথিথ—93  
 ব্রেথিএ—337  
 ব্রেথিও—93  
 ব্রেথিতে—443  
 ব্রেথিতে আছেন্ত—1023  
 ব্রেথিতেছি—1023  
 ব্রেথিতে পাওয়া—1051  
 ব্রেথিব—1018  
 ব্রেথিবা-মাত্র—1018  
 ব্রেথিরা—396  
 ব্রেথিরা-বিলে—1004  
 ব্রেথিরাহি—996, 1010  
 ব্রেথিরে—394  
 ব্রেথিল—940, 984  
 ব্রেথিলাম—93  
 ব্রেথিলাহৌ—93  
 ব্রেথিলি—93  
 ব্রেথিলে—984  
 ব্রেথিলেক—95

- দেখিলেন—987  
 দেখিলু—93  
 দেখিহ—93  
 দেখুক—396, 397  
 দেখুই—653  
 দেখে—260, 328, 391, 396,  
 397, 410, 411, 984  
 দেখে-দেখে—1047  
 দেখে' (= দেখিয়া) —397  
 দেখেন—458  
 দেখো—93, 327  
 দেখু—411  
 দেখতা—962  
 দেখতাম—962  
 দেখতে—443  
 দেখতে পাওয়া—1051  
 দেখতো—962  
 দেখল—985  
 দেখলে—93, 984  
 দেখু—157, 351, 494, 802  
 দেখে—351  
 দেখে—508  
 দেখান—336  
 দেখন—411, 657  
 দেখা—657  
 দেখো—386, 679  
 দেখু—903  
 দেখ—411  
 দেখসনে—774  
 দেখা—411  
 দেখার—1019  
 দেখী—826  
 দেখো-না-ক'—990  
 দেখোনে—998  
 দেখা—826  
 দেখাক, দেখাপ—580, 600,  
 602  
 দেয় (adjective)—304  
 দেহ (verb)—328, 411, 421,  
 533  
 দেহ-নিক'—990  
 দেহাতি—933  
 দেহলা—412  
 দেহা—(noun) 328, 342, 505;  
 (verb) 1029  
 দেহান—585, 616  
 দেহাল—584, 610, 617  
 দেহালী—324  
 দেহাশলাই—324  
 দেহাসিনী—325  
 দেহ—718, 728, 730, 775  
 দেহাখো, দেহাখো—278, 324,  
 331, 679  
 দেহ—611, 617  
 দেহাজ—647  
 দেহানা—1033  
 দেশ—142, 411  
 দেশর—706, 1073  
 দেশমি—751  
 দেশলাই—324, 351, 416  
 দেশত—1073  
 দেশী—398, 672  
 দেহ—(noun) 304, (verb) 421,  
 423, 903  
 দেহি—933  
 দেহা—328, 352, 553, 701  
 দেহা—412  
 দেহা—701  
 দেহা—412  
 দৈ—315  
 দৈত—425  
 দৈবজ্ঞ, -জ্ঞ—406  
 দৈবারিক—426  
 দো—554  
 দোআশা—785  
 দোকর—683  
 দোকা—786  
 দোকান—454, 586, 602  
 দোখ—460  
 দোছুট—337, 472, 785  
 দোজ—476, 805  
 দোজক—203  
 দোজবরিয়া, দোজব'রে—476,  
 805  
 দোখারী—785  
 দোনা—330, 505  
 দোপহর—785  
 দোপাটি—795  
 দোকরকা—682  
 দোভাষী—785  
 দোহ—426  
 দোহজ—805  
 দোহয়—614  
 দোহা (= to give)—427  
 দোহা (= prayer)—596  
 দোহাৎ—403  
 দোহাদিশ—427  
 দোহাদশী—427, 534  
 দোহা—429, 441, 668  
 দোহ—429  
 দোহর—593  
 দোহ—414  
 দোহন—657  
 দোনা—329  
 দোলাই—(verb) 414; (noun)  
 661  
 দোলানি—414  
 দোলে—395, 414  
 দোশ—215  
 দোষার—929  
 দোসর—700  
 দোসরা—700, 805  
 দোষ—612  
 দোহাভা—785



দোহার—340, 420, 441, 686, 701	ত্রাণ—304	খাউস—507
দোহার—701	খ—272, 522, 643	খালা—448, 499, 507
দোহে—426	খকল—448, 507, 698	খালা—499
দোড়—345, 348, 427, 505, 691	খড়—315, 355, 496, 506	খালা—508
দোড়া—887	খড়া—355	খাত—310, 385
দৌলতমহ—709	খড়াস—700	খান—506, 529
দৌলৎ—587, 602	খড়ী—355	খানুখা—386, -খা—879
দাঁ—520, 637	খড়ীবাক—709	খামলা—507, 889
দাঁড়—384, 494, 505, 1034	খন—320, 506	খামা—507
দাঁড়-করান—1033	খনী—506	খামালি, -লী—439, 498, 507, 889
দাঁড়কাক—282, 1074	খনুক—682	খাট—320, 345, 422, 506
দাঁড়াইরা—1003	খপাস—700	খাট—305, 313, 507
দাঁড়াইল—1035	খমকা—886	-খাট—859
দাঁড়ার—882, 1034	খম—449	খাটাল—689
দাঁড়ালুহে—1035	খর—258, 536, 873	-খাটে—859
দাঁত—301, 363, 362, 532, 505	খরণ—656	খাটে(verb)—877
দাঁতটাত—176	খরমা—331	খিজি—508
দাঁতন—658	খর-পাকড়—696	খীট—507
দাঁতা—883	খরম—376	খুলা—325, 341
দাঁতাল—669	খরা—896	খুই—428
দাঁদড়া—887	খরাটী—687	খুইরা—428
দাঁদলা—887, 888	খরিছ—1023	খুকখুকা—891
দাঁদলান—698	খরিলেক—990	খুচনী—508
দাঁদিয়া, দাঁদে—386, 505	খরিল'ই—987	খুতি—506
দাঁতি—937	খরিহ—908	খুতী—473
দোহ—725, 786	খর—903	খুতু—311, 677
দোহা(কা)র—701, 725, 786	খরে—506, 877	খুখুয়া—326
দোহাকে—786	খর্দ—304, 449	খুন—873
দোহে—725, 786	খল—346, 652	খুনা—507
দ—619	খলা—346, 506	খুনারী—398, 668
দা—534	খস—507, 873	খুনি—507, -নী—529
দারা—770	খা—348, 873	খুখরি—668, -রী—398
দিক—503	খাই—(verb) 349	খুনে—506, 875
দাখে—260, 391, 410	খাইত—385	খুপুস—700
দাখেক—918, 990	খাত—310	খুয়া—341
দাল—617	খাউড়, -ড়ী—688	খুয়াটক—429
	খাউত—310, 385	খুয়ে—428

ধূম-ধূম—1048

ধূলা—507

ধূআ—340

ধূআ—659

ধূও—429

ধূণী—352

ধূনাটী—708

ধূনে—325

ধূদ—507

ধূমসা—507

ধূয়া—340, 342, 429, 507

ধূয়াক—429

ধূয়ো—429

ধূয়াক—429

ধূয়ী—659

ধূল—716

ধূলি—716

ধূলে—716

ধূলো—401

ধেইধেই—420

ধেং—508

ধেমুকল—727

ধেনো—385, 679

ধেরায়—421

ধো—429, 873

ধোআ—429

ধোইরা-পোছির—1048

ধোও—429

ধোকড়—508

ধোখা—506

ধোবা—330

ধোবানী—695

ধোয়—353, 506

ধোয়া—342, 415

ধোয়াট—415

ধোয়ানি—666

ধোলাই—662, 1033

ধোলাট—687

ধোসা—506

ধোঁচা—482, 499, 507

ধোঁজ—482

ধোঁখা—366, 507

ধোঁআ—520

ধোঁই—529

ধোঁয়া—506

ধোঁয়া—882

ধোঁড়ন—507, 699

ধোঁড়ি—699

ধোঁকা—506

ধোঁকবাজ—709

ধোঁড়া—507

ধোঁয়া—520

ধোঁয়াট—685

ধোঁয়াটে—686

ধোঁয়ায়—882

ধন—879

ধন—873

ধ্যা—879

ধ্যাস—421

ন—(sound) 272, 524; (= nine) 346, 792; (= not) 347; (suffix) 692, 725, 853, 925

নঅলী—698

নই—(noun) 308, 315, 344, 346; (numeral) 799; (verb) 527; (conjunctive affix) 1007

নই-ক—991

নইলে—777, 1039

নও—425

নওবং—588

নওলা—425

নকর—588

নকল-নথি—708

নকানী—575

নকশী—545

নকড়র—376

নগ—305

নগর—575, 597, 603

নগরালী—670

নগরীয়া—394, 417, 674, 542

নগিচ—585

নগীচ—598, 603, 618

নগীজ—598

নগুণ—346

নগুরে, ন'গুরে—394, 674

নগুথি—462

নথ-কুশি—672

নথতা—376, 527

নথানি—666

নথিন্দর—545

নথর—540, 611

নথরিক—585

নথর—613, 1072

নথিক—585

নথীর—575

নট (= নঠ )—445

নঠ—318, 319, 445

নড়—(verb) 185, 545, 497, 878; (noun) 355, 496

নড়কা—886

নড়ী—498, 530

নড়—304

নড়ন—345, 527

নড়নই—705

নড়া—541

নথ—305, 318, 319, 504

নথী—220

নথীকর—757

নথীয়া, ন'থ—346, 701

নথর—184, 346

ননন—305, 315, 371, 506, 528, 694

নননিনী—694, 695



- ননী—309, 346, 396, 528  
 নন্দাই—309  
 নন্দা—530  
 নব—305  
 নবাব—582, 605, 616  
 নবিশ—616, 708  
 নবিশি—708  
 নবেশ্বর—643, 647  
 নবোঢ়া—500  
 নব্বই, নব্বই—514, 799  
 নভেশ্বর—647  
 নম—879  
 নমস্কার—452  
 নমাল—315, 575, 577, 607  
 নমিত—704  
 নম্বর—400, 638, 639, 647  
 নয়—(verb) 424, 545, 555, 1039; (= nine) 424, 545, 792  
 নয়ন—303  
 নয়নজ্বলি—66  
 নয়ল—527  
 নয়ান—336, 405  
 নয়ক—455  
 নয়ন—592, 607, 609  
 নয়না—884  
 ন-নাচিরা—541  
 নয়—677  
 নয়ন—331, 347, 398  
 নয়ন—331, 347  
 নয়ন—453, 553  
 নয়না—523  
 নয়না—334  
 নয়নী—299  
 নয়গান—530  
 ন'লে (= নইলে)—770  
 নলেন—530  
 নদীপুর—605, 618  
 নদীব—607  
 নদীদাম—605, 618  
 নদ্র—611  
 নজদান—708  
 নহ—347, 885  
 নহএ—424  
 নহবৎ—588, 618  
 নহর—424, 555, 1039  
 নহরে—424  
 নহর—575, 592  
 নহলী—698  
 নহিবে—347  
 নহিলাই—975  
 নহিক—991  
 নহিব—1039  
 নহিবেক—990  
 নহিলে—347, 777, 1039  
 নংব—518  
 না (noun)—302, 320  
 না (negative)—925  
 না (expletive)—320, 520, 527  
 না (= to bathe)—528  
 না (suffix)—637, 1012  
 না- (prefix)—713  
 নাই (= ছাত্র)—406  
 নাই (= does not exist)—419, 555, 953  
 নাই (= নাতি)—422  
 নাইক—990, 991  
 নাইর—528, 545  
 নাইরা—345  
 নাইর—528, 553  
 নাইরুল—380  
 নাউ—545  
 নাউড়—688  
 নাও—421, 423, 904, 906  
 নাক—456  
 নাকচ—583, 613  
 নাকরা—576  
 নাকানি—666  
 নাকার—456  
 নাকরা—576, 597  
 নাগোরা—582, 599  
 নাগপুরিরা, নাগপুরে—675  
 নাগরা—576, 597  
 নাগরানী—670  
 নাগলা—888  
 নাগাং, নাগান—611  
 নাগরা—597  
 নাগিনী—695  
 নাঙল—544, 545  
 নাঙা—370, 527  
 নাঙা—370, 527  
 নাচ—355, 527, 955  
 নাচ-করান—1033  
 নাচন—656, 985  
 নাচনী—657  
 নাচনী—653  
 নাচা—963, 1016  
 নাচাইরা—394  
 নাচি-নাচি—1003  
 নাচিতে—477  
 নাচিতে-নাচিতে—1000, 1052  
 নাচিরা-নাচিরা—1047  
 নাচিয়ে—394  
 নাচুনি, নী—398, 657  
 নাচুয়ী—653  
 নাচে—516, 875  
 নাচে-কোচে—1048  
 নাচুড়—477  
 নাচুবে-কুঁচুবে—1048  
 নাচুল-কুঁচুল—1048  
 নাচলে—985  
 নাছ—258, 306, 473, 536, 543, 545

নাছ-দোহার-545  
 নাজিনা-530  
 নাজির-580, 607  
 নাজেহাল-501  
 নাট-( < naṭa ) 318, 527,  
 445; ( < nāṭya ) 491  
 নাটাই-545  
 নাটম-545  
 নাটকে-399  
 নাট-545  
 নাট(=নাট)-318, 445  
 নাড়-365, 406  
 নাড়া (= shaven-headed) 442,  
 498, 530  
 নাড়ালোল-66  
 নাড়ী-490  
 নাড়-545, 678  
 নাড়া-442, 408  
 নাডান-617  
 নাতি-502, 527  
 নাতিম-337, 694  
 নাতিমৌ-694  
 নাতিম-675  
 নাডী-675  
 নাডোয়ান-589, 607, 617  
 নাডির-539, 543  
 নাডমৌ-694  
 নাডান-726  
 না-পাখিমান-713  
 নাপিত-528  
 নাপিতানৌ, নাশিনৌ,-২নৌ-696  
 নাপি-197  
 নাক-এ-512  
 নাব-367  
 নাবালক-580, 600, 712, 713  
 নাব (verb)-367  
 নাবতা-892  
 নাব-নগর-1851

নামা-709  
 নামাজ-577  
 নামে-876  
 নাম-367  
 নায়-(noun) 422; (verb)  
 321, 917  
 নায়ক-533  
 নায়র-335, 528, 540  
 নারে-422  
 নারোব-588  
 নারের-300, 321, 528, 545,  
 553  
 নার-509, 885  
 নারকল-380, 403  
 নার(ং, ন-349, 528  
 নারিকেল-380  
 নারে-517  
 নাল-(= saliva) 66, 306;  
 (= arable land) 188; (= horse-shoe) 578; (= red)  
 545  
 নালিশ-580, 610  
 নাসপাতি-604  
 নাসিতৌ-960  
 নাজা-384  
 নাহ-873  
 নাহক-713  
 নাহা-528  
 নাহিক-683, 990  
 নাহিকর-683  
 নাহৌ-555  
 নাহে-321  
 নাটৌ-491  
 নি (verb)-1045  
 -নি-692, 773  
 নি-711  
 নিবীক্ষিত-1027  
 নিউগী-399

নিউজিশ-711  
 নিকড়ি-526  
 নিকর-711  
 নিকলা-889  
 নিকলে-445  
 নিকা-456  
 নিকা(হ)-579, 595  
 নিকানি-665  
 নিকাম-445  
 নিকাল-456  
 নিকালে-445  
 নিকাশ, -ন-324, 445, 456  
 নিকাহিতা ঙী-704  
 নিকি-456  
 নিকুনি-665  
 নিকে-583  
 নিক্ (= লউক)-454, 907  
 নিধর-874  
 নিধাইক-711  
 নিধা(উ)হি-711  
 নিধ-ত-711  
 নিধাই-711  
 নিধড়া-887  
 নিধ-445  
 নিচল-445  
 নিছ-372  
 নিছনি, -নৌ-324, 551  
 নিছা-551  
 নিছ-850  
 নিখুয়-408, 482  
 নিখুয়-322, 324, 337, 493  
 নিড়ানৌ-665  
 নিবর-324, 711  
 নিবালী-670  
 নিদ্-305  
 নিবাই, নিবাণ, নিবায়-711  
 নিব-305, 370, 505  
 নিব-883



- নিম্বালী—৪৭০  
 নিম্ব—৩৩১  
 নিবড়—৩২৪, ৪৭৪  
 নিবড়া—৪৪৭  
 নিবড়ে—৪৭১  
 নিবন্ত—৩৩৩  
 নিবর (= Eng. liver)—৬৩৯, ৬৪৪  
 নিবা—৪৪০, ৭১১, ৪৭৪  
 নিবাহ—৩২৪, ৫১৬  
 নিবু-নিবু—৪৭৪  
 নিবেবিহু—৩৩৪  
 নিবো-নিবো—৪৭৪  
 নিবোঁক—৩৩৩  
 নিবুতল—৭১১  
 নিভ-নিভ—৪৭৪  
 নিভা—৪৪০, ৪৭৪  
 নিভার—৫১৬  
 নিভুল—৭১১  
 নিম—৩২৪, ৪২২, ৫৩১  
 নিমকী—৪৪৭  
 নিমন্ত—৩৫৭  
 নিমাই—৪২২  
 নিমাখি, নিমাখিতী—৭১১  
 নিমিত্ত, -স্ত—৭৭০  
 নিমড়—৩২৪, ৩৩৫, ৩৪০, ৪৭৬  
 নিময়—৪১৪  
 নিমায়ং—৫৩৬  
 নিমোং—৪১৪  
 নিমোগী—৪১৪  
 নিমোজিলী—৭২১  
 নিরমা, নির্মা—৪৭৭  
 নিরানই—৪০৫  
 নিরান(সই)—৭১২, ৪০০  
 নিরানল ই—৪০৫  
 নিরালী—৩২৪  
 নিরিক, -ক—৫১২, ৫১৩  
 নিরিবিজি—৪০২
- নিরদিগ, -ক—৭১১  
 নিরু—৭১১  
 নির্গাঞি—৭১১  
 নির্গি—৪৭৭  
 নির্প (= নৃপ)—৩৫৭  
 নিতুল, নিতুল—৭১১  
 নির্দা—৪৭৭  
 নিল—৩৫১, ৩৪৪  
 নিলাজ—৭১১  
 নিলাম—৬২৫, ৬২৭  
 নিলিমিহি—৪০১  
 নিলিস—৩৭৭  
 নিলে—৩৪৪, ৩৩৭  
 নিলেই—৩৪১  
 নিশাহল—৬১০  
 নিশান—৫৪৪, ৫৭৭, ৬০৭  
 নিশাস—৩২৪, ৩৩৬, ৫৪৪  
 নিশিধো—৫৫১  
 নিশি—৩২৪  
 নিশেন—৫৪৩  
 নিশি—৪৭৭  
 নিশিত্ত—৩০৪  
 নিষব্ধ—৩০৩  
 নিবৃত্ত—৩৩৭  
 নিবৃত্তি—৩২৪, ৫০২, ৫৫০  
 নিবৃত্তী—৪৪৫  
 নিসর—৪৭৪  
 নিসান—৩২৪, ৩৩৬, ৫৪৪  
 নিহড়—৩৩৩  
 নিহার—৫৪০, ৪৭৪  
 নিহারে—৫৫৪  
 নিহাল—৪৭৪  
 নিহালে—৩৩৬, ৫৫৪  
 নিহড়—৩৩৩  
 নিঃশেষিত—৭০৪  
 নিঃশাস—৪০১, ৫৫৪  
 নী (verb)—৩৩৭  
 নী, -নি—৬৫৭, ৬১২, ৬১৫, ১০১২
- নীচু—৪৭৪  
 নীচে—৭৭০  
 নীচের—৫৩৩  
 নীট—৬৪৭  
 নীড়—৪০৬  
 নীহ—৫০৫  
 নীলাম—৬২৪, ৬২৫  
 নীলিয়া—৭০৩  
 নীলে (= নীল)—৪০১  
 নু (verb)—৪৭৪  
 -নু—৫৪৫, ৪৭৭, ৩৭৪, ৩৭৫  
 নুই—৪২৪  
 নুটী—৫৪৫  
 নুটিং—৪৪৭  
 নুড়ী—৩০৭  
 নুন—৩৩০, ৫২৪, ৫৪৫  
 নুলা—৫৩০  
 নুর—৫৪৬  
 নে—৪৭৭, ৩০৩, ৩০৪, ১০০৭, ১০৪৫  
 নেত—৩০৩, ৩০৬  
 নেত—৩৩৫  
 নেতালী—৫২০  
 নেই (= is not)—৪১৭  
 নেই (= snēha)—৩০৪, ৩২৪, ৪০৬, ৪১১, ৪১৭, ৫২৪, ৫৫৭, ৭৪১  
 নেই (= nyāya)—৪০৬  
 নেই-নীচু—৪১৭, ৬৭৫  
 নেটগী—৩৩৭, ৪১৪, ৪২১  
 নেটহ—৩৩৫  
 নেটহা—৩২৪, ১০৭১  
 নেটট—৪৭৪  
 নেটটা—৪৪৭, ৪১২  
 নেটর—৩৩৭, ৪০৭, ৪২০  
 নেটল—৪০৭, ৪২০  
 নেও—৪২১, ৩০৪, ৩০৬  
 নেওহ—৩৩৫  
 নেওটা, -টা—৪১১, ৪২১, ৪৩১, ৬৪৫

নেওরা—420, 427	নে—(noun) 330, 555; (verb)	পইশে—384, 510
নেক—585	873	পইস—574
নেকরা—577	নোক—545	পইসে—344, 379
নেকাম, -বি—667	নোকর—588, 607	পক—455, 534
নেকার—456	নোকসানি—581	পখালে—317
নেকা(হ)—579	নোকানি—666	পগার—281, 403, 462
নেট্টা—685	নোজা—581, 607	পচ—873, 896
নেত্রা—889	নোঙা—520	পচ্চিম—473
নেজ—545	নোঙে—577	পছন্দ—473, 593
নেড়ু—328, 365, 411	নোট—648	পহিম—473
নেড়া—442, 498, 530	নোতুন—345, 413, 527	পক—789
নেত—328, 411, 502	নোতুনব—703	পকসেরী—451
নেতা—659	নোনা—622, 626, 630	পকার—789, 797
নেতা—432	নোত্র—877	পকাশ—789, 796
নেবড়া—887	নোয়া—427	পট—878
নেব—157, 303, 367, 514	নোশেরা—518, 608	পটক—681
নেম—351	নোহা—555	পটকা—681
নেমক—577, 598	নোকতা—453	পটাং—655
নেমগুহ—357	নোকর—588	পটান—700
নেমাজ—577	নোতুন—345, 527	পটীয়া—396
নেম—411, 421	নোবৎ—588	প'টৌ—395
নেহা—420	ন—162	পটোল—516
নেহাই—420	নুহ—132	পট্টান—213
নেহালি—409	নশীদ—305, 370, 527	পড়—443, 925, 926
নেহে (=nāvika)—345	নোঁরা—520	পড়তি—655
'নেসগেবা'—278	জাও—906	পড়ন—656
নেই—(noun) 328, 528,	জাকার—457	পড়ু—999
567; (verb) 421, 423,	জাযা—304	পড়বেলী—334
906	জামা (=নাজা)—384	পড়ুই—332, 334, 496, 550
নেহা—659		পড়ুই—932
নেহাই—324, 336	প—272	পড়া (=paṭha)—336, 405
নেহাৎ, -রৎ -রৎ—594, 614	পইঠা—344, 580	পড়া—(=√paṭh) 926
নেহার—540	পইচা—882	পড়াক—681
নেহারে—324	পইতা—315, 344, 384, 425,	পড়ার—877
নেংটা—685	502, 509	পড়াহ—336
নেংড়া—887	পইতার—882	পড়ি—497
নে—220, 315, 344	পইতে—334, 425	পড়িছা—315, 337
নেহাটা—219, 344	পই-পই—426	পড়িছে—1023



- পড়িঞা আছে—1027  
 পড়িল—517, 1044  
 পড়িলাহা—981  
 পড়িলাহে—975  
 পড়িশি, -শি—332, 334, 380,  
 406, 496, 510, 550  
 পড়িহার—497  
 পড়িহাস—497  
 পড়ীছা—473, 496, 510  
 পড়ে—133, 315, 319, 497, 499,  
 509, 876  
 প'ড়ে-ই-ছে—1028  
 প'ড়েছেই-প'ড়েছে—1028  
 পড়োল—334  
 প'ড় ল—1044  
 প'ড় শি, -শি—282, 332, 380  
 পঢ়—442  
 পঢ়া—440  
 পঢ়ে—133, 315, 499  
 পণ (= Eng. pound)—647  
 পণ—528  
 পণকিরা—682  
 পণকে—682  
 পণ্ডিতানী—696  
 পণ্ডিতী—673  
 পণ্ডি—396  
 পণ্ডির—503  
 পণ্ডিয়া—882  
 পণ্ডর—376  
 পণ্ডান—363  
 পণ্ড—443  
 পণ্ডাট—449  
 পণ্ডর—709  
 পণ্ডিক—396  
 পণ্ডা—406  
 পণ্ডা—406, 705  
 পণ্ডেবা—305  
 পণ্ডিনি—377  
 পণ্ড—377  
 পণ্ড—200, 373  
 -পণ—511, 797  
 —789  
 পণ্ড—317, 347, 409  
 -পণা—511, 696, 706  
 পণ্ড—604  
 পণ্ড—317, 347, 409, 426,  
 555, 789  
 পণ্ডর—718  
 -পণ্ড—796  
 পণ্ডর—203, 587, 600, 604  
 পণ্ডান—336  
 পণ্ডর—696  
 পণ্ডান—583, 609, 615  
 পণ্ডা—698  
 পণ্ডা—300, 315, 424, 510,  
 557, 804  
 পণ্ডা—424, 509, 699  
 পণ্ডর—285, 315, 668  
 পণ্ডা—332  
 পণ্ড (verb)—199, 452, 874  
 পণ্ড (= prahara)—347, 510  
 পণ্ড (post-position)—312, 313,  
 770  
 পণ্ডান—604, 617  
 পণ্ড—305, 332, 403, 510, 874  
 পণ্ডা—332  
 পণ্ডার—929  
 পণ্ডা—595  
 পণ্ডা—604, 617  
 পণ্ডর—1019  
 পণ্ডিট—396  
 পণ্ডা—334  
 পণ্ড—376, 511, 874, 883  
 পণ্ড—313, 315, 407, 548  
 পণ্ডে—332, 334  
 পণ্ড—303  
 পণ্ডে—334  
 পণ্ডা—1019  
 পণ্ডা—1019  
 পণ্ডা—376  
 পণ্ডা—376  
 পণ্ডা—623, 626, 627  
 পণ্ডা—617  
 পণ্ডে—357  
 পণ্ডা—413  
 পণ্ডা (verbal noun)—1019  
 পণ্ডার—392  
 পণ্ডর—874  
 পণ্ড—300, 332, 509, 540  
 পণ্ড (তে)—770  
 পণ্ডা—334  
 পণ্ডা—575  
 পণ্ডে—617  
 পণ্ড(র)া—647  
 পণ্ডান—595  
 পণ্ডা—302, 315  
 পণ্ডাইরাছে—509  
 পণ্ডা—317  
 পণ্ডান—347  
 পণ্ডা—591, 617  
 পণ্ডে—591  
 পণ্ড—575, 592, 604, 612  
 পণ্ডা—451, 529  
 পণ্ডা—659  
 পণ্ড—384, 510  
 পণ্ডিয়া, পণ্ডিহে—675  
 পণ্ড—511  
 পণ্ড—874  
 পণ্ডা—331, 529  
 পণ্ডা—877  
 পণ্ড—379  
 পণ্ডা, পণ্ডিহে—379  
 পণ্ড—379  
 পণ্ডা—379

পত্নী—379, 903  
 পসে—344  
 পহরী—398  
 পহলওয়ান—595  
 পহিচান—452  
 পহিলে—452  
 পহির—452, 874  
 পহিরে—509  
 পহিলা—557  
 পহ—311, 509, 554  
 পহরী—398  
 পহুতে—357  
 পহেলা—510, 804  
 পহু—311, 509, 554  
 পহু—370, 1036  
 পহু—344  
 পহু—575  
 পহু—199, 452  
 পহু—332, 509  
 পহু—518  
 পা—84, 211, 302, 320, 369, 509  
 পাখন—656  
 পাই—(verb) 422; (noun) 421, 673, 802  
 পাই—915  
 পাইক—194, 345, 385  
 পাইকার—587  
 পাইকাল—383  
 পাইকের—587  
 পাইখানা—587  
 পাইন—520  
 পাইনুত—381  
 পাইয়া—1003  
 পাইয়াছি—509  
 পাইল—299, 379, 386, 957, 984  
 পাইলে—984

পাউক—907  
 পাউব—355, 510, 548  
 পাওন—656  
 পাওনা—657  
 পাও—203, 385, 446, 510, 896, 1034  
 পাকডু—888  
 পাকড়াও—663  
 পাকড়া—701  
 পাকড়ী—446  
 পাকল—698  
 পাকা—456, 956  
 পাকাটা—492  
 পাকাম, পাকামি—667  
 পাকিতেছে—1034  
 পাকিল—331, 677, 957  
 পাকু—907  
 পাকুড়—456  
 পাকে—882  
 পাকো—পাকো—678  
 পাকিছে—1034  
 পাক্যাল—383, 669  
 পাধ—316, 657  
 পাধু—159, 888  
 পাধড়া—691  
 পাখনা—657, 658  
 পাখনার—333  
 পাখা—441  
 পাখাজ, পাখাজু—351  
 পাখাল—474, 1012  
 পাখালি—1012  
 পাখালে—282, 317, 460, 544  
 পাখি—460  
 পাখিকুল—727  
 পাখিরে—732  
 পাখে—771  
 পাখোয়াজ—351  
 পাখ—461

পাখড়ী—446  
 পাখল-পাখা—706  
 পাখলিনী—694, 695  
 পাখলী—672, 694  
 পাড—211, 519  
 পাছে—1026  
 পাছ—305, 404, 771  
 পাছা—473  
 পাছ—771  
 পাছা—883  
 পাছড়া—888  
 পাছরা, পাছরান—771  
 পাছে—771  
 পাডী—475  
 পাড়া—607  
 পাট—490  
 পাটকাটা—492  
 পাটাতন—349  
 পাটয়ালা—670  
 পাটিল—196  
 পাণ—509, 529  
 পাণ্ডা—496  
 পাঠশাল—451  
 পাঠাইল—984  
 পাঠাইলে—984  
 পাঠা—283  
 পাঠান—213  
 পাঠার—317, 493  
 পাঠাইল—984  
 পাঠাইলে—984  
 পাঠাল—984  
 পাঠালে—984  
 পাড়—877  
 পাড়ন—656  
 পাড়া—(= neighbourhood) 179;  
 (= buffalo) 498; (verb) 497  
 পাড়াপাইয়া, পাড়ার্গে—675  
 পাড়ার—877



- পাড়িয়া—387, 532  
 পাড়িয়াছে—389  
 পায়ে—319, 320, 404, 876  
 পাড়তে—387  
 পাণি—666  
 পাতি—301, 602  
 পাতি—1073, 1074  
 পাতিকো—1073  
 পাতিক্ষীয়—449  
 পাতিকি—532, 708  
 পাতিড়া—691  
 পাতিমোড়—1074  
 পাতিমুচি—532  
 পাতিলা—898  
 পাতিলী—695, 698  
 পাতি—659  
 পাতি—1073, 1074  
 পাতি আছে—1027  
 পাতিবুঝা—1073  
 পাতিতে—447  
 পাতিনেড়ে—1073  
 পাতিতড়ি—1074  
 পাতিল—877  
 পাতিলেবু—1073  
 পাতিশা(হ)—604  
 পাতিশিয়াল—1073  
 পাতিহীন—1073  
 পাতির—378  
 পাতি—447  
 পাতিতে—447  
 পাতির—504  
 পাতিরিয়া—542  
 পাতি—606  
 পাতি—853  
 পাতিক-জন—431, 453  
 পাতি—624, 628, 630  
 -পান—305  
 পান (noun)—509, 529  
 পান (a surname)—520  
 পানই—313, 510, 528  
 পান-করান—1033  
 পানকোড়ী—333  
 পান-ফল—333  
 পান—510  
 -পান—696  
 পানান—529  
 পানিতা—380  
 পানিয়া—699  
 পানী—320, 520, 528, 647  
 পানী-ফল—333  
 পানীহাটি—393  
 পান্ডুরা—679  
 -পানে—771  
 পাঞ্চা—332, 381  
 -পাঞ্চ—789  
 পানদী—647  
 পান্দে—699  
 পাণ—509  
 পাণ্ডা—446, 511  
 পাণ্ডী—446, 509, 511  
 পাণনা—65  
 পাণ (verb)—349, 877; (noun)  
 422  
 পাঞ্চানা—587  
 পাঞ্চাল—615  
 পাঞ্চ—533  
 পাঞ্চা—614  
 পাঞ্চিল—379  
 পাণ—312, 379, 901, 1014  
 পাণক-পক্ষে—458  
 পাণক-পক্ষে—458, 654  
 পাণত—654  
 পাণত-পক্ষে—458, 654  
 পাণদী—609  
 পাণা (noun)—350  
 -পাণা—696, 706  
 পাণালী—665  
 পাণিব—463  
 পাণিবান—463  
 পাণিন—463  
 পাণিরা—883  
 পাণুল—186, 308, 398, 540  
 পাণে—320, 877  
 পাণে—932  
 পাণ—347, 639  
 পাণকী—372  
 পাণে—544  
 পাণক—316, 372  
 পাণক—372, 400  
 পাণট—444, 491, 543  
 পাণটাই—661  
 পাণম—544  
 পাণ—316, 372, 543  
 পাণা—543  
 পাণা—283  
 পাণানি—(noun) 544; (verb)  
 1032  
 পাণানো—1032  
 পাণায়—317, 543  
 পাণি—379  
 পাণিত—304  
 পাণিশ—637, 638  
 পাণিস—647  
 পাণো—347  
 পাণোরান—557, 576, 595  
 পাণা—299  
 পাণ—321, 548, 771, 772  
 পাণটা—886  
 পাণা—188  
 পাণুলি—398  
 পাণে—771  
 পাণাত্য—201, 382  
 পাণ-করা, -হওয়া—1051  
 পাণের—548, 1068

পানানো—৪৪৪  
 পাহারানো—৪৪৪  
 পাহাড়—৪৯৬  
 পাহারগুলা—৬৭১  
 পাহারালী—৬৭০  
 পাহন—৩৩৭  
 পাংশা—১৪০  
 পি—৪৭৩  
 পিউ—৪১৭  
 পিউলি—৩২৪, ৩৭৭  
 পিউলী—৩৪৫  
 পিএ—৪১৭  
 পিও—৪১৪  
 পিকদানী—৭০৪  
 পিকলা—৪৪৪  
 পিহল—৩২৪  
 পিচবোট, -বোড—৬৪১, ৬৪৭  
 পিচাশ—৪৫২  
 পিছ—৪০৪  
 পিছমোড়া—৭৭১  
 পিছল—৩২৪, ৩৩৫, ৪৭৩  
 পিছু—৭৭১  
 পিছুনো—৭৭১  
 পিছে—৪০৬, ৭৭১  
 পিছবোট, -বোড—৬৪১, ৬৪৭  
 পিটনা—৬৫৭  
 পিটে—৪৪২  
 পিট—৩২৫, ৩৫৫, ৪৭৩, ৭৭১  
 পিঠমোড়া—৭৭১  
 পিঠা—৩২৫  
 পিঠালি, পিঠুলি—৩০৪  
 পিতল—৩২৫, ৩৩৫, ৫০১, ৫৪৪  
 পিত্তমাতৃহীন—২০১  
 পিতিয়ে—৪০১  
 পিত্তে—৪০১, ৫৫৭  
 পিতিয়ে—৪০১  
 পিখো—৫৫৩  
 পিদিষ—৩৫৭

পিদীম—৫২১, ৫৪১  
 পিদীম—৩৫৭  
 পিনহে—৪৫২  
 পিন্ধ—৩১৩, ৫০৭  
 পিন্ধে—৩২৪  
 পিপা—৬২২, ৬২৫, ৬৩০  
 পিপুল—৩২৫, ৫১০  
 পিপে—৬২২  
 পিবই—৩৪০  
 পিরা—৩২৪, ৫১০  
 পিরার—৬৬৪  
 পিরারী—৩২৪, ৩৪২, ৬৬৪  
 পিরাল—৩২৪, ৪১৭, ৫১০  
 পিরাম—৩০৫  
 পিরে—৩২৪, ৩৪০, ৪১৭, ৫০৭  
 পিরিচ—৫৫১, ৬২৪, ৬২৫, ৬৪১  
 পিরীত, পিরীতি—৩০৪, ৩৭৬  
 পিলখানা—৫৪৪, ৬০৪  
 পিলপিল—৪৭১  
 পিলহুত—৬১৪  
 পিলা—৫৪৪  
 পিলিহা, পিলীহা—৩৭৬, ৫৪৪  
 পিলে—৩৭৬, ৩৭০, ৫৪৪  
 পিলা—৩৭০  
 পিশি—৩২৪  
 পিশি—৩৫৭  
 পিসে—৩২৪  
 পিসতুতা—৫০৩, ৫৫২  
 পিসপাল—২১৫  
 পিসি—৩৪৫, ৫০৭  
 পিসী—৩৫৫, ৫৪৪  
 পিস্ত, -তা—৬০২, ৫০৩  
 পিসে—৬৭৭  
 পিস্তল—৬২২, ৬৩০, ৬৩১  
 পিছে—৭৭১  
 পিট—৬৩৬  
 পিতরে—৭২৬  
 পির—২০৩, ৬০৪, ৬০৭

পিল—৫৪৪  
 পুখা—৫০৭  
 পুইন—৩৪১  
 'পুওর'—৬৪০  
 পুহুর—৩৭৭, ৪০৪, ৫০৭  
 পুহুর—৩২৬, ৩৭৭, ৪৬০  
 পুহুরী—৩২৬  
 পুহু—৪৭৩  
 পুহিহু—৭০৪  
 পুহে—৩২৬, ৩৫৫, ৪৭৩, ৫০৭, ৪৭৫  
 পুট—৬৪৭  
 পুটিং—৬৪৭  
 পুডিং—৬৪৭  
 পুড়—৪৭৪  
 পুড়ি—৩৭৬  
 পুড়িষা, পুড়িকা—৩৭৬  
 পুড়ে—৩২৫, ৪৭৬, ৫১০  
 পুত—(noun) ১৬০, ২৫৫, ৩২৬,  
 ৫০২, ৫০৭, ৭৪১, ৭৬৩, ৭৬৪;  
 (verb) ৪৭৪  
 পুতক—৭৬৫  
 পুতকে—৭৬৪  
 পু(ত)তে, পুতৎ—৭৬৫  
 পুতমি—৭৬৫  
 পু(ত)তর—৭৬৫  
 পুতরে, -রে—৭৬৪  
 পুতাইন—৭৬৫  
 পুতি—৫১০, ৭৪১, ৭৬৩  
 পুতে—৭৪১, ৭৬৩, ৭৬৪, ৭৬৫  
 পুতেকে, পুতেকে—৭৬৪  
 পুতরে, -রে—৭৬৪  
 পুতে—৭৬৪  
 পুতুর—৩৭৭  
 পুখি—১৭৪, ৩৭০, ৫০৪  
 পুখী—১৭৪, ৩২৭, ৩৭৫, ৬৭৩  
 পুন—৫২৪  
 পুনমি—৫৪২  
 পুনঃপুনঃ—৫৫৪



পুনি—381  
 পুনিম—326, 532  
 পুন—381  
 পুরা—509  
 পুরাণ—347, -ন—325  
 পুরুত—399  
 পুরুবে—417  
 পুরুকিত—304  
 পুরাণ—577  
 পুনিম—633, 647  
 পুন্টিশ—647  
 পুরুনী—641  
 পুন্ডি—398  
 পুংপ—377  
 পুন্—873  
 পুন্—509  
 পুন্জারী—668  
 পুন্জা—401  
 পুন্—160  
 পুন্—326  
 পুনিয়া, পুন্বে—417, 676  
 পুন্—540  
 পুন্ব—304  
 পুন্বিয়া—417  
 পুন্—325, 877  
 পুন্—304  
 পুন্কাউজেল—358  
 পুন্জেন—357  
 পুন্—460, 510  
 পুন্গব—587  
 পুন্জাপ—473  
 পুন্—771  
 পুন্নো—771  
 পুন্—771, 883  
 পুন্নো—771  
 পুন্জাম, -নি—667  
 পুন্ট—328, 411, 490, 500, 510  
 পুন্ডরা—702

পেটা—491  
 পেটুক—704  
 পেটেলী—670  
 পেটোটি, পেটুটি—687  
 পেটুপেটু—411  
 পেড়ে—387  
 পেড়েছে, পেড়াছে—389  
 পেট লেন—647  
 পেতি—1074  
 পেতি-কোয়া—1074  
 পেতি-মেহুর—1074  
 পেতুনী—332, 696  
 পেনেটা—393  
 পেনো—679  
 পেয়াব—632  
 পেন—328, 510  
 পেয়—804  
 পেয়ালা—584  
 পেয়ালা—412, 625, 630  
 পেয়ারী—324  
 পেয়ালা—580, 584, 614  
 পেয়ে—1003  
 পেয়—624, 627, 630  
 পেয়েক—624, 626, 629  
 পেয়েত—377  
 পেয়ে—883  
 পেলে—984, 985  
 পেলে—159, 328, 386, 438,  
 510, 512, 543, 984, 1003  
 পেলেগ—640  
 পেলায়—405  
 পেশ—585  
 পেশবাজ—616  
 পেশা—585, 612  
 পেশোয়াজ—616  
 পেহনো—884  
 পেঠা—344  
 পেতা—344

পৈখান—343, 345, 504  
 পৈল—517, 1044  
 পৈশে—384  
 পৈশী—379  
 পৈহ—379  
 পো—255, 698, 802  
 পোখা—802  
 পোখাতী—663  
 পোক, পোকা—510  
 পোজ—593, 599  
 পোখিরি—327, -রী—326  
 পোড়ন—656  
 পোড়নী—658  
 পোড়া—956  
 পোড়াবাড়ী—65  
 পোড়ে—396  
 পোড়েক—990  
 পোশ—319  
 পোখা—327, 329, 395, 673  
 পোখী—329  
 পোখ—372  
 পোখার—586  
 পোয়া—330, 427, 698, 802  
 পোহাতী—663  
 পোয়াল—544  
 পোয়ামিট—396  
 পোলা—329, 509, 544, 698  
 পোলাও—577, 604, 617  
 পোলিন—633  
 পোব—329  
 পোকের—392, 541  
 পোষ্টাই—662  
 পোস্ত—398  
 পোস্তা—581  
 পোহা—874  
 পোহাতী—663  
 পোহার—554  
 পোহাল—544

পোহা'ল—319  
 পোনে—427, 509, 808  
 পটুয়া—375, 520  
 পট—789  
 পটাত্তর—555  
 পটিশ—317  
 পটিশ—808  
 পয়—424, 789  
 পয়তালিশ—796  
 পয়ত্রিশ—331, 792  
 পয়বটি—789, 798  
 পহু—554  
 পহুচে—472  
 পা (ই) ত—674  
 পাই পাই—422  
 পাউ—624  
 পাউরুটি—630  
 পাণ্ড—624  
 পাক—362, 456  
 পাককাঠি—492  
 পাকাটি—492, 664  
 পাকাল—322, 669  
 পাচ—360, 362, 471, 788  
 পাচই—303, 372, 512  
 পাচগোত্র—451  
 পাচনবাড়ী—446, 471  
 পাচপন—789, 797  
 পাচমুড়া—788  
 পাচশ—451, 800  
 পাচসাত—451  
 পাচহাতী—788  
 পাচালী—336  
 পাটাল—247, 258, 337, 370,  
 470, 510, 536, 543  
 পাচু—677  
 পাচুই—512, 806  
 পাচে—464  
 পাজর—335, 364, 475

পাজা—808, 617  
 পাজি, -জী—446, 364  
 পাঠা—493  
 পাড়—365, 498  
 পাড়ে—496  
 পাত—308  
 পাত্তি—362, 501, 652, 674  
 পাপড়, -র—647  
 পাশ—310, 362  
 পাশুটা, -টে—685, 686  
 পিঙ্গ—873, 878  
 পিঙ্গরা—364, 475  
 পিঙ্গে—324  
 পিড়া—365  
 পিধে—324  
 পিপড়া—370, 510  
 পিপড়া—510  
 পিপীড়া—332  
 পিপড়া—332  
 পিহাজ—504  
 পুঁই—325, 428, 682  
 পুঁটকে—682  
 পুঁটি, -টা—370, 510, 682  
 পুঁটীমাছ—509  
 পুঁটি, -জী—493, 510  
 পুঁড়—62, 326, 365, 496  
 পুঁড়ো—62  
 পুঁত—878  
 পুঁতি—301  
 পুঁথি—194, 369, 370, 504,  
 673  
 পুঁচ—411, 601, 608  
 পুঁচা—328, 370, 411, 470  
 পুঁচানো—665  
 পুঁচাল—669  
 পুঁচড়া, -রা—541, 691

পেটরাবল, -দ্বি—708  
 পেড়া—328, 370, 496  
 পেপে—371, 623, 625, 630  
 পেহাজ—420, 584, 608  
 পোষার—319, 372, 519, 521,  
 540  
 পোছ—362, 530, 874  
 পোছে—510  
 পোটা—510  
 পোছ—370  
 পোছ—344  
 প্যাটুপ্যাটু—411  
 প্যাদা—584  
 প্যাররা—412, 625  
 প্যারলা—614  
 প্যারা—625  
 প্যারী—324, 342  
 প্যারা—412, 584  
 প্রণম—879  
 প্রণমহো, প্রণমহ—932  
 প্রণাম—357  
 প্রতিবিধিংস—884  
 প্রত্যক—382  
 প্রথক—357  
 প্রথম—505  
 প্রদীপ—357  
 প্রবোধ—357  
 প্রভৃতি—357  
 প্রমাণ-সহি—709  
 প্রমারা—625, 626  
 প্রহ—304  
 প্রাচিং—350  
 প্রাচিতির—350  
 প্রাচীর—217  
 প্রিতি—358  
 প্রিয়াবেলাইট—217  
 প্রেক—624, 626  
 প্রেত—411



প্রতিদী—695  
 প্রেমার—625, 626  
 প্রোটোপ্রাক্তন—217  
 প্রট—217  
 প্রভো(ন্)—641  
 প্রিটোলিন—217  
 পাল্ল—584, 608

ফ—135, 272, 442, 511, 605,  
 629, 643  
 ফকির—605  
 ফকীর—204  
 ফচকেমি, ফচকাম—667  
 ফজল—604  
 ফটক—679  
 ফটকা—681  
 ফটা—527  
 ফটিক—303, 512  
 ফটো—400, 640  
 ফটোগেরাপ—640, 647  
 ফটুকিরি—402  
 ফটুকে—333  
 ফড়িঙ্গ—335, 497, 512  
 ফড়িং—335, 438, 488  
 ফড়িঙ্গা, ফাড়ে—512  
 ফণ—305  
 ফণা—528  
 ফজুই—575  
 ফতে—203, 575, 592, 596  
 ফতেহাবাজ—604  
 ফতেহ্—592  
 ফদল—604  
 ফনি—440  
 ফহতা—617  
 ফরসলা—587  
 ফরকা—540  
 ফরহা—512  
 ফরফরা—591

ফরমা—630  
 ফরমাইব—591  
 ফরমাণ—523  
 ফরমায়—591  
 ফরশা—512  
 ফরসা—699  
 ফরাক—605  
 ফরাস, ফরাসী—215  
 ফরাসীস—627, 632  
 ফরিদাব—603, 605, 615  
 ফর্দ—593, 603  
 ফর্দা—622, 626  
 ফর্দান—605  
 ফল—315, 511, 584  
 ফলঙ্গ—212  
 ফলসা—584  
 ফলা—511  
 ফলাবা—605  
 ফলার—315, 511  
 ফসকা—886  
 ফসল—605  
 ফস্—512  
 ফস্কা—512, 584  
 ফস্ত—593, 603  
 ফাইন—639  
 ফাউ—512  
 ফাউগ—383  
 ফাউড—512  
 ফাউড়া—514  
 ফাউল—639  
 ফাপ—310, 462, 511  
 ফাপ্ত—383  
 ফাপ্তন—462, 511  
 ফাজিল—580  
 ফাট—573, 596  
 ফাটক—679  
 ফাটফুট—896

ফাটল—698  
 ফাটে—491, 512  
 ফাড়ে—496, 512, 577  
 ফাতা—512  
 ফানুস—605  
 ফারহা—588  
 ফারহ—641  
 ফারসী—609  
 ফারাক—605  
 ফাফা—512  
 ফাল—452, 511, 512  
 ফালাও—664  
 ফালুতো—512  
 ফি—713  
 ফিউচারিজম—217  
 ফিকর—629  
 ফিকা—512  
 ফিকির—592  
 ফিকুবাখা—512  
 ফিগু—622, 625, 627, 629  
 ফিঙ্গা—512  
 ফিচল(টি)ম, -লামি, -লিমি—667  
 ফি-জন—713  
 ফিজিল—217  
 ফিট—647  
 ফিটকিরি—406  
 ফিটন—647  
 ফিটকিরি—402  
 ফিতা—625, 629, 631  
 ফিতে—401, 629  
 ফিত্ত—629  
 ফির—512, 578  
 ফিরহী—583  
 ফিরতী—654  
 ফিরলে—1003  
 ফিরাদী—583  
 ফিরি—1013

কিরিদি—583, 605, 607

কিরিপি—593, 595

কিরে—412

কিরেদা—583

কিরোজা—584, 605

কি-লোক—713

কিলুহাল—610

কি-হাত—713

কিহিরিপি—595

কু—511

কুইটে—381

কুক—680, 801

কুকরা—880

কুকরে—159, 438

কুদী—197

কুট (=foot)—630

কুট (verb)—873

কুটখ—999

কুটিত—957

কুটিতে—381

কুটিল—957

কুটে—326, 356, 491, 512

কুটেতে—381

কুড়ে—325

কুরসং—581, 612

কুস্তি—512

কুল—511

কুল-আখড়াই—714

কুলখুরি—481

কুল-বাবু—714

কুলম্পেড়ে—532

কুলুট—377, 647

কুলুড়ি—691

কুসলা—889

কুইল—639, 647

কুউ—421, 512, 542

কুকা—512

কুটিন, কুটিং—647

কেন—411

কেনা—411, 511

কেরত—654

কেরার—809

কেরি—1013

কেরে—412

কেরেব—577, 595

কেরো—512

কেল—639, 647

কেল-করা, -হওয়া—1051

কেলে—159, 328, 411, 438,

510, 512, 543

কেসাদ—577

কেস্তা—629

কেজব—617

কেভুন—335, 656

কেড়া—329, 512

কেড়ে—496

কেয়ারা—589, 605

কেস্কা—691

কেজ—587, 605

কেং—587

কেক—405

কেকাসিমা—700

কেকি—370, 511

কেড়—365, 496, 511

কেড়া—498, 512

কেড়ানার—708

কেদ—366

কেদল—698

কেপ—405

কেগর, কেবর—512

কেস—370, 438, 512

কেসাদ—577

কেস্কা—512

কেস্কে—687

কেতে—629

ক—646

ক ক—680

ক দিল—627, 628, 629

ক পি—440

কেকানে—700

কেসাদ—577, 608

কেসো—512

কেকর—405

কেপরা—405

কেপল—405

কেসা—891

কাচ, কাচি—412

কাশানি—647

কুট—647

ব—272, 340, 443, 615, 631,

643, 644

ব—534, 586, 988

বই—(verb) 425, 926 ; (post-position) 772, 1075

বইয়া—513

বইন—308

বইয়াম—624, 625

বইস—384, 874

বইসে—313, 383, 513

বইসেতে—384

বইচি—482, -চী—334, 361

বউ—310, 315, 344, 385, 397,

513, 554

বউক—427

বউল—301, 385

বএল—424

বক—457

বকরা—513, 659

বকরীদ—575

বকশী—213

বকশীশ—585

বকা-বকা—478

বকিয়া, বকে বাওয়া—1052



- বকেরা—575, 599  
 ব'ক—427  
 বক্তিতার—599  
 বকী—542  
 বক্‌সিস—599  
 বখশীশ—613, 618  
 বখা—460, 586  
 বখেরা—575, 599, 615  
 বখ'শীশ—599  
 বখ—445  
 বগররা—587, 615  
 বগল—577, 600  
 বগলস—647  
 বগী—647  
 বগুড়া—66  
 বকিমা—705  
 বঙ্গভাষা—149  
 বঙ্গা—197  
 বচন—468, 470  
 বচ্ছর—471  
 বছরকার—755  
 বজবজা—591  
 বজর—376  
 বজ্রা—575  
 বজ্রর—376  
 বজ্রাং—603  
 বজ্র—476  
 বটে—95, 318, 319, 573, 1035,  
 1042, 1043  
 বটি—932, 1043  
 বটিম্—1043  
 বটে—319, 1042, 1043  
 বটেন—1043  
 বটিয়া—946  
 বডি—647  
 বড়—(noun) 355 ; (adjective)  
 422, 496  
 বড়কী—682  
 বড়-বরানা—707  
 বড়-ঠাকুর—450  
 বড়হ—705  
 বড়-বান্দী, -মা'মুখী—673  
 বড়শী—332  
 বড়াই—422, 661  
 বড়াম্, বড়াং—667  
 বড়ী—496  
 বড়—677  
 বক্তিরিশ—786  
 বড়ীস—336, 796  
 বত্রিশ—786, 796  
 বৎসর—200  
 বৎসকের—759  
 বচ—713  
 বদ—879  
 বচ-গন্ধ—713  
 বদতি—933  
 বদনা—443  
 বদরাগী—713  
 বদরীত—713  
 বদল—602  
 বদলা—884  
 বধনা—318, 331, 443, 507  
 বন—315, 320  
 বনওয়ারী—521, 671  
 বনাও—664  
 বনারলী—403, 513, 672  
 ব'নিহি—572  
 বনিবনা, বনিবনাও—664  
 ব'নেহি—572  
 -বন্ত—697  
 -বন্দ—708  
 বন্দ—879  
 বন্দবস্ত—586  
 বন্দম—932  
 বন্দর—660  
 -বন্দি—708  
 বন্দি—696  
 বন্দুক—575, 602  
 বন্দো—932  
 বন্দোবস্ত—586  
 বন্দো—932  
 বরনা—541  
 বহ—(verb) 424, 513, 554 ;  
 (noun) 586 (Persian),  
 640 (English)  
 বরড়া—180, 324, 403, 424  
 বহন—416, 424, 533  
 বরা—622, 625, 626, 627  
 বরান—336, 342, 405  
 বরাম—624, 625  
 বহর—219  
 ব'হে—772  
 বহেত—587  
 বহেন—602  
 বর—873  
 বরকলাজ—575  
 বরখাস্ত—600  
 বরগা—449, 622, 627, 629,  
 631  
 বরগী—196, 583, 618  
 বরছা—473  
 বরণ—883  
 বরদাস্ত—593, 602, 612  
 বরগী—606  
 বরক—396, 592, 606  
 বরকী—396, 606  
 বরাবর—604  
 বরবাব—604  
 বরা—557  
 বরাং—602  
 বরাখ—350  
 বরাহি—557  
 বরিখন—461  
 বরিখে—461

- বরিষা—376  
 বরেন—334  
 বর্ণা—627  
 বর্ণা—196, 609  
 বর্ষ—879  
 বর্ষাইন—647  
 বর্জিত—304  
 বর্জিল (= *Virgil*)—643  
 বর্টন (= *Burton*)—638  
 বর্ণাকুলার—644  
 বর্ষ—879  
 বর্জিয়া, ব'র্জ-বাওয়া—879  
 বরনগর—299  
 বরনা—334  
 বল—320, 899  
 বলটিন ডুবাল (= *Valentin Duval*)—644  
 বলতবা—705  
 ব'লভেম—392  
 বলবাম—422  
 বলশেভিক—197  
 বলাই—422, 662  
 বলাইয়া—394  
 বলাবলি—1048  
 বলিতাম—392  
 বলিতেছেন—725  
 বলিবামাত্র—1017  
 বলিবার—1018  
 বলিয়া—177, 392  
 বলিয়া, ব'লে-ফেলা—1052  
 বলিয়ে—394, 675  
 ব'লিয়ে—394  
 বলিলাই—987  
 বলিলাম—392  
 বলিস্ নাহি—401  
 বলিস্ না—401  
 বলিস্নি—402  
 বলিস্নে—401  
 বলু—677  
 বলে—403, 513, 876, 933  
 ব'লে, বলে—392  
 বলে—932  
 ব'লেয়ার (= *Voltaire*)—644  
 বল্যা, বলো—392  
 ব'লুল—684  
 বল্লম—595  
 ব'লুলে—984  
 ব'লুলেম—392  
 বষ্টম—399  
 বষ্টমী—673  
 বষ্টম—399, 521, 527, 531  
 বষ্টমী—673  
 বস—873, 874  
 ব'স—416  
 বসতি—933  
 বসিঈ-আছেলু—1027  
 বসিঈ-খাক—1028  
 বসিছলু—1024  
 বসিতে—384  
 বসিতে, ব'সতে বেওয়া—1051  
 বসিয়া (ব'সে) খাকা, রহা  
 (বেওয়া)—1052  
 বসিয়া-পড়া—1050, 1052  
 বসিয়া-বাওয়া—1052  
 বসে—313, 344, 513, 933  
 বস্—384  
 বস্কীস্—618  
 বস্তা—604, 612  
 বস্ত্র—383  
 বহ—873, 1045  
 বহকা—460, 886  
 বহড়া—180, 334  
 বহতা—654  
 বহর—575, 592, 595, 604  
 বহস—594  
 বহারী—384  
 বহাল—594  
 বহি—772, 1075  
 বহিত—337  
 বহিন—315, 452, 514  
 বহিব—1039  
 বহিতে—988  
 বহিয়া—772  
 বহী—772, 1075  
 বহ—668  
 বহক—427  
 বহড়া—337, 691  
 বহত—502, 554  
 বহতর—708  
 বহয়ারী—668  
 বহয়ের—719  
 বহর—719  
 বহশঃ—558  
 বহে—513, 554  
 বহেড়া—497, 513, 554  
 বা—302, 320, 513  
 বা- —766  
 বাই—406, 422  
 বাইকোট (= *viscount*)—643  
 বাইগণ—320, 383, 399  
 বাইগণিয়া—394  
 বাইগণিয়া—674  
 বাইচ, -ছ—437, 471  
 বাইছা—393  
 বাইতি—663  
 বাইয়া—389  
 বাইর—350, 379, 385, 386,  
 422  
 বাইয়াইল—389  
 বাইরান—386  
 বাইরে—772  
 বাইশ—342, 363, 385, 415,  
 513, 786  
 বাইস—416



- বাইন মাদ—639, 647  
 বাইন-মান—639  
 বাইসর(ী)র—644  
 বাইসিকিল—639, 641  
 বার—360  
 বার বিয়া—384  
 বাউ—310, 423  
 বাউরী—514  
 বাউরী-চুল—514  
 বাউল—342, 423, 513  
 বাএ—320  
 বাও—259, 302, 342, 423  
 বাওলা—423, 889  
 বাকী—542, 597, 604  
 বাজ—305, 453, 637, 638,  
 641, 647  
 বাজবন্দ, -ন্দি—708  
 বাধান—283, 317, 321, 335,  
 459, 513  
 বাধানে—882  
 বাধ—462, 600  
 বাধড়া—462, 514, 691  
 বাধড়ী—74, 181  
 বাধদী—449  
 বাধান—600, 617, 707  
 বাধার—669  
 বাধিচা—600, 604, 706  
 বাধন—152, 320  
 বাধোয়ান—617, 707  
 বাগ্যান—383  
 বাধ—321, 443, 463, 513  
 বাধবন্দী—449  
 বাধা—659  
 বাধিনী—695  
 বাঙলা—609  
 বাঙাল—363, 669  
 বাঙালী—670, 678  
 বাখুর—460  
 বাঙ্গলা—149, 332  
 বাঙ্গলি—363  
 বাঙ্গলা—149, 669  
 বাঙ্গালিনী—694  
 বাঙ্গালী—336, 670  
 বাঙ্গালনী—694  
 বাঙলা—149  
 বাঢ়াল—669  
 বাছ—878  
 বাছা—473, 697  
 বাছাই—661  
 বাছিয়া—393  
 বাছুর—352, 381, 473, 697  
 বাছুর-সহ—706  
 বাছা—393  
 বাজ—316, 475, 513, 613  
 -বাজ—709  
 বাজন—657  
 বাজন—656, 657  
 বাজনদার, -বারিরা—708  
 বাজা—475  
 বাজা—475  
 বাজাএ—283  
 বাজিএ—675  
 বাজী—584  
 -বাৰী—709  
 বাজীকর, বাজীগর—707  
 বাজু—583  
 বাজুনবেরে—708  
 বাজে—321, 882, 919  
 বাজেরাঙ—606  
 বাজের—695  
 বাজেশ—431  
 বাট—491  
 বাটনা—657  
 বাটপাড়—689  
 বাটুরা—381, 679  
 বাটে—319, 877  
 বাটোহাড়—689  
 বাটুটে, বাটুটা—1065  
 বাড়ই—308, 316, 672  
 বাড়তি—655  
 বাড়ন—500, 656  
 বাড়ন্ত—653  
 বাড়ী—307, 496  
 বাড়ীখানা—670  
 বাড়ীখানী—670, 671  
 বাড়ীউলী—670  
 বাড়ুই—316, 500, 672  
 বাড়ু—499  
 বাঢ়ই—500  
 বাঢ়ন—500  
 বাঢ়ন্ত—653  
 বাঢ়াএ—283  
 বাঢ়িলাহৌ—975  
 বাঢ়ে—442, 499  
 বাণ—513  
 বাণান—523, 529  
 বাণিজার—337, 475, 668  
 বাণোল—628  
 বাত—305, 321, 652  
 বাতলা—889  
 বাতলান—1033  
 বাতান—503  
 বাতি—502, বাতী—673  
 বাধান—504  
 বাধ—578, 603  
 বাধ-বাধে—451  
 বাধল—506, 699  
 বাধলা—331, 698  
 বাধলিহা—394  
 বাধশা—604  
 বাধাব—576  
 বাধিহা—340  
 বাধুলে—394  
 বান—305, 513, 529

বানাই—662  
 বানান—529  
 বানিয়া—315, 337, 674  
 বানী—196, 662  
 বান্বে—366  
 বান্ধা—579, 604  
 বান্ধা নিছে—1016  
 বাপ—510  
 বাপকে—251  
 বাপত—751  
 বাপু—446  
 বাপুত—736  
 বাপ্তা—606  
 বাপ্তাইজিত—704  
 বাব—605  
 বাবর—602  
 বাবরচী—616  
 বাবলা—513  
 বাবু—446  
 বাবুগিরি—707  
 বাবুতে—719  
 বাবুয়ানা—707  
 বাবুয়ানী—704  
 বাবুয়ে—719  
 বাবুয়চী—616  
 বাবুচী—213  
 বাবুল—513  
 বাবলা—333  
 বামন—399, 513, 516, 531  
 বামনা—659  
 বামনাই—661  
 বামনী—673  
 বানী—695  
 বামুন—321, 367, 399, 513, 516, 531  
 বামুনহ—705  
 বাহ—254, 259, 302, 342, 345, 422 ; (verb) 422, 423, 877

বায়না—587, 590, 595  
 বায়ল—614  
 বায়ল—389  
 বায়—347, 350, 385, 386, 422  
 বায় (twelve)—441, 513, 540, 555, 772  
 বায়ই—672  
 বায়ইপাড়া—188  
 বায় + ইয়ার—427  
 বায়-উয়ারী—325, 668  
 বায়হ—441  
 বায়ি—379  
 বায়ই—672  
 বায়দ—586, 603  
 বায়শ—215  
 বায়ে—877  
 বায়েয়ারী—325, 426  
 বায়িশ—643, 647  
 বায়ক—600  
 বায়তি—692  
 বায়তি, বায়নি—624, 628  
 বায়লা—889  
 বালা—513  
 বালাই—588, 593  
 বালাপোষ—613  
 বালি—153  
 বালী—307  
 বালুটে—65, 186  
 বালুতি—623, 627  
 বালুনি—623  
 বাশ—385  
 বাষটি—793  
 বাষ্পকট—216  
 বা'স—416  
 বাস—898, 899  
 বাসর—282, 321, 347, 550, 553  
 বাসহর—553

বালা—899  
 বাসিড়িয়া, -ড়ে—687  
 বাসিএ—632  
 বাসোরা—219, 1069  
 বাস—453, 641, 647  
 বাহ—310, 513, 554  
 বাহড—333  
 বাহান্তর—555, 798  
 বাহাদুর—213, 576, 604  
 বাহানা—595  
 বাহার—341, 789, 797  
 বাহার—576  
 বাহাল—594  
 বাহিয়া—359  
 বাহিবারে—1018  
 বাহির—337, 379, 385, 513, 554, 772  
 বাহিরাইল—389  
 বাহিরান—386  
 বাহিরে—772  
 বাহড—333  
 বাহড়ে—496, 553  
 বাহে—877  
 বাহ—200, 482  
 বাংলা—149, 669  
 বি—406, 712, 713, 786  
 বিয়া—678  
 বিউনি—399, -নী—419, 468  
 বিউলা—341  
 বিউলি—399, -নী—342  
 বিক—874  
 বিকশ—712  
 বিকলী—695  
 বিকাল—712  
 বিকি—456  
 বিকিকিনি—456  
 বিটোরিয়া—644  
 বিগড়া—462



- বিষং—439, 463  
 বিচালি—471  
 বিচি—446, 513  
 বিছনা—477  
 বিছা—325, 355, 473  
 বিছানা—325, 471, 473, 477  
 বিছোহ—337  
 বিজলী—247, 406, 468, 475  
 বিজন্মা—712  
 বিজলী—333, 475, 698  
 বিজুরী—698  
 বিজুলী—333, 475, 698  
 বিজ্ঞ—304, 373  
 বিটলা—325, বিটলা—491  
 বিভূবিড়া—591  
 বিভপণী—695  
 বিতিকিচ্ছি—402, 503  
 বিদগধ—376  
 বিদায়—596, 616  
 বিদোহ—304  
 বিধেয়—304  
 বিনতি—325, 502, 528, 655  
 বিনা—772, 777  
 বিনান—529  
 বিনি—530, 772  
 বিনি যাচিলে—1017  
 বিনুকী—529  
 বিনে—400, 772  
 বিনোদিয়া—417  
 বিন্তি—624  
 বিন্তি—625, 630, 631  
 বিন্সেট (= Vincent)—644  
 বিপনে—333  
 বিবাহ—304  
 বিবি—213  
 বিবুধি—712  
 বিভল—325, 516  
 বিভা—302, 440  
 বিভো—653  
 বিন্মিধ—376  
 বিন্মিন্ন—605, 619  
 বিন্নলী—342  
 বিন্না—302, 304, 416, 440, 513  
 বিন্নার—640  
 বিন্নান্নিধ—786, 796  
 বিন্নান্নিস—406, 417, 468  
 বিয়ে—416  
 বিন্নোগ—418, 477  
 বিন্নোড়—712  
 বিন্নানই—542, 800  
 বিন্নানকই—542, 799  
 বিন্নাশি—786, -শী—542, 799  
 বিন্নিশি—799  
 বিন্নেই—799  
 বিল—513  
 বিলা—892  
 বিলাত—583, 590, 602  
 বিলাত-কোরত, -কোরত—654  
 বিলাতি—398, -তী—583  
 বিলাৎ—614, 616  
 বিলিতি—141, 398, 583  
 বিলেত—401, 583  
 বিলেতি—398  
 বিশ—363, 513, 794  
 বিশেষ—800  
 বিশাস—401  
 বিশা—883  
 বিশাইল—957, 1033  
 বিষ্ট—527  
 বিসরে—513, 548  
 বিষ্টবিসস (= Vesuvius)—643  
 বিষ্টট—625, 626, 627, 631  
 বিষ্টরণ—373  
 বিষ্ট্রিগী—695  
 বিষ্ট্র—712  
 বিহনে—772  
 বিহরাম—555  
 বিহা—878  
 বিহান—336, 554  
 বিহি—324  
 বিহিত—304  
 বিহলা—341  
 বীড়া—324  
 বীড়া-বাড়ন—500  
 বীবর—644, 647  
 বীমা—206, 584  
 বীধ—540  
 বীরত্ব—304, 447  
 বীরা, বীর্য—534  
 বীস—302, 548  
 বুইক্কে—381  
 বুইন—308, 440  
 বুইল—984  
 বুইলে—984  
 বুওর (= Eng. boor)—640  
 বুক—457  
 বুসই—700  
 বুজ—513  
 বুজতে—443, বুজতে—477  
 বুজক—582, 598, 618  
 বুজক—598  
 বুঝ—114, 873  
 বুঝতে—451  
 বুঝাইয়া (বুঝিয়ে)-বোঝা—1052  
 বুঝিতে—381, 443, 451, 477  
 বুঝে—326, 461, 513, 875  
 বুঝে-বুঝে—1048  
 বুঝতে—381, 477  
 বুড়—347, 495, 878  
 বুড়কে—682  
 বুড়ম—607  
 বুড়া—326, 355, 500  
 বুড়াম, বুড়ানি—687

বুড়ি—496  
 বুড়িকিরা—682  
 বুড়ী (= a number) —182  
 বুড়ী (= old woman)—672  
 বুড়া—355, 442, 500  
 বুৎ—203  
 বুধি—507  
 বুধী—513  
 বুধি—716, বুধে, বুধের—716  
 বুদ—308, 440  
 বুনিয়াদ—603, 615  
 বুহুই, বুহুই—800  
 বুহর (= Eng. boor)—640  
 বুয়িল—984  
 বুয়োর (= Eng. boor)—640  
 বুজ—203, 559, 581, 593,  
 601  
 বুজ—640, 647  
 বুজ—873  
 বুজগারিরা (= Bulgaria)—641  
 বুজবুল—581, 604  
 বুজি—1013  
 বুজিছে—1024  
 বুজী—673, 1013  
 বুজু—647  
 বুজিত—337, 407, 502  
 বুজিনি—407  
 বুটেন—358  
 বুলাবনী—672  
 বুজ—304  
 বুজপতি—452  
 বু—(noun) 416, 513, 585;  
 (prefix) 712, 713, 786  
 বৈ—199, 420  
 বৈডু—421, 496  
 বৈগুরা—421, 513  
 বৈকু—376  
 বৈকু—572, 606, 617

বৈগম—213  
 বৈগর—587, 777  
 বৈগুন—152, 320  
 বৈগুনি—671  
 বৈগুনে—394, 674  
 বৈগু—409, 411, 514  
 বৈগু—409  
 বৈগু—658  
 বৈচার—579  
 বৈচাল—713  
 বৈচে—471  
 বৈছে—393  
 বৈজ—328, 475  
 বৈজ্ঞ—712  
 বৈজ—216, 641, 647  
 বৈটা—328, 411, 491  
 বৈটাইন, টাইন—713  
 বৈটো—491, 679  
 বৈঠন—493  
 বৈঠ—513  
 বৈঠা—328, 499  
 বৈঠা—499  
 বৈঠিলের—995  
 বৈঠ—327  
 বৈঠ—328, 502  
 বৈঠু—299  
 বৈঠা—351  
 বৈঠে—340  
 বৈঠ—352  
 বৈঠা—525, 542  
 বৈঠারী—672  
 বৈঠিরা—390  
 বৈঠে—337, 390, 674  
 বৈঠোরী—521  
 বৈঠন—1069  
 বৈঠা—351  
 বৈঠাক—591, 597  
 বৈঠার—351, 440

বৈঠা—619  
 বৈঠাই—199, 328, 412, 420  
 বৈঠা—462, 496, 714  
 বৈঠান—308, 694  
 বৈঠা—412  
 বৈঠারান—584  
 বৈঠা—412, 622, 625, 627  
 বৈঠালিশ—786  
 বৈঠে—389  
 বৈঠ—350, 386, 422, 772  
 বৈঠিক—713  
 বৈঠাইল—389  
 বৈঠার—604  
 বৈঠাল—336, 540  
 বৈঠে—444  
 বৈঠো—386  
 বৈঠল, বৈঠো—389  
 বৈঠা—624, 628, 631  
 বৈঠ—327, 513, 544, 716  
 বৈঠা—411, 716  
 বৈঠ—716  
 বৈঠে—716  
 বৈঠোরী—647  
 বৈঠোরী—580, 588, 591,  
 604  
 বৈঠ—411, 585  
 বৈঠা—446, 548  
 বৈঠা—446  
 বৈঠালি—623, 630, 631  
 বৈঠ, বৈঠ—542  
 বৈঠাই—199, 328, 412, 420,  
 672, 694  
 বৈঠ(ই)ন—808, 694  
 বৈঠা—713  
 বৈঠারি—361  
 বৈঠা—622, 625, 629  
 বৈঠাগা—736  
 বৈঠা—341



- বেহেড—713  
 বেইশ, বেইশ—594  
 বৈষ্ণব—457, 680  
 বৈষ্ণবানা—707  
 বৈঠকী—681  
 বৈঠা—946  
 বৈয়াম—624, 625  
 বৈরী—425  
 বৈসে—313, 344  
 বো—586  
 বোইসে—384  
 বোউল—385  
 বোগদাদ—577  
 বোঙ্গা—197  
 বোঝা—413  
 বোট—640  
 বোড—642  
 বোড়া—329, 496  
 বোতল—400, 622, 625, 626, 630  
 বোতাঙ—522  
 বোতাম—522, 624, 626, 627  
 বোৎ—203  
 বোন—308, 440, 452, 514  
 বোনাই—300, 309  
 বোনেব—602, 615  
 বোম—215  
 বোমা—622, 626, 627  
 বোম্বাটিকা—625  
 বোম্বোট—625, 626  
 বোম্ব—586  
 বোয়াল—320  
 বোর—343  
 বোরঙ্গ—516  
 বোল—301, 385, 513, 552, 573, 1013  
 বোলই—309  
 বোলতা—503  
 বোলিয়ে—394  
 বোলে—392, 513, 576  
 বোস—431  
 বোসলা—684  
 বোসতে—384  
 বোহিত—337, 502  
 বো—310, 315, 385, 554  
 বোল—385  
 বোহারী—345, 384, 440, 513, 608  
 বইচী—361, 556  
 বইচি, বইচী—513  
 বড়শী—496  
 বঁধু—311, 362  
 বা—513, 520  
 বাই বাই—422  
 বাঁক—554  
 বাউনী—423  
 বাঁও—513, 520  
 বাঁক—513, 554  
 বাঁকা—322, 456  
 বাঁকড়া—66, 687  
 বাঁকে—882  
 বাঁচ—573, 578  
 বাঁচতে, বাঁচিতে—477  
 বাঁচোরা—664  
 বাঁক—305  
 বাঁকা—312, 364, 452  
 বাঁট—355, 362, 491, 573  
 বাঁটুল—370, 491  
 বাঁটে—491  
 বাঁস্তে—366  
 বাঁদর—306, 506  
 বাঁদরাম, বাঁদরামি—667  
 বাঁদী—366  
 বাঁদতে—366  
 বাঁধ—362, 366, 443, 507, 513, 573  
 বাঁধন—335, 656  
 বাঁধা—362  
 বাঁধাই—661  
 বাঁধা—283  
 বাঁধায়—350, 352  
 বাঁধিতে—366  
 বাঁধলী—337, 352, 361, 698  
 বাঁধে—575  
 বাঁশ—362, 547, 549  
 বাঁশরী—691  
 বাঁহক—554  
 বিধ—507, 573  
 বিধন—656  
 -বিধ—531, 987  
 বিজ—513  
 বিধ—326, 365, 399, 407, 513  
 বৈকা—322  
 বৈচে-ব'চে—879  
 বৈধন—656  
 -বৈ—531, 987  
 বৈচ—482, 556  
 বৈচকা—213, 453, 581, 600, 608, 618  
 বৈচী—352, 356, 491  
 ব্যক্ত—410  
 ব্যক্তি—410  
 ব্যঙ্গ—462  
 ব্যতীত—410  
 ব্যথার ব্যথী—410  
 ব্যক্তি—410  
 ব্যাই—199, 420  
 ব্যাখ্যা—458  
 ব্যাখ্যাত—364  
 ব্যাখ্যাতা—431  
 ব্যায়—462  
 ব্যাৎ—409  
 ব্যাটনল—632  
 ব্যাটনল—532, 647

ব্যাঙল—628  
 ব্যান—554  
 ব্যামো—353  
 ব্যাহরা—412  
 ব্যাহরাশ—584  
 ব্যাহলা—412, 625  
 ব্যাহা—584  
 ব্যালট—217  
 ব্যালা—412  
 ব্যালিশ—786  
 ব্যাকা—322  
 ব্রজবুলী—103  
 ব্রণ—304  
 ব্রত—357  
 ব্রক্ষাল—65  
 ব্রক্ষণ—557  
 ব্রাক্ণেরি—721  
 ব্রিটেন—358  
  
 ভ—135, 272, 442, 443, 615,  
 616, 631, 643, 644  
 ভই—1038  
 ভইল—1038  
 ভকত—376  
 ভগতী—347  
 ভজ—471  
 ভজ—873  
 ভগবা—522  
 ভগ্ন—879  
 ভট্টাচার্য—431  
 ভট্টপন্নী—65  
 ভড়—315, 356, 496, 553  
 ভড়কা—886  
 ভড়ং—516  
 ভহতা—705  
 ভহ—424, 899  
 ভহবা—372, 440, 515, 659  
 ভহস—344, 424

ভহাউনী—665  
 ভহিল—1038  
 ভহ—713, 873  
 -ভহ—702  
 ভহতি—655  
 ভহ-সক্যা—713  
 ভহসা—347, 515  
 ভহসাকা—713  
 ভহা—702  
 ভহাট—685  
 ভহিল—975  
 ভহে—919  
 ভহতি—655  
 ভহং—879  
 ভহমনস (= voluminous)—644  
 ভহই—308, 320, 385, 386, 415,  
 421, 515, 550  
 ভহইহে-ভহইহে—386  
 ভহিহ—275, 307  
 ভহিলিয়া—516  
 ভহং—363  
 ভহগ—461  
 ভহগাড—688  
 ভহগিনা—461  
 ভহগিয়া (ভেগে) পড়া—1051  
 ভহগাবহ—697  
 ভহগিস—550  
 ভহগে—363  
 ভহগ—363  
 ভহগ-গড়—896  
 ভহগা—699, 889  
 ভহগ-কুর—896  
 ভহগড়—688  
 ভহগা—883, 956  
 ভহগিয়া (ভেগে) দেওয়া—1051  
 ভহিল—677  
 ভহগে—363, 919  
 ভহত—(noun) 275, 307, 475,

515 ; (verb) 475, 515, 873  
 ভহট—486, 491  
 ভহটপাড়া—65  
 ভহটা—516  
 ভহটা—516  
 ভহটগাল—669  
 ভহা—515  
 ভহাটগি, ভহাটে—686  
 ভহগি—1033  
 ভহগাইলি—1033  
 ভহত—502, 515  
 ভহতার—317, 486  
 ভহদরবট, ভহদরবু—376  
 ভহনা—452  
 ভহপ—159, 440, 511, 515,  
 553  
 ভহপনা—699, 889  
 ভহভান—516  
 ভহবিহেন—1024  
 ভহবিলাই—967  
 ভহগ—320, 1038  
 ভহগা—691  
 ভহগা—446  
 ভহগে—877  
 ভহগত—400  
 ভহগাহা—305  
 ভহগা—671  
 ভহগই—399, 672  
 ভহগ—154, 302, 316, 347, 515,  
 543, 652  
 ভহগটা, -টা—686  
 ভহগবাসা—899  
 ভহগ—718  
 ভহগাই—661  
 ভহগক—544  
 ভহগে—154, 302, 652, 899  
 ভহগোবাসা—899  
 ভহগুর—331, 327



- ভাব—305  
 ভাস—878  
 ভাস্কর—653  
 ভিক্ষুণী—696  
 ভিক্ষে—400  
 ভিখ—160, 305, 325, 515  
 ভিখারী—668  
 ভিখিরি—668  
 ভিজ—313, 372, 475, 515, 874  
 ভিজার—313  
 ভিজিট—647  
 ভিজের—876  
 ভিটা—66, 516  
 ভিট—66  
 ভিড়—498, 515  
 ভিড়ি—114  
 ভিত—308, 322, 501, 773  
 ভিতর—313, 372, 405, 406, 515, 773  
 ভিতরে—773  
 ভিতে—773  
 ভিদ—879  
 ভিন—325, 515, 529  
 ভিন্নকল—522  
 ভিন্নকল—331, 355  
 ভিল—325  
 ভিশি—580, 590, 594  
 ভিস্তী—515  
 ভীখ—160, 305  
 ভীত—501, 773  
 ভীতে—773  
 ভীমকল—402  
 ভীমকল—325  
 ভীষ—873  
 ভূখ—305, 325, 440, 515  
 ভূখিল—677, 956, 957  
 ভূখালি, -লী—326, 349  
 ভূজি—406  
 ভূঞা—522  
 ভূতড়ী, 'বুতড়ী—515  
 ভূনা—355  
 ভূনি—355  
 ভূরা—516  
 ভূর—377  
 ভুল—515  
 ভুলচুক—896  
 ভূসি—438  
 ভূঞা—520  
 ভূত—203  
 ভূব—874  
 ভূনি—515  
 ভেংচা—699  
 ভেক—1070  
 ভেকট—516  
 ভেকটী—516  
 ভেখ—1070  
 ভেঙ্গচা—889  
 ভেজ—912  
 ভেজার—313, 475  
 ভেড়া—328, 440, 515  
 ভেরে ভেরে—386  
 ভেল—515  
 ভেলা—328  
 ভেলুকী—515  
 ভেন—211  
 ভেস্ত—203  
 ভেস্তা—516  
 ভৈল—1038  
 ভৈলা—1038  
 ভৈলি—956, 958  
 ভোগতী—347  
 ভোজপাতা—475  
 ভোজগি—326  
 ভোজ্য—406  
 ভোট—217  
 ভোটান—726  
 ভোমরা—413, 515  
 ভোমা—326  
 ভোরহ—516  
 ভোল—515  
 ভুইখা—440  
 ভুইখা—522  
 ভুইখা—424  
 ভুইখা—363, 461  
 ভুগিলি—1048  
 ভুগিল—957  
 ভুগিল—957  
 ভুজি—364, 475, 515, 873  
 ভুজের—875  
 ভুটা—322, 516  
 ভুটী—516  
 ভুড়ি—321, 365, 515, 553  
 ভুড়ার—350, 496, 669  
 ভুড়ারী—669  
 ভুড়ি—502  
 ভুই—326  
 ভুড়ি—516  
 ভুই—372, 515, 520, 522  
 ভুইখা—520  
 ভুই—522  
 ভেড়া—440  
 ভৈব—344, 515, 522  
 ভৈবা—344  
 ভৈবা—516, 553  
 ব—(sound) 272, 519, 521  
 ব—(=) 521; (affix) 531, 651, 652, 666, 667, 987  
 বই—(noun) 307; (Pronoun) 811, 815  
 বউ—310, 315, 554  
 বউড়—403  
 বউন—304, 427  
 বউনি—399

মটন—659  
 মটর—427  
 মটরী—337, 554  
 মটরীমটী—533  
 মণ্ডা—425  
 মণ্ডা—364  
 মকদ্দমা—581, 582, 609, 610  
 মকবুল—577  
 মকদ্দমা—454, 618  
 মকেল—590, 617  
 মকস, মক্স—593, 597, 618  
 মগল—592, 608, 613  
 মগন—376  
 মগর—446, 462  
 মজল—384  
 মজলা—364  
 মচকা—886  
 মচমচা—891  
 মচকা—457  
 মজ্জ—471  
 মজলম—608, 612  
 মজ—874  
 মজবু—602  
 মজলিস—396  
 মজা—608  
 মজব—587, 588  
 মজর—582, 618  
 মজু—311, 813  
 মজরী—431  
 মটন (mutton)—647  
 মটর—640, 648  
 মটর—453  
 মটর—457, 679  
 মড়া—315, 343, 355, 403, 487,  
 530, 942  
 মড়া, মড়া—532  
 মণ—652  
 মণিকর—682

মড—304, 320, 696, 852 ;  
 (affix) 696, 851  
 মডন—592, 696, 852  
 মডল—575  
 মডি—303, 379  
 মডো—852  
 মড—200  
 মড—605  
 মড—305, 610  
 মড—397  
 মডা—406  
 মডা—1073  
 মডি—406  
 মন—320, 528, 530, 652  
 মন—(plural affix) 737 ;  
 (affix) 696, 851  
 মনকা—597  
 মনহে—776  
 মনিব—582, 585  
 মনিহি—399  
 মনু—397  
 মনু—(affix) 696, 709  
 মন—899  
 মনবাসা—899  
 মনবল—534, 558  
 মনবল—558  
 মনবল—534, 558, 582  
 মন—305, 814  
 মনব—204  
 মন (affix)—706  
 মনদা—587, 602, 608  
 মনদান—587  
 মনদা—331, 1069  
 মনদামটী—533  
 মনদা—331, 403, 424  
 মনদা—404, 424  
 মনদা—424  
 মনদা—315

মন—536  
 মন (=দার)—815  
 মনগিজ—647  
 মনগ—856  
 মনগকা—418  
 মনগ—376  
 মনব—305  
 মনব—376  
 মনবী—671  
 মনব—580, 610  
 মনব—618  
 মন—956  
 মনাই—542  
 মনচা—610  
 মনিতা—975  
 মনব—994  
 মনব—1043  
 মন—315, 877  
 মন—(noun) 305, (verb) 879  
 মন—1043  
 মন—874  
 মন—1043  
 মন—595, 610  
 মনটি—687  
 মন—1020, 1026  
 মন—1043  
 মন—589, 590  
 মন—550  
 মনাই—407  
 মনান—200, 315, 336, 530  
 মনদা—407, 423, 848  
 মনদা—579, 612  
 মনদা—213  
 মনদা, মনদা—603, 618  
 মনদা—577, 599  
 মন—811, 874  
 মনদা—591, 595  
 মনদা—425



- মহানন্দ—204  
 মহর—814  
 মহরম—646  
 মহল—575, 608, 768  
 মহল্ল—557  
 মহাশয়—407, 848  
 মহিষ—384  
 মহা—340  
 মহরী—337  
 মহেশ—424  
 মহো—811  
 মা—307, 320, 404, 530  
 মাথ—751  
 মাই—320  
 মাইঠা—381  
 মাইতি—502  
 মাইনে—590, 592  
 মাইর—674  
 মাইর—1044  
 মৌর—539  
 মজিগ—381, 385, 462  
 মাউগী—381  
 মাউলানী—342, 345, 544, 695  
 মাউলী—196  
 মাউসী—385  
 মাও—307, 342, 423  
 মাওরাণী—196  
 মাং—370  
 মাকড়—316, 456, 691  
 মাকড়সা, মাকসা—1070  
 মাথ—874  
 মাখন—530  
 মাখে—460, 530  
 মাগ—381  
 মাগনা—657  
 মাগা—363  
 মাগী—381  
 মাঙ—381, 462  
 মাঙর—482  
 মাঙরা—780  
 মাপু—381  
 মাগে—370, 462, 882  
 মাপৌ—932  
 মাপুগী—431, 443  
 মাতে—370  
 মাক্স—364  
 মাক্সা—657  
 মাঙ্গে—321, 370, 462, 882  
 মাটা—362, 371, 471  
 মাছ—443, 473  
 মাছি—473  
 মাক (-কাক)—306, 475  
 মালধানে—476  
 মালী—475  
 মালিষ্টর—647  
 মাথ—112, 302, 481, 530  
 মাঝার, -রী—669  
 মাঝি—443  
 মাকুখা দালা—477  
 মাকুখা—381, 395  
 মাঝে—773  
 মাট—697  
 মাটির—674  
 মাজি—307, 355, 491, 673, 687  
 মাঠ—443  
 মাঠা—493  
 মাঠুয়া—381  
 মাড়—496, 499, 874  
 মাড়লী—541  
 মাড়ে—497  
 মাড়োয়ারী—452  
 মাড়—499  
 মাক—501, 583  
 মাকবর—589, 590  
 মাকবর—619  
 মাকল—671, 698  
 মাউলা—671  
 মাকাল—349, 501, 671  
 মাউল—940  
 মাতে—882  
 মাতে-মাকতে—719  
 মাতেয়ারী—349, 671  
 মাতে—447  
 মাক—1017  
 মাথট—685  
 মাখন—371  
 মাথা—441, 504  
 মাথানী—666  
 মাথাল—669  
 মাকল—399, 400, 506, 698  
 মাক্রাসা—612  
 মাথাই—662  
 মান—347, 737  
 মানবিকতা—705  
 মানা—576, 579, 884  
 মানান—664  
 মান্নান-মই, -মহি—709  
 মানিক—456  
 মাকু—626  
 মান্ব—337, 528, 545, 728, 778  
 মান্বগা—758  
 মান্বগালা—729, 733  
 মান্বগলি—729  
 মান্বগো—758  
 মান্বগা, -গা—778  
 মান্বগি(কে)—729  
 মান্বগিগ—728, 729  
 মান্বগের—728, 731  
 মান্বগের—728, 729, 731  
 মান্বগদি—731  
 মান্বগের—754, 758  
 মান্বগেরগো—758  
 মান্বগের দিগর—728, 729

মাহুকের বের—729  
 মানে—(noun) 578, 590 ;  
 (verb) 529, 875  
 মানোহরি—(= man-of-war)  
 647  
 মাকারণ—299, -ন—347  
 মাপ-মই—709  
 মাপে—320, 877  
 মাকিক—590  
 মামড়া—531, 691  
 মামলা—590  
 মামলেট (= comet)—648  
 মানাতুতা—503  
 মামী—672, 695  
 মামু—576, 595  
 মার—342  
 মারনা—590  
 মায়—420, 533  
 মারে-মীয়ে—719  
 মায়েতে-মীয়েতে—719  
 মার—587, 927  
 মা-র—674, 718  
 মারকাট—896  
 মারকিন—648  
 মারগিজ (= mortgage)—647  
 মারতে—447  
 মারধর—896  
 মারদা—1000  
 মারফৎ—602  
 মারহাটি—672  
 মারা—922  
 মারাজি, -জী—672  
 মারামারি—1048  
 মারি—539, 674  
 মারিঅ—922  
 মারিতে—447  
 মারিবাক—1018  
 মারিবার—1018

মারিল—541, 1044  
 মারিলান—972  
 মারিলি—972  
 মারিলুন—972  
 মারিলেক—986  
 মারুলি—541  
 মারে—877  
 মারু—922  
 মার্ক—622, 630  
 মার্কল, মার্কাল—626  
 মারুলে—541, 1044  
 মারুলেও—1004  
 মাল—306, 312, 543, 544  
 মালক—347  
 মালক-মাড়ী—187  
 মালয়ালম্—197  
 মালয়ালী—197  
 মালি—312  
 মালেক—608  
 মাল্লা—576, 583  
 মালুলে—1044  
 মাল্লে—541  
 মালুল—595  
 মালুল-চোর—610  
 মাষ্টর—648  
 মাষ্টার—216, 648  
 মাষ্টারবী—695  
 মাস—321, 362, 548  
 মাসতুতা—503, 552  
 মাসরা—347  
 -মাসিরা—700  
 মাসী—199, 355, 385, 548  
 মাহুত—692  
 মাহুল—610  
 মাহুল—626, 630, 631  
 মাহিতী—502  
 মাহিনা—592  
 মাহিনে—590

মাহিরনা—592  
 মাহুত—350, 502  
 মি—(affix) 666, 667, 751, 778  
 মিউনিসিপালিটি—648  
 মিউমিউ—419  
 মিছ-কউনে—306, 399  
 মিছ-কহ্নিছা—306  
 মিছরী—551  
 মিছা—312, 473, 530  
 মিছিল—579, 592, 612  
 মিঞা—522, 608  
 মিঠা—355, 493  
 মিঠাই—407, 661  
 মিঠি—407  
 মিড়—538  
 মিতা—530  
 মিতানরাকে—725, 736  
 মিতিন—694  
 মিতু—311  
 মিষ্টিরজা—694  
 মিথ্যা—382, 503  
 মিথ্যুক—704  
 মিথ্যা—400  
 মিনসা—399, 406  
 মিনসে—406  
 মিনার—608  
 মিনি—530, 773  
 মিন্সা—332, 381  
 মিয়ার—614  
 মিয়ান—418  
 মিয়ারো—418  
 মিহা—522, 608  
 মিহজা—584  
 মিল—874  
 মিলে—412  
 মিশ—874  
 মিশার—325  
 মিশাল—548



- মিত্তিক—704  
 মিশে—325  
 মিশেল—400  
 মিসরী—703  
 মিস্তিরি—627  
 মিহী—627, 631  
 মিহি—577, 608  
 মীনা—737  
 মীর্জা—357, 584  
 মু—303, 326, 530, 553, 557 ;  
 (affix) 531  
 মুই—303, 350, 428, 809-816,  
 987  
 মুইরা—814  
 মুইসকল—812  
 মুকল—456  
 মুক্কে—409  
 মুক্কা—377  
 মুখখানি—449  
 মুখপানে—771  
 মুখপোড়া—440  
 মুখস—699  
 মুখামুখি—1049  
 মুখুরজা—409  
 মুগ—326, 462, 530  
 মুগর—462  
 মুগ—462  
 মুকা—886  
 মুকিয়া হালা—467, 530  
 মুড়া—888  
 মুচলকা—213, 618  
 মুচি—194  
 মুচিগিরি—707  
 মুচুরমান—612  
 মুচ্ছন্দী—578, 581, 589  
 মুছ—530  
 মুছিয়া পেলাইবো—1050  
 মুছিয়া ( মুছে ) ফেলা—1052  
 মুক্তি—350, 522, 811  
 মুটিয়াগিরি—707  
 মুঠ—308, 312  
 মুঠি—312, 493  
 মুঠু হাত—530  
 মুড়—407, 878  
 মুড়ন্দী—186  
 মুড়া—365  
 মুড়ি-কেওরা—1013, 1051  
 মুড়ন্দী—65, 186  
 মুড়ো—401  
 মুতি—303  
 মুতী—502  
 মুখা—326, 504  
 মুখড়ী—306, 326, 505, 690  
 মুদি—690  
 মুদীখানা—707  
 মুদে—882  
 মুদই—588  
 মুদকা—596  
 মুনিএ, -তে—719  
 মুনিব—562, 585  
 মুনিয়ের—719  
 মুনির—719  
 মুনিস—332, 381, 399, 528,  
 530, 548  
 মুনিসা—381  
 মুন্কে—682  
 মুন্সিপাল (= municipal)—216  
 মুন্সেফ—581  
 মুফৎ—602  
 মুরে—428  
 মুরি—811  
 মুরত—308  
 মুরচা—203  
 মুরকবী—578  
 মুরোদ—583  
 মুর্দাকরাস—581  
 মুন্ডবী—616  
 মুন্সুক—581  
 মুন্সুক—454, 581  
 মুন্সুকে—454  
 মুশর—407  
 মুবড়া—888  
 মুসলমান—551, 612  
 মুসলমানব—705  
 মুসাবিদা—616  
 মুহড়া—601  
 মুহা—659  
 মুহরী—572, 578, 610, 618  
 মুচ—500  
 মুত—502  
 মুতে—882  
 মুহা—376  
 মুহতি—376  
 মুর্জা—448  
 মুলা—544  
 মুলা—326  
 মুলো—401  
 মুগ—304  
 মুজা—357, 584  
 মেওরা—616  
 মেঘ—411, 450  
 মেঘলা—331  
 মেচা—1073  
 মেচ কো-কর—1073  
 মেছ—473  
 মেছুবী—694  
 মেছো—679  
 মেজ—391  
 মে'জ—391  
 মেজ—622, 624, 631  
 মেজকী—682  
 মেজদা—477  
 মেজরাপ, -ব—580  
 মেজাজ—601, 613

মেজার-খেলাস-643  
 মেজিষ্টর-647  
 মেজো, মেজো-391, 395, 443  
 মেজোদাদা-477  
 মেঝো-395  
 মেটে-390, 674, 1066  
 মেঠাই-407  
 মেঠো-381  
 মেড়া-555  
 মেথর-595  
 মেথরনী, মেথরাণী-695  
 মেম-648  
 মেমাব-584, 614  
 মেয়ে-390  
 মেয়েলী-670  
 মেয়-608  
 মেয়াজি-588  
 মেয়াজাব-613  
 মেয়া-211  
 মেয়াপ-446, 595, 605  
 মেয়াবৎ-577  
 মেয়ানো-625, 626  
 মেয়ে-388  
 মেয়ে-ব'রে-1048  
 মেল-306  
 মেল-ট্রেন-639  
 মেনে-411, 412, 1044  
 মেশামিশি, -মেশি-398  
 মেসো-385, 679  
 মেহরৎ-591, 595, 619  
 মেহার-336, 540, 669  
 মেহারী-540, 669  
 মেহেরবাণী-580, 592  
 মৈল-342, 355, 487, 517,  
 942, 1043  
 মৈলান-157  
 মৌ (affix)-531  
 মো (=my)-329, 330, 520

মো (pronominal stem)-413,  
 810, 811, 812, 815  
 মোখা-329, 341  
 মোই-811  
 মোইব-384  
 মোএ, -এ-811  
 মোক-815  
 মোকদ্দা-454, 542, 581  
 মোকরর-589, 610, 618  
 মোকররী মোররী-578  
 মোকদ্দা-542, 610  
 মোকা-609  
 মোকুব-606  
 মোকে-611, 614  
 মোক্তার-599  
 মোকম-582  
 মোখল-582  
 মোখো-758  
 মোচরমান-612  
 মোচা-329  
 মোচোরমান-551  
 মোছব-432, 473  
 মোছ-310, 473, 530  
 মোছলমান-612  
 মোজা-194  
 মোজাহেব-580  
 মোজুন-587  
 মোঞ-320, 811  
 মোঞি-811  
 মোঞে-811  
 মোঞ-811  
 মোটি-490  
 মোটা-491  
 মোটিমু-814  
 মোড়-327  
 মোড়ক-457, 679  
 মোড়তে-610  
 মোড়ল-320, 327

মোতফরকা-589, 618  
 মোত-হুস্তে-776  
 মোতাজে-590  
 মোতারেন-590  
 মোতি-303, 397  
 মোতী-502  
 মোতে-811, 814  
 মোদিগ-812  
 মোদিয়া-814  
 মোদের-812, 814  
 মোদেরতে-814  
 মোকা-590  
 মোনকা-596, 606, 607  
 মোরে-814, 815  
 মোরেকার-814  
 মোহ-586  
 মোহা-341, 342, 427  
 মোহ-145, 211, 754, 758,  
 811, 814, 815  
 মোহগ-400, 582, 593, 600  
 মোহগো-815  
 মোহতে-610  
 মোরমনকার, -মেনকার-814  
 মোরমেনে-814  
 মোরা-735, 736, 812, 813,  
 815  
 মোরাগো-758  
 মোরোগ-593  
 মোর্চে-590  
 মোল-827  
 মোলাগ-187  
 মোলা-581  
 মোশাই-848  
 মোষ-384  
 মোই-811  
 মোছড়া-691  
 মোছ'তে-814  
 মোহন-400



মোহনভোগ—1070  
 মোহাশ্বদ—581, 594  
 মোহির—(noun) 592, 595 ;  
 (pronoun) 811, 814  
 মোহিরদ—594, 610  
 মোহি—811  
 মোহে—877  
 মোহো—811  
 মো—310, 315, 530, 554  
 মোচাক—344  
 মোজা—587, 596  
 মোজুদ—587  
 মোড়—496  
 মোং—602  
 মোন—304  
 মোরশ—586  
 মোরী—554  
 মোরশী—588, 612  
 মোলবী—577, 578, 588, 616  
 মোলভী—588, 616  
 মোলুবী—578  
 মোদন—587  
 মোসিন—580  
 মোহন—580, 610  
 মোহারী—345  
 ম'হির—337, 365  
 ম'ড়—496  
 ম'ড়ব, ম'ড়স—526  
 ম'দ—321, 362  
 মু'ই—522  
 মু'ড়িন—526  
 মু'রি—522  
 মু'হি—811  
 মে'—815  
 মে'ং—815  
 -ম—619  
 মাণ্ড—421  
 মাজেটা—197, 647

মাজেটার—647  
 মাজেটার—197, 647  
 মাদ—584, 614  
 মাম—648  
 মাল—391  
 মাটির—648  
 মগ—357  
 মহ (sound)—132  
 ম—227, 272, 474, 840, (= হ)  
 227, 272, 340, 341, 381,  
 402, 411, 413, 533, 534,  
 614 ; ( হ = j )—299  
 -ম—(affix) 739  
 মক ; মকি—406  
 মখন—317, 857  
 মজ—533  
 মজু—311, 474, 841  
 মজ—879  
 মজা—382, 406  
 মজি—406  
 মত—733, 854  
 মতন—376, 400, 475  
 মতক—855  
 মথা—505, 858  
 মথার—858  
 মথি—841, 858  
 মথিত—841  
 মথির—841  
 মদি—396, 901, 902, 1043  
 মদিও—1043  
 মদ্র—397  
 মজুদা—679  
 ম'দো—679  
 মদিন—331  
 মনস—533  
 ম-কলা—381  
 মব—475

মবে—114, 474, 856  
 মব্দে—853  
 মদী—353  
 মদিন—477  
 মহির—841  
 মা—(sound) 404  
 মা—(root) 912, 921, 923, 924,  
 925, 1014, 1044, 1052 ;  
 (noun) 474 ; (pron.) 846,  
 874, 893, 901  
 -মা ( -ji )—394, 410  
 মাই—419, 422, 1069  
 মাই—(sound) 421  
 মাইছে—1026  
 মাইত—335  
 মাইতা-লাগুগিল(1)—1015  
 মাইতাম-লাগুগিলাম—1015  
 মাই-তাই—860  
 মাইতু-মাইলু—1016  
 মাইছে—393, 451, 1000, 1014,  
 1015  
 মাইতেছ—994  
 মাইতেছি—994  
 মাইতো—960  
 মাইতাম—994  
 মাইতাম—994  
 মাইবাম—994  
 মাইবার—762  
 মাইবেক—457  
 মাইরা—1044  
 মাইরার—994  
 মাইল—1044  
 মাইলে—1044  
 মাউ—310  
 মাউক—310, 423  
 মাউক-গিরী—447  
 মাউ—1029  
 মাও—421, 423

বাণেশ্বর—933  
 বাণেশ্বরী—660  
 বাণী—932  
 বাক—310, 907  
 বাক্যে, বাণ্যে—447  
 বাচ—422, 874  
 বাচাই—422, 661  
 বাচ্ছিলস—979  
 বাচ্ছ—1026  
 বাচ্—523  
 বাতে—901  
 বাতো—393  
 বাদিগ—839  
 বাহুবর—219  
 বাদের—839  
 বান—528  
 বাবাকে—752  
 বাবানে—998  
 বাবো (অ)বুন—997  
 বামি—533  
 বার—422, 474  
 বারের—বানে—996  
 বার—162  
 ভার—534  
 বারী—839  
 বাহ—903  
 বাহা—839, 903  
 বাহাদিগ—839  
 বাহাদের—839  
 বাহারী—839  
 বাহ—405  
 বাহি—124, 839, 840  
 বাহার—533  
 বাহদী—601, 615  
 বাহী (sound)—465  
 বাহু—624, 627, 629  
 বা (sound)—407  
 বাহি—477

বুগ—482, 475  
 বুগিং—308  
 বুগসেত—65  
 বুগ—874  
 বুগে—322, 326, 475, 482, 875  
 বুগুন—533  
 বুগ—305  
 বু (sound)—407  
 বে, বৈ (sound)—402, 408  
 বে—474, 839, 840, 846, 902  
 বেই—419, 841  
 বেউ—846  
 বেঙ—420  
 বেথেনে—401  
 বেছে—1026  
 বেত (= বত )—854  
 বেতে—393  
 বেতেম—400  
 বেথা—412, 504, 858  
 বেথায়—858  
 বেন—95, 313, 555, 853, 901  
 বেনা—839  
 বেনে—853  
 বেমন—696, 851  
 বেমন—411, 851  
 বেমনতর—708  
 বেমনে—853  
 বেয়ে—918, 1044  
 বেলে—1044  
 বেপ্ত—624  
 বেস্ (= yes)—534  
 বে-, সে—1030  
 বেহেন—95, 313, 853  
 বেহো—846  
 বেহু—95, 853  
 বেহুমনে—852  
 বৈহন—854  
 বে—303, 329, 474

বৈ (sound)—413  
 বোগ—477  
 বোগাড়—687  
 বোগাড়িয়া, বোগাড়—687  
 বোগান, বোগান্—665  
 বোগা—382, 398  
 বোড়া—183  
 বোড়াসাঁকো—65, 66  
 বোত—329, 475  
 বোয়ান—336  
 বোয়ার—329  
 বোয়াল—475  
 বোরোপ (= Europe)—534  
 বোর্ক (= York)—534  
 বোবন—427  
 বা—839  
 বাইআর—994  
 বাতা—475, 501, 673  
 বাতী—673  
 বাদিগ—839  
 বাদের—839  
 বারা—839  
 বাহা—839  
 বাহাদিগ—839  
 বাহাদের—839  
 বাহারী—839  
 বাহ—124  
 বাই—325  
 বে (affix)—1006  
 বেহ—124, 725  
 বা—636  
 বা (sound)—410  
 -বা—133  
 -বা—421  
 বাদিন—391  
 বাত্র (-গা)—421  
 ব—(sound) 138, 272, 642;



(affix) 540, 717, 718, 734,  
739, 776, 855; (-ত-) 691,  
729, 885, 888

রখানী—468

রইদ—344

রঙগন—588

রঙনা—590

রঙরাক—213, 617

রং—383

রক—213, 617

রকম—592

রকা—384, 413, 460

রগড়া—888

রঙ—863

রঙানা—608

রজকিনী—201, 696

রজকুল—648

রজনী—468

রজপুত—321

রট—879

রড়—879

রণ—304, 320

রণমুখো—305

রতন—256, 376, 400

রতি—318, 319, 502

রদী—603

রপটা—887

রপ্ত—593, 605

রপ্তানী—678, 606

রকা—315, 575, 609

ররাব—609

রমজান—577, 589, 609

রয়টার (= Reuter)—640

রজনী—468

র'য়ে—392

র'য়েছি—1028

রজা, রজো—392

রক্তন—539

রস—315

রসদ—577, 603, 612

রসান—315, 350

রসীদ—603

রসুই—347

র'স—885

র'সকে—333

রহ—879, 885, 1035, 1040

রহ-ইহ—896

রহমান—557

রহ-মহ—896

রহাএ—1040

রহিয়া—392

রহিলেন—987

রা—320, 539

-রা—95, 173, 668, 734, 735,  
736, 776

রাই—247, 320, 421, 422,  
554, 672, 673

রাইখ—383, 908

রাইখা—133, 381, 393

রাখা—133

রাইখো—393

রাইত—308, 345, 381, 385,  
386

রাইরং—589

রাউত—468

রাউং—320, 337, 342, 346

রাউল—320, 468

রাং—363, 539

রাংতি—363

রাকড়া—885

রা-কাড়া, রাকড়া—114, 885

রাখ—443, 874, 1033

রাখোয়াল—349

রাখতুম, রাখতুম—393

রাখলুম, রাখলুম—393

রাখা—690

রাখা-করান—1033

রাখাইরা—416

রাখাইহ—352

রাখাল—300, 349, 426, 455,  
670

রাখালী—670, 673

রাখি (= রাখিরা)—690, 1006

রাখিখ—383, 908

রাখিখা—660

রাখিও—352, 418, 458

রাখিঞা—142

রাখিতাম—393, 394

রাখিতুম—393

রাখিতে—393

রাখিরা—133, 142, 381, 387,  
393, 416, 417, 1006

রাখিরে—416

রাখিল—308, 974

রাখিলাম—393, 394

রাখিলুম—393

রাখিহ—352, 383, 908

রাখী (= রাখিরা)—660

রাখে—460

রাখেক—918, 990

রাখো—932

রাখোয়াল—670

রাখোয়াল—426, 458

রাখত—387

রাখা—383, 908

রাখা—391, 393

রাখো—393

রাখলা—332

রাখে—142

রাখিঞা—142

রাখি—671

রাঙ—363

রাঙা—363, 659

রাঙা—363

রাজ্য—692  
 রাজ্য—363, 669, 686, 883  
 রাজ্যটে—686  
 রাজ্য—475, 879  
 রাজ্য—691  
 রাজনীতিক, নৈতিক—703  
 রাজপুত—321  
 রাজহীন—506  
 রাজাই—577, 661  
 রাজ্যতে—751  
 রাজ্য (ag.)—780  
 রাজ্য—476  
 রাজ্য—539  
 রাজ্য—500, 539  
 রাজ্য—672  
 রাজ্য—227, 523, 674  
 রাজ্য—308, 381, 385, 386,  
 502  
 রাজ্য—502  
 রাজ্য—345, 381, 502, 539,  
 652  
 রাজ্য—703  
 রাজ্য—337, 502, 698  
 রাজ্য—539  
 রাজ্য—503  
 রাজ্য—506  
 রাজ্য—677  
 রাজ্য—227, 523, 539, 674,  
 696  
 রাজ্য—657  
 রাজ্য—648  
 রাজ্য, -টা—686  
 রাজ্য—732  
 রাজ্য—717  
 রাজ্য—659  
 রাজ্য—662  
 রাজ্য—695  
 রাজ্য—732

রাজ্য—717  
 রাজ্য—(<raj) 247, 320, 342 ;  
 (=judgment) 615  
 রাজ্য—589  
 রাজ্য—590  
 রাজ্য—548  
 রাজ্য—640  
 রাজ্য—308, 609  
 রাজ্য—648  
 রাজ্য—593, 595  
 রাজ্য—595  
 রাজ্য—320, 421, 554, 672  
 রাজ্য—356, 358  
 রাজ্য—539, 543  
 রাজ্য—648  
 রাজ্য—577, 606, 609  
 রাজ্য—641, 648  
 রাজ্য—648  
 রাজ্য—606, 609  
 রাজ্য—648  
 রাজ্য—639, 648  
 রাজ্য—577, 616  
 রাজ্য—66  
 রাজ্য—325  
 রাজ্য, রিজিটার—648  
 রাজ্য—358  
 রাজ্য—313, 493, 543  
 রাজ্য—308  
 রাজ্য—548  
 রাজ্য—325, 539  
 রাজ্য—697  
 রাজ্য—396, 428, 539, 555  
 রাজ্য—215, 428  
 রাজ্য—373, 458  
 রাজ্য—355  
 রাজ্য—471, 875  
 রাজ্য—581, 600

রাজ্য—307, 625, 673  
 রাজ্য—326  
 রাজ্য—882  
 রাজ্য—653  
 রাজ্য—882  
 রাজ্য—586, 609  
 রাজ্য—700  
 রাজ্য—988  
 রাজ্য—418  
 রাজ্য—703  
 রাজ্য—548  
 রাজ্য—396  
 রাজ্য—396  
 রাজ্য—181  
 রাজ্য—699  
 রাজ্য—510, 539  
 রাজ্য—758  
 রাজ্য, রাজ্য, রাজ্য—670  
 রাজ্য—1069  
 রাজ্য—112, 739  
 রাজ্য—420  
 রাজ্য—589  
 রাজ্য—598  
 রাজ্য—306  
 রাজ্য—133, 141, 381, 387,  
 391, 393, 416, 1006  
 রাজ্য—352, 383, 418  
 রাজ্য—133, 391  
 রাজ্য—133, 416  
 রাজ্য—577  
 রাজ্য—577  
 রাজ্য—704  
 রাজ্য—648  
 রাজ্য—704  
 রাজ্য—313, 372, 539  
 রাজ্য—886  
 রাজ্য চিনি—578, 603, 618



- রেবেন তিনি—578  
 রেমো—679  
 রেহাৎ—590  
 রেলওয়ে—216, 645  
 রেলগাড়ী—216  
 রেশম—585, 609  
 রেস্তা—624, 626, 630  
 রেস্তো—626  
 রেহ—328, 553  
 রেহাই—594  
 রোখ—460  
 রোগন—688  
 রোগা—659  
 রোগাটে—686  
 রোচে—875  
 রোজ—586, 609, 613  
 রোজকার—451  
 রোজদাদ—615  
 রোজা—203, 542  
 রোড—640  
 রোডসেস—640  
 রোদ—344  
 রোমজান—577  
 রোমান্টিক—217  
 রোমান্টিকতা—705  
 রোম(ি)ল্—217  
 রোর—329, 342, 353, 426, 539  
 রোরাক—617  
 রোরো—392  
 রোশনাই—589  
 রোশনো—586  
 রোষলি—957  
 রোষিলী—721  
 রোসো—885  
 রোহিলা, রোহেলা—213  
 রোগন—588  
 রোঁধ—344  
 রোঁশন—588  
 রোঁশনজাকী—588  
 র'ড়—306, 365, 539  
 র'ড়বাজ—709  
 র'দি—366  
 র'খনা—657  
 র'খনো—658, 672  
 র'খা-বাড়া—1016  
 র'খুনি—672  
 র'খুনী—658  
 র'খে—875, 877  
 রে'দা—366  
 রে'—303, 329, 520, 539  
 রে'দি—648  
 রে'রা—520, 539  
 ল—(sound) 217, 272, 538 ;  
 (verb) 1044  
 ল (= Eng. law)—636, 642  
 -ল—697, 885, 888  
 লক্ষ—903  
 লই—774, 1044  
 লইছে—1022  
 লইব—1045  
 লইরা—1045  
 লইব—1045  
 লইস—1044  
 লউক—1045  
 লউন—1045  
 লও—1044  
 লওরা—1045  
 লং—363  
 লক—546, 599, 607  
 লক্খী—480  
 লক্—382, 383, 392  
 লক্ষী—200, 460  
 লখ—318, 874  
 লখিত—704  
 লখিনর—460  
 লখে—319  
 লগন—376  
 লখে—145, 774  
 লগ্খী—462  
 লঘু—397  
 লক্—346, 363  
 লকর—540, 611  
 লক্খুন—648  
 লটকা—886  
 লড়—498, 545, 879  
 লড়াই—661  
 লড়াইহ—1037  
 লড়িলী—958  
 লটন—216, 641, 64  
 লগু—628  
 ল'ন—424, 1044  
 লপটা—887  
 লবাদা—623  
 লবান—586  
 লবেজান—610  
 লবেদা—623  
 লম্পা—641, 648  
 লক্ষ-প্রদান করা—1015  
 লখর—546  
 লক্—543, 545, 554  
 লরে—774  
 লরেন—424, 1044  
 লনাটেতে হস্তে—776  
 লকর—203, 610, 611  
 লহ—874, 997, 1044  
 লহমা—610, 617  
 লহর—308  
 লহে—543, 554  
 লহেন—1044  
 লা—306, 460, 543, 545, 553, 554, 637  
 লা- —545

-লা—669, 697  
 লাইওর—528  
 লাইহর—545  
 লাইহোর—528, 545  
 লাউ—310, 313, 385, 423, 543  
 লাও—1045  
 লাখ—460, 543, 801  
 লাক্ষেকর—757  
 লাগ—363, 461, 543, 874  
 লাগাং—611  
 লাগাম—576, 598, 610  
 লাগারং—611  
 লাগানু (সে)—1032  
 লাগি—774  
 লাগি গেল—1050  
 লাগিরা—172, 774  
 লাগিরা (লগে) থাকা, রহা—1052  
 লাগিরা (লগে) যাওয়া—1052  
 লাগিলী—958  
 লাগু—311  
 লাগে—774  
 লাঙল—544  
 লাক্ষট—347, 490, 687  
 লাক্সা—545, 546  
 লাচাড়ী—289  
 লাচ্ছ—258  
 লাছ—185, 258, 306, 473, 543  
 লাক্স—306, 475, 543, 874  
 লাক্সউলী—698  
 লাক্সবর্দ—593, 603  
 লাক্সক—704  
 লাট—218, 545, 633, 636, 638, 641, 642, 648  
 লাটি—443  
 লাঠা—883

লাঠি—443, 493, 543, 673  
 লাডলী—959  
 লাড়ু—311, 498, 678  
 লাখানো—665  
 লাক—452, 512  
 লাক-দেওয়া—1051  
 লাকরা—513, 541  
 লাক্সা—512  
 লাক্সাল-স্মিথপাল—1048  
 লাভাড়া—513, 541  
 লান—367  
 লান—197  
 লান্ন—774  
 লান্নেক—588, 597, 610  
 লার্ড মার্গিটটান—637  
 লাল—306, 545 ; 578, 610 ; 874  
 লাল-পান্না—696  
 লালস—306, 335  
 লালিমা—703  
 লালুড—700  
 লাস—213, 321, 548 ; 610, 612  
 লাহা—460, 554, 637  
 লাহিড়ী—182  
 -লি—997  
 লি(ই)—1045  
 লিখ—443, 460  
 লিজে—476  
 লিজে—476, 900  
 লিপ—414  
 লিপটা—887  
 লিবার (= Eng. liver)—639, 648  
 লিবে—1045  
 লিয়ে—1045  
 লিলে—997, 1045  
 লিষ্ট—641

লিস—1045  
 লিহে—553  
 -লী—697  
 -লু—975  
 লুই—428  
 লুকাইলিস—979  
 লুকী—197  
 লুচী—196  
 লুট—491, 492  
 লুটিশ—546, 647, 648  
 লুট—492, 543, 874  
 লুটেরা—688  
 লুডী—307  
 লুগ—528  
 লুন—330, 543  
 লুবধ—376  
 লুবধ—377  
 -লুম, -লুম্—545, 974, 975  
 লুম—879  
 লুম—879  
 লে—774, 1045  
 -লে—1003  
 লেই—419  
 লেউটা—892  
 লেও—1045  
 লেওয়া—414  
 লেখা—956  
 লেখা-লেখা—1016  
 লেখ—411  
 লেগে—774  
 লেড—699  
 লেডা—699  
 লেড—857  
 লেডচা—889  
 লেডট—325, 687  
 লেডটা—685  
 লেডড়া—699  
 লেড—482



- লেজুড়—482, 543  
 লেজুড়ী—482  
 লেন—657  
 লেনা—657  
 লেপ্টেনাণ্ট—638  
 লেপ্টেনেণ্ট—642  
 লেফাফা—606  
 লেহু—157, 367  
 লেবে—1045  
 লেহ—1045  
 লেলা—892  
 লৈক—136, 383  
 লৈবেক—990  
 লো—330  
 লোকগান—546, 581, 607  
 লোকে—719  
 'লোকখো'—392  
 লোট—491, 546, 648  
 লোটন—400  
 লোটিইল—1032  
 লোণ—330  
 লোধ—329  
 লোনা—659  
 লোম—539  
 লোসকান—546  
 লোহা—330, 543, 555  
 -লু—974  
 '-ল্য'—380  
 ল্যাংবেটি—648  
 ল্যাম্প—641, 648  
 ব (= বসন্ত: হ ব [= v, w] )—  
 272, 534 ; see under ব (=   
 বর্গীয় ব=b), pp. 1147-1155  
 ব—(sound) 272, 465, 546,  
 547, 548, 551, 611, 613,  
 628, 630, 642 ; (suffix)  
 363 ; (hundred) 84, 302,  
 347, 547, 800  
 বইল—304, 344, 425  
 বউল—344  
 বকুন—454  
 বক্ত—599  
 বজুনা—530  
 বটকে—682  
 বণ—528, 1034  
 বত—682  
 বতকরা—702  
 বতকিরা—682  
 বতুর—377  
 বক্র—716, বক্র—716  
 বনান্ত—599  
 ব'বাজার—644  
 বম—305  
 বমন—648  
 বয়—800  
 বয়তান—583, 587, 602  
 বয়স—592, 609, 611  
 বয়ী—315, 547  
 বয়প—605  
 বয়ল—677  
 বরীক—585  
 বরীল—677  
 বর—679  
 বকরা—679  
 বর্ড—593, 602  
 বলা—307  
 বলা—315  
 বলাগ—697  
 বদ—548  
 বহর—575, 592, 595, 611  
 বহরে—399  
 বা—305, 557, 595, 611  
 বাইল—674  
 বাও—342, 345  
 বাক্য—458  
 বাখা—480  
 বাগ—445  
 বাউন—321, 521, 528, 548  
 বাউল—548  
 বাজাধা—613  
 বাজাহান—594  
 বাগ—528  
 বাগা—883  
 বাগা(ই)ল—1034  
 বাধ—190  
 বাবাই—589, 595  
 বাপড়—878  
 বাপড়ান—878  
 বাবল—335  
 বাম—548  
 বামিহানা—592  
 বামী—695  
 বামুক—366, 682  
 বাট—639  
 বাপী—648  
 বাল—674  
 -বাল—306  
 বালা—321, 544, 548  
 বালাজ—307, 475  
 বালিক—460, 536, 543  
 বালিখ—480  
 বালী—695  
 বাব—310, 691  
 বাবমল—801  
 বাবী—648  
 বাউড়ী—337, 548, 691  
 বাবুর—376  
 বাহ—305  
 বাহা—557, 611  
 বাহেরন—580  
 বাবর—324, 351  
 বাউলি—254, 399, 419  
 বাউলী—554

শিঙুর—351, 553  
 শিং—355, 363  
 শিক—584  
 শিকড়—454, 457, 554  
 শিকনি—408, 457  
 শিকল—355, 372, 444, 454,  
 457, 547  
 শিকল—325, 456  
 শিকনি—364  
 শিকানবিশ—708  
 শিক—196, 443  
 শিঙ—363  
 শিঙা—355, 363  
 শিঙা, শিঙা—363  
 শিঙাড়া—497  
 শিঙনি—364  
 শিঙা—325, 491  
 শিঙা—325  
 শিঙান—324, 331, 336, 505  
 শিঙি—541, 584, -শিঙা—610  
 শিঙ—311  
 শিঙেরা—736  
 শিঙা—653  
 শিঙ—366  
 শিঙুল—366  
 শিঙর—324, 418  
 শিঙাল—324, 336, 341, 355,  
 404, 417  
 শিঙালগোরা—452  
 শিঙ—324  
 শিঙকা—612  
 শিঙা—584, -শিঙা—541, 610  
 শিঙপেচ—577, 601, 604  
 শিঙিশ—585  
 শিঙী—608  
 শিঙেশ—585  
 শিঙ—306, 324, 544  
 শিঙে—543

শিঙা—306  
 শিঙিঙা—66  
 শিঙে—543, 648  
 শিঙ—549  
 শিঙ—554  
 শিঙ—351  
 শিঙী—254  
 শিঙ—352, 364  
 শিঙা—462  
 শিঙ—462  
 শিঙ—648  
 শিঙ—407, 892  
 শিঙ—397  
 শিঙে—397  
 শিঙা—428  
 শিঙে—394  
 শিঙ—341  
 শিঙতা—449, 456  
 শিঙে—394  
 শিঙতা—550  
 শিঙ—397  
 শিঙ—447, 458  
 শিঙা—657  
 শিঙা—322, 327, 401, 460  
 শিঙাইরা—394  
 শিঙা—882  
 শিঙাল—1031  
 শিঙা—401  
 শিঙে—1026  
 শিঙা—1027  
 শিঙী—958  
 শিঙে—397  
 শিঙে—1005  
 শিঙ(1)—706, 775  
 শিঙ—507  
 শিঙ—507  
 শিঙ—706  
 শিঙ—874

শিঙ—656  
 শিঙা—397, 548  
 শিঙা—665  
 শিঙ—397  
 শিঙে—932  
 শিঙ—397  
 শিঙ—326, 356, 397, 528,  
 575  
 শিঙ—397  
 শিঙ—428  
 শিঙ—586  
 শিঙা—586  
 শিঙ—400, 407  
 শিঙ—407, 574  
 শিঙ—575  
 শিঙ—341  
 শিঙ—428  
 শিঙ—401, 428  
 শিঙ—377  
 শিঙ—327  
 শিঙ—529  
 শিঙ—326, 341  
 শিঙা—412, 421  
 শিঙ—443  
 শিঙ—443, 587, 599  
 শিঙ—306, 328, 409, 475  
 শিঙতোলা—665  
 শিঙ—328, 493, 547, 548  
 শিঙ—679  
 শিঙ—328  
 শিঙা—640  
 শিঙা—328, 412  
 শিঙ—585  
 শিঙে—572  
 শিঙ—328, 341, 409, 544  
 শিঙে—648  
 শিঙা—412  
 শিঙ—304



শো—397, 874  
 শোকাইয়া—394  
 শোভিল—385  
 শোএ—426  
 শোনি—397  
 শোনা—397  
 শোনান—665, 666  
 শোনে—397  
 শোনো—397  
 শোভ—879  
 শোভা—644  
 শোভাবাজার—644  
 শোভিছে—1024  
 শোভের—995  
 শোর—397, 426, 533  
 শোয়া—397  
 শোরাস—548  
 শোর—341, 413, 428, 586  
 শোল—344, 385  
 শোলোক—377  
 শোহ—874  
 শোহরৎ—646  
 শোহে—329  
 শোল—385  
 শাই—315, 422  
 শাঁও—321, 342  
 শাঁৎ—316, 459  
 শাঁখা—322, 362  
 শাঁবারী—668  
 শাঁপ—510  
 শাঁশ—316, 370  
 শাঁস—548  
 শুক—408, 457, 874  
 শুক্কা—685  
 শুক্কা—686  
 শুক—327, 362, 493  
 শুক্কা—327, 365, 496  
 শুক্কা—526, -ক্কা—672

শুক্কা—707  
 শুক্কা—326  
 শুক্কা—372  
 শুক্কা—408, 457  
 শুক্কা—200, 373  
 শুক্কা—695  
 শুক্কা—640  
 শুক্কা—341  
 শুক্কা—190  
 শুক্কা—357  
 শুক্কা—826  
 শুক্কা—826  
 শুক্কা—696, 700  
 শুক্কা—304  
 শুক্কা—548  
 শুক্কা—411  
 শুক্কা—272, 465, 546, 547, 548,  
 551, 611, 613, 628, 642  
 শুক্কা—308, 383, 674, 797  
 শুক্কা—797  
 শুক্কা—716  
 শুক্কা—308, 674, 797  
 শুক্কা—383  
 শুক্কা—701  
 শুক্কা—493, 547, 798  
 শুক্কা—674, -ক্কা—716  
 শুক্কা—716  
 শুক্কা—701  
 শুক্কা—716  
 শুক্কা—329, 347, 543, 547,  
 555  
 শুক্কা—362, 365, 496, 547  
 শুক্কা—527  
 শুক্কা—640  
 শুক্কা—1078  
 শুক্কা—527  
 শুক্কা—105

শুক্কা—272, 465, 546, 547, 548,  
 551, 611, 613, 628, 630,  
 642  
 শুক্কা—712 ; -শুক্কা—699, 798, 885,  
 889 ; -শুক্কা—550  
 শুক্কা—(noun) 308, 344, 425,  
 426, 547, 553, 589, 594,  
 595, 611 ; (verb) 425 ;  
 (affix) 700, 709  
 শুক্কা—384  
 শুক্কা—381  
 শুক্কা—698  
 শুক্কা—213, 588  
 শুক্কা—588  
 শুক্কা—770, 803  
 শুক্কা—616, 777  
 শুক্কা—313, 589, 1066  
 শুক্কা—616  
 শুক্কা—শুক্কা—800  
 শুক্কা—597  
 শুক্কা—526  
 শুক্কা—372, -ক্কা—331  
 শুক্কা—454, 455, 550, 727,  
 730, 733  
 শুক্কা—755  
 শুক্কা—446, 578, 597  
 শুক্কা—712  
 শুক্কা—755  
 শুক্কা—725  
 শুক্কা—599  
 শুক্কা—712  
 শুক্কা—588, 597  
 শুক্কা—705  
 শুক্কা—372  
 শুক্কা—446, 454  
 শুক্কা—363  
 শুক্কা—578, 597  
 শুক্কা—363

সঙ্ক—403  
 সঙ্ক—363  
 সঙ্ক—145, 363, 774, 775  
 সঙ্ক—317  
 সঙ্ক—712  
 সঙ্ক—523  
 সঙ্ক—606, 608  
 সঙ্ক—886  
 সঙ্ক—712  
 সঙ্ক—355, 497, 679, 682  
 সঙ্ক—886  
 সঙ্ক—681  
 সঙ্ক—891  
 সঙ্ক—681  
 সঙ্ক—317, 347, 409  
 সঙ্ক—532, 601, -হি—601  
 সঙ্ক—347, 693, 694  
 সঙ্ক—694  
 সঙ্ক—694  
 সঙ্ক—317, 347, 409, 502,  
 555, 791, 792  
 সঙ্ক—308, 347, 693, 694  
 সঙ্ক—308, 502, 540, 674  
 সঙ্ক—382  
 সঙ্ক—308, 347  
 সঙ্ক—304, 382, 383, 384,  
 392, 406  
 সঙ্ক—406, 705  
 সঙ্ক—592, 611  
 সঙ্ক—575, 610  
 সঙ্ক—611  
 সঙ্ক—608, 611  
 সঙ্ক—608  
 সঙ্ক—580, 593, 599, 602,  
 607  
 সঙ্ক—523, 529, 774  
 সঙ্ক—334, 403, 507  
 সঙ্ক—507

সঙ্ক—398  
 সঙ্ক—398  
 সঙ্ক—398  
 সঙ্ক—891  
 সঙ্ক—648  
 সঙ্ক—631, 632  
 সঙ্ক—449  
 সঙ্ক—648  
 সঙ্ক—585  
 সঙ্ক—659  
 সঙ্ক—318, 440, 514, 516, 531,  
 727, 730, 732, 733, 735  
 সঙ্ক—648, 714  
 সঙ্ক(ই)—724  
 সঙ্ক—648  
 সঙ্ক—654  
 সঙ্ক—648  
 সঙ্ক(ই)—706  
 সঙ্ক—726  
 সঙ্ক(ই)কার—755  
 সঙ্ক—712  
 সঙ্ক—611  
 সঙ্ক—726  
 সঙ্ক—712  
 সঙ্ক—726  
 সঙ্ক(ই)কার—755  
 সঙ্ক—440, 516, 727, 732  
 সঙ্ক—606  
 সঙ্ক—644, 732  
 সঙ্ক, সঙ্ক—725  
 সঙ্ক—1073  
 সঙ্ক—305; (=all) 531  
 সঙ্ক—708  
 সঙ্ক—74  
 সঙ্ক—541  
 সঙ্ক—648  
 সঙ্ক—366  
 সঙ্ক, সঙ্ক—533

সঙ্ক—733  
 সঙ্ক—367  
 সঙ্ক—367  
 সঙ্ক—453  
 সঙ্ক—481, 875  
 সঙ্ক—366  
 সঙ্ক—523, 774  
 সঙ্ক—216  
 সঙ্ক—366  
 সঙ্ক—367  
 সঙ্ক—367  
 সঙ্ক—424, 555  
 সঙ্ক—604, 614  
 সঙ্ক—424, 698  
 সঙ্ক—336  
 সঙ্ক—426  
 সঙ্ক—874  
 সঙ্ক—700  
 সঙ্ক—598  
 সঙ্ক—585  
 সঙ্ক—1012  
 সঙ্ক—611  
 সঙ্ক(ই)—595  
 সঙ্ক—609, 611  
 সঙ্ক—332  
 সঙ্ক—700  
 সঙ্ক—589, 611  
 সঙ্ক—1012  
 সঙ্ক(পঙ্ক)—1051  
 সঙ্ক—332, 374, 376, 381  
 সঙ্ক—679  
 সঙ্ক—877  
 সঙ্ক—540  
 সঙ্ক—593  
 সঙ্ক—449  
 সঙ্ক—675, 610  
 সঙ্ক—449  
 সঙ্ক—550



সরসে—374  
 সর্ষে—381  
 সহ—574, 585  
 -সহ—706  
 সহভবা—705  
 সহবৎ—582, 595  
 সহ্য—777  
 সহায়—533, 777  
 -সহি—700, 709  
 সহিত—396  
 সহিতবা—705  
 সহিতে—384  
 সহিব—1039  
 সহিরা—426  
 সহিলি, সহিলী—698  
 সহী—595  
 সহে—315, 555  
 সহেন—416  
 সহেলি—698  
 সহ—531, 727  
 সহাই—726  
 সহাক্ষি—726  
 সহকে—812  
 সহ—476, 482  
 সহোদ—367  
 সহযুক্ত—477  
 সা—310, 554, 557, 637  
 -সা—699, 701  
 সাধর—341  
 সাইত—596  
 সাইখা—345, 380  
 সাখা—340, 382  
 সাইখ—381, 385, 386  
 সাখে—716  
 সাইখের—381  
 সাখের—384, 716  
 সাইর—674  
 সাউখা—345, 380, 382

সাউর—381, 383  
 সাউখ—381, 383, 385, 386  
 সাউখের—381, 384  
 সাউতাল—502  
 সাংগানগার—725  
 সাফী—458  
 সাফীসাব্দ—582  
 সাফা, সাফি—406  
 সাঙ—197, 461, 622, 627, 629  
 সাঙন—528  
 সাঙল—321, 520  
 সাঙাৎ—363, 663  
 সাফন—519, 652  
 সাফ—112, 363, 364  
 সাফা—364  
 সাফাৎ—322, 363, 663  
 সাফানগার—736  
 সাচান—372  
 সাজি—306, 475, 895  
 সাজতে—477  
 সাজত—999  
 সাজশ—580  
 সাগন্তক—706  
 সাজা—576, 611  
 সাজাই—662  
 সাজার—317  
 সাজিতে—477  
 সাজাদ—619  
 সাজি—522  
 সাজি—527  
 সাজী—321, 496  
 সাজে—500, 802, 803  
 সাজে—560  
 সাজি—502, 791  
 সাজই—303, 372, 512  
 সাজশি—796  
 সাজটা, সাজটা—451  
 সাজস্তর—555

সাজি—789  
 সাজশ—318, 795  
 সাজসে—700  
 সাজুই—512, 805  
 সাধ—321, 504, 774  
 সাধু—340, 345, 380, 395  
 সাধুরা—340, 382  
 সাধে—145, 504, 774  
 সাধবা—443  
 সাধিনা—450  
 সাধী—578  
 সাধ—190, 306, 381, 385, 386,  
 507  
 সাধিলেই—981  
 সাধু—381, 383, 716  
 সাধুধান—443  
 সাধুধা—89  
 সাধুর—384  
 সাধা, সাধি—406  
 সান—306, 527, 528, 652  
 সানক—576, 595, 598, 611  
 সানকী—595  
 সানি—367, 529  
 সানাই—407  
 সানি—407, 612  
 সান্তরা—626  
 সান্ধা—382  
 সাপ—(noun) 318, 369, 511 ;  
 (adjective) 606  
 সাপট—684  
 সাপিনী—695  
 সাপুড়ে—688  
 সাপ্টা—449  
 সাফ—806  
 সাফাই—662  
 সাফ—648, 714  
 সাফকাশ—712  
 সাফধান—449

সাঁবাং, সাঁবান—530, 624, 630  
 সাঁবালক—712  
 সাঁবাশা—884  
 সাঁবাস—611  
 সাঁবু—197, 622, 629  
 সাঁবুদ—582, 602  
 সাঁবেক—611  
 সাঁব্যন্ত—453  
 সাঁভার—317, 515, 669  
 সাঁমার—367, 440  
 সাঁমাল—874  
 সাঁমালে—367, 440  
 সাঁমী—519  
 সাঁম্বা—283  
 সাঁম্বার, সাঁম্বার—367, 440  
 সাঁম্বালে—440  
 সাঁয়—423  
 সাঁয়র—219, 321, 335, 341,  
 342, 404, 540  
 সাঁয়—622, 625, 631  
 সাঁয়েত—596  
 সাঁয়েজ—217  
 সাঁয়েবানী, সাঁয়েমানী—531  
 সাঁয়ের—335, 341, 423, 589  
 সাঁর—674  
 সাঁরং—598  
 সাঁরি—674  
 সাঁরে—877  
 সাঁরেং—595, 598  
 সাঁরু—639  
 সাঁরুদ—639  
 সাঁরুদ—619  
 সাঁরী—648  
 সাঁলসা—622, 629, 631  
 সাঁলানা, সাঁলিয়ানা—592  
 সাঁলিস—580, 611  
 সাঁস—310  
 সাঁহ—310, 554, 557, 595

সাঁহসরান—801  
 সাঁহা—554, 557, 595, 639  
 সাঁহার্ণা—542  
 সাঁহেব—589, 594  
 সাঁহেবানী—531  
 সাঁহেবিয়ানা—592, 707  
 সাঁ—874  
 সাঁ—550  
 সাঁউনী—468  
 সাঁউই—195  
 সাঁগি, সাঁগি—364  
 সাঁগিনী—695  
 সাঁক—599  
 সাঁকা—1076  
 সাঁকলর—578  
 সাঁকি—399, 406, 1076  
 সাঁকা—195  
 সাঁগ—599  
 সাঁগারেট, সাঁগ—646  
 সাঁগান—1031  
 সাঁগ—874  
 সাঁগে—482, 875  
 সাঁগা—313  
 সাঁকিত—704  
 সাঁন্মে—333  
 সাঁগা—325  
 সাঁগে—653  
 সাঁগ—550  
 সাঁগান—376  
 সাঁগেহ—376  
 সাঁগু—440, 597, 603  
 সাঁগুরি—452  
 সাঁগু—440, 597, 603  
 সাঁগিলেসন—644  
 সাঁগা—313  
 সাঁগিমাঝ—604  
 সাঁলেট (= Eng. slate)—640  
 সাঁ—364

সাঁ—699, 701  
 সাঁম—306  
 সাঁরে—324  
 সাঁল—648  
 সাঁ—407, 892  
 সাঁ—712  
 সাঁসা—656  
 সাঁসা-সাছে—1027, 1028  
 সাঁই—428, 468  
 সাঁও—198, 554  
 সাঁকি—399, 406  
 সাঁখ—460  
 সাঁখর—712  
 সাঁখমুরা—597  
 সাঁখু—377  
 সাঁখা—384  
 সাঁহাঁদ—712  
 সাঁজন—712  
 সাঁড়ং, সাঁ—195  
 সাঁড়ক—680  
 সাঁডোল—712  
 সাঁত—502, 903  
 সাঁতালী—670  
 সাঁতিঝা আঁহিলে—1027  
 সাঁতিল—331, 677, 940, 956  
 সাঁদ—586, 603  
 সাঁদিন—712  
 সাঁঙ্ক(ী)—776  
 সাঁখ—507  
 সাঁবি—507  
 সাঁবু—706  
 সাঁনজর—712  
 সাঁনয়নী—673  
 সাঁনাম—712  
 সাঁন্দর—407  
 সাঁকি, সাঁকো—309, 352  
 সাঁরং—203  
 সাঁপারিশ, সাঁ—580, 606



- হকদনী—678  
 হবা—596  
 হবে বাজনা—596  
 হমন—712  
 হমর—377  
 হম্ব—531  
 হম্বি—366  
 হম্বি—477  
 হম্ব—198  
 হযোগ—477  
 হর—407, 548  
 হরকি, -কী—581, 611  
 হরং—586  
 হরতি—524  
 হরাক—213, 600  
 হর—596  
 হরক—213  
 হরহা—586, 605  
 হর্ডি—626, 631  
 হহা—554  
 হহ—308, 408, 470  
 হতা—323  
 হর্বা—324  
 হজম—201  
 হে—145, 820, 821, 823, 826, 827, 828  
 হেই—419, 828, 835  
 হেউ—420  
 হেওয়ার—616, 777  
 হেউ—195  
 হেক—204, 443, 599  
 হেকরা—181, 194, 457, 668  
 হেকরানী—695  
 হেকেন্দ্র—578  
 হেকটো—217  
 হেখ—599  
 হেখান—836  
 হেখানে—859  
 হেখেনে—401  
 হেখান—372  
 হেটি, -টি—859  
 হেংখানা—595  
 হেখা—412, 858  
 হেখুহা—382  
 হেখো—340, 345, 380, 382, 395  
 হেখিনে—333  
 হেখে—716  
 হেখের—381  
 হেন—411  
 হেগাই—589, 611  
 হেব—879  
 হেবা—411  
 হেবাইড—663  
 হেবিজ—648  
 হেরন—614  
 হেরাই—589  
 হেরানী—412  
 হেরকে—682  
 হেরেপ—606  
 হেরেক—580, 606, 612  
 হেরেস্তা—577, 610, 618  
 হেলাই—662, 1033  
 হেলাম—576  
 হেলাম-আলেকোম, -কম—587, 609  
 হেলেট (= Eng. slate)—640  
 হে-সব—735, 821  
 হে-সি—550  
 হেহি—828  
 হৈতা—136, 383  
 হৈরদ—587, 614  
 হৈরভ—426  
 হো—198, 554, 826, 874  
 হোঙর—377  
 হোঙরে—520  
 হোজা—413  
 হো-এ-র—519  
 হোভা—648  
 হোখা—523, 529  
 'হোজো'—392  
 হোদা—413  
 হোদো—605  
 হোদো ভাসান—505  
 হোনা—330, 367, 529  
 হোনালী—670  
 হোপরক—593, 604, 619  
 হোবে—596  
 হোবে দাদেক—580  
 হোমড়া—66  
 হোমন্ত—431, 541  
 হোমাই—662  
 হোর—330, 353  
 হোহাখ—427, 534  
 হোহাদ—534  
 হোহামী—427, 534  
 হোহাং—589  
 হোহাতি—427, 534  
 হোহাই—589  
 হোরোভ—377  
 হোলো—596  
 হোদর—700  
 হোহ—574  
 হোহরং—582, 591  
 হোহাগ—330, 336, 554  
 হোহাগলী—698  
 হোহাগিনী, হোহাগী—694  
 হোখীন—588  
 হোজজ, -তা—705  
 হোদা—588  
 হোরভ—427  
 হাঁকড়ি—372  
 হাঁপ—348, 874  
 হাঁপে—347, 511, 520

সাঁ—479  
সাঁই—321, 422, 519, 520,  
522, 548  
সাঁইত্রিশ—791, 792  
সাঁইসাঁই—422  
সাঁও—321  
সাঁওতাল—520  
সাঁকালি, -সাঁ—623, 627  
সাঁকো—282, 347, 456, 519,  
520  
সাঁচ—362  
সাঁচা—160, 312, 362, 370, 464,  
471  
সাঁচাই—661  
সাঁচা—100, 447  
সাঁজার—352, 370, 409, 476,  
646, 697  
সাঁজোরা—337, 364  
সাঁঝ—306, 364, 481  
সাঁঝাড়া, সাঁঝড়া—399  
সাঁঝুতি—476  
সাঁট—879  
সাঁড়ানী—365, 497  
সাঁতর—874  
সাঁতরা (noun)—626, 628, 630  
সাঁতরা—502, 520  
সাঁতরাগাছি—626  
সাঁতার—336  
সাঁথ—404  
সাঁপুড়া—337, 510  
সাঁরত্রিশ—792  
সাঁরি—522  
সাঁড়ো—499  
সাঁতা—504  
সাঁতি—502, 504  
সাঁথা—331, 504  
সাঁথি—504  
সাঁদুর—325, 337, 365, 506

সাঁধ—308, 404, 406,  
সাঁতি—324, 351, 520  
সাঁথি—520  
সাঁটুকী—452  
সাঁড়লক—526  
সাঁদুরী—365  
সাঁওতী—328  
সাঁকো—622, 625, 626, 627,  
630  
সাঁচে—327  
সাঁজা—697  
সাঁজার—370, 409, 476  
সাঁঝুতি—476  
সাঁতান—502  
সাঁতার—882  
সাঁঅর—519  
সাঁঅরিতে—1001  
সাঁআ—520  
-সাঁআ—701  
সাঁটা—649  
সাঁতা—329, 501, 548, 652  
সাঁথা—309, 366  
সাঁপ—874  
সাঁপ—348  
সাঁ—(sound) 377  
সাঁভেজুর (= scavenger)—644  
-সাঁ—1073  
সাঁন—527  
সাঁহ—304, 527  
সাঁকীর—534  
সাঁগ—449  
সাঁতদুর—376  
সাঁহ—382, 534  
সাঁদ—403, 534  
সাঁপন—376  
সাঁরগ—376  
সাঁর্গ—449  
সাঁতি—534

সাঁশুন—431  
সাঁজ—403  
সাঁদ—403, 534  
সাঁদী—403  
সাঁদুরী—519  
সাঁর—879  
সাঁরতি—933  
সাঁই—589  
সাঁকত—584  
সাঁগাং—363  
সাঁরনা—412  
সাঁলাদ—576  
সাঁহী—589  
সাঁথ—580, 606, 612  
সাঁংসাঁতে—451  
  
হ—272, 341, 454, 594, 642 ;  
(verb) 347, 555, 923, 926,  
1014, 1035, 1038 ; (suffix)  
554, 903  
হঅন—335, 400, 656  
হআ—341, 350, 425  
হই—93, 425  
হইঅ—392  
হইতে—161, 172, 728, 739,  
768, 775, 776  
হইতেছে—443, 472, 1023  
হইতে—775  
হইব—1039  
হইবার—393  
হইবে—143  
হইবেক—683  
হইম—392  
হইয়াই—394  
হইয়াছিল—474  
হইয়া—381  
হইল—299, 383, 384, 392,  
1038



হাইদারহী—976	হন—424	হরণ, -ক—575, 592, 606
হইলে—777	হন—853	হরবালা—714
হইলে বিহনে (=বিনে, বিনা) — 1017	হনুমত(ী)—697	হরনার—620, 623, 629
হউক—383, 907	হনে—775	হরিকেন—638
হউ—313	হস্ত—776	হরিধ—461
হএ—1038, 1039	হস্তি—1038	হরিণ—337
হও—425, 906	হস্তে—161, 775, 776	হরিয়াল—337
হওয়া—341	হন্দর—638, 641, 648	হর—677
হও—341	হণ্ডা—443, 449, 594, 606	হ'রে—381
হওন—302, 335, 400, 656, 1008	হব—1039	হরে—577
হওয়া—341, 350, 393, 425	হবু—678	হর্দ—619
হনে—304	হবে(ক)বুন—997	হল—384
হক—576, 594, 597, 618	হর—93, 415, 424, 533, 555, 1038, 1039	হ'ল—592
হকীম—585, 609	হর—1029	হল'—392
হকু—383, 907	হরহ—1038	হলদিয়া—674
হকুক—575, 597	হরতি—1038	হলপ, -ক—577, 594, 606
হকলাইন—725	হরত—994	হলুন—306, 315, 407, 505, 543, 553
হগল—446	হররাণ, -ন—523, 587	হলুদিয়া—674
হহে—443	হহা—341	হ'লুদে—674
হ'হে, হ'হে—472, 1029	হহিরা—379	হ'লে—777, 1006
হজ—203	হহিলাহা—981	হ'লে—777, 1006
হজম—594	হহিলাহী—975	হ'ল'হে—1020, 1026
হজরৎ—594	হহে—391	হ'ল'দে—674
হজরৎ—594	হ'হে—391, 426, 918	হলা—299, 383
হজরৎ—1027	হ'হেই—394	হসি—379
হঠ—553	হ'হেইল—388	হসি-মৌগদি—431
হডকা—556, 886	হ'হেইলো—474	হা—712
হডতাল—196	হ'হেই—1028	হা—903
হডগী—511	হহেন—416, 424	হাইকোট, হাইকোট—639, 642
হডহডা—891	হ'হেলো—474	হাইবাস—556
হডভাগিনী—695	হহো, হ'হো—392	হাঁর—539
হ'তে—728, 768, 775	হর—714	হোল—556
হটে—775	হরকৎ—598	হাউই—589, 590
হতা—413, 503	হরকরা—583	হাউলী—576, 591, 618
হতো—775	হরতন—215	হাউস—639
হনীস—612	হরতাল—196	হাউহাউ—424
হদ—593, 594, 603, 619	হরদিন—714	হাওড়া—66, 535

- হাওনা—588  
হাওরা—576, 594, 616  
হাক—456  
হাকিম—454, 594  
হাকুলি—558  
হাগরে—462  
হাঘরিয়া—713  
হাঘরে—462  
হাঘ'রে—713  
হাকর—557  
হাকনা—557  
হাকনা—576  
হাকর—594, 602  
হাকরে—590  
হাক—557  
হাকাম—601  
হাকার—576, 583, 594, 801  
হাকারী—203  
হাকির—580, 613  
হাট—490  
হাটখোলা—449  
হাটবাজার—450  
হাটরিয়া—542  
হাজি—181  
হাজিরা—386  
হাজিরা—679  
হাজিরে—542  
হাজিবাক—1018  
হাড়—498  
হাড়ী—672  
হাড়ীগাঙ্গ—280  
হাত—302, 442, 443, 448, 503, 505, 552  
হাতছান—306  
হাতড়া—588  
হাতপা—449  
হাতর—717  
হাতল—698  
হাতমান—306, 528  
হাতা—559, 583  
হাতানো—685  
হাতাহাতি—1049  
হাতিচাখ—216  
হাতী—442  
হাতীশাল—306  
হাতে—303, 744  
হাতেতে—744  
হাতের—717  
হাতা—448  
হাংগা—736  
হাখ—302, 503, 505  
হাখেত—743  
হাখে—744  
হানিকল—216  
হানে—321  
হাপ (= half)—643, 648  
হাপ-আখড়াই—714  
হাপর—553  
হাপ-লাইড—648  
হাপুতি—713  
হাপুস—713  
হাপ-আখড়াই—714  
হাকের—594  
হাবড়া—535  
হাবলী—576, 591, 616  
হাবলী—576  
হাবাতে—462, 713  
হাবিলাত—556  
হাবেলী—576, 585, 616  
হাভাতিয়া—462, 713  
হাকলী—616  
হাম—535  
হামরা—815  
হামরাই—594  
হামলা—594, 889  
হামা—405, 552, 888  
হামা- (pronoun)—815  
হামা(ন)দিতা—617  
হামা-দেওয়া—1051  
হামার—553, 815  
হানি—815  
হানীর—440  
হামেশা—585, 594, 612  
হানীর, হানীর—367, 440  
হামাম—619  
-হার—701  
হারজিত—896  
-হারা—701  
হারা—956  
হারাইল—957  
হারাইলা—1017  
হারাকিরি—197  
হারাম—203, 576, 609  
হারামদ—556, 620, 623, 629  
হারান—1031  
হারি—589  
হারিরা—388  
হারে—877  
হারেছ—590  
হার্দাম—619  
হার্দোনিয়া(ন)—648  
হাল—(Persian) 611, (English) 636  
হালওয়াই—589, 616  
হালকা—315, 457, 553  
হালদার—590  
হালাল—583, 594, 611  
হালি—543, 556  
হালিয়া—674  
হালুই—589, 616  
হালুয়া—576, 583, 616  
হালুকা—452  
হালুক—619  
হাস—321, 370, 548, 674



হাসিতে-খাকা—1052  
 হাসিরা-হাসিরা—1047  
 হাসেষ্ঠ—933  
 -হি—555  
 হিং—325, 552  
 হিংস—879  
 হিংস্ক—704  
 হিংস্বে—686  
 হিঙ—310  
 হিন্দুল—337  
 হিজড়া—691  
 হিজরা—583  
 হিতে—825, 827  
 হিতেরা—827  
 হিনস্থা—347  
 তিনি—827  
 হিন্দু—594  
 হিন্দু—705  
 হিন্দুয়ানী—707  
 হিন্দুয়ান—709  
 হিকিলেক—990  
 হিজ্রা—648  
 হিরা—324, 342, 355, 417,  
 552  
 হিলান—313, 324, 452, 554  
 হিলে—313, 324  
 হিলোল—337  
 হিসাব—594, 605  
 হিসাব-কিতাব—583  
 হিসাবী—583, 671  
 হিসিবি—583  
 হিসেব—401  
 হিসেব-কিতাব—583  
 হিসেবী—583  
 হিহি—557  
 হীরকর—758  
 হীরা—552  
 -হু—554

হুইল—648  
 হুএ—1038  
 হুকুম—581, 593  
 হজুর—577, 586  
 হট্টকানো-পাট্টকানো—1048  
 হড়কা—556, 681  
 হড়া—556  
 হড়াহড়ি—408, 1048  
 হড়ী—553  
 হড় ম—556  
 হতোম—556  
 হযুমান—431  
 হযুর—578, 594  
 হনে—553  
 হমড়া—888  
 হমড়ি—405  
 হমা—883  
 হরা-হরা—429  
 হরী—586, 594  
 হুল—556  
 হলান—557  
 হলিয়া—581  
 হল্লাস—556  
 হুল্লয়—557  
 হে—827  
 হেইরার—827  
 হেউ—421  
 হেউং—520  
 হেগেলীয়—703  
 হেজামা—576  
 হেট (= Eng. hat)—648  
 হেটো—386, 391, 679  
 হেড-গোমস্তা—714  
 হেড-পণ্ডিত—714  
 হেড-বাবু—714  
 হেড-মুহুরী—714  
 হেড-মোলবী—714  
 হেতার—827


হেতিন—827  
 হেখা—327, 328, 412, 504,  
 556, 858, 859  
 হেখাকার—755  
 হেথার—858  
 হেদা—892  
 হেন—313, 350, 528, 555,  
 853  
 -হেন—853  
 হেনক—1008  
 হেনমতে—852  
 হেনরা—827  
 হেনস্তা—347  
 হেনা—580  
 হেনার—827  
 হেনারগো—827  
 হেয়ার (= Eng. Hare)—640  
 হের—(pron.) 827, (verb) 874  
 হেরগো—827  
 হেরা—827  
 হেরার—827  
 হেরে—388  
 হেলা—411  
 হেলান—313  
 হেলে—313, 674  
 হেস্তনেস্ত—577, 593, 612  
 হৈতে—161, 739, 775  
 হৈতে—1001  
 হৈবের—995  
 হৈল—384  
 হৈলাহৌ—975  
 হৈ হৈ—426  
 হৌ—555, 1035, 1038  
 হৌই—93  
 হৌইতে—775  
 হৌইব—1039  
 হৌইল—1038  
 হৌডি—310

হাউক—310, 383  
 হাএ—93, 353, 877, 1038  
 হাক্—310  
 হাড়—498, 556  
 হাতেছে—1023  
 হোখা—556, 858  
 হোখায়—858  
 হোন্তে—161, 775  
 হোমরা—557  
 হোমরা-চোমরা—557  
 হোমিওপ্যাথী—638  
 হোয়ে—391  
 হোয়ে—392  
 হোল—392  
 হোলাইন—725  
 হোলো—392  
 হোক—310, 455  
 হোল—588, 594  
 হোস—639  
 হ—359  
 হাউ—313  
 হাউমাউ—424  
 হাক—456, 457, 891  
 হাকড়া—888  
 হাকডাক—896  
 হাকড়ায়—880  
 হাকরা—889  
 হাকাড়ে—880  
 হাকরা—889  
 হাকরায়—880  
 হাট—891

হাটী—516  
 হাট—556, 879  
 হাটতে—446  
 হাটলে—985  
 হাটরা (হেটে) চলো—1012  
 হাটু—311, 556  
 হাটু—311  
 হাড়কাট—450  
 হাড়ল—698  
 হাড়িকাট—450  
 হাড়িয়া—197  
 হাড়ী—365, 553  
 হাড়ীশাল—517, 1070  
 হাদা—556  
 হাফ—556  
 হাস—362, 368, 370, 547,  
 549, 552  
 হাসপাতাল—216, 503, 634, 642  
 হাসপাতালে—371  
 হাসিয়া—608, 615  
 হাতাল—517  
 হা—555  
 হিতাল—325  
 হিঁদু—366, 580, 594, 608  
 হিঁদুখানী—707  
 হিঁসকটে—686  
 হঁকা—371, 401, 594, 597,  
 608  
 হঁকাছাড়া—769  
 হঁকো—401, 572, 608  
 হঁশ—371, 608

হঁসিয়ার—608  
 হেইও—419  
 হেঁচকা—556, 886  
 হেঁচকা—457  
 হেঁচকি—681  
 হেঁচড়া—887  
 হেঁচড়ানি—681  
 হেঁচড়ায়—876  
 হেঁজা—409, 476, 697  
 হেঁট—328, 370, 411, 443,  
 1068  
 হেঁঠ—494  
 হেঁড়াল—553  
 হেঁতাল—325, 336  
 হেঁদু—366, 580, 594, 608  
 হেঁরালী—328  
 হেঁশেল—1070  
 হেঁসেল—517  
 হো—520  
 হো—344, 359  
 হোঁচট—685  
 হোঁৎকা—557, 681  
 হোঁদল—553  
 হু (sound)—132  
 হু—853  
 হু (sound)—132, 144, 557  
 হু (sound)—482  
 হ্যাট (= Eng. hat)—648  
 হ্যার (= Eng. Hare)—640  
 হুখ—557  
 :—272





Archaeological Library,

23470

Call No. 491.4409/cho

Author—Chatterji, S.K.

Title—*The origin and development of the Bengali Language*

Borrower No.

Date of Issue

Date of Return

*"A book that is shut is but a block"*

CENTRAL ARCHAEOLOGICAL LIBRARY  
GOVT. OF INDIA  
Department of Archaeology  
NEW DELHI.

Please help us to keep the book  
clean and moving.

---